

Technical Assignment #2 Cost and Methods Analysis

Faculty Consultant: Dr. John Messner
Department of Architectural Engineering
The Pennsylvania State University
October 30, 2006



Table of Contents

A. Executive Summary	3
B. Detailed Project Schedule	
C. Site Layout Planning	6
D. Assemblies Estimate for Fire Protection System	7
E. Detailed Structural System Estimate	8
F. General Conditions Estimate	10
Appendix A	13
Appendix B	14
Appendix C	15
Appendix D	16



A. Executive Summary

The second technical assignment for Ursinus College Residence Hall 2, located in Collegeville, Pennsylvania, analyzes key features of the project that affect project execution. These key features are the project schedule, a specific construction site plan, an assembly's estimate, detailed structural estimate, and a general conditions estimate.

Residence Hall 2 is one part of a three part construction plan that Ursinus College (UC) is currently undertaking. The first item analyzed in this assignment is a detailed project schedule. This schedule is highlighted by many key activities and milestones that are broken down in to a floor by floor sequence. It shows construction beginning in May 2006 with a substantial completion and building turnover date in late July 2007. The next item analyzed is the site layout plan. A site layout plan was developed for a specific construction phase, structural sequence, that illustrates how the site is set up and where trades are located at this time in construction. The third analysis is an assembly's estimate of the sprinkler system used in Residence Hall 2. This project utilizes a wet pipe system with a dry standpipe in each major stairwell. The next item completed is a detailed structural estimate. This project is built with CMU load bearing walls and precast plank as the structural system. A cost analysis of this will allow for other structural systems cost comparison to the one being utilized. The last item in this assignment is the calculation of a general conditions estimate for a 14 month timeframe. Certain items were provided by the construction manager, and other items were added in order to complete the general conditions estimate.



B. Detailed Project Schedule

Please see Appendix A for Detailed Project Schedule

The detailed project schedule for Residence Hall 2 is a 14 month schedule for a 52,144 square foot dormitory located on the North campus of Ursinus College (UC). This is a very tight schedule for a project of this size and the completion date is not negotiable. The project must be completed for the start of the Fall 2007 semester at the college. Warfel Construction Company (WCC) has an outstanding relationship with UC and will execute this project in the time frame that has been provided. WCC broke the schedule down in to a floor by floor sequence so as the project continued, the different subcontractors could keep moving from one floor to the next. Below are some of the key project milestones for Residence Hall 2.

Key Project Milestones

May 15, 2006
May 2, 2006
June 6, 2006
June 14, 2006
October 20, 2006
December 7, 2006
January 12, 2007
May 21, 2007
July 25, 2007
May 27, 2007
June 26, 2007
July 30, 2007
August 27, 2007

Superstructure

Residence Hall 2 is constructed of cast in place continuous/strip concrete footings, load bearing CMU walls, precast hollow core plank, minor structural steel, and wood roof trusses. It is essential that the footings and load bearing walls be ready for the first delivery of plank scheduled for July 27, 2006. Before excavation for these footings could begin, Deep Dynamic Compaction of the site had to occur in order to properly treat unsuitable soils. The plank is being delivered from Portage, Pennsylvania which is over four hours from the site and delays will prove to be costly for completing the rest of the

superstructure on schedule. The remainder of the superstructure will be constructed on a floor by floor basis. Once the plank is erected the CMU load bearing walls will be constructed and prepared for the next floor of plank. All four floors must be completed by October 20, 2006 in or to stay on track for building enclosure by December 7, 2006.

Interior Sequence

The interior phases of this project are on a floor by floor basis. Each trade will move through the building completing their scope of work starting with the ground floor and finishing with the fourth floor. There is repetition and redundancy to this project and that should allow for trades to move as quickly as possible through the building while staying out of each other's way in the process. The first trades to start will be the plumbing contractor and electrical contractor because they must rough-in underslab conduit and piping prior to superstructure completion. The typical sequence of trades through a floor is as follows:

- Interior Metal Stud Walls
- Plumbing Rough-ins
- Electrical Rough-ins
- HVAC Rough-ins
- Sprinkler Rough-ins
- Drywall
- Painting
- Plank Topping
- Wood Doors and Trim
- Millwork
- Acoustical Ceiling Grid
- Electrical Fixtures
- HVAC Fixtures
- Flooring

As one trade finishes their scope they will move to the next floor and begin work on that level. The average time allowed for a single floor completion is 8 months. Keep in mind that each trade will move forward once work is complete so all four floors will be completed on schedule for project completion

Landscaping and FF&E

Ursinus College is performing these activities on their own as they have an Office of Physical Plant. This allows the college to save money on certain fees and other costs. Currently the college has a preliminary set of landscaping drawings that are out for approval and they are awaiting bids for the furniture for Residence Hall 2. Both are scheduled to be completed by the project completion date, July 30, 2007.



C. Site Layout Planning

Please See Appendix B for Site Layout Plan

The site where Residence Hall 2 is being built is a clear site with only minor slopes during construction. The site layout plan illustrates the location of temporary trailers, the crane, site access, site mobility for deliveries, staging areas, dumpsters, portable toilets, and temporary electric during the construction of the superstructure of the building. Access to the site is through one of two places. The main entrance by the construction trailers is directly off one of the colleges main roads and the deliveries entrance for the precast plank, masonry, and steel is off to the West of the building next to a parking lot. The crane for this project will be located on the North side of the building located directly at the center. The crane that the precast plank manufacturer uses to set the plank can reach all lifts necessary during this phase of the project from that specific location. Concrete delivery for slab on grade and footings is noted on the site layout plan as well. There are only two storage trailers on the site. One is a WCC storage trailer and the second is a storage trailer for the plumbing subcontractor. The site is located on the colleges North campus and the only building near this project is directly to the South across the street.

Even though this site plan is specifically for the superstructure phase of this project, similar traffic and delivery patterns will be utilized throughout the entire project. It is an open site and therefore they have capacity to move trailers or staging areas if need be. All tools on site are brought by workers and few are left on site each night. Since WCC is the general contractor all tools are locked in their site trailer. Safety is a huge issue for WCC and the college and the site fence around the entire perimeter is locked every day after construction is complete for that day. This was the best way for the contractor to use the site efficiently. The only time when traffic flow is interrupted on site is when precast hollow core plank is being set. In this case a controlled access zone must be established around the crane for safety reasons.



D. Assemblies Estimate for Fire Protection System

Please See Appendix C for Detailed Assemblies Takeoff

Residence Hall 2 utilizes two types of fire protection systems. The system in this building is a wet sprinkler system. There is a four inch standpipe that runs through the center of the building and supplies all floors with three inch mains. All sprinkler heads are quick response and there are fire extinguisher cabinets located throughout the residence hall. Also installed in this building are two dry standpipes in the East and West Stairs. Installation and all materials are included in this estimate. The following table represents a summary of the assembly estimate as well as the comparison to the fire protection bid number that WCC awarded to Precision Fire Protection. All numbers that are a part of the assembly estimate were taken from the RS Means Assemblies Estimating guide for 2006.

Table 1 Fire Protection System Cost Comparison

Fire Protection System Est.	Cost	% Project Cost	Cost/SF
Precision Fire	\$105,000	9.90%	\$2.01
Assemblies Estimate	\$206,341.50	19.40%	\$3.96
Difference	\$101,341.50		

Ursinus College Residence Hall 2 contains many added features that assist the fire protection system while serving another purpose. Two of these features are the pressure and fire treated wood roof trusses and the precast plank structural system. The total project cost for the project is \$10.6 million. As seen above the fire protection system accounts for only 9.9% of that cost. Several reasons for the discrepancy in cost between actual and estimated are that the assembly's estimate includes equipment such as fire extinguishers and boxes, manual pull stations, and the emergency generator to which the emergency lighting is connected. Those pieces of the system account for roughly \$60,600. This is a very important system for the college as student safety ranks very high among the facilities department standards.



E. Detailed Structural System Estimate

Please See Appendix D for the Detailed Structural System Estimate

Residence Hall 2 is the second new dormitory that Ursinus College is building within the past 3 years. The previous dorm, Richter/North Hall, is located directly south of new site and has the exact structural system that Residence Hall 2 is using. This system uses cast in place continuous/strip footings, load bearing CMU walls, precast hollow core concrete plank, wood roof trusses, and minor structural steel. The construction of the superstructure began May 28, 2006 and is scheduled for completion on November 8, 2006.

The table on the next page highlights key features for the structural system and the cost associated with them. This estimate was produced while making several assumptions about the system itself.

Assumptions

- All concrete is 3000 psi
- All grout is 3000 psi
- Floors 2-4 are typical.
- Structural rebar reinforcement is a part of the concrete and masonry sections, they are not included in the metals section.
- Placement method is direct chute.
- Not all masonry was included because not all masonry is load bearing and a part of the structural system.
- No typical bay size was used for the precast hollow core plank.

Table 2 Detailed Structural Estimate Summary

Sitework		Quantity	Unit	Amount	Cost Per
Soil Excavation		328	CY	\$15,721.33	\$47.93/CY
	•				
Concrete					
Continuous Footing		208	CY	\$13,677.17	65.75/CY
SOG		152	CY	\$9,982.03	65.67/CY
PC Hollow Core					
Plank	(39,774.29	SF	\$187,209.64	\$4.70/SF
Masonry					
Mortar		70	CY	\$3,476.43	\$49.66/CY
8x8x16 Concrete					
Block		35,199	PCS	\$92,322.98	\$2.62/PC
Metals					
Structural Steel		17	Tons	\$35,767.34	\$2,103.96/Ton
Woods and Plastics					
Structural Roof			Total		
System	-	Trusses	Cost	\$48,796.81	
Thermal and					
Moisture					
		Ground	Total		
Waterproofing	I	Flr	Cost	\$13,162.51	
Finishes					
	- /	All	Total		
Gypsum/Nails/Paint		System	Cost	\$9,756.24	
Total Estimate				\$547,652.80	\$10.52/SF

This detailed estimate was produced using ICE 2000 Estimating. It is broken into the cost for concrete, steel, plank, and minor waterproofing for the ground floor CMU walls. Also included in this section is the tonnage of steel and total cubic yards for the structural system. For a further breakdown in major structural system costs please see Appendix D.



F. General Conditions Estimate

The general conditions estimate for Residence Hall 2 was provided by Warfel Construction Company (WCC). These numbers were then expanded upon to reach a final general conditions estimate for this project. Ice 2000 Estimating was used to gather further cost information for the general conditions. The general conditions estimate has many items not present due to other parties paying for them. Since this is on a college campus the college provides many items such as temporary internet and paying for permits. Another factor in the cost is WCC provides many items on there own. At the home office they have an equipment yard and also have many construction items for the multiple projects they are involved with. This is also a very simple design so the general conditions cost is not very high.

General Conditions Estimate Ursinus College Residence Hall 2 Warfel Construction company

Personnel	Comments	Weeks	Hours/Wk	Price
				\$
Project Manager	2 PM's For Job	56	30	67,200.00
	Cost Provided by			
Director of Field Operations	WCC	56	5	
	Cost Provided by			
Superintendent	WCC	56	40	
	Cost Provided by			
Foreman	wcc	56	40	
	Cost Provided by			
Building Surveyor	WCC	56	5	
	Cost Provided by			
Safety Director	WCC	56	10	
				\$134,400.0
Laborers	Average 6 on Job	56	40	0
				\$201,600.0
Subtotal Personnel				0

				\$123,635.0
Cost Provided by WCC				0
				\$325,270.0
Personnel Total				0
Temporary Facilities				
1 Jobsite Trailer	Cost Provided by WCC	56	40	\$ 6,000.00
Temporary Phone	Cost Provided by WCC Cost Provided by	56		\$ 1,875.00 \$
Temporary Toilets	WCC	56		2,250.00
WCC Fax		56		\$ 1,875.00
Temporary Stairs	Cost Provided by WCC	56		\$ 4,000.00
Cell Phone Useage	Cost Provided by WCC	56		\$ 3,750.00
Cost Provided by WCC				\$ 19,750.00
Tax @ 6%				\$ 1,185.00
Temp. Facility Total				\$ 20,935.00
Equipment Rental				\$
Large Equipment	Allowance			10,000.00
Crane	Precast Plank Erection	15 days	550/Day	\$ 8,250.00
Small Tools	Bought by Field	56		\$ 5,000.00
Temporary Lifts	Allowance	56		\$ 1,000.00
Subtotal				\$ 24,250.00
Tax @ 6%				\$ 1,455.00
Equip. Rental Total				\$ 25,705.00
Temporary Utilities				\$
Electric	Temporary Electric	56	40	1,160.00
Water	Temporary Water	56 56	40	\$ 450.00 \$ -
I Ethornot			40	.D -
Ethernet	By College	00		
Temp. Utility Total	By College	00		\$ 1,610.00
	By College	00		\$

Permitting	By Owner			
Temporary Job Fence	2000ft	56		\$ 24,000.00
				\$
Dumpster	1	56		15,000.00
Final Cleaning				\$ 14,492.00
Drinking Water		56		\$ 375.00
Fac. Subtotal				\$ 53,867.00
Tax @ 6%				\$ 3,232.02
Facility Costs Total				\$ 57,099.02
,				,
Miscellaneous Items				
Mileage	All Parties Traveling	56		\$ 3,422.00
Job Sign				\$ 390.00
Job Clean up		56	cost/SF	\$ 19,814.72
Miscellaneous Items(General)		56		\$ 7,000.00
				\$
Total Miscellaneous Items				30,626.72
Total Miscellaneous Items Tax @ 6%				30,626.72 \$ 1,837.60
				\$
Tax @ 6%				\$ 1,837.60 \$

This estimate comes in low as stated above. Possible reasons that were also stated above are that costs are being dispersed and are not getting charged to general conditions. The general conditions estimate is approximately 5% of the total project cost.





Appendix A

Detailed Project Schedule

URSINUS COLLEGE RESIDENCE HALL 2








ID T	Fask Name	Duration	Start	Finish		2006					2007		
	Final Landscaping	20 days	Mon 7/2/07	Fri 7/27/07	Sep Oct Nov D	ec Jan Fet	o Mar Apr Ma	ay Jun Jul	Aug Sep Oct	Nov Dec	Jan Feb Mar	Apr May Jun Jul Aug Se	p Oc
	Acoustical Ceiling Tile	65 days	Wed 1/17/07	Tue 4/17/07								Acoustical Ceiling Tile	caping
	HVAC System Start-up and Testing	35 days	Wed 5/9/07	Tue 6/26/07								HVAC System Start-	-up and T
	Final Inspections	12 days	Wed 6/27/07	Thu 7/12/07								Final Inspection	
I .	Punchlist	10 days	Mon 7/16/07	Fri 7/27/07								Punchlist	
	Owner Occupancy	0 days		Mon 7/30/07								7/30	
roject: D	retailedSchedule.mpp T 10/28/06	ask		Milestone	•	Rolled Up Task		Rolled Up Pi	rogress	External Tas	sks	Group By Summary	
٠,٥٥٠. ٥	10/28/06			0		Rolled Up Milest		Split		Project Sum	man,	Deadline	
ate: Sat	10/20/00 F	rogress		Summary		Rolled Up Milesi	one 🔻 🖯	JUIL		Project Sum	mary	Deadline 2.5	



Appendix B

Site Layout Plan For Superstructure





URSINUS COLLEGE RESIDENCE HALL 2

COLLEGEVILLE, PA
WARFEL CONSTRUCTION
WRT DESIGNS

RUSTY HOFFMAN, CM

COLOR KEY

Green = Storage

BROWN = DUMPSTER

BLUE = CRANE LOCATION
CYAN = TRAILER/TRUCKS

GRAY = ELECTRIC

LLOW - BOOTABLE TOUR

RED = SITE FENCE

NAVY BLUE = RES. HALL 2

TECHNICAL ASSIGNMENT #2

METHODS ANALYSIS
OCTOBER 30, 2006



Appendix C

Detailed Assemblies System Takeoff

Spec. Sec.	System Component	Quantity	Unit	Cost	Total Cost	Cost/SF
15500	Wet Sprinkler System	1 Floor	2000 SF	\$9,498.52		\$4.75
	Ground Floor	6,399 SF	Cost/10,000 SF	\$2.30	\$ 14,717.70	\$2.30
	First Floor	11,655 SF	Cost/10,000 SF	\$2.30	\$ 26,806.50	\$2.30
	Second Floor	11,580 SF	Cost/10,000 SF	\$2.30	\$ 26,634.00	\$2.30
	Third Floor	10,930 SF	Cost/10,000 SF	\$2.30	\$ 25,139.00	\$2.30
	Fourth Floor	11,580 SF	Cost/10,000 SF	\$2.30	\$ 26,634.00	\$2.30
				Total	\$119,931.20	\$2.30
15500	4" Wet Standpipe Riser	1	Cost/10' Floor	\$5,200	\$ 5,200.00	
13300	4" Wet Standpipe Add. Floor		Cost/10 Floor	\$1,500	\$ 4,500.00	
	· · · · · · · · · · · · · · · · · · ·		00001011001	Total	\$ 9,700.00	
15500	Single Extinguisher	13	Cost Each	\$191	\$ 2,483.00	
	Manual Pull Station	18	Cost Each	\$135	\$ 2,430.00	
				Total	\$ 4,913.00	\$0.09
15520	4"Dry Standpipes In Stairs	2	Cost/10' Floor	\$3,825	\$ 7,650.00	
	Each Additional Floor		Cost/10' Floor	\$1,410	\$ 8,460.00	
				Total	\$ 16,110.00	
16610	125kW Emergency Generator	1	Cost/kW	\$445.50	\$ 55,687.50	\$1.07
	3 y					·
		Total Fire	Protection Syste	m Cost	\$206,341.70	\$3.95



Appendix D

Detailed Structural System Estimate



Detailed Structural System Estimate

Structural Steel

Table 3 Shop Bill of Material #1

			Assembly	
No.	Shape	Length	Mark	Cost
				\$
2	L4x3.5x5/16	5'-4"	3L1	72.00
				\$
2	L4x3.5x5/16	4'	3L2	54.00
112	L4x3.5x5/16	4'-8"	3L3	\$3,158.00
		7 1 411		#0.400.00
30	LL6x4x.5	7'-4"	3ML3A	\$6,123.00
١ ,	LLCv4v5	01.411	OMI OD	\$
3	LL6x4x.5	9'-4"	3ML3B	779.00 \$
1	L6x4x.5	9'-4"	3ML4A	թ 130.00
<u>'</u>	LUX4X.J	3-4	SIVILAA	\$
2	L8x6x.75	7'-4"	3ML9A	Ψ 421.00
	LOXOXIIO		SIVILE) (121.00
28	PL 7.5x3/8	1'	BP1	\$2,631.00
		-		\$
10	PL 7.5x3/8	10"	BP2	918.00
6	W8x31	12'-8"	3B1	\$1,600.00
				\$
1	W8x35	12'	3B2	301.00
				\$
1	W8x21	14'-8"	3B3	223.00
	1440 04	4.01	0.004	\$
1	W8x31	12'	3B4	267.00
1	1/10/24	14'-8") 2DE	\$
	W8x31	14-0	3B5	327.00 \$
1	W8x31	20'	3B6	Ф 446.00
<u>'</u>	VVOAST	20	350	\$
2	W8x21	12'-8"	3B7	φ 591.00
	110/121	.20		\$
1	PL 14x3/8	20'	pa	519.00
· •		<u> </u>	F =	

2	PL 12x3/8	12'-8"	dq	\$ 601.00
3	W8x31	5'-3"	3B8	\$ 351.00
1	W8x10	5'-3"	3B9	\$ 39.00
3	W8x31	20'	3B10	\$1,337.00
1	W8x21	20'	3B11	\$ 304.00
4	W8x31	15'	3B12	\$1,070.00
3	TS12x8x5/8	16'5"	3B13	\$2,919.00
6	L4x4x.5	16'5"	aa	\$1,059.00
1	W12x35	16'5"	3B14	\$ 606.00

Table 4 Shop Bill of Material #2

			Assembly	
No.	Shape	Length	Mark	Cost
				\$
2	TS4x4x.5	4'-9.5"	1c1	215.00
				\$
2	PL5.5x3/4	10.5"	pa	146.00
				\$
2	PL6x3/4	10"	ba	105.00
١ ,	T000 5	12'-	4-0	\$
1	TS6x6x.5	1.25"	1c2	106.00 \$
1	DI 6x2/4	1'-1"	nh	т
<u> </u>	PL6x3/4	1-1	pb	299.00 \$
1	PL12x1	1'	bb	57.00
-	FLIZAI	<u> </u>	DD	\$
1	WT9x30	5.5"	wa	76.00
'	Wickes	0.0	Wa	\$
1	TS6x6x.5	2'-9.25"	1c3	154.00
				\$
1	PL6x.5	1'	pb	68.00
				\$
1	PL6x.5	10"	bb	146.00
				\$
1	WT6x6	2'-9"	wa	40.00
1	WT5x16.5	5.5"	wb	\$ 1.00
				\$
3	L6x4x.5	7'-4"	1ML3A	333.00
				\$
3	L6x4x.5	7'-4"		333.00

				\$
1	L6x4x.5	4'-8"	1ML3B	141.00
				\$
1	L6x4x.5	4'-8"	1L1	141.00
				\$
2	L4x3.5x5/16	5'-4"	1L2	72.00
				\$
2	L4x3.5x5/16	4'	1L3	54.00
				\$
1	L4x3.5x5/16	4'-8"	LP1	31.00
				\$
4	PL12x1/4	1'	LP2	235.00
				\$
2	PL6x1/4	10"		97.00
20	3/4" Anchor	1'-2"		\$3,283.00

Table 5 Shop Bill of Material #3

			Assembly	
No.	Shape	Length	Mark	Cost
		15'-		\$
1	W8x31	11.25"	2B1	355.00
				\$
2	L8x4x1/2	8'-2"	aa	275.00
				\$
1	W8x21	23'-6"	2B2	357.00
		12'-		\$
1	W8x31	1.25"	2B3	270.00
		13'-		\$
1	W8x21	2.25"	2B4	200.00
				\$
1	W8x21	7'-6"	ma	114.00
				\$
1	W8x31	12'-8"	2B5	282.00
				\$
1	TS8x6x3/8	10'-7"	2B6	243.00
				\$
1	PL10x3/8	9'-4"	pa	200.00
				\$
2	PL7.5x3/8	1'	BP1	108.00
				\$
6	PL7.5x3/8	10"	BP2	311.00

Concrete Detailed Takeoff

Concrete	Mark	Quantity	Unit	Price
Ground Floor				
Footing	CF20	10.52	CY	\$ 2,904
	CF30	19.11	CY	\$ 4,279.00
	CF36	14.77	CY	\$ 3,222.00
	CF40	26.07	CY	\$ 5,039.00
	CF46	26.07	CY	\$ 5,562.00
	CF46A	5.33	CY	\$ 1,093.00
	CF50	33	CY	\$ 5,856.00
Ground Floor SOG	4" Slab	6,399	SF	\$ 5,214.70
First Floor Footing	CF20	8.15	CY	\$ 2,230.00
	CF30	22	CY	\$ 4,887.00
	CF36	11.67	CY	\$ 2,545.00
	CF40	27.19	CY	\$ 5,268.00
First Floor SOG	4" Slab	5,850	SF	\$ 4,767.20

Precast Plank	Thickness	Size	Pieces	Price
				\$
1st Floor	8"	8'-7"	5	902.00
				\$
	8"	14'-6"	2	610.00
				\$
	8"	13'	2	547.00
				\$
	8"	16'-6"	5	1,735.00
		_		\$
	8"	17'	3	1,072.00
			_	\$
	8"	9'-5"	5	990.00
				\$
	8"	25'-5"	12	6,415.00
		401.01		\$
	8"	18'-8"	9	3,533.00
	0.11	001.011	40	# 40.405.00
	8"	26'-9"	18	\$10,125.00
	0"	401.01	_	\$
	8"	18'-8"	7	2,748.00
0 1 . 445 . 15	0"	401.011	0.4	\$
2nd-4th Floor	8"	18'-8"	21	8,096.00

				.
	8"	25'-5"	84	\$44,902.00
	8"	18'-8"	54	\$21,196.00
	8"	22'	24	\$11,103.00
	8"	21'-8"	22	\$10,023.00
	8"	27'-6"	20	\$11,277.00
	8"	9'-5"	33	\$ 6,537.00
	8"	25'-8"	37	\$19,970.00
	8"	26'-9"	54	\$30,375.00
	8"	16'-8"	21	\$ 7,359.00
Core Roof Area	8"	27'-6"	7	\$ 3,759.00
	8"	10'	4	\$ 841.00
	8"	23'	7	\$ 3,144.00
	8"	12'-6"	7	\$ 1,840.00
Total Concrete				
Cost				_267,158.16_

Masonry Detailed Takeoff

Masonry	Block Size			Price
Ground Floor	8x8x16	640	10ft	\$ 19,828.00
1st Floor	8x8x16	856	10ft	\$ 29,185.00
2nd-4th Floor	8x8x16	2,244	10ft	\$111,326.00
	PSI	CY		Price
Voids w/Concrete	3000	197.3		\$ 14,905.44
Voids w/Grout	3000	196.7		\$ 13,878.13
Scaffold				\$ 18,010.24
Total Masonry				\$157,290.41

Detailed Wood Takeoff

Wood and Plastics	Truss Mark	Quantity	Price		
Roof System	T1	42	\$22,189.00		
	T2	24	\$ 6,717.00		
	Т3	13	\$ 3,220.00		
	T4	1	\$ 134.00		
	T5	25	\$11,658.00		
	Т6	7	\$ 1,746.00		
	T7	32	\$12,587.00		
	T8	12	\$ 9,818.00		
	10	12	3,010.00		
Total System Estimate \$68,069.00					

• The following two pages are a printout of the estimate summary organized in CSI Uniformat from ICE 2000 Estimating.

5 / 11 MPJ T	
Detail - With Taxes and Insurance	Group 1: Divisions
Estimator : Project Size : sqft	
ItemCode Description Quantity UM Lab.Unit Mat.Unit Eqp.Unit Sub	ıb.Unit Eqp.Rent.Unit Temp.Mat.Unit Other Unit Tot.UnitCost TotalCost
Sitework	0.405
02316.001 FINE GRADE FLOOR BY HAND 12,249.00 SQFT 0.4046 02316.022 WASHED GRAVEL SLAB FILL 226.83 CUYD 16.1864 5.120	0.405 4,955.95 21.306 4,833.00
02316.100 MACH EXCAV CONTINUOUS FTG 327.74 CUYD 6.9549 0.950 02316.102 FINE GRADE CONTINUOUS FTG 4,740.00 SQFT 0.4761	7.905 2,590.76 0.476 2,256.71
02316.130 MACH BACKFILL CONTINUOUS FTG 120.54 CUYD 8.5005 0.500	9.001 1,084.91
02316.134 EXCESS CONTINUOUS FOOTING SOIL 207.20 CUYD * Total Sitework	15,721.33
Concrete	
03110.510 CONTINUOUS FOOTING EDGE FORMS 3,111.73 SQFT 4.4257 1.039 03150.650 SCREEDS FOR SLAB 1,469.88 LNFT 0.9219 0.320	5.464 17,003.75 1.242 1,825.44
03210.200 CONTINUOUS FOOTING REBAR 106.08 CWT 31.7857 26.750	58.536 6,209.66
03220.011 6x6 W2.1/W2.1 MESH 134.74 SQS 22.0080 10.650 03310.150 **CONC IN CONTINUOUS FOOTING** *****	32.658 4,400.31
03310.151 3000 PSI DIRECT 207.20 CUYD 11.0090 55.000 03310.350 **CONC IN SLAB ON GRADE** *****	66.009 13,677.17
03310.351 3000 PSI DIRECT 151.22 CUYD 11.0090 55.000 03315.971 *CONTINUOUS FOOTING LENGTH * 1,368.00 LNFT	66.009 9,982.03
03315.976 * SOG AREA * 12,249.00 SQFT	0.075
03350.132 FLOAT FINISH 12,249.00 SQFT 0.2754 03350.143 TROWEL FINISH TOPPING 39,774.29 SQFT 0.3442 0.077	0.275 3,373.37 0.421 16,744.98
03390.010 PROTECT & CURE 12,249.00 SQFT 0.1102 0.019 03390.010 PROTECT & CURE 39,774.29 SQFT 0.1102 0.019	0.129 1,585.02 0.129 5,146.79
03410.105 PC HOLLOW CORE PLANK 39,774.29 SQFT 1.1228 3.584	4.707 187,209.64
* Total Concrete	267,158.16
Masonry 04210.011 MORTAR 69.53 CUYD 50.000	50.000 3,476.43
04210.581 ADD FOR VEE CUT 31,608.00 SQFT 0.2280 04219.101 EXTERIOR TUBULAR SCAFFOLDING 31,608.00 SQFT 0.4698 0.100	0.228 7,206.62 0.570 18,010.24
04219.990 * MASONRY WALL AREA * 31,608.00 SQFT	·
04220.102 FILL VOIDS W/ CONCRETE 197.29 CUYD 20.5520 55.000 04220.106 FILL VOIDS W/GROUT 196.71 CUYD 20.5520 50.000	75.552 14,905.44 70.552 13,878.13
04220.502 8X8X16 CONC BLOCK 35,198.82 PCS 1.9929 0.630 04224.122 MASONRY REBAR 158.36 CWT 20.5520 26.750	2.623 92,322.98 47.302 7,490.56
* Total Masonry	157,290.41
Metals 05129.101 STEEL BEAMS ****	
05129.102 I BEAMS 110.25 CWT 28.7300 35.000 5.000	68.730 7,577.72
05129.106 STRUCTURAL TUBING 36.75 CWT 38.3067 35.000 5.000 05129.121 STEEL COLUMNS *****	78.307 2,878.00
05129.125 STRUCTURAL TUBING 7.31 CWT 28.7300 35.000 5.000 05129.181 BRACING *****	68.730 502.58
05129.184 ANGLES 8.64 CWT 45.9680 35.000 10.000	90.968 785.91
05129.221 FLOOR ITEMS	
05129.222 I BEAMS 16.40 CWT 28.7300 35.000 5.000 05129.224 ANGLES 125.59 CWT 38.3067 35.000 10.000	68.730 1,126.98 83.307 10,462.56
05129.224 ANGLES 20.23 CWT 38.3067 35.000 10.000 05129.225 TEES 2.26 CWT 38.3067 35.000 10.000	83.307 1,685.32 83.307 188.03
05129.227 STRUCTURAL TUBING 3.45 CWT 28.7300 35.000 5.000	68.730 236.98
05129.304 ASTM A572 50 KSI STEEL ADDER 117.95 CWT 05129.501 SHOP PAINT ****	
05129.501 SHOP PAINT ***** 05129.505 TYPE A PAINT 3,482.73 SQFT 0.0990 0.154	0.253 879.74
05129.505 TYPE A PAINT 201.49 SQFT 0.0990 0.154	0.253 50.90
05129.601 ANCHOR BOLTS, 3/4"X14" 120.00 EACH 7.6080 5.608 05129.601 ANCHOR BOLTS, 3/4"X6" 152.00 EACH 7.6080 2.403	13.216 1,585.90 10.011 1,521.72
05129.700 BASE PLATE 10"X5"X3/4" 2.00 EACH 35.3600 6.762 05129.700 BASE PLATE 10"X6"X1/4" 2.00 EACH 35.3600 2.342	42.122 84.24 37.702 75.40
05129.700 BASE PLATE 10"X6"X3/4" 2.00 EACH 35.3600 7.025	42.385 84.77
05129.700 BASE PLATE 10"X7"X3/8" 16.00 EACH 35.3600 4.449 05129.700 BASE PLATE 11"X10"X3/8" 1.00 EACH 35.3600 66.443	39.809 636.95 101.803 101.80
05129.700 BASE PLATE 12"X12"X1" 1.00 EACH 35.3600 22.481 05129.700 BASE PLATE 12"X12"X1/4" 4.00 EACH 35.3600 5.620	57.841 57.84 40.980 163.92
05129.700 BASE PLATE 12"X7"X3/8" 30.00 EACH 35.3600 5.339	40.699 1,220.98
05129.700 BASE PLATE 12"X8"X1/2" 30.00 EACH 35.3600 7.494 05129.700 BASE PLATE 13"X6"X3/4" 1.00 EACH 35.3600 9.133	42.854 1,285.61 44.493 44.49
05129.700 BASE PLATE 15"X12"X3/8" 2.00 EACH 35.3600 108.208 05129.700 BASE PLATE 24"X14"X3/8" 1.00 EACH 35.3600 199.330	143.568 287.14 234.690 234.69
05129.700 BASE PLATE 33"X6"X1/2" 2.00 EACH 35.3600 15.573	50.933 101.87
05129.710 BASE PLATE GROUT 114.31 SQFT 6.1715 5.760 05129.715 1/4" STEEL BP TEMPLATE 94.00 EACH 5.760	11.932 1,363.88 5.760 541.44

Estimate Detail - Standard Construction Project

Detail - With Taxes and Insurance	Group 1: Divisions
Estimator : Project Size : sqft	

ItemCode Description	Quantity UM	Lab.Unit	Mat.Unit	Eqp.Unit	Sub.Unit Eqp.Rent.Unit Temp.Mat.Unit	Other Unit Tot.UnitCost	TotalCost	
05129.990 * STRUCTURAL STEEL WEIGHT * 05129.990 * STRUCTURAL STEEL WEIGHT * 05129.991 * NO. OF BASE PLATES * * * Total Metals Wood and plastics 06110.140 NAILS & ROUGH HARDWARE 06110.400 TRUSS 9 /12 PITCH 10' O" 06110.400 TRUSS 9 /12 PITCH 17' O" 06110.400 TRUSS 9 /12 PITCH 27' O" 06110.400 TRUSS 9 /12 PITCH 27' O" 06110.400 TRUSS 9 /12 PITCH 8' O" 06110.420 FLAT TRUSS 40' O" 06110.420 FLAT TRUSS 8 'O" 06110.420 FLAT TRUSS 8 'O" 06110.503 * WOOD ROOF AREA *	97.32 LBS 80.00 EACH 96.00 EACH 86.00 EACH 51.00 EACH 32.50 EACH 19.00 EACH 7.00 EACH 7.790.50 SQFT	69.5914 69.5914 69.5914 69.5914 69.5914 60.8925 60.8925	1.088 42.560 72.352 110.656 114.912 34.048 158.464 31.693			1.088 112.151 141.943 180.247 184.503 103.639 219.357 92.585	35,767.34 105.89 8,972.11 12,207.13 9,192.62 5,996.36 1,969.15 1,535.50 92.59	
06160.179 5/8" CDX PLYWOOD @ ROOF	560.00 SQFT	0.2246	0.750			0.975	545.78	
06160.181 3/4" CDX PLYWOOD @ ROOF * Total Wood and plastics	9,172.13 SQFT	0.2418	0.650			0.892	8,179.70 48,796.81	
Thermal and moisture protection 07140.011 WATERPROOFING ON MASONRY 07210.040 2" foundation insulation 07210.091 3-1/2" BATT INSULATION 07260.012 6MIL VISQUEEN SUBGRADE PAPER 07310.100 ASPHALT SHINGLES 07310.140 15 LB FELT 432 SQFT ROLL 07310.800 ROOFING NAILS 07530.011 MEMBRANE ROOFING * Total Thermal and moisture protection Finishes	3,526.00 SQFT 52.12 SQFT 9,732.13 SQFT 134.74 SQS 97.08 SQS 22.53 ROLL 97.08 LBS 0.24 SQS	0.4983 0.6476 1.1018 32.9250 14.9240 699.6000	0.358 0.499 2.900 30.707 12.480 1.267 100.000		0.250	0.857 1.147 0.250 4.002 63.632 27.404 1.267 799.600	3,020.72 59.78 2,433.03 539.20 6,177.49 617.36 123.02 191.90 13,162.51	
09250.432 5/8" FIRECODE GYP BD @ CEILING	7,790.50 SQFT		0.650			0.650	5,063.83	
09250.500 NAILS FOR GYPSUM BOARD 09250.520 HANG GYPSUM BOARD @ CEILING 09250.550 FINISH GYPSUM BOARD @ CEILING 09970.101 FIELD PAINT	77.91 LBS 7,790.50 SQFT 7,790.50 SQFT	0.2252 0.3660	0.768			0.768 0.225 0.366	59.83 1,754.42 2,851.32	
09970.105 TYPE A PAINT * Total Finishes Total Estimate	98.54 SQFT	0.1188	0.154			0.272	26.84 9,756.24 547,652.80	