


Wellington Condominiums

*Exton, PA* Spring Thesis Research BUILIDING FOR THE FUTURE

# **D.2** Appendix

The following appendix references that are attached for further research support are listed as followed:

- Detailed Project Schedule
- D4 Cost Estimate
- Assemblies Estimate
- Structural Systems Estimate
- General Conditions
- Site Plan with Utilities
- Superstructure Phased Site Plan
- Hambros Joist Composite Deck System Comparison Chart
- Geotechnical Test Boring Results
- PCA MAT® Contours and Analysis
- Crane Selection Information



					Wellington Condominiums Detailed Project Schedule
ID 31	Task Name Pan stair shops	Duration 20 days	Start Thu 8/3/06	Finish Thu 8/31/06	Aug '  Sep '  Oct '  Nov '  Dec '  Jan '  Feb '  Mar '  Apr '  May '  Jun '  Jul '0  Aug '  Sep '  Oct '  Nov '  Dec '  Jan '  Feb '  Mar '  Apr '  May '  Jun '  Jul '0  Aug '  Sep '  Oct '  Nov '  Dec '  Jan '  Feb '  Mar '  Apr '  May '  Jun '  Jul '0  Aug '  Sep '  Oct '  Nov '  Dec '  Jan '  Feb '  Mar '  Apr '  May '  Jun '  Jul '0  Aug '  Sep '  Oct '  Nov '  Dec '  Jan '  Feb '  Mar '  Apr '  May '  Jun '  Jul '0  Aug '  Sep '  Oct '  Nov '  Dec '  Jan '  Feb '  Mar '  Apr '  May '  Jun '  Jul '0  Aug '  Sep '  Oct '  Nov '
31	Pari star snops	20 days	110 0/3/00	1110 0/31/00	<b>Pan stair shops</b>
32	Sprinkler shops	40 days	Wed 12/7/05	Tue 1/31/06	Sprinkler shops
33					
34	Fabrication	265 days	Mon 1/30/06	Mon 2/5/07	
35	Storm Sewer Structure	5 days	Mon 1/30/06	Fri 2/3/06	Storm Sewer Structure
36	Panels	30 days	Thu 7/27/06	Thu 9/7/06	A construction of the second sec
37	Trusses	40 days	Thu 9/21/06	Thu 11/16/06	Trusses
38	Hambro Joists	25 days	Thu 8/3/06	Thu 9/7/06	t tambro eoists
39	Balconette fab	40 days	Mon 12/11/06	Mon 2/5/07	4Balconette fab
40	Elevator shop drwg review	2 days	Thu 3/2/06	Mon 3/6/06	Elevator shop drwg review
41	Elevator permit	20 days	Mon 3/6/06	Mon 4/3/06	
42	Elevator fab	65 days	Thu 11/2/06	Thu 2/1/07	
43	Pan stair fab	20 days	Thu 8/31/06	Thu 9/28/06	u and a stair fab
44	Sprinkler & Water service material	15 days	Wed 2/1/06	Tue 2/21/06	Sprinkler & Water service material
45					
46	Construction	340 days	Mon 1/16/06	Fri 5/4/07	
47					
48	Exterior, shell	335 days	Mon 1/16/06	Fri 4/27/07	Exterior, shell
49	Sitework	49 days	Mon 1/16/06	Thu 3/23/06	
50	Clear & grub	5 days	Mon 1/16/06	Fri 1/20/06	
51	Strip topsoil	5 days	Mon 1/23/06	Fri 1/27/06	Strip topsoil
52	Parking lot	39 days	Mon 1/30/06	Thu 3/23/06	Parking lot
53	Fill Parking Lot	35 days	Mon 1/30/06	Fri 3/17/06	Fill Parking Lot
54	Curb Parking Lot	2 days	Mon 3/20/06	Tue 3/21/06	Curb Parking Lot
55	Stone subgrade parking lot	1 day	Wed 3/22/06	Wed 3/22/06	Stone subgrade parking lot
56	Binder Parking Lot	1 day	Thu 3/23/06	Thu 3/23/06	Binder Parking Lot
57	Township approval for bulk excave	1 day	Mon 1/16/06	Mon 1/16/06	Township approval for bulk excavation
58	Security Fence	2 days	Thu 1/26/06	Fri 1/27/06	Security Fence
59	Bulk Excavation	10 days	Mon 1/30/06	Fri 2/10/06	Bulk Excavation
60	Boulder Removal	13 days	Mon 2/6/06	Wed 2/22/06	Boulder Removal
			· · · · · · · · · · · · · · · · · · ·	l	
	ct: Wellington Condominiums			Progress	Summary External Tasks Deadline
Date:	10/30/06 Split			Milestone	Project Summary     External Milestone
					Page 2

					Wellington Condominiums Detailed Project Schedule
	Task Name	Duration	Start	Finish A	ugʻ Sep' Oct' Nov' Dec' Jan' Feb <sup>*</sup>  Mar' Apr' May' Jun' Julʻ0 Augʻ Sep' Oct' Nov' Dec' Jan' Feb <sup>*</sup>  Mar' Apr' May' Jun' Julʻ0 Augʻ Sep' Oct' Nov
61	Dewatering pipe	5 days	Thu 2/23/06	Wed 3/1/06	Dewatering pipe
62	Storm Sewer	6 days	Thu 2/23/06	Thu 3/2/06	Storm Sewer
63	Substructure	146 days	Wed 2/22/06	Wed 9/13/06	
64	Foundation & Columns	30 days	Mon 3/13/06	Fri 4/21/06	
65	Spread and Column Footing I	2 days	Mon 3/13/06	Tue 3/14/06	Spread and Column Footing Layout
66	Spread Footing Rebar and Co	5 days	Mon 3/13/06	Fri 3/17/06	Spread Footing Rebar and Concrete Placement
67	Column Footing Rebar and C	10 days	Fri 3/17/06	Thu 3/30/06	Column Footing Rebar and Concrete Plecement
68	Foundation Wall Formwork Pl	5 days	Mon 3/27/06	Fri 3/31/06	Foundation Wall Formwork Placement
69	Foundation Wall Rebar and C	10 days	Wed 3/29/06	Tue 4/11/06	Foundation Wall Rebar and Concrete Placement
70	Foundation Columns Formwo	10 days	Fri 4/7/06	Thu 4/20/06	Foundation Columns Formwork Plagement
71	Foundation Columns Rebar a	10 days	Mon 4/10/06	Fri 4/21/06	Foundation Columns Rebar and Concrete Placement
72	Elevator Jack Holes	5 days	Mon 4/3/06	Fri 4/7/06	Elevator Jack Holes
73	Under-slab drainage system & sto	5 days	Mon 4/17/06	Mon 4/24/06	under-slab drainage system & ston∳ subgrade
74	Sprinkler and Domestic water serv	10 days	Wed 2/22/06	Tue 3/7/06	Sprinkler and Domestic water service
75	Garage Slab	5 days	Mon 4/24/06	Fri 4/28/06	
76	W.W.F. Layout	2 days	Mon 4/24/06	Tue 4/25/06	HW.W.F. Layout
77	Concrete Pour Bay 1	1 day	Wed 4/26/06	Wed 4/26/06	Concrete Pour Bay 1
78	Concrete Pour Bay 2	1 day	Thu 4/27/06	Thu 4/27/06	Concrete Pour Bay 2
79	Concrete Pour Bay 3	1 day	Fri 4/28/06	Fri 4/28/06	Concrete Pour Bay 3
80	Transfer Slab	65 days	Thu 6/1/06	Wed 8/30/06	
81	Formwork Placement and Sh	17 days	Thu 6/1/06	Fri 6/23/06	Formwork Placement and Shoring
82	Rebar Placement	18 days	Mon 6/26/06	Wed 7/19/06	
83	Concrete Pour Bay 1	10 days	Thu 7/20/06	Wed 8/2/06	Concrete Pour Bay 1
84	Concrete Pour Bay 2	10 days	Thu 8/3/06	Wed 8/16/06	
85	Concrete Pour Bay 3	10 days	Thu 8/17/06	Wed 8/30/06	Concrete Pour Bay 3
86	Foundation waterproofing	5 days	Mon 4/24/06	Fri 4/28/06	Foundation waterproofing
87	Footing, downspout & condensate	10 days	Mon 5/1/06	Fri 5/12/06	Footing, downspout & condensite drains
88	Backfill	10 days	Thu 8/31/06	Wed 9/13/06	
89	Superstructure	172 days	Thu 8/31/06	Fri 4/27/07	
90	Panels and Hambro, floors 1-4	50 days	Thu 9/7/06	Wed 11/15/06	Panels and Hambro, floors 1-4
	t: Wellington Condominiums 10/30/06 Solit			Progress	Summary     External Tasks     Deadline     Project Summary     External Milestone
	Split			Milestone	Project Summary     External Milestone

					Wellington Condominiums Detailed Project Schedule
ID	Task Name	Duration	Start		Aug 'Sep 'Oct 'Nov 'Dec 'Jan 'Feb 'Mar' Apr' May Jun 'Jul 'Aug 'Sep 'Oct 'Nov 'Dec 'Jan 'Feb 'Mar' Apr' May Jun 'Jul 'Aug 'Sep 'Oct 'Nov
91	1st floor panels	5 days	Thu 9/7/06	Wed 9/13/06	1st floop panels
92	2nd floor deck	10 days	Thu 9/14/06	Wed 9/27/06	and foor deck
93	2nd floor panels	5 days	Thu 9/28/06	Wed 10/4/06	2nd floor panels
94	3rd floor deck	10 days	Thu 10/5/06	Wed 10/18/06	
95	3rd floor panels	5 days	Thu 10/19/06	Wed 10/25/06	3rd floor panels
96	4th floor deck	10 days	Thu 10/26/06	Wed 11/8/06	th floor deck
97	4th floor panels	5 days	Thu 11/9/06	Wed 11/15/06	the floor panels
98	Masonry shafts	16 days	Thu 8/31/06	Thu 12/7/06	Masonry shafts
99	Pan stairs	30 days	Thu 9/28/06	Tue 1/9/07	Pan stairs
100	Roof Trusses & Decking	20 days	Thu 11/16/06		Roof Trusses & Decking
101	Flat Roofing & Felt Paper	20 days	Thu 12/14/06		Flat Roofing & Felt Paper
102	Electrical Service	15 days	Thu 1/11/07	Wed 1/31/07	
103	Shingle Roofing	30 days	Mon 3/12/07	Fri 4/20/07	Shingle Roofing
104	Windows and Exterior Doors	20 days	Thu 10/5/06	Thu 12/7/06	Windows and Exterior Doors
105	Elevator installation	40 days	Thu 2/1/07	Wed 3/28/07	Elevator installation
106	Arriscraft & Brickwork	80 days	Mon 1/8/07	Fri 4/27/07	
107	First Floor Arriscraft & Brickw	-	Mon 1/8/07	Fri 2/2/07	First Floor Arriscraft & Brickwork
108	Second Floor Arriscraft & Brid	_	Mon 2/5/07	Fri 3/2/07	Second Floor Arriscraft & Brickwork
109	Third Floor Arriscraft & Bricky		Mon 3/5/07	Fri 3/30/07	Third Floor Arriscraft & Brickwork
110	Forth Floor Arriscraft & Bricky		Mon 4/2/07	Fri 4/27/07	Forth Floor Arriscraft & Brickwork
111	Install balconettes	60 days	Mon 2/5/07	Fri 4/27/07	
112	Second Floor Balconettes	20 days	Mon 2/5/07	Fri 3/2/07	Second Floor Balconettes
113	Third Floor Balconettes	20 days	Mon 3/5/07	Fri 3/30/07	
114	Forth Floor Balconettes	20 days	Mon 4/2/07	Fri 4/27/07	Forth Floor Balconettes
115	Soffits and Trim	20 days	Mon 3/26/07	Fri 4/20/07	Soffits and Trim
116	Gutters & Downspouts	10 days	Thu 4/12/07	Wed 4/25/07	Gutters & Downspouts
117	Interior shell only	10F dovr	Thu 0/20/00	Wod 2/21/07	
118	Interior, shell only Partitions, non-load bearing	125 days	Thu 9/28/06 Thu 9/28/06		Interior, shell only
	·	80 days			
120	First Floor, non-load bearing	20 days	Thu 9/28/06	Wed 10/25/06	First Floor, non-load bearing
		<b>B</b>		Deserves	Summary External Tasks Deadline
Projec Date: 1	t: Wellington Condominiums 10/30/06 Split			Progress Milestone	Summary     External Tasks     Deadline
				-	Page 4

						Wellin	gton Co	ndomir	niums D	Detaile	d Projec	ct Sch	edule								
	Task Name	Duration	Start		Aug '	Sep ' O	ct ' No	v ' Dec	' Jan '	Feb	' Mar '	Apr '	May '	Jun '	Jul '0	Aug ' S	Sep ' C	Oct ' No			an '   Feb '   Mar '   Apr '   May '   Jun '   Jul '0   Aug '   Sep '   Oct '   Nov
121	Second Floor, non-load bearing	20 days	Thu 10/26/06	Wed 11/22/06															Se	cond	Floor, non-load bearing
122	Third Floor, non-load bearing	20 days	Thu 11/23/06	Wed 12/20/06														1111111111111111	Ú.	Thi	rd Floor, non-load bearing
123	Forth Floor, non-load bearing	20 days	Thu 12/21/06	Wed 1/17/07														WWWWWW		Ţ.	Forth Floor, non-load bearing
124	MEP rough-in & Distribution	80 days	Thu 11/9/06	Wed 2/28/07																	
125	First Floor MEP rough-in	10 days	Thu 11/9/06	Wed 11/22/06															Fir	st Flo	or MEP rough-in
126	First Floor Distribution	10 days	Thu 11/23/06	Wed 12/6/06														wawan	ф	First I	oor Distribution
127	Second Floor MEP rough-in	10 days	Thu 12/7/06	Wed 12/20/06														THINTING	l	Se	cond Floor MEP rough-in
128	Second Floor Distribution	10 days	Thu 12/21/06	Wed 1/3/07														anvaanvaa		<b>Þ</b>	Second Floor Distribution
129	Third Floor MEP rough-in	10 days	Thu 1/4/07	Wed 1/17/07														WINNIN			Third Floor MEP rough-in
130	Third Floor Distribution	10 days	Thu 1/18/07	Wed 1/31/07														VIINVIINVI			
131	Forth Floor MEP rough-in	10 days	Thu 2/1/07	Wed 2/14/07														111241112411			Forth Floor MEP rough-in
132	Forth Floor Distribution	10 days	Thu 2/15/07	Wed 2/28/07														WIIIWWIIW			Forth Floor Distribution
133	Drywall & Finishing	40 days	Thu 1/11/07	Wed 3/7/07														<u>an</u> tanan a			
134	First Floor Drywall & Finishing	10 days	Thu 1/11/07	Wed 1/24/07														INVENTIVALINA			First Floor Drywall & Finishing
135	Second Floor Drywall & Finishing	10 days	Thu 1/25/07	Wed 2/7/07														WINWIN			Second Floor Drywall & Finishing
136	Third Floor Drywall & Finishing	10 days	Thu 2/8/07	Wed 2/21/07														IIIWAIIWAII			Third Floor Drywall & Finishing
137	Forth Floor Drywall & Finishing	10 days	Thu 2/22/07	Wed 3/7/07														WRITERIUS.			Forth Floor Drywall & Finishing
138	Paint	30 days	Thu 2/1/07	Wed 3/14/07														VIINVIINVI			Paint
139	Doors, Frames, Hardware	30 days	Thu 2/8/07	Wed 3/21/07														INVERVENTIN			Doors, Frames, Hardware
140	<b>F</b> 1.55			<b>-</b>														WINWIINWA.			
141	Exterior	55 days	Mon 2/19/07	Fri 5/4/07														WYNWYNW			Exterior
142 143	Site lighting, rough-in Sidewalks	10 days	Mon 2/19/07	Mon 3/5/07														annaanna.			Site lighting, rough-in
143	Pavers	10 days	Mon 3/5/07 Mon 3/19/07	Fri 3/16/07 Fri 3/30/07														IIIWWWW		-	Sidewalks
144	Paving	10 days	Mon 4/2/07	Fri 4/13/07														ATTINTTINA			Pavers
145	Landscaping	15 days	Mon 4/16/07	Fri 5/4/07														IIIWIIIWIII			Landscaping
140	Landoodping	10 00/5	Won 4/10/07	110,401														WAINAAINA			Lanuscapiny
147	FITOUT	95 davs	Thu 11/16/06	Wed 3/28/07																	FITOUT
140		oo uuya																mannan			
150	Phase 1	77 davs	Thu 11/16/06	Fri 3/2/07														wiinwiinw			Phase 1
																		ALLWALL			
	Tor!			Prograss				<b>.</b>	mmorr						Evet-	rnal Tas	ke			_	Deadline 🗸
Projec Date: 1	t: Wellington Condominiums 10/30/06 Split			Progress Milestone		• • • • • • • • • • • • • • • • • • •			mmary oject Su		ry 👅					rnai Tas rnal Mile					
					•				Page		· •			*				*			

							-		domin			-										
ID 51	Task Name FRAMING & BLOCKING, 1	Duration 7 days	Start Thu 11/16/06	Finish Fri 11/24/06	Aug '	Sep '	Oct '	Nov	Dec	' Jan	' Feb	o ' Mar	Apr '	May	/ ' Jun	' Jul	'0 Au	g' Sep	o '   Oct '			an '   Feb '  Mar '   Apr '   May '   Jun '   Jul '0   Aug '   Sep '  Oct '   N
52	MEP ROUGH, 1	7 days	Thu 1/11/07	Fri 1/19/07																		MEP ROUGH, 1
53	INPECTION, FITOUT, ROUGH, 1	0 days	Fri 1/19/07	Fri 1/19/07																anvanvan		INPECTION, FITOUT, ROUGH, 1
54	INSULATION, 1	1 day	Mon 1/22/07	Mon 1/22/07																WINNIN	[	
55	DRYWALL, 1	5 days	Mon 1/22/07	Fri 1/26/07																//////////////////////////////////////		DRYWALL, 1
56	TAPE & FINISH, 1	5 days	Mon 1/29/07	Fri 2/2/07																INVERTIME		TAPE & FINISH, 1
57	PAINT, SPRAY, 1	3 days	Mon 2/5/07	Wed 2/7/07																WIINWIIN		PAINT, SPRAY, 1
58	DOORS, TRIM, CABINETS, 1	10 days	Thu 2/8/07	Wed 2/21/07																minana		DOORS, TRIM, CABINETS, 1
59	FLOORING, 1	10 days	Mon 2/12/07	Fri 2/23/07																(1)/(1)/(1)		FLOORING, 1
60	MEP FINISH, 1	5 days	Thu 2/22/07	Wed 2/28/07																NTINTTIN		MEP FINISH, 1
61	INSPECTION, FITOUT, FINAL, 2	0 days	Wed 2/28/07	Wed 2/28/07																711177111771		2/28
62	APPLIANCES, 1	1 day	Wed 2/28/07	Wed 2/28/07																INVERSION		APPLIANCES, 1
53	PAINT, FINISH, 1	4 days	Mon 2/26/07	Thu 3/1/07																WINNIN		PAINT, FINISH, 1
64	PUNCHLIST, 1	1 day	Fri 3/2/07	Fri 3/2/07																11111111111		PUNCHLIST, 1
65																				www.www		
6	Phase 2	88 days	Mon 11/27/06	Wed 3/28/07																		Phase 2
67	FRAMING & BLOCKING, 2	7 days	Mon 11/27/06	Tue 12/5/06																	FRAM	ING & BLOCKING, 2
68	MEP ROUGH, 2	7 days	Mon 1/22/07	Tue 1/30/07																WIIIWIIIW		MEP ROUGH, 2
69	INPECTION, FITOUT, ROUGH, 2	0 days	Tue 1/30/07	Tue 1/30/07																annaanna.		INPECTION, FITOUT, ROUGH, 2
70	INSULATION, 2	1 day	Wed 1/31/07	Wed 1/31/07																INVERVEN		INSULATION, 2
1	DRYWALL, 2	5 days	Thu 2/1/07	Wed 2/7/07																WIIIWIIIW		DRYWALL, 2
2	TAPE & FINISH, 2	5 days	Thu 2/8/07	Wed 2/14/07																anaanaa		TAPE & FINISH, 2
73	PAINT, SPRAY, 2	3 days	Thu 2/15/07	Mon 2/19/07																INVIINVIIN		PAINT, SPRAY, 2
74	DOORS, TRIM, CABINETS, 2	10 days	Thu 2/22/07	Wed 3/7/07																WIINWIINW		DOORS, TRIM, CABINETS, 2
75	FLOORING, 2	10 days	Thu 3/8/07	Wed 3/21/07																4WWIIIWWII		FLOORING, 2
76	MEP FINISH, 2	5 days	Thu 3/22/07	Wed 3/28/07																WINWIN		MEP FINISH, 2
7	INSPECTION, FITOUT, FINAL, 2	0 days	Wed 3/28/07	Wed 3/28/07																4000000		3/28
78	APPLIANCES, 2	1 day	Wed 3/28/07	Wed 3/28/07																INVERSION		APPLIANCES, 2
'9	PAINT, FINISH, 2	4 days	Thu 3/22/07	Tue 3/27/07																WIINWIINW		PAINT, FINISH, 2
0	PUNCHLIST, 2	1 day	Wed 3/28/07	Wed 3/28/07																unwunwun		PUNCHLIST, 2
				Drogroop	_				0.							-	vto	Tasks				Deadline 🗸
rojec ate:	ct: Wellington Condominiums 10/30/06 Split			Progress Milestone		•				mmary oject S		ary							ione			
				-	-								·							~		

# **Estimate of Probable Cost**

	Wellington Condomin	iums Estimate - O	ct 2006 - PA - Allent	town	
	Prepared By:		Prepared For:		
	Fax: Building Sq. Size: Bid Date: No. of floors: No. of floors: Project Height: 1st Floor Height: 1st Floor Size: <b>29134</b>		Site Sq. Size: Building use: Foundation: Exterior Walls: Interior Walls: Roof Type: Floor Type: Project Type:	, Fax: 1807740 Residential CON MET SLA CON NEW	
Division		Percent	;	Sq. Cost	Amount
00	Bidding Requirements Bidding Requirements	<b>0.49</b> 0.49		<b>0.74</b> 0.74	<b>86,421</b> 86,421
01	General Requirements General Requirements	<b>11.48</b> 11.48		<b>17.23</b> 17.23	<b>2,005,168</b> 2,005,168
02	Site Work Site Work	<b>12.34</b> 12.34		<b>18.51</b> 18.51	<b>2,154,162</b> 2,154,162
03	Concrete Concrete	<b>9.25</b> 9.25		<b>13.88</b> 13.88	<b>1,615,254</b> 1,615,254
04	Masonry Masonry	<b>1.87</b> 1.87		<b>2.81</b> 2.81	<b>327,256</b> 327,256
05	Metals Metals	<b>2.25</b> 2.25		<b>3.38</b> 3.38	<b>392,830</b> 392,830
06	Wood & Plastics Wood & Plastics	<b>7.08</b> 7.08		<b>10.63</b> 10.63	<b>1,236,949</b> 1,236,949
07	Thermal & Moisture Protection Thermal & Moisture Protection	<b>1.80</b> 1.80		<b>2.70</b> 2.70	<b>314,027</b> 314,027
08	Doors & Windows Doors & Windows	<b>6.64</b> 6.64		<b>9.97</b> 9.97	<b>1,159,506</b> 1,159,506
09	Finishes Finishes	<b>15.61</b> 15.61		<b>23.42</b> 23.42	<b>2,724,936</b> 2,724,936
10	Specialties Specialties	<b>0.79</b> 0.79		<b>1.18</b> 1.18	<b>137,381</b> 137,381
11	Equipment Equipment	<b>1.40</b> 1.40		<b>2.10</b> 2.10	<b>243,768</b> 243,768
12	Furnishings Furnishings	<b>0.20</b> 0.20		<b>0.30</b> 0.30	<b>35,411</b> 35,411
13	Special Construction Special Construction	<b>0.57</b> 0.57		<b>0.86</b> 0.86	<b>99,921</b> 99,921
14	Conveying Systems Conveying Systems	<b>1.08</b> 1.08		<b>1.63</b> 1.63	<b>189,366</b> 189,366
15	<b>Mechanical</b> Mechanical	<b>18.08</b> 18.08		<b>27.14</b> 27.14	<b>3,157,420</b> 3,157,420
16	Electrical Electrical	<b>9.05</b> 9.05		<b>13.59</b> 13.59	<b>1,581,068</b> 1,581,068
Total Bui	Iding Costs	100.00		150.07	17,460,844

# **Estimate of Probable Cost**

	Prepared By:		Prepared For:		
	Baker Barrios Architect	ts, Inc.	•		
	300 South Orange Aver	nue Ste 900			
	Orlando, FL 32801			,	
	Fax:		0.14 0 0 0.1-0	Fax:	
	Building Sq. Size: 60000 Bid Date: 11/1/2003		Site Sq. Size:	435600 Residential	
	No. of floors: 4		Building use: Foundation:	PIL	
	No. of buildings: 1		Exterior Walls:	PRE	
	Project Height: <b>50.8</b>		Interior Walls:	MAS	
	1st Floor Height: <b>11.8</b>		Roof Type:	BUP	
	1st Floor Size: <b>15000</b>		Floor Type: Project Type:	CON NEW	
Division		Doroont	Project Type.		Amount
00	Bidding Requirements	Percent 0.31		Sq. Cost 0.30	Amount 18,000
	Permits	0.31		0.30	18,000
01	General Requirements	14.29		13.72	823,342
	Builder's Risk Insurance	0.12		0.12	7,000
	Building Permit Fees	0.43		0.42	25,000
	Change Orders	3.18		3.05	183,222
	Contractor's Fee	3.41		3.27	196,250
	Equipment Tools	0.14		0.13	8,050
	Field Labor, Safety, Clean-up Field Supervision	1.29 1.15		1.24 1.10	74,500 66,000
	General Conditions	1.15		1.10	65,700
	General Requirements	1.14		1.50	90,000
	Insurance (General Condition Items)	0.42		0.40	24,200
	MEP Consulting Fees	0.63		0.61	36,330
	MOT, Traffic Control	0.20		0.19	11,500
	Temporary Utilities	0.39		0.37	22,250
	Trash Removal/Hoisting	0.23		0.22	13,340
03	Concrete	36.01		34.58	2,074,734
	2nd FI Post Tension-1st FI Columns	4.25		4.08	245,000
	3rd FI Post Tension-2nd FI Columns	4.25		4.08	245,000
	4th FI Post Tension-3rd FI Columns Architectural Precast North Elevati	4.25		4.08	245,000
	on	2.60		2.50	150,000
	Architectural Precast South Elevati	2.60		2.50	150.000
	on Architectural Precast West Elevatio	2.60		2.50	150,000
	n	6.77		6.50	390,100
	Elevator Shaft	0.69		0.67	40,000
	Pile Caps/Foundations	3.47		3.33	200,000
	Retaining Wall	0.31		0.30	18,000
	Roof Post Tension-4th FI Columns	4.25		4.08	245,000
	Slab-On-Grade Stair Enclosures/Shear Wall	1.24 1.30		1.19 1.25	71,634 75,000
~ .					
04	Masonry Masonry	<b>1.04</b> 1.04		<b>1.00</b> 1.00	<b>60,000</b> 60,000
05	Madala	2.20		2.05	404 75
05	Metals Exterior Handrails	<b>3.38</b> 1.52		<b>3.25</b> 1.46	<b>194,75(</b> 87,750
	Metal Stairs (2)	1.52		1.08	65,000
	Misc. Metals	0.03		0.03	2,000
	Roof HVAC Screen Wall	0.69		0.67	40,000
06	Wood & Plastics	3.54		3.40	204,100
	Closets	0.22		0.21	12,650
	Millwork/Countertops	2.60		2.50	150,000
	Rough Carpentry-Blocking Wood Trim/Base	0.46 0.26		0.44 0.25	26,600 14,850
07	Thermal & Moisture Protection Balcony Coatings	2.32		2.23	133,535
	Balcony L'optinge	0.29		0.28	16,650

	Dampproofing/Caulking	0.49	0.47	28,3
	Modified Bituminous Roof System	1.54	1.47	88,4
08	Doors & Windows	4.72	4.54	272,2
	Aluminum Windows & Doors	2.67	2.57	153,9
	Doors, Frames & Hardware	1.63	1.56	93,8
	Mirrors	0.12	0.12	7,0
	Shower Doors	0.30	0.29	17,5
09	Finishes	15.89	15.26	915,3
	Carpet/VCT	1.08	1.03	62,0
	Drywall Floor Topping	4.06 0.38	3.90 0.37	234,0 22,0
	Metal Studs/Drywall/Plaster	4.76	4.58	274,5
	Painting	2.60	2.50	150,0
	Special Coating - Stain	0.12	0.12	7,1
	Stone Flooring	0.14	0.14	8,2
	Tile	0.78	0.75	45,0
	Wood Floor	1.95	1.88	112,5
10	Specialties	0.57	0.54	32,6
	Entrance Canopy	0.09	0.08	5,0
	Fire Extinguishers	0.02	0.02	1,0
	Lockers	0.03	0.03	1,8
	Mailboxes	0.07	0.07	4,0
	Signage Toilet Accessories	0.09 0.27	0.08 0.26	5,0 15,7
11	Equipment	1.28	1.23	73,6
••	Appliances	1.28	1.23	73,6
12	Furnishings	0.33	0.32	18,9
	Garage Entrance Door	0.23	0.23	13,5
	Trash Chute	0.10	0.09	5,4
14	Conveying Systems Elevator System	<b>0.95</b> 0.95	<b>0.92</b> 0.92	<b>55,0</b> 55,0
15	Mechanical	8.93	8.58	514,6
	Fire Protection	1.29	1.24	74,1
	Fixtures	0.43	0.42	25,0
	HVAC/Ductwork/Piping	3.73	3.58	215,0
	Plumbing	3.48	3.34	200,5
16	Electrical	6.44	6.18	370,9
	CATV/Audio/Music Distribution Panels	0.17	0.17	10,0
	Electrical	0.26 3.75	0.25 3.60	15,0 216,0
	Fire Alarm	0.17	0.17	10,0
	Panel Boards	0.26	0.25	15,0
	Rough-In/Wire/Conduit	1.82	1.75	104,9
Total Bu	uilding Costs	100.00	96.03	5,761,8
02	Site Work	100.00	0.88	381,3
	Asphalt Pavement/Striping	7.87	0.07	30,0
	Auger Cast Piling	38.20	0.33	145,6
	Building Demolition	4.89	0.04	18,6
	Chain Link Fence	0.79	0.01	3,0
	Concrete Sidewalks/Curbs	3.67	0.03	14,0
	Dewatering System	5.77	0.05	22,0
	Earthwork Gravity Wall	6.82	0.06	26,0
	Gravity Wall Landscape Irrigation	1.84 6.56	0.02 0.06	7,0 25,0
	Utilities	23.60	0.00	90,0
		100.00		
Total Si			0.88	381,3

Page 2

# **Estimate of Probable Cost**

## **Project Notes**

Eola South Residential Condominium - Nov 2003 - FL - Orlando

\* Orlando, Florida

\*\* Construction Period: Dec 2003 to Jan 2005

**Special Project Notes** 

Sited in downtown Orlando, at the edge of the Thornton Park residential fabric and immediately across the street from a high-rise/multi-family condominium, Eola South Condominium becomes an important element of scale and proportion. The four-story height of the building tempers the 10-story vertical element located across the street as it acts as a proper introduction and transition to the surrounding residential neighborhood.

Its character and design supports the nearby commercial and mixed use buildings. The increased density will support the new, burgeoning retail businesses while the streamlined contemporary design will create a sense of unity with the existing and growing new urban fabric. One of the primary considerations in the design was identifying a way to responsibly take advantage of the natural beauty of Lake Eola Park, located northwest of the building site.

The building program is issue driven and responds to the need for height, both as a transition and a way to take advantage of the view of Lake Eola and the surrounding green-space. Other identified issues that influenced the design were parking density, circulation, security of unit occupants, and the market ability of the units themselves based on current trends and developer philosophies.

The building design responds to the identified program issues by utilizing large glass expanses on the afternoon shaded western and northern elevations of the building. The fenestrations and massing interplay create a unique rhythm connecting the units to the streets below. The building units also feature large balconies, some of which are partially covered.

The building is constructed of cast-in-place concrete as it provided the best quality finish opportunities expected by the developer and prospective occupants. The majority of the units are sized to allow more moderate-income levels the opportunity to experience the downtown urban lifestyle becoming more prevalent in Orlando.

The overall design provides a sense of connectedness and unity to the surrounding urban fabric. The design results in positive interaction and interplay between the building residents and the surrounding neighbors and businesses, providing an expanded sense of community.

MANUFACTURERS/SUPPLIERS DIV 07: Roofing: Johns Manville. DIV 08: Window System, Entrances & Storefronts: Vistawall.

CONSTRUCTION TEAM

STRUCTURAL ENGINEER: Walter P. Moore and Associates, Inc. - 300 South Orange Avenue, #875, Orlando, FL 32801 GENERAL CONTRACTOR: Jennings Construction Services, LLC - 1030 Wilfred Drive, Orlando, FL 32803 ELECTRICAL & MECHANICAL ENGINEER: CHP & Associates Consulting Engineers, Inc. - 1051 Winderly Place, #101, Maitland, FL 32751

LANDSCAPE ARCHITECT: Lucido & Sole Design - 827 N. Thornton Avenue, Orlando, FL 32803

Photos Courtesy of Ray Acosta/Taina Benitez

\* Illustrations in the D4COST CD-ROM Architectural Library are reproduced, with permission, from the pages of Design Cost Data magazine, (c) DCD.

Unless noted otherwise illustrations are copyrights of the architectural firm in "Prepared By" on the Sources tab. Illustrations are for reference only and may not be reproduced by users of D4COST.

# **Estimate of Probable Cost**

		Convent & High S	School - Jan 20	02 - PA - Other		
	Prepared By:			Prepared For:		
		Perkins Eastman 1100 Liberty Avenue Pittsburgh, PA 15222			,_	
	Building Sq. Size: Bid Date:	Fax: 161428 1/1/2002		Site Sq. Size: Building use:	Fax: 3179880 Residential	
	No. of floors: No. of buildings: Project Height:	4 1 49		Foundation: Exterior Walls: Interior Walls:	EXT EXT GYP	
	1st Floor Height: 1st Floor Size:	9.8 46482		Roof Type: Floor Type: Project Type:	MEM WOD REN	
Division			Percent	1 10,000 1 9 90.	Sq. Cost	Amount
00	Bidding Requiren Bond	nents	<b>0.66</b> 0.66		<b>0.65</b> 0.65	<b>104,754</b> 104,754
01	General Requiren Scaffold at Cl	napel	<b>12.74</b> 0.31		<b>12.58</b> 0.31	<b>2,031,254</b> 49,815
	General Cond Fees	ditions	8.19 4.23		8.09 4.18	1,306,529 674,910
03	Concrete Building Cond	crete	<b>1.55</b> 1.07		<b>1.53</b> 1.06	<b>247,095</b> 170,704
		Concrete Underlayment	0.05 0.03		0.05 0.03	7,973 5,298
04	Patching Masonry		0.40 <b>2.54</b>		0.39 <b>2.51</b>	63,120 <b>404,712</b>
•••	•	airs - New Openings	0.71 1.66 0.17		0.71 1.64 0.17	113,826 264,038 26,848
05	Metals Structural Ste	el/Joists & Decking	<b>2.29</b> 1.72		<b>2.26</b> 1.70	<b>365,020</b> 274,800
	Miscellaneou		0.54 0.02		0.54 0.02	86,810 3,410
06	Wood & Plastics Rough Carpe	ntry	<b>9.73</b> 0.57		<b>9.61</b> 0.57	<b>1,552,040</b> 91,435
	Plywood Und Finish Carper	erlayment	0.73 2.71		0.72 2.68	116,719 432,412
		Woodwork (Casework)	2.06 2.97		2.04 2.94	328,766 474,296
07	Wood Labora	tory Casework	0.68 <b>1.97</b>		0.67 <b>1.94</b>	108,412 <b>313,593</b>
01	Waterproofing Membrane R	g	0.05		0.05 1.75	7,350 282,100
	Metal Roofing Roof Accesso		0.12 0.01		0.12 0.01	19,072 1,556
08	Caulking Doors & Windows	5	0.02 <b>8.62</b>		0.02 <b>8.52</b>	3,515 <b>1,375,241</b>
	Doors & Hard Storefront/Gla Metal Windov Decorative G	ass & Glazing vs	2.21 0.22 5.29 0.45		2.19 0.22 5.23 0.45	352,913 34,995 844,048 72,285
09	Fireproofing Finishes		0.45 <b>18.56</b>		0.44 <b>18.34</b>	71,000 <b>2 960 675</b>
03	Plaster - (Pate Drywall/Metal		0.40 10.73		0.40 10.60	<b>2,960,675</b> 64,513 1,711,424
	Acoustical Wa	all Panels Work Allowance	0.29 1.06		0.29 1.05	46,667 169,165
	Terrazzo (Pat Wood Floor 8		0.13 1.44		0.12 1.42	20,000 229,566

Total Si	te Costs	100.00	0.84	2,677,4
	Remote Garage	0.56	0.00	15,0
	Courtyard Improvements	5.60	0.05	150,0
	Underpinning	1.21	0.01	32,3
	Site Retaining Walls	0.46	0.00	12,4
	Relocation of Underground Pipelines	0.37	0.01	10,0
	Storm Drainage	0.86	0.01	22,9
	Relocation of Statues	0.13 0.67	0.00	3,4 18,0
	Site Concrete Trash Enclosure Fence	2.25 0.13	0.02 0.00	60,2 3 /
	Landscaping Site Concrete	4.93	0.04	132,0
	Asphalt Paving	2.17	0.02	58,7
	Excavation & Grading	9.66	0.08	258,
	Structural Demolition Phase 1a	17.35	0.15	464,4
	Demo/Salvage/ASB Abate Phase 1	53.78	0.45	1,439,9
02	Site Work	100.00	0.84	2,677,4
Total B	uilding Costs	100.00	98.81	15,949,9
	Light Allowance	0.18	0.18	29,:
	Electrical	11.57	11.44	1,845,
16	Electrical	11.76	11.62	1,875,
	HVAC	17.10	16.90	2,728,
	Fire Protection	2.34	2.31	373,
15	Plumbing	5.44	5.37	3, <b>90</b> 8,0 867,0
15	Mechanical	24.88	24.58	3,968,
14	Conveying Systems Elevator	<b>1.34</b> 1.34	<b>1.33</b> 1.33	<b>214,</b> : 214,:
	-			
13	Special Construction Fixed Auditorium Seating	<b>0.44</b> 0.44	<b>0.44</b> 0.44	<b>70,</b> 70,
	Floor Mats & Frames Window Treatment	0.03 0.17	0.03 0.17	4, 27,
12	Furnishings	0.20	0.20	31,
	Barber & Beauty	0.02	0.02	2,
	Residential Appliances	0.16	0.16	25,
	Food Service	1.52	1.50	242,
••	Projection Screens	0.01	0.01	2,3
11	Equipment	1.71	1.69	273,
	Stage Curtains	0.05	0.05	8,
	Folding & Portable Stages	0.16	0.15	24,
	Toilet Accessories	0.29	0.28	45,
	Fire Protection	0.03	0.03	4,
	Metal Lockers	0.13	0.12	20, 32,
	Impact-Resistant Wall Protection Signs Allowance	0.01 0.13	0.01 0.12	1, 20,
	Toilet Compartments	0.13	0.13	20,
	Visual Display Boards	0.03	0.03	5,
10	Specialties	1.02	1.01	162,
	Flooring Carpet/Resilient	2.18	2.16	348,
	Painting/High Performace Coatings	1.88	1.86	300,

## **Project Notes**

Convent & High School - Jan 2002 - PA - Other

\* Coraopolis, Pennsylvania

\*\* Construction Period: Mar 2002 to Aug 2003

\*\*\* LEED(R) GOLD PENDING

**Special Project Notes** 

The Franciscan nuns of the Felician Sisters Convent wanted to renovate their 70-year-old provincial house to feel less like an institution and more like a home. The community was living in two buildings: St. Joseph Hall, a 1960's infirmary building, and the 1930's motherhouse, which also housed Our Lady of the Sacred Heart High School.

Perkins Eastman completed a master planning study and the Sisters decided to renovate the motherhouse and consolidate the community under one roof. As such, the existing building plan was not workable as an assisted living facility. The elderly Sisters' bedrooms were too far from existing gang bathrooms, which were too small to negotiate with walkers or wheelchairs. The building systems had not been upgraded since the 1930's, there were no individual temperature controls, and the existing partitions contained asbestos. The building needed to be gutted, yet doing so would jeopardize the very reason for renovating the motherhouse.

With full community participation, Perkins Eastman re-configured the 150,000-square-foot convent into clusters of individual rooms with private baths in 10 households arrayed around a living room, kitchen and dining room. Spatially, four different Halls organize the new school plan and express the Franciscan Order's ethics: the Hall of Life, the Hall of Social Justice, the Hall of Peace, and the Hall of Community. These Halls are focal points on each floor and are used for the presentation of student work and as informal gathering spaces. Large openings in the classrooms provide natural light, along with high reflectance paint and mecco shades. On the grounds, the students enjoy trails cut into seven acres of newly planted meadow from an area previously maintained as lawn. All plants are selected from native species.

The project team held a strong commitment to making the renovation environmentally responsible and to preserving the house's historic architectural character. While the Felician Sisters were not educated about many environmental issues, they are followers of Saint Francis of Assisi who is the Patron Saint of the Environment. This commitment allows them to view environmental stewardship as a responsibility. As the project evolved and the Sisters became more aware of the building's potential environmental impacts, they consistently made decisions based on stewardship.

Working through the project and environmental goals, the team soon realized the value in the resources that the building contained. Many materials installed in 1930 were still in excellent condition. If the Sisters wanted low maintenance and durable materials, they could not buy new materials that would perform as well as the old. A subcontractor was hired to catalog, remove, touch-up, repair and reinstall the doors, flooring, trim and cabinetry.

More than 300 original hardwood doors and transoms were refinished and re-hung; over an acre of hardwood flooring was lifted, cleaned and re-laid; over a mile of trim was removed, preserved and installed; and over 275,000 pounds of ballast for the roof was stockpiled and reused as underlayment for paving. New windows were made using energy efficient technologies but were manufactured to look like the original windows. The perimeter of the building was studded out and insulated. Construction waste was recycled and all new finishes were made from low emitting materials to preserve indoor air quality. New energy efficient systems for both lighting and heating were installed as well as solar hot water panels to aid in energy reduction.

As the project progressed it became clear that decisions most benefiting the community were also beneficial to the environment. The building has preserved the character of the original structure, is energy efficient, better serves an aging and student population, and promotes environmental stewardship. The architect achieved over a 30% reduction in energy consumption compared to a baseline model. Systems used to achieve the reduction included heat recovery from air and kitchen exhausts; individual controls in each classroom; landscaped plantings that shade the south and west facades; and recycled roof water used in the evaporative cooler. The client has used the project, which is seeking a gold LEED(R) rating, to educate their Sisters, students and staff in issues of the environment including green cleaning, recycling, vermicomposting, renewable energy, and the building itself.

### MANUFACTURERS/SUPPLIERS

DIV 02: Pavers: Hanover Architectural Products.

DIV 07: Wall Insulation: Johns Manville; Roof Insulation: Carlisle Sure-Seal(R); Membrane Roofing: Carlisle Sure-Weld(R).

DIV 08: Windows: Keystone Industries.

DIV 09: Paint: Sherwin Williams; Linoleum: Forbo Marmoleum; Carpet: Interface, Collins & Aikman; Ceramic Tile: Terra Green.

CONSTRUCTION TEAM

GENERAL CONTRACTOR: Sota Construction Services, Inc. - 80 Union Avenue, Pittsburgh, PA 15202

STRUCTURAL ENGINEER: The Kachele Group - 1014 Perry Highway, #100, Pittsburgh, PA 15237

ELECTRICAL/MECHANICAL/PLUMBING ENGINEER: Elwood S. Tower Corp. - 115 Evergreen Heights Drive, #400, Pittsburgh, PA 15229

MATERIALS REUSE CONTRACTOR: Clearview Project Services Company - 3977 William Flynn Highway, Allison Park, PA 15101 LANDSCAPE ARCHITECT: Rolf Sauer and Partners, Ltd. - 3868 Terrace Street, Philadelphia, PA 19128

Photos Courtesy of Denmarsh Photography

Estimating Form		Project Summary	
PROJECT	Wellington Condominiums	TOTAL SITE AREA	5.88 Acres
BUILDING TYPE	Residential	OWNER	Hankin Group
LOCATION	Exton PA	ARCHITECT	Minno & Wasko
DATE OF CONSTRUCTION	Spring '06 - Spring '07	ESTIMATED CONSTRUCTION PERIOD	18 Months
BRIEF DESCRIPTION	ground level. The 147,069 SF by a series of Hambros Joist 3	a 4 story luxery complex that houses a parking o condominium project features a concrete subst " Slab on Deck Composite System. The roof sy brane and slate roof system supporting by meta	ructure followed stem utilizes a

### Assemblies Estimate - Wellington Condominiums Building Envelope

stimati	ng Form					Systems Costs			
Qty	Assembly Numbe	r Description	Unit	Mat.	Inst.	Total	Zip Code Prefix Typ	e Release	Note
20 Exterior	Closure								
9,312.00	0 B20101017600	Conc wall reinforced, 8' high, 12" thick, plain finish, 5000 PSI	S.F.	63,787.20	142,939.20	206,726.40	181 Open	2006	Walls are 12' high, 6000 PSI Strength
670.91	0 B20101023000	Flt precast conc,4" thick,5x18',smooth gray,low rise	S.F.	4,193.19	2,475.66	6,668.85	181 Open	2006	5 · 5
8,998.60	0 B20101023150	Flt precast conc,4" thick,12x20',smooth gray,low rise	S.F.	79,187.68	9,898.46	89,086.14	181 Open	2006	
14,588.33	0 B20101305200	Brk vnr/met std bkup,std face,20gax3-5/8"nlb std,16" OC sp,rnng bnd	S.F.	86,071.15	199,860.12	285,931.27	181 Open	2006	22 Gage studs utilized
350.00	0 B20201046350	Windows,steel,csmt,insul gl,5'-11" x 5'-2",3 lite	Ea.	586,250.00	154,000.00	740,250.00	181 Open	2006	Average window size
221.00	0 B20302102500	Doors,birch,solid core,single door,hinged,3'-0" x 7'-0" opening	Opng.	226,525.00	54,587.00	281,112.00	181 Open	2006	J.
30 Roofing									
7,289.00	0 B30101202000	Sgl ply memb, EPDM, 45mils, fully adhered	S.F.	6,195.65	5,758.31	11,953.96	181 Open	2006	
25,018.00	0 B30101402800	Slate roofing, 4" min slope, shingles, 3/16" thick, 8.0 PSF	S.F.	162,617.00	61,043.92	223,660.92	181 Open	2006	
7,289.00	0 B30104300700	Flashing,copper,no backing,16 oz,< 500 lbs	S.F.	22,158.56	26,313.29	48,471.85	181 Open	2006	6" Half round copper gutter
776.00	0 B30106103300	Gutters,half round,copper,16 oz thick,5",mill finish	L.F.	4,462.00	3,360.08	7,822.08	181 Open	2006	
1,395.87	5 B30106200700	Downspouts,copper,rectangular corr,3"x4",mill,16 oz thick	V.L.F.	7,049.17	4,997.23	12,046.40	181 Open	2006	
1.00	0 B30202100200	Roof hatches, with curb, and 1" fiberglass insulation, 2'-6"x3'-0",al	Opng.	605.00	172.00	777.00	181 Open	2006	
		Tota	ls	\$1,249,101.59	\$665,405.27	\$1,914,506.86			
				х	х	х			
		Allentown PA location factor multiplier		0.98	1.074	1.027			
				\$1,224,119.56	\$714,645.26	\$1,966,198.55			

Qty CSI Number	Description	Total
ision 3 Concrete - Forms an	d Arrassories	
1.000 31104107750	CLP: concrete forms, column, square, steel framed plywood, 24" x 24", rent, 4 uses per month, includes erecting, bracing, stripping and cleaning	\$14,951,04
1.000 31104201000	CI.P. concrete forms, elevated slab, flat plate, plavod, to 15' high, 1 use, includes shoring, erecting, bracing, stripping and cleaning	\$250,836.35
1.000 31104206500	C.I.P. concrete forms, elevated slab, cub forms, wood, 6 <sup>+</sup> to 12 <sup>+</sup> high, 1 use, includes shorting, erecting, bracing, stripping and cleaning	\$4,578.40
1.000 31104207000	C.I.P. concrete forms, elevated slab, edge forms, to 6" high, 4 use, includes shoring, erecting, bracing, stripping and cleaning	\$1,750.00
1.000 31104559260	C.I.P. concrete forms, walls, steel framed plywood, over 8' to 16' high, based on 100 uses of purchased forms, 4 uses of bracing lumber, includes erecting, bracing, stripping and cleaning	\$66,704.20
1.000 31500800020	Anchor bolts, J-type, 1/2" diameter x 6" long, includes nut and washer	\$1,338.60
1.000 31501701000	Column clamp, adjustable, buy, to 24" x 24"	\$85.00
1.000 31506001500	Shores, reshoring	\$20,912.40
ision 3 Concrete - Reinforce	ment	
1.000 32101001200	High chairs, for reinforcing steel, individual, no plates, plain, to 3" high, includes material only	\$19,821.00
1.000 32101001500	Bar chair, for reinforcing steel, plain, includes material only	\$14,852.26
1.000 32106000200	Reinforcing steel, in place, columns, #3 to #7, A615, grade 60, incl access. Labor	\$8,465.76
1.000 32106000400	Reinforcing steel, in place, elevated slabs, #4 to #7, A615, grade 60, incl access. Labor	\$67,314.35
1.000 32106000500	Reinforcing steel, in place, footings, #4 to #7, A615, grade 60, incl access. Labor	\$40,692.09
1.000 32106000700	Reinforcing steel, in place, walls, #3 to #7, A615, grade 60, incl access. Labor	\$16,049.42
1.000 32202000200	Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1 (8 x 8) 30 lb. per C.S.F., A185	\$12,748.80
1.000 32202000300	Welded wire fabric, sheets, 6 x 6 - W2.9 x W2.9 (6 x 6) 42 lb. per C.S.F., A185	\$58,268.00
sion 3 Concrete - Cast-In-P		
1.000 33102200150	Structural concrete, ready mix, normal weight, 3000 psi, includes material only	\$132,168.96
1.000 33102200411	Structural concrete, ready mix, normal weight, 6000 PSI, includes material only	\$207,304.69
0.000 33102201000	Structural concrete, ready mix, high early strength cement, add, includes material only	
1.000 33107000800	Structural concrete, placing, column, square or round, pumped, 24" thick, includes vibrating, excludes material	\$1,820.03
1.000 33107001400	Structural concrete, placing, elevated slab, pumped, less than 6" thick, includes vibrating, excludes material	\$18,764.50
1.000 33107001600	Structural concrete, placing, elevated slab, pumped, over 10" thick, includes vibrating, excludes material	\$14,104.62
1.000 33107002650	Structural concrete, placing, spread footing, pumped, over 5 C.Y., includes vibrating, excludes material	\$8,204.02
1.000 33107003250	Structural concrete, placing, grade beam, pumped, includes vibrating, excludes material	\$1,043.47
1.000 33107004350	Structural concrete, placing, slab on grade, pumped, 4" thick, includes vibrating, excludes material	\$8,267.89
1.000 33107005100	Structural concrete, placing, walls, pumped, 12" thick, includes vibrating, excludes material	\$8,208.07
1.000 33503000250	Concrete finishing, floors, monolithic, machine trowel finish	\$61,705.35
1.000 33503250120	Control joint, concrete floor slab, saw cut in green concrete, 1* depth	\$794.04
sion 5 Metals - Cold Forme	1 Framing	
1.000 54104006400	Partition, galv LB studs, 16 ga x 6" W studs 16" O.C. x 12' H, incl galv top & bottom track, excl openings, headers, beams, bracing & bridging	\$403,447.20
1.000 54204100550	Floor joist, galv CF steel, 12 ga x 12" D, incl joists (2" flange) & fasteners, excl band joists (track), web stiffeners, headers, beams, bridging & bracing, materials only	\$153,159.24
1.000 54204101550	Floor joist, galv CF steel, 12 ga x 12" D, incl fastening to band joists, beams & headers, excl materials, labor only	\$46,305.00
		Total: \$1,664,664.75
	ENR Building Cost Index Inflation from 2005 to 2006	(Addition of 3.9% Total Cost Esca
	Allentown, PA Location Factor already in calculations	
		\$1,729,586.68

Qty CS	SI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix T	pe Rel
vision 3 Concrete	1												
7.610 3210	1001200	High chairs, for reinforcing steel				С	506.07	0.00	0.00	506.07	555.53 1	81 Ope	n 2005
7.610 3210	1001500	Bar chair, for reinforcing steel				С	285.38	0.00	0.00	285.38	312.01 1	81 Ope	n 2005
2.445 3210	6000500	Reinforcing steel, in place, footings, #4 to #7	4 Rodm	2.1	15.238	Ton	1,919.33	1,088.03	0.00	3,007.35	4,034.25 1	81 Ope	n 2005
84.56 3310	2200411	Structural concrete, ready mix, normal weight				C.Y.	7,737.24	0.00	0.00	7,737.24	8,510.96 1	81 Ope	n 2005
84.56 3310	7003250	Structural concrete, placing, grade beam	C20	180	0.356	C.Y.	0.00	634.20	409.27	1,043.47	1,509.40 1	81 Ope	n 200
		Totals	S				\$10,448.01	\$1,722.23	\$409.27	\$12,579.50	\$14,922.15		
				E	INR Building Cost	Index Infla	tion from 2005 to 2	2006	(Addition of 3	8.9% Total Cost E	scalation)		
				A	Ilentown, PA Loca	tion Facto	r already in calcul	ations					
										\$13.070.10			

Single Slab Column F	ootings			Foι	Indation	IS						
Qty CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix Type	Release
Division 3 Concrete												
98.000 32101001500	Bar chair, for reinforcing steel				С	3,675.00	0.00	0.00	3,675.00	4,018.00 1	81 Open	2005
30.638 32106000500	Reinforcing steel, in place, footings, #4 to #7	4 Rodm	2.1	15.238	Ton	24,050.83	13,633.91	0.00	37,684.74	50,552.70 1	81 Open	2005
556.205 33102200411	Structural concrete, ready mix, normal weight				C.Y.	50,892.76	0.00	0.00	50,892.76	55,982.03 1	81 Open	2005
556.205 33107002650	Structural concrete, placing, spread footing	C20	150	0.427	C.Y.	0.00	4,978.03	3,225.99	8,204.02	11,958.41 1	81 Open	2005
	Totals	;				\$78,618.59	\$18,611.94	\$3,225.99	\$100,456.52	\$122,511.14		
			i	ENR Building Cost	Index Infla	tion from 2005 to	2006	(Addition of 3	3.9% Total Cost E	Escalation)		
				Allentown, PA Loca	ation Facto	r already in calcul	ations					
									\$104,374.32			

Foundation	Walls				Sub	structu	re							
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Туре	Release
Division 3 Concr	rete													
21,942.170 3	1104559260	C.I.P. concrete forms, walls	C2	450	0.107	SFCA	8,338.02	58,366.17	0.00	66,704.20	108,174.90 1	81 C	Open	2005
14.657 32	2106000700	Reinforcing steel, in place, walls, #3 to #7	4 Rodm	3	10.667	Ton	11,505.75	4,543.67	0.00	16,049.42	20,886.23 1	81 C	Open	2005
406.340 33	3102200411	Structural concrete, ready mix, normal weight				C.Y.	37,180.11	0.00	0.00	37,180.11	40,898.12 1	81 C	Open	2005
406.340 33	3107005100	Structural concrete, placing, walls, pumped	C20	110	0.582	C.Y.	0.00	4,977.67	3,230.40	8,208.07	11,783.86 1	81 C	Open	2005
		Totals	5				\$57,023.88	\$67,887.51	\$3,230.40	\$128,141.79	\$181,743.10			
			ENR Building Cost Index Inflation from 2005 to 2006 (Addition of 3.9% Total Cost Escalation)											
		Allentown, PA Location Factor already in calculations \$133,139.32												

oundation	n Columns				Sub	structur	re							
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Туре	Releas
ivision 3 Cond	crete													
4,516.930	31104107750	C.I.P. concrete forms, column, square	C1	440	0.073	SFCA	6,865.73	8,085.30	0.00	14,951.04	21,274.74 1	81	Open	2005
1.000 3	31501701000	Column clamp, adjustable, buy, to 24" x 24"				Set	85.00	0.00	0.00	85.00	93.50 1	81	Open	2005
5.879	32106000200	Reinforcing steel, in place, columns, #3 to #7	4 Rodm	1.5	21.333	Ton	4,850.18	3,615.59	0.00	8,465.76	11,758.00 1	81	Open	2005
75.520 3	33102200411	Structural concrete, ready mix, normal weight				C.Y.	6,910.08	0.00	0.00	6,910.08	7,601.09 1	81	Open	2005
75.520 3	33107000800	Structural concrete, placing, column, square	C20	92	0.696	C.Y.	0.00	1,106.37	713.66	1,820.03	2,643.20 1	81	Open	2005
		Totals	5				\$18,710.99	\$12,807.26	\$713.66	\$32,231.91	\$43,370.53			
				1	ENR Building Cost	Index Infla	tion from 2005 to 2	2006	(Addition of 3	3.9% Total Cost E	scalation)			
					Allentown, PA Loca	tion Facto	r already in calcul	ations						
										\$33,488.95				

Slab on G	irade				Sub	structu	re							
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Туре	Release
Division 3 Co	ncrete													
307.20	32202000200	Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1	2 Rodm	31	0.516	C.S.F.	8,140.80	4,608.00	0.00	12,748.80	17,203.20 1	181	Open	2005
484.92	33102200150	Structural concrete, ready mix, normal weight				C.Y.	38,405.66	0.00	0.00	38,405.66	42,246.23 1	181	Open	2005
484.92	33107004350	Structural concrete, placing, slab on grade	C20	130	0.492	C.Y.	0.00	5,018.92	3,248.96	8,267.89	11,880.54 1	181	Open	2005
30,720.00	33503000250	Concrete finishing, floors, monolithic	1 Cefi	550	0.015	S.F.	0.00	10,752.00	0.00	10,752.00	17,510.40 1	181	Open	2005
509.00	33503250120	Control joint, concrete floor slab	C27	2,000	0.008	L.F.	0.00	96.71	35.63	132.34	193.42 1	181	Open	2005
		Totals					\$46,546.46	\$20,475.63	\$3,284.59	\$70,306.69	\$89,033.79			
		ENR Building Cost Index Inflation from 2005 to 2006 (Addition of 3.9% Total Cost Escalation)												
	Allentown, PA Location Factor already in calculations \$73,048.65													

Transfer SI	lab				Supe	erstructu	ıre						
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix Ty	pe Releas
Division 3 Cond	crete												
29,045.000 3	31104201000	C.I.P. concrete forms, elevated slab, flat plate	C2	470	0.102	S.F.	118,503.60	74,064.75	0.00	192,568.35	255,596.00 1	81 Oper	2005
776.000 3	31104206500	C.I.P. concrete forms, elevated slab, curb forms	C1	180	0.178	SFCA	1,171.76	3,406.64	0.00	4,578.40	7,022.80 1	81 Oper	2005
388.000 3	31500800020	Anchor bolts, J-type, 1/2" diameter x 6" long	1 Carp	90	0.089	Ea.	372.48	966.12	0.00	1,338.60	2,056.40 1	81 Oper	2005
29,045.000 3	31506001500	Shores, reshoring	2 Carp	1,400	0.011	S.F.	11,327.55	9,584.85	0.00	20,912.40	28,173.65 1	81 Oper	2005
290.450 3	32101001200	High chairs, for reinforcing steel				С	19,314.93	0.00	0.00	19,314.93	21,202.85 1	81 Oper	2005
290.450 3	32101001500	Bar chair, for reinforcing steel, plain				С	10,891.88	0.00	0.00	10,891.88	11,908.45 1	81 Oper	2005
56.330 3	32106000400	Reinforcing steel, in place, elevated slabs	4 Rodm	2.9	11.034	Ton	49,288.75	18,025.60	0.00	67,314.35	85,903.25 1	81 Oper	2005
1,143.000 3	33102200411	Structural concrete, ready mix, normal weigh				C.Y.	104,584.50	0.00	0.00	104,584.50	115,042.95 1	81 Oper	2005
1,143.000 3	33107001600	Structural concrete, placing, elevated slab	C20	180	0.356	C.Y.	0.00	8,572.50	5,532.12	14,104.62	20,402.55 1	81 Oper	2005
29,045.000 3	33503000250	Concrete finishing, floors, monolithic	1 Cefi	550	0.015	S.F.	0.00	10,165.75	0.00	10,165.75	16,555.65 1	81 Oper	2005
509.000 3	33503250120	Control joint, concrete floor slab	C27	2,000	0.008	L.F.	0.00	96.71	35.63	132.34	193.42 1	81 Oper	2005
		Totals					\$315,455.44	\$124,882.92	\$5,567.75	\$445,906.11	\$564,057.97		
				E	tion from 2005 to :	2006	(Addition of 3	3.9% Total Cost E	Escalation)				
Allentown, PA Location Factor already in calculations \$463,296.45													


letal Stud Framing				Supe	rstructu	ure							
Qty CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Туре	Relea
Division 5 Metals 13,936.000 54104006400	Partition, galv LB studs, 16 ga x 6" W studs	2 Carp	51	0.314	L.F.	262,693.60	140,753.60	0.00	403,447.20	529,568.00	181	Open	2005
	Totals	S				\$262,693.60	\$140,753.60	\$0.00	\$403,447.20	\$529,568.00			
		ENR Building Cost Index Inflation from 2005 to 2006 (Addition of 3.9% Total Cost Escalation)											
			Α	llentown, PA Loca	tion Facto	r already in calcul	ations		\$419,181.64				


Ha	mbro J	oist System	and Components			Supe	erstruct	ure							
	Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Туре	Release
		als 54204100550 54204101550	Floor joist, galv CF steel, 12 ga x 12" D Floor joist, galv CF steel, 12 ga x 12" D	2 Carp	30	0.533	L.F. Ea.	153,159.24 0.00	0.00 46,305.00	0.00 0.00	153,159.24 46,305.00	167,198.84 1 78,300.00 1		Open Open	2005 2005
				Totals				\$153,159.24	\$46,305.00	\$0.00	\$199,464.24	\$245,498.84			
					ENR Building Cost Index Inflation from 2005 to 2006 (Addition of 3.9% Total Cost Escalation) Allentown, PA Location Factor already in calculations										
					·	Allentown, PA Loca	ation racio	aneady in calcul			\$207,243.35				

Deck Slat	S				Supe	erstruct	ure						
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix T	pe Releas
Division 3 Co	ncrete												
29,134.000	31104201000	C.I.P. concrete forms, elevated slab, flat plate	C2	470	0.102	S.F.	14,567.00	14,567.00	0.00	58,268.00	98,181.58 1	81 Ope	n 2005
1,000.000	31104207000	C.I.P. concrete forms, elevated slab, edge forms	C1	500	0.064	L.F.	170.00	1,580.00	0.00	1,750.00	2,860.00 1	81 Ope	n 2005
1,165.360	32202000300	Welded wire fabric, sheets, 6 x 6 - W2.9 x W2.9	2 Rodm	29	0.552	C.S.F.	39,622.24	18,645.76	0.00	58,268.00	76,331.08 1	81 Ope	n 2005
1,183.880	33102200150	Structural concrete, ready mix, normal weight				C.Y.	93,763.30	0.00	0.00	93,763.30	103,139.63 1	81 Ope	n 2005
1,183.880	33102201000	Structural concrete, ready mix				C.Y.	10.00%				1	81 Ope	n 2005
1,183.880	33107001400	Structural concrete, placing, elevated slab	C20	140	0.457	C.Y.	0.00	11,424.44	7,340.06	18,764.50	27,229.24 1	81 Ope	n 2005
116,536.000	33503000250	Concrete finishing, floors, monolithic	1 Cefi	550	0.015	S.F.	0.00	40,787.60	0.00	40,787.60	66,425.52 1	81 Ope	n 2005
2,036.000	33503250120	Control joint, concrete floor slab	C27	2,000	0.008	L.F.	0.00	386.84	142.52	529.36	773.68 1	81 Ope	n 2005
		Totals					\$148,122.64	\$87,391.64	\$7,482.58	\$272,130.75	\$374,940.73		
			3.9% Total Cost E	Escalation)									
	Allentown, PA Location Factor already in calculations \$282,743.85												

Description	Quantity	Unit	Unit Cost	Total
SR. PROJECT MANAGER	35	WKS	\$3,500.00	\$122,500
SUPERINTENDENT	60	WKS	\$3,000.00	\$180,000
LABORER	52	WKS	\$800.00	\$41,600
ASSISTANT SUPERINTENDENT	30	WKS	\$2,500.00	\$75,000
SURVEYING	1	L.S	\$22,000.00	\$22,000
INSPECTIONS	1	L.S	\$30,000.00	\$30,000
TWP BLDG PERMIT	1	L.S	\$44,405.00	\$44,405
FITOUT PERMIT	48	EACH	\$400.00	\$19,200
TEMPORARY UTILITIES	1	L.S	\$30,000.00	\$30,000
TEMPORARY SIGNS	1	EACH	\$2,500.00	\$2,500
CONSTRUCTION TRAILERS	14	MTH	\$300.00	\$4,200
OFFICE EXPENSES (BLUE PRINTS)	116,000	S.F.	\$0.22	\$25,520
TRASH REMOVAL (DUMPSTERS)	60	EACH	\$500.00	\$30,000
EQUIP & TOOL RENTALS	1	L.S	\$20,000.00	\$20,000
MATERIALS & SUPPLIES	12	MTH	\$200.00	\$2,400
FINAL SITE CLEAN-UP	1	EACH	\$5,000.00	\$5,000
FINAL BUILDING CLEAN-UP	48	EACH	\$400.00	\$19,200
PUNCH LIST	48	EACH	\$400.00	\$19,200

# General Conditions Estimate for Wellington Condominiums







Compare and Contrast Floor-Ceiling Assemblies	Hambro	os Joist Cor	nposite I	Deck Sys	stem	Conven	tional Steel	Joist &	Metal De	eck System	Epicor	e MSR Com	posite Fl	oor Syst	em
Categories of Interest	Ratings	Total Weight	Weight	Grade	Comment	Ratings	Total Weight	Weight	Grade	Comment	Ratings	Total Weight	Weight	Grade	Comment
Fire Ratings	8	6.83	5.12	75.00%	Good	8	6.83	5.12	75.00%	Good	8	6.83	5.81	85.00%	Great
Composite Design	9	5.83	4.37	75.00%	Good	9	5.83	4.37	75.00%	Good	9	5.83	4.96	85.00%	Great
Cost Savings	1	13.83	10.37	75.00%	Good	1	13.83	8.99	65.00%	Okay	1	13.83	10.37	75.00%	Good
Slab Penetrations	10	4.83	4.11	85.00%	Great	10	4.83	3.14	65.00%	Okay	10	4.83	3.14	65.00%	Okay
Schedule Savings	2	12.83	9.62	75.00%	Good	2	12.83	9.62	75.00%	Good	2	12.83	10.91	85.00%	Great
Mechanical Interfacing	7	7.83	6.66	85.00%	Great	7	7.83	5.87	75.00%	Good	7	7.83	5.87	75.00%	Good
Acoustical Properties	3	11.83	7.69	65.00%	Okay	3	11.83	8.87	75.00%	Good	3	11.83	8.87	75.00%	Good
Bearing Systems	11	3.83	2.49	65.00%	Okay	11	3.83	2.49	65.00%	Okay	11	3.83	2.49	65.00%	Okay
Labor Intensive	6	8.83	4.86	55.00%	Poor	6	8.83	6.62	75.00%	Good	e	8.83	7.51	85.00%	Great
Installation	5	9.83	6.39	65.00%	Okay	5	9.83	7.37	75.00%	Good	6	9.83	7.37	75.00%	Good
Versatility	12	2.83	1.56	55.00%	Poor	12	2.83	2.12	75.00%	Good	12	2.83	2.41	85.00%	Great
Quality Control	4	10.83	7.04	65.00%	Okay	4	10.83	8.12	75.00%	Good	4	10.83	8.12	75.00%	Good
TOTAL		100.00	70.3		Okay-Good		100.00	72.75		Good		100.00	77.85		Good-Great
Average				70.00%					72.50%					77.50%	


	Scaling Factor		Rating Factor	
12	2.83333333	A	100-90	Excellent
11	3.83333333	в	90-80	Great
10	4.83333333	С	80-70	Good
9	5.83333333	D	70-60	Okay
8	6.83333333	F	60-50	Poor
7	7.83333333			
6	8.83333333			
5	9.83333333			
4	10.83333333			
3	11.83333333			
2	12.83333333			
1	13.83333333	1		


				Mai	in L	ine 1	Drillin	g Com	pany	
			-	1	01 Calv	varese L	ane - Wa	ayne, PA 19 nail: MLDril	187 1@aol.com	
				Phone/Fa	ax: (61(	J) 341-9.	296 - Ell			
Bori	no#	5						Job#	1871	
	ent:		Enginee	ring Inc				ate Started: Completed:	5/23/2005 5/23/2005	
	ject:	Eaglevi	am Corcoran							
Locat Drill			leville obile B			-		Driller: Assistant:		phen Luner
<u>Dim</u> .		Ground S	urface I	Elevation:	43	4.1		oundwater Info	and the second se	Comments
		quipment Used 1				10101	Depth	Time	Date 5/23/2005	SR= Spoon refusal, large
1	3	1/4" Hollow au	ger	0" 18'6"	To To	18'6" 18'10"	Dry 13'10"	2.5 hrs	5/23/2005	rock fragments to 3',
2 Depth	S#	Split spoon Sample Depth	Blow	/Counts	10			scription		augered to 3'6" after
					Topsoil	<u> </u>			4 <sup>11</sup>	first sample
	\$1	0" - 2'	3-5-1	0-27-SR						S1 13"
 					leandy a	ilt to s	ilty sand	with rock		S2 12" S3 14"
 5'	S2	3'6"-5'6"	5-3	5-6-7	fragmen	nts, some	clay, tr	ace organics		S4 15"
	S3	5'6"-7'6"	11-14	4-18-15	orange-	-brown, b	rown, and	gray		S5 13" S6 12"
		7'6"-9'6"	12-11	6-15-13			(Fill)			S7 4"
	S4	1.02.0								
10' 	S5	9'6"-11'6"	12-1	6-20-19					11'6"	
1					Sandy	silt, gra	y and ora	inge brown	13'	
15'	S6	13'6"-15'	19-	-18-20	Fine t	o medium	sand, wit	ch rock fragm	ents	
<b>!</b>					gray,	tan, and (We	orange-bi eathered o	rown meiss)		
·										
	s7	18'6"-18'10"	1(	00/4"					18'10"	
		19 0 -10 10	-							
¦										
25'										
[					Ì					
<b>I</b>										
30'										
			l							
					ł					
35'										
[			ļ							
40'			1							
					1					
45'			1							
			1							· · ·
		1			1					
50'			* 77597	BORIN	TREST	LTS REP	RESENT	EACH BORIN	NG LOCATIO	N ONLY *
ļ	* ന		LEVE		/N ARE	RECORI	DED AT F	BORING COM	PLETION UN	VLESS OTHER WISE NOTED *
		CONDWATER	ائلا ۷ ناریا ک		IT AILE	10010				



## • PCA MAT<sup>®</sup> Contours







• PCA MAT<sup>®</sup> Analysis

nvelope -	Desig	n Moment	& Steel -	Тор				
C5a - El	LEMENT	TOP DES	GN MOMENT I	AND REIN	FORCEI	MENT:		
=======					=====	=====		
			-ft/ft), As	-	-			
							[*] Cannot	
Elem	Node l	Ld Comb.	Max. M(ux)	As(XX)	Node	Ld Comb.	Max. M(uy)	As(yy)
	2	U1	9.26	0.518m	16	U1	46.97	0.522
2	3	U1	20.69	0.518m	3	U1	17.00	0.518m
3	3	U1	10.10	0.518m	3	U1	14.72	0.518m
4	19	U1	4.39	0.518m	19	-	0.00	0.518m
5	5	-	0.00	0.518m	5	-	0.00	0.518m
6	6	-	0.00	0.518m	6	-	0.00	0.518m
7	8	-	0.00	0.518m	7	-	0.00	0.518m
8	23	U1	0.45	0.518m	9	-	0.00	0.518m
9	25	U1	37.31	0.518m	25	U1	14.63	0.518m
10	25	U1	57.52	0.635	25	U1	19.87	0.518m
11	27	_	0.00	0.518m	12	U1	7.66	0.518m
12	28	U1	12.82	0.518m	12	U1	11.85	0.518m
13	14	U1	13.40	0.518m	28	-	0.00	0.518m
14	29	U1	16.25	0.518m	30	U1	50.11	0.558
15	17	U1	13.76	0.518m	17	U1	31.47	0.518m
16	33	U1	16.85	0.518m	17	U1	25.39	0.518m
17	33	U1	15.40	0.518m	34	U1	23.84	0.518m
18	34	U1	10.68	0.518m	34	U1	24.57	0.518m
19	36	U1	3.56	0.518m	35	U1	23.51	0.518m
20	36	U1	3.50	0.518m	37	U1	23.24	0.518m
21	38	U1	4.40	0.518m	37	U1	23.24	0.518m
22	38	U1	4.96	0.518m	39	U1	26.39	0.518m
23	25	U1	39.08	0.518m	40	U1	27.45	0.518m

nvelope - Design Moment & Steel - Bot									
C5b - EL	EMENT	BOTTOM I	DESIGN MOME	NT AND RI	EINFO	RCEMENT:			
					=====				
		•	-ft/ft), As						
							[*] Cannot		
E16M	Node L	Ld Comb.	Max. M(ux)		Node	Ld Comb.	Max. M(uy)	As(yy) 	
1	17	U1	-13.22	0.518m	1	U1	-49.32	0.549	
2	18	U1	-37.79	0.518m	18	U1	-45.64	0.518m	
3	18	U1	-8.51	0.518m	18	U1	-30.80	0.518m	
4	4	U1	-5.65	0.518m	4	U1	-29.41	0.518m	
5	5	U1	-4.54	0.518m	5	U1	-26.56	0.518m	
6	7	U1	-4.07	0.518m	6	U1	-26.41	0.518m	
7	7	U1	-4.02	0.518m	8	U1	-26.67	0.518m	
8	9	U1	-8.52	0.518m	8	U1	-26.88	0.518m	
9	24	U1	-14.35	0.518m	10	U1	-38.32	0.518m	
10	26	U1	-37.70	0.518m	10	U1	-40.16	0.518m	
11	26	U1	-19.58	0.518m	27	U1	-35.25	0.518m	
12	27	U1	-45.93	0.518m	27	U1	-52.06	0.580	
13	28	U1	-1.03	0.518m	28	U1	-9.85	0.518m	
14	15	U1	-5.43	0.518m	15	U1	-47.75	0.531	
15	32	U1	-36.59	0.518m	32	U1	-52.92	0.590	
16	32	U1	-36.49	0.518m	32	U1	-48.44	0.539	
17	18	U1	-20.91	0.518m	18	U1	-48.37	0.538	
18	20	U1	-3.08	0.518m	20	U1	-9.73	0.518m	
19	20	U1	-2.27	0.518m	20	U1	-9.67	0.518m	
20	22	U1	-1.52	0.518m	22	U1	-9.25	0.518m	
21	22	U1	-1.58	0.518m	22	U1	-9.26	0.518m	
22	24	U1	-9.06	0.518m	24	U1	-15.12	0.518m	
23	24	U1	-13.55	0.518m	24	U1	-15.17	0.518m	



# Lifting Capacities

Lattice Boom Crawler Crane

# LS-218H II 100-ton (90.72 metric ton) **HYLAB** Series

### Angle Boom Capacities 40' – 150' (12.19 – 45.72 m)

### 26' (7.92 m) Live Mast Capacities

- Extended / Retracted Side Frames
- On Carbody Jacks

### 5' (1.52 m) Tip Extension Capacities

### **Duty Cycle Capacities**

- 40' 100' (12.19 30.48 m) Angle Boom
- Extended Side Frames
- Dragline
- Clamshell / Magnet
- "AB" and "A" Counterweight Options

### **Angle Boom Capacities**

- 40' 150' (12.19 45.72 m) Angle Boom
- 48" (1.22 m) Wide x 48" (1.22 m) Deep Boom
- 20' (6.10 m) Open Throat Top Section
- With or without 26' (7.92 m) Live Mast
- Extended / Retracted Side Frames
- 360° Capacities
- Over End Blocked Capacities
- "AB", "A", and "0" Counterweight Options
- 20' 10.5" in. (6.36 m) Crawler Length

CAUTION: This material is supplied for reference use only. Operator must refer to in-cab Crane Rating Manual to determine allowable machine lifting capacities and operating procedures.



# WARNING

# READ AND UNDERSTAND THE OPERATOR'S AND SAFETY MANUALS AND THE FOLLOWING INSTRUCTIONS AND CHART VALUES BEFORE OPERATING THE CRANE. OPERATION WHICH DOES NOT FOLLOW THESE INSTRUCTIONS MAY RESULT IN AN ACCIDENT.

### **OPERATING INSTRUCTIONS**

### **GENERAL**:

- 1 Rated lifting capacities in pounds as shown on lift charts pertain to this crane as originally manufactured and normally equipped. Modifications to the crane or use of optional equipment other than that specified can result in a reduction of capacity.
- Construction equipment can be dangerous if improperly operated or maintained. Operation and maintenance of this crane must be in compliance with the information in the Operator's, Parts, and Safety Manuals supplied with this crane. If these manuals are missing, order replacements through the distributor.
- 3. The operator and other personnel associated with this crane shall read and fully understand the latest applicable American National Standards Institute (ANSI) safety standards for cranes.
- 4. All capacities listed in this book are in compliance with ASME/ANSI B30.5c–1998, SAE J987–April 1994, and SAE J–765 October 1990.

### LIFT CR ANE OPERATION:

- 1. Capacities shown are in pounds and are not more than 75% of the tipping loads with the crane standing level on firm supporting surface. A deduction must be made from these capacities for weight of hook block, hook ball, sling, grapple, etc. When using main hook while jib is attached, reduce capacities by values shown on Capacity Deductions For Lifting Off Main Boom Hook With Jib Installed. When using main hook while 5 foot tip extension or pile driver lead adapter is attached, reduce capacities by values shown on Capacity Deductions For Lifting Off Main Boom Hook With Jib Installed. When using main hook while 5 foot tip extension or pile driver lead adapter is attached, reduce capacities by values shown on Capacity Deductions For Lifting Off Main Boom Hook With 5 Foot Tip Extension or Pile Driver Lead Adapter Installed. See Operator's Manual for all limitations when raising or lowering attachment.
- 2. The crane capacities in the shaded areas are based on structural strength. The crane capacities in the non-shaded areas are based on stability.
- 3. For recommended reeving, parts of line, wire rope type, and wire rope inspection, see Wire Rope Capacity Chart, Operator's Manual, and Parts Manual. Rated lifting capacities are based on correct reeving. Deduction must be made for excessive reeving. Any reeving over minimum required (see Wire Rope Capacity Chart) is considered excessive and must be accounted for when making lifts. Use Working Range Diagram to estimate the extra feet of rope. See Wire Rope Capacity for the weight to deduct for each extra foot of wire rope before attempting to lift a load.
- 4. Rated lifting capacities in this Crane Rating Manual are based on freely suspended loads and make no allowances for such factors as the effect of ground conditions and operating speeds. The operator shall therefore reduce load ratings in order to take these conditions into account.
- 5. Rated lifting capacities do not account for the effects of wind on a suspended load or boom.

Lifting capacities should be considered acceptable for wind speeds less than 20 mph and appropriately reduced for wind speeds greater than 20 mph. (See General Wind Restrictions Guide.)

- 6. The capacities listed are for the crane equipped with or without live mast and with the gantry in the raised position.
- 7. The least stable rated condition is over the side.
- Booms should be erected and lowered over the end for maximum stability. See Liftoff Capabilities before erecting or lowering boom.
- 9. Do not operate at radii and boom lengths where the Crane Rating Manual lists no capacity. Do not use longer booms or jibs than those listed in this Crane Rating Manual. Any of the above can cause a tipping condition, or boom and jib failure.
- 10. These capacities apply only to the crane as originally manufactured and normally equipped by Link–Belt Construction Equipment Company.

# FOR OVER END BLOCKED CAPACITIES ONLY:

- These capacities can be lifted over either end with the crane standing level on a firm supporting surface with adequate blocking placed under the tread member sprockets/idlers, to prevent rocking.
- 2. Do not travel with a load.

### **TRAVELING WITH A LOAD:**

- 1. All 360° Rotation Capacities listed in this Crane Rating Manual are pick and carry capacities.
- 2. The boom must be pointing straight over one end of the crawler lower. If the load was lifted over the side, swing the load over the end and/or if the load was lifted at a long radius and the load is at or near capacity for that radius, boom up to obtain a greater lifting capacity before beginning travel.
- 3. Engage the swing lock and apply swing brake.
- 4. Travel slowly and cautiously on a firm and level-supporting surface.

### **DEFINITIONS:**


- 1. Load Radius: Horizontal distance from a projection of the axis of rotation to the supporting surface, before loading, to the center of the vertical hoist line or tackle with load applied.
- 2. Boom Angle: The angle between the boom base section and horizontal with freely suspended load at the rated radius.
- Working Area: Area measured in a circular arc about the centerline of rotation as shown on the Working Area Diagram.
- 4. Freely Suspended Load: Load hanging free with no direct external force applied except by the hoist line.
- 5. Side Load: Horizontal side force applied to the lifted load either on the ground or in the air.



### WIRE ROPE CAPACITY

Parts of		1"		3/4"			
Line	Type "CC"	Type "RB"	Type "DB"	Type "DB"	Notes		
1	30,760	22,700	29,500	16,800	Capacities shown		
2	61,520	45,400	59,000	33,600	Capacities shown are in pounds and working loads must		
3	92,280	68,100	88,500	50,400	not exceed the rat- ings on the capacity		
4	123,040	90,800	118,000	67,200	charts in this Crane Rating Manual.		
5	153,800	113,500	147,500	84,000	Study Operator's Manual for wire rope		
6	184,560	136,200 177,000		100,800	inspection proce- dures.		
7	215,320	158,900 206,500		117,600			
8	246,080	181,600	236,000	134,400			
Rope weight per foot	2.03	2.00	1.85	1.04			
LBCE Type			Desc	ription			
DB					Extra Improved Plow ar Lay – I.W.R.C.		
RB*					proved Plow Steel – Swaged – SF = 5:1		
сс	36 x 7 Cla			xtra Extra I lar Lay – S.	mproved Plow Steel – F. = 5:1		
	* Use of sw	ivel end wit	h 1 part of l	ine is not re	commended.		
**Weig	ht to be dec	lucted from	main capa	cities when	using extra reeving.		

### **WORKING AREAS**



### LIFTOFF CAPABILITIES

Counterweight	Over End / Over Side (Gantry In Raised Position)						
(Side Frames)	Maximum Boom (ft.)	Maximum Boom + Jib (ft.)					
NO (RETRACTED)	90	N/A					
NO (EXTENDED)	120	N/A					
A (RETRACTED)	120	N/A					
A (EXTENDED)	150	N/A					
AB (EXTENDED)	150	150 + 60					

### NOTES:

- 1. For maximum boom stability, booms must be erected or lowered over the end with no load hook block on ground.
- 2. Crane on firm and level surface.
- 3. Gantry pins must be installed with the gantry in the raised position.
- 4. For 140 ft. + 60 ft. or 150 ft. + 60 ft. (side frame extended) with "AB" counterweight only – Adequate blocking must be placed under both treadmembers sprockets (or idler rollers) at the end that the boom is to be lifted to prevent rocking. Liftoff over end with 140 ft. + 60 ft. and 150 ft. + 60 ft. boom. The ramps supplied with the crane are considered to be adequate blocking.

### **GENERAL WIND RESTRICTIONS GUIDE**

### 🛕 WARNING

Failure to follow these wind speed restrictions may result in structural failure of the boom, which would cause property damage and/or bodily injury.

- The effects of the wind force on the hook load are the responsibility of the user and are not taken into account. When hoisting any load in windy conditions, the load wind area and load controllability must be considered for safe crane operation.
- 2. Wind speed is to be determined at the boom top section.

### WIND SPEED CHART

Boom Lengths: 40' to 250'						
DESCRIPTION	ALLOWABLE WINDSPEEDS					
1. Normal Lifting Operation. (See Capacity Charts.)	0–20 m.p.h.					
2. Reduced Operation. Capacities must be reduced by 20%.	21–30 m.p.h.					
3. Reduced Operation. Capacities must be reduced by 40%.	31–40 m.p.h.					
4. Reduced Operation. Capacities must be reduced by 70%.	41–45 m.p.h.					
4. No Operation. Store Attachment On Ground.	Over 45 m.p.h.					

### CRANE ASSEMBLY COMPONENT WEIGHTS

Component	Wei	ght
Component	lbs.	kg
1. 20 Ft. Top Section With Sheave Machinery	3,646	1 654
2. 20 Ft. Top Section With Sheave Machinery and 5 Ft. Tip Extension	4,286	1 944
3. 20 Ft. Base Section	2,695	1 222
4. Boom Extensions		
<ul> <li>10' Boom Extension With Pendants</li> </ul>	823	373
<ul> <li>20' Boom Extension With Pendants</li> </ul>	1,318	598
<ul> <li>30' Boom Extension With Pendants</li> </ul>	1,845	837
5. Upper Counterweights		
<ul> <li>Counterweight "A"</li> </ul>	25,350	11 499
<ul> <li>Counterweight "B"</li> </ul>	25,350	11 499
6. Side Frames (Each)	23,561	10 687
7. Tube Jib Including Strut, Head Machinery, and Pendants		
30' Tube Jib Assembly	1,965	891
<ul> <li>15' Extension With Pendants</li> </ul>	290	132

### LIVE MAST LIFTING CAPACITIES


Live	Live Mast						
Radius (ft.)	Angle (deg)	(See Note 10)					
10	78.0	30,000					
11	75.7	30,000					
12	73.4	30,000					
13	71.1	25,000					
14	68.8	20,000					
15	66.4	20,000					
16	64.0	15,000					
17	61.5	15,000					
18	59.0	15,000					
19	56.4	15,000					
20	53.7	15,000					
21	50.9	10,000					
22	48.0	10,000					
23	44.9	10,000					
24	41.7	10,000					
25	38.3	10,000					

### NOTES:

- 1. Refer to the Operator's Manual.
- 2. Live mast backstops must be in position and operative.
- Assemble track frames to carbody prior to assembly of counterweights to upper frame.
- 4. Reeve hoist rope with three (3) parts of 1" diameter wire rope on rear drum.
- 5. The crane shall be leveled on a firm supporting surface.
- 6. All capacities are listed in pounds and are not more than 75% of the tipping loads.
- For self-assembly of counterweights, boom extensions, and side frames only. See Crane Assembly Component Weights chart for weight of components for crane assembly.
- 8. Rated capacities for 360  $^\circ$  rotation.
- 9. Gantry must be in the high (working) position.

10. Mast capacities apply to the following conditions:

	COUNTERWEIGHTS				
	NONE	A	AB		
ON CARBODY JACKS	1	N/A	N/A		
SIDE FRAMES RETRACTED	1	1	N/A		
SIDE FRAMES EXTENDED	$\checkmark$	/			





### **DUTY CYCLE NOTES FOR ANGLE BOOM**


- The capacities included in the "Duty Cycle Capacities Angle Boom" chart are the maximum allowable, and are based on an LS–218H II crawler crane with counterweight standing level on firm supporting surface under ideal job conditions.
- 2. Capacities are based on 75% of minimum tipping loads for dragline; 67.5% for clamshell.
- Capacities are maximum recommended by PCSA Standard #4. Operator must make allowances for soft or uneven supporting surfaces, rapid cycle operations, bucket suction, or other unfavorable conditions which may require smaller buckets for most efficient operation.
- 4. Weight of bucket plus load, must not exceed these capacities.
- 5. Dragline operation is not recommended with boom angles less than  $35^{\circ}.$
- 6. Boom length for dragline/clamshell attachment operation should not exceed 100 ft.
- 7. Retractable high gantry must be pinned in the raised position for all capacities on the "Duty Cycle Capacities Angle Boom" chart.
- These capacities apply to the crane as originally manufactured and normally equipped by Link–Belt Construction Equipment Company.

Load Radius	Boom Length	Boom Angle		"A" Coun	terweight	s Extended erweight ed are in pounds)		Load Radius	Boom Angle		"A" Coun	Side Frames Extended "A" Counterweight (All capacities listed are in pounds)			
(ft.)	(ft.)	(deg)	Drag	line	Clamshel	I / Magnet	Length (ft.)	(ft.)	(deg)	Drag	gline	Clamshel	/ Magnet		
			"A" ctwt	"AB" ctwt	"A" ctwt	"AB" ctwt				"A" ctwt	"AB" ctwt	"A" ctwt	"AB" ctwt		
40	11	80.8			29,500	29,500	70	19	78.1			29,500	29,500		
40	12	79.3			29,500	29,500	70	20	77.3			29,500	29,500		
40	13	77.9			29,500	29,500	70	25	73.1			29,500	29,500		
40	14	76.4			29,500	29,500	70	30	68.7			29,500	29,500		
40	15	74.9			29,500	29,500	70	35	64.3			29,500	29,500		
40	16	73.4			29,500	29,500	70	40	59.6	28,620	29,500	28,620	29,500		
40	17	71.9			29,500	29,500	70	50	49.6	20,790	29,500	20,790	29,500		
40	18	70.4			29,500	29,500	70	60	37.7	15,930	25,700	15,930	23,130		
40	19	68.9			29,500	29,500	70	70	20.9			12,510	18,630		
40	20	67.3			29,500	29,500	80	16	81.8			29,500	29,500		
40	25	59.3	29,500	29,500	29,500	29,500	80	17	81.1			29,500	29,500		
40	30	50.6	29,500	29,500	29,500	29,500	80	18	80.4			29,500	29,500		
40	35	40.5	29,500	29,500	29,500	29,500	80	19	79.6			29,500	29,500		
40	40	27.7			28,530	29,500	80	20	78.9			29,500	29,500		
50	12	81.5			29,500	29,500	80	25	75.2			29,500	29,500		
50	13	80.3			29,500	29,500	80	30	71.5			29,500	29,500		
50	14	79.2			29,500	29,500	80	35	67.7			29,500	29,500		
50	15	78.0			29,500	29,500	80	40	63.7			28,440	29,500		
50	16	76.8			29,500	29,500	80	50	55.4	20,610	29,500	20,610	29,500		
50	17	75.6			29,500	29,500	80	60	46.2	15,750	25,600	15,750	23,040		
50	18	74.4			29,500	29,500	80	70	35.2	12,420	20,600	12,420	18,540		
50	19	73.3			29,500	29,500	80	80	19.5			9,900	15,210		
50	20	72.1			29,500	29,500	90	18	81.4				29,500		
50	25	65.9			29,500	29,500	90	19	80.8				29,500		
50	30	59.5	29,500	29,500	29,500	29,500	90	20	80.1				29,500		
50	35	52.5	29,500	29,500	29,500	29,500	90	25	76.9				29,500		
50	40	44.9	28,710	29,500	28,710	29,500	90	30	73.6	e		G	29,500		
50	50	24.8			20,800	29,500	90	35	70.3	PROHIBITED		PROHIBITED	29,500		
60	13	81.9			29,500	29,500	90	40	66.8	Ë		Ξ	29,500		
60	14	81.0			29,500	29,500	90	50	59.7	RO	29,500	Ro	29,430		
60	15	80.0			29,500	29,500	90	60	52.0	Ē	25,400	_ ₽	22,860		
60	16	79.0			29,500	29,500	90	70	43.4		20,400		18,360		
60	17	78.1			29,500	29,500	90	80	33.1				15,030		
60	18	77.1			29,500	29,500	90	90	18.4				12,510		
60	19	76.1			29,500	29,500	100	19	81.7				29,500		
60	20	75.1			29,500	29,500	100	20	81.7				29,500 29,500		
60	25	70.1			29,500	29,500	100	20 25	78.2				29,500 29,500		
60	30	64.9			29,500	29,500		-							
60	35	59.6	29,500	29,500	29,500	29,500	100	30 25	75.3			0	29,500		
60	40	53.8	28,710	29,500	28,710	29,500	100	35	72.3	Ð		PROHIBITED	29,500		
60	50	40.8	20,800	29,500	20,880	29,500	100	40	69.3	PROHIBITED		<u>18</u>	29,500		
60	60	22.6			15,930	23,220	100	50	63.0	H		но	29,250		
70	15	81.5			29,500	29,500	100	60	56.4	PRC	25,100	PR 1	22,590		
70	16	80.6			29,500	29,500	100	70	49.2	4	20,200		18,180		
70	17	79.8			29,500	29,500	100	80	41.1		16,500		14,850		
70	18	79.0			29,500	29,500	100	90	31.3				12,330		
							100	100	17.4				10,350		

### **DUTY CYCLE CAPACITIES – ANGLE BOOM**



# WORKING RANGE DIAGRAM



Notes:

- 1. Boom geometry shown is for unloaded condition and crane standing level on firm supporting surface. Boom deflection, subsequent radius, and boom angle change must be accounted for when applying load to hook.
- 2. Maximum and minimum boom angles are equal to the values listed in the capacity chart for each boom length.

### CAPACITY DEDUCTIONS FOR LIFTING OFF MAIN BOOM HOOK WITH JIB INSTALLED

When using main boom hook, while jib is attached, reduce boom capacities by the values in the following chart:

Jib Length (ft.)	Capacity Deduction (lb)
30	2,000
45	2,400
60	3,200

### CAPACITY DEDUCTIONS FOR LIFTING OFF MAIN BOOM HOOK WITH 5 FOOT TIP EXTENSION OR PILE DRIVER LEAD ADAPTERS INSTALLED

When using main boom hook, while 5 foot tip extension or pile driver lead adapter is attached, reduce boom capacities by the values in the following chart:

Extension/Adapter	Capacity Deduction (lb)
5 (ft.)	700
Pile Driver Lead Adapter	200

### MAXIMUM ALLOWABLE CAPACITIES FOR 5 FOOT TIP EXTENSION

LIFTING CAPACITY TO BE THE SMALLEST OF THE FOLLOWING VALUES:

- 1. 18,000 lb (Maximum).
- 2. The standard crane lift capacity minus 700 lb for the crane configuration in use.

### NOTES:

- 1. All notes are to be adhered to as listed on the standard lift crane capacity charts .
- 2. Reduce the main boom lift capacities by 700 lb when the tip extension is installed.
- 3. The maximum boom length on which the tip extension can be installed is 150 ft.
- 4. Do not lift or suspend a load from the boom tip extension and main boom at the same time.


### MAXIMUM ALLOWABLE CAPACITIES FOR PILE DRIVER LEAD ADAPTER

LIFTING CAPACITY TO BE THE SMALLEST OF THE FOLLOWING VALUES:


- 1. 70,000 lbs.
- 2. The standard crane lift capacity minus 200 lbs. for crane configuration in use.

### NOTES:

- 1. All notes are to be adhered to as listed on the standard lift crane capacity charts.
- 2. Reduce the main boom lift capacities by 200 lb when the pile driver lead adapter is installed.
- 3. The maximum boom length on which the pile driver lead adapter can be installed is 150 ft.









### Note: Refer To Page 7 For "Capacity Deductions" Caused By Any Attachment At The Boom Tip.

	MAIN BOO	M CAPACI	TIES – 40 F	T OPEN TH	IROAT ANG	GLE BOOM			
		Over	360° Rotation						
Load Radius	Boom Angle	End Blocked	S	ide Frame Extended	S	Side Frames Retracted			
(Ft.)	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (Ib)		
11	80.8	200,000	200,000	199,600	179,600	139,600	85,500		
12	79.3	200,000	200,000	184,200	165,700	119,900	73,200		
13	77.9	190,600	190,600	171,000	137,100	105,000	63,900		
14	76.4	177,900	177,900	159,500	115,700	93,200	56,500		
15	74.9	166,600	166,600	149,400	100,000	83,800	50,600		
16	73.4	156,700	156,700	133,500	87,900	76,000	45,800		
17	71.9	147,800	147,800	119,200	78,300	69,500	41,700		
18	70.4	139,900	139,900	107,500	70,500	63,900	38,200		
19	68.9	132,700	132,700	97,900	64,000	59,100	35,200		
20	67.3	126,300	123,500	89,800	58,600	55,000	32,600		
25	59.3	101,200	87,200	63,000	40,700	40,300	23,500		
30	50.6	80,400	66,900	48,000	30,600	31,400	17,900		
35	40.5	64,100	53,800	38,400	24,200	25,400	14,100		
40	27.7	52,900	44,800	31,700	19,600	21,000	11,300		

	MAIN BOO	M CAPACI	TIES – 50 F	T OPEN TH	IROAT ANG	GLE BOOM				
		Over		360° Rotation						
Load Radius		End Blocked	5	Side Frames Extended			rames icted			
(Ft.)	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)			
12	81.5	200,000	200,000	183,800	165,400	120,200	73,500			
13	80.3	190,300	190,300	170,600	137,800	105,300	64,100			
14	79.2	177,500	177,500	159,200	116,300	93,500	56,800			
15	78.0	166,300	166,300	149,100	100,500	84,000	50,800			
16	76.8	156,400	156,400	134,000	88,300	76,200	45,900			
17	75.6	147,600	147,600	119,600	78,600	69,600	41,800			
18	74.4	139,700	139,700	107,900	70,800	64,000	38,400			
19	73.3	132,500	132,500	98,200	64,300	59,300	35,400			
20	72.1	126,100	123,800	90,100	58,900	55,100	32,800			
25	65.9	101,000	87,400	63,200	40,900	40,400	23,600			
30	59.5	80,600	67,000	48,200	30,800	31,500	18,000			
35	52.5	64,300	54,000	38,600	24,300	25,500	14,200			
40	44.9	53,100	45,000	31,900	19,800	21,200	11,500			
50	24.8	38,900	33,200	23,200	13,900	15,300	7,800			


	MAIN BOC	M CAPACI	ries – 60 f	T OPEN TH	IROAT ANG	GLE BOOM	
		Over		3	60° Rotatio	n	
Load Radius	Boom Angle			Side Frame: Extended	Side Frames Retracted		
(Ft.)	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (Ib)	A CTWT (Ib)	0 CTWT (Ib)
13	81.9	189,700	189,700	170,100	138,300	105,300	64,200
14	81.0	177,000	177,000	158,700	116,700	93,500	56,800
15	80.0	165,900	165,900	148,700	100,700	84,000	50,900
16	79.0	156,000	156,000	134,200	88,500	76,200	46,000
17	78.1	147,200	147,200	119,700	78,800	69,600	41,800
18	77.1	139,300	139,300	108,000	71,000	64,000	38,300
19	76.1	132,200	132,200	98,300	64,400	59,200	35,300
20	75.1	125,700	123,900	90,200	59,000	55,000	32,700
25	70.1	100,700	87,400	63,200	40,900	40,300	23,500
30	64.9	80,600	67,000	48,200	30,800	31,400	17,900
35	59.6	64,300	54,000	38,600	24,300	25,400	14,100
40	53.8	53,100	44,900	31,900	19,800	21,100	11,400
50	40.8	39,000	33,200	23,200	14,000	15,300	7,800
60	22.6	30,300	25,800	17,700	10,200	11,500	5,300

	MAIN BOO	M CAPACI	FIES – 70 F	T OPEN TH	IROAT ANG	GLE BOOM			
		Over	360° Rotation						
Load Radius	Boom Angle	End Blocked	S	Side Frames Extended			rames icted		
	(deg)		AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)		
15	81.5	165,300	165,300	148,200	100,900	83,900	50,800		
16	80.6	155,500	155,500	134,300	88,600	76,100	45,900		
17	79.8	146,800	146,800	119,800	78,900	69,500	41,700		
18	79.0	138,900	138,900	108,100	71,000	63,900	38,200		
19	78.1	131,800	131,800	98,300	64,500	59,100	35,200		
20	77.3	125,300	123,900	90,200	59,000	54,900	32,600		
25	73.1	100,300	87,300	63,200	40,800	40,200	23,300		
30	68.7	80,600	66,900	48,100	30,700	31,200	17,700		
35	64.3	64,200	53,900	38,400	24,200	25,200	14,000		
40	59.6	53,100	44,800	31,800	19,700	20,900	11,300		
50	49.6	38,900	33,100	23,100	13,800	15,200	7,600		
60	37.7	30,200	25,700	17,700	10,200	11,400	5,200		
70	20.9	24,300	20,700	13,900	7,600	8,800	3,500		

	MAIN BOO	M CAPACI	ΓIES – 80 F	T OPEN TH	IROAT ANG	SLE BOOM			
		Over	360° Rotation						
Load Radius	Boom Angle	End Blocked	S	ide Frames Extended	6	Side Frames Retracted			
(Ft.) (deg)		AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)		
16	81.8	154,900	154,900	134,300	88,700	76,000	45,700		
17	81.1	146,200	146,200	119,800	78,900	69,400	41,600		
18	80.4	138,400	138,400	108,100	71,000	63,800	38,100		
19	79.6	131,300	131,300	98,300	64,400	59,000	35,100		
20	78.9	124,800	123,900	90,100	58,900	54,800	32,400		
25	75.2	99,900	87,200	63,000	40,700	40,000	23,200		
30	71.5	80,500	66,800	47,900	30,500	31,000	17,500		
35	67.7	64,100	53,700	38,300	24,000	25,000	13,800		
40	63.7	52,900	44,700	31,600	19,500	20,700	11,100		
50	55.4	38,700	32,900	22,900	13,700	15,000	7,400		
60	46.2	30,100	25,600	17,500	10,000	11,200	5,100		
70	35.2	24,200	20,600	13,800	7,500	8,600	3,400		
80	19.5	19,900	16,900	11,000	5,600	6,700	2,100		

	MAIN BOC	M CAPACI	FIES – 90 F	T OPEN TH	IROAT ANG	GLE BOOM			
		Over		30	60° Rotatio	n			
Load Radius	Boom Angle	End Blocked	S	Side Frames Extended			rames acted		
	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)		
18	81.4	137,900	137,900	108,000	70,900	63,600	37,900		
19	80.8	130,800	130,800	98,200	64,400	58,800	34,900		
20	80.1	124,300	123,800	90,000	58,800	54,600	32,200		
25	76.9	99,400	87,100	62,900	40,600	39,800	22,900		
30	73.6	80,300	66,600	47,800	30,400	30,800	17,300		
35	70.3	63,900	53,500	38,100	23,900	24,800	13,500		
40	66.8	52,700	44,500	31,400	19,300	20,500	10,800		
50	59.7	38,500	32,700	22,700	13,500	14,700	7,200		
60	52.0	29,900	25,400	17,300	9,800	11,000	4,800		
70	43.4	24,000	20,400	13,600	7,300	8,400	3,200		
80	33.1	19,800	16,700	10,900	5,500	6,500	2,000		
90	18.4	16,600	13,900	8,800	4,000	5,000	<u> </u>		







I	MAIN BOO	M CAPACIT	IES – 100 F	T OPEN T	HROAT AN	GLE BOON	1	
		Over	360° Rotation					
Load Radius	Boom Angle	End Blocked	Side Frames Extended			Side Frames Retracted		
(Ft.) (deg)		AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	
19	81.7	130,200	130,200	98,100	64,300	58,600		
20	81.1	123,800	123,700	89,900	58,700	54,400		
25	78.2	98,900	86,900	62,700	40,400	39,600		
30	75.3	80,200	66,400	47,600	30,200	30,600		
35	72.3	63,700	53,300	37,900	23,600	24,600	A	
40	69.3	52,500	44,200	31,200	19,100	20,200	E E	
50	63.0	38,300	32,500	22,500	13,200	14,500	РСОНІВІТЕР	
60	56.4	29,600	25,100	17,000	9,600	10,800	R	
70	49.2	23,800	20,200	13,400	7,100	8,200		
80	41.1	19,600	16,500	10,700	5,200	6,300		
90	31.3	16,400	13,700	8,600	3,800	4,800		
100	17.4	13,800	11,500	6,900	2,700	3,600		

		Over		360° Rotation					
Load Boom Radius Angle (Ft.) (deg)	Boom Angle	End Blocked	Side Frames Extended			Side Frames Retracted			
		AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)		
20	81.9	120,600	120,600	89,800	58,600	54,100			
25	79.3	98,400	86,700	62,600	40,200	39,300			
30	76.6	80,000	66,200	47,400	30,000	30,300			
35	74.0	63,500	53,100	37,700	23,400	24,300			
40	71.2	52,300	44,000	30,900	18,900	20,000	e		
50	65.6	38,100	32,200	22,200	13,000	14,200	118		
60	59.8	29,400	24,900	16,800	9,300	10,500	PROHIBITED		
70	53.5	23,600	19,900	13,100	6,800	7,900	РК		
80	46.7	19,300	16,300	10,400	5,000	6,000			
90	39.1	16,200	13,500	8,400	3,600	4,500			
100	29.8	13,600	11,300	6,700	2,500	3,300			
110	16.6	11,600	9,500	5,400		2,400			

		Over		360° Rotation						
Radius Angl	Boom Angle	End Blocked	5	Side Frames Extended			rames acted			
	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)			
25	80.2	93,400	86,600	62,400	40,000	39,100				
30	77.8	79,800	66,000	47,200	29,800	30,100				
35	75.3	63,300	52,900	37,400	23,200	24,000				
40	72.8	52,100	43,800	30,700	18,600	19,700				
50	67.8	37,800	32,000	22,000	12,700	13,900	0			
60	62.5	29,200	24,600	16,500	9,100	10,200	E E			
70	57.0	23,300	19,600	12,800	6,500	7,600	ROHIBITED			
80	51.1	19,100	16,000	10,100	4,700	5,700	R			
90	44.6	15,900	13,200	8,100	3,300	4,300				
100	37.3	13,400	11,100	6,500	2,200	3,100				
110	28.6	11,400	9,300	5,200	—	2,100				
120	15.9	9,700	7,800	4,000						

I	MAIN BOO	M CAPACIT	IES – 130 I	FT OPEN TI	HROAT AN	GLE BOON	I		
		Over	360° Rotation						
Load Boom Radius Angle		End Blocked	5	Side Frames Extended			rames icted		
(Ft.)	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)		
25	81.0	82,900	73,500	62,200			1		
30	78.7	72,500	62,500	46,900					
35	76.5	62,500	52,600	37,200					
40	74.2	51,900	43,500	30,500					
50	69.6	37,600	31,700	21,700					
60	64.8	28,900	24,400	16,300					
70	59.8	23,000	19,400	12,600	P	ROHIBITEI	2		
80	54.5	18,800	15,700	9,900					
90	48.9	15,600	13,000	7,800					
100	42.8	13,100	10,800	6,200					
110	35.8	11,100	9,000	4,900					
120	27.4	9,500	7,600	3,800					
130	15.3	8,000	6,300	2,900					

r	MAIN BOO	M CAPACIT	IES – 140 F	T OPEN TH	HROAT AN	GLE BOOM	l		
		Over	360° Rotation						
Load Radius	Boom Angle	End Blocked				Side Frames Retracted			
(Ft.)	(deg)	AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)		
25	81.6	65,200	62,800	62,000					
30	79.5	55,400	52,600	46,700					
35	77.5	52,100	44,700	37,000					
40	75.4	45,600	39,100	30,200					
50	71.1	34,800	28,300	21,400					
60	66.7	26,500	21,900	16,000					
70	62.1	21,200	17,000	12,300		ROHIBITED			
80	57.4	16,900	13,600	9,600	P	RUNIBITEL	,		
90	52.4	14,000	11,200	7,500					
100	47.0	11,500	9,500	5,900					
110	41.2	9,800	7,800	4,600					
120	34.5	8,500	6,700	3,500					
130	26.4	7,300	5,800	2,600					
140	14.7	4,500	4,500						

MAIN BOOM CAPACITIES – 150 FT OPEN THROAT ANGLE BOOM								
	Boom <b>Angle</b> (deg)	Over End Blocked	360° Rotation					
Load Radius (Ft.)			Side Frames Extended			Side Frames Retracted		
		AB CTWT (lb)	AB CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	A CTWT (lb)	0 CTWT (lb)	
30	80.2	46,600	46,600	46,500	PROHIBITED			
35	78.3	40,200	40,200	36,700				
40	76.3	35,200	35,200	29,900				
50	72.4	25,800	25,800	21,200				
60	68.3	20,300	20,300	15,700				
70	64.1	16,000	16,000	12,000				
80	59.8	12,700	12,700	9,300				
90	55.3	10,300	10,300	7,200				
100	50.5	8,500	8,500	5,600				
110	45.4	7,200	7,200	4,300				
120	39.7	6,000	6,000	3,300				
130	33.3	5,100	5,100	2,300				
140	25.5	4,300	4,300					
150	14.2	3,200	3,200					