

Exton, PA **Spring Thesis Research BUILIDING FOR THE FUTURE**

C.3 Foundation Redesign ~ *Structural Breadth*



Figure 1: Foundation Excavation

The Current Foundation System for the Wellington Condominiums has been analyzed and is broken down as followed:

•	C.3.1	Problem Statement	Page 96
•	C.3.2	Proposed Solution	Page 96
•	C.3.3	Analysis Steps	Page 96
•	C.3.4	Analysis Result Overview	Page 97
	0	C.3.4.1.A Overview of the Current Foundation System	
	0	C.3.4.1.B Original Estimate and Schedule	
	0	C.3.4.1.C Geotechnical Report Summary	

- o C.3.4.1.D Foundation Construction
- o C.3.4.2.A Overview of the Foundation Redesign
- o C.3.4.2.B Mat Foundation Concept Applied to Wellington Condominiums
- o C.3.4.2.C Mat Foundation Design Background
- o C.3.4.2.D Mat Foundation Design Input Data and Assumptions
- o C.3.4.2.E Mat Foundation Design
- o C.3.4.2.F Other Mat Foundation Design Considerations
- o C.3.4.2.G Mat Foundation Schedule Implications

Sean Flynn – Construction Management

Page 95 of 147



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

o C.3.4.2.H Mat Foundation Budget Implications

• C.3.4.3 Comparison of the Two Foundation Systems

Page 113

C.3.1 Problem Statement

With poor subsurface conditions prevalent, can the foundation system be redesigned to possibly reduce cost and time spent without interfering with architects or owner needs?

This problem was identified through the geotechnical reports, change orders, and project manager interviews. A lot of money, time, and energy were spent by the project team having to deal with poor subsurface conditions. An analysis communicating some potential solutions is one study of great interest to many on the Wellington Condominiums Project.

C.3.2 Proposed Solution

A possible solution to the Wellington Condominiums Project is for a structural redesign of the foundation system. A structural breath will be utilized in the analysis of the comparison between the current and proposed systems. The current foundation system makes use of single slab column footings and will be challenged through the redesign of a matt slab foundation. A matt slab foundation system is proposed and will be researched to do the following possibilities:

- 1. Save time and money by not having to excavate as deep in rock material.
- 2. If footing depth can be decreased possible savings in the dewatering system could happen.
- 3. Using a matt slab could reduce the strength needed for foundation concrete and also if designed correctly act as a slab on grade. This could potentially save time and cost to the project.

C.3.3 Analysis Steps

The procedure to investigating if a matt slab foundation system would be more viable than a traditional single slab column footing is as followed:

- 1. Learn in more detail and have available the single slab column footing's estimate, schedule, design documentation, specifications, and methods of construction.
- 2. Redesign the foundation system utilizing a matt slab foundation. Figure out how much material, cost, and time would be spent to construct.
- 3. Compare the two systems and create a matrix chart based on the owner requirements of which system overall is better for the project.

Sean Flynn – Construction Management



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

C.3.4 Analysis Result Overview

The matt slab foundation system at first seems to be an ironic system to select rather than pouring single slab column footings. When looking at the following items: cost and time spent to rock excavate by rock hammering, putting in a extensive permanent dewatering system and support equipment, weeks of delays that would push back the façade construction to the winter months, and the structural engineer specifying the use of 6,000 PSI concrete for footings. Once you look at all those variables the cost and ease of simply pouring the entire slab may be a better alternative. Also the analysis can be swayed either way by the owners inputs of the foundation system based on a matrix chart.

C.3.4.1.A Overview of the Current Wellington Condominium's Foundation System

The Wellington Condominium's foundation consists of a large part of the cast in place concrete that was done on the construction site. The type of horizontal and vertical formworks and concrete placement methods of the foundation are described in more detail as followed:

Footings:

- Normal weight concrete with a minimum compressive strength of 3,000 PSI at 28 days (This was value engineered due to the CM questioning the specified 6,000 PSI compressive strength in the contract documents by the engineer of record.)
- Reinforcing will consist of A615, Grade 60
- Average size of column footing 15'L X 15'W X 18"D
- Minimum of 3 feet below finished surface where exposed to frost
- Minimum allowable bearing pressure of 3,500 PSF



Figure 2: Wellington Condominium's Foundation

Sean Flynn – Construction Management

Page 97 of 147



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

Slab on Grade:

 5 inches of normal weight concrete with a minimum compressive strength of 3,000 PSI at 28 days

8" and 12" normal weight reinforced concrete with a minimum compressive

 Reinforced with 6 X 6 – W2.1 X W2.1 welded wire fabric, over a 14 inch crushed stone sub base and vapor barrier

Foundation Bearing and Shear Wall Construction: (includes exterior and stair and tower walls)



Figure 3: Substructure from RAM Concept

Since the soil at the time had enough cohesion to stay in place, the foundation strip and column footings did not require any horizontal or vertical formwork. The only task left was to situate the footing rebar and place the concrete with a concrete pump at the locations required. Once the footings were to the strength required, the foundation's exterior walls and columns took form with large gang forms. These large forms took shape very quickly with a 120 ton AmQuip crane tipping up each one into position. The formwork was connected and reinforced into place with lateral bracing. After the formwork was set and properly supported, the rebar was placed in the foundation walls and columns. Following inspection from the project management team, the concrete was placed with a concrete pump and allowed time to gain strength.



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

C.3.4.1.B Original Estimate and Schedule

The Wellington Condominium's original foundation system estimate and schedule are detailed as followed:

Original Estimate:

	Total:	\$357.119
•	Slab on Grade:	<u>\$73,048</u>
	Foundation Columns:	\$33,488
٠	Foundation Walls:	\$133,139
•	Wall Strip Footings:	\$13,070
•	Single Slab Column Footings:	\$104, 374

~See Attached Appendix for Detailed Structural Takeoff~

Original Schedule:

5	Site Work	49 days	Mon 1/16/08	Thu 3/23/08		
	Parking Lot	39 days	Mon 1/30/06	Thu 3/23/06		
}	Excavation	34 days	Mon 1/16/08	Thu 3/2/06		
0	Foundation and Columns	44 days	Wed 2/22/08	Mon 4/24/08		
D	Garage Slab	5 days	Tue 4/25/06	Mon 5/1/06		

Total:

83 Work Days = 17 Weeks Mon 1/16/06 – Mon 5/1/06

~See Attached Appendix for Full Schedule~

C.3.4.1.C Geotechnical Report Summary

The Wellington Condominium's project team hired on Earth Engineering, a geotechnical engineer and geologist company located in East Norriton PA, to perform a geotechnical investigation for the site conditions at Wellington Condominiums. Fifteen test borings were completed for the investigation from May 23 through May 25, 2005. The borings were conducted by Main Line Drilling Company of Wayne, PA and were field located to the project team's specifications by the surveyor Hopkins and Scott, Inc. A representative of Earth Engineering supervised and monitored the test boring activities.



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE



Figure 4: Site Boring Investigation

The laboratory results indicated that the soil classification for a majority of the soil according to ASTM specifications was sandy silt. It has a bearing capacity of 4 KSF and a fair drainability record. Groundwater was encountered at all of the boring locations and as much as 5 feet above the proposed finished floor garage. Earth Engineering recommends raising the finished floor grade or providing permanent waterproofing and drainage system to maintain groundwater levels below the proposed finished floor grade. Substantial soil and rock excavations below the existing grade must be done to achieve the correct soil bearing pressure.

~See Attached Appendix for Test Boring Results~

C.3.4.1.D Foundation Construction

The project team armed with this information knew that soil conditions would be an issue and therefore took the recommendation of Earth Engineering to provide waterproofing and permanent dewatering systems to the foundation system. The architects did not want to raise the finished floor grade due to the parking garage at the foundation level. An increase in elevation would make the parking garage more visible and possibly make the building less architecturally pleasing. During excavation the project team encountered poor subsurface conditions and had to take extra measures through change orders to ensure a proper foundation design. During the course of excavation the following amounts of change orders had to be conducted to correct the poor subsurface conditions:



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

	Change Orders	
#	DESCRIPTION	AMOUN
1	Site plan topography wrong, and poor soils had to be excavated	\$20,00
2	Unsuitable soils	\$38,48
3	Unsuitable soils	\$1,76
4	Unsuitable soils	\$12,94
5	Change under slab drainage pipe from SDR35 to SCH10 so it won't get crushed. It wasn't spec'd.	\$1,93
6	Unsuitable soils	\$35,80
(Rock Crusher	\$43,00
8	Additional cleanouts and floor drains at garage	\$1,74
9	Footing over-excavation and lean till	\$12,62
10	Add'I 3" ID binder	\$1,39
11	Unsuitable soils	\$10,00
12	Waterproofing	\$80,00
	TOTAL CHANGES	\$253,15

Figure 5: Foundation Change Orders

The total amount for change orders was \$253,159 and resulted in a total payout of \$610,278. This ended up being a 70% increase in the total budget for the foundations. The encounter of poor subsurface conditions led to delaying the project by more than 3 weeks. This created a domino effect to the entire schedule and was one of the major reasons why the façade construction was pushed to the middle of winter.

C.3.4.2.A Overview of the Foundation Redesign

With the encounter of poor subsurface conditions there was an opportunity to investigate whether or not the foundation system should have been changed. It is through this analysis to decide whether or not a redesign of the foundation system would be deemed a viable solution. The selection of a particular foundation was based on a number of factors from the *Building Design and Construction Handbook by Merritt* and is as followed:

- 1. Adequate Depth: Preventing frost damage and undermining by scour.
- 2. Bearing Capacity Failure: Foundation must be safe against failure.
- 3. Settlement: Must not settle to the extent that it damages the structure.
- 4. Quality: Must have adequate quality so that it is not subjected to deterioration.
- 5. Adequate Strength: Must be built to sufficient strength so that it does not fracture or break apart under superstructure loads. The foundation construction must conform to design specifications.
- 6. Adverse Soil Changes: The foundation must be able to resist adverse soil conditions. Expansive soils such as silt and clay could expand or shrink, causing movement of the foundation and damage to the structure.
- 7. Seismic Forces: Foundation must be able to support the structure during an earthquake without excessive settlement or lateral movement.

Sean Flynn – Construction Management



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

Footing types other than spread footings are usually used for the following reasons and were used as a guide from the 2007 RS Means Assemblies Data to the selection of the Wellington Condominiums foundation redesign:

- 1. Bearing Capacity of soil is very low.
- 2. Very large footings are required, at a cost disadvantage.
- 3. Soil under footing is very compressible, with the probability of causing excessive or differential settlement.
- 4. Good bearing soil is deep.
- 5. Potential for scour action exists.
- 6. Varying subsoil conditions within building perimeter.

All these reasons apply to the Wellington Condominium Foundation. The bearing capacity can only be designed to withstand 3500 PSI which is considered fairly low. With varying subsoil conditions within the building perimeter, comes the requirement of utilizing large and deep footings to prevent excessive settlement and have good bearing soil.

	TYPE OF SOIL Symb	ol Bearin	^{9.} Drainability	
eased Bearing Capacity	Solid hard granite, gneiss, other bedrock Solid limestone, sandstone, slate, marble Soft limestone, shale, crumbly slate Hardpan, other cohering inorganic solls Boulders with rocks or sand Rotten or loose rock Compact gravel (rocks 2 mm-6 in. in size) Firm dry clay, other fine inorganic solls	80-160 50-80 24-30 16-28 12-16 10 10 8 10	None None Poor Good Fair Excellent Poor	
Decr	Compact sand (rocks 0.5-2 mm. in size)	7 6 6	Excellent Poor Good	
	Clay with sand or silt	4	Fair Poor	
	Clay with organic soll or silt, Loess Peat, topsoll, loam, organic soil	2	Fair Good Poor	

Figure 6: Properties of Soils

From Figure 6, it can be shown that the bearing capacity for the soils at Wellington Condominiums is poor and that the drainability is between the range of fair and poor. Therefore due to the reasons listed above, it was determined to analyze the redesign of the Wellington Condominiums foundation system by utilizing a mat foundation.



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

C.3.4.2.B Mat Foundation Concept Applied to Wellington Condominiums

According to the *Building Design and Construction Handbook by Merritt*, a mat foundation is defined: as a single combined footing for an entire building unit. It is economical when building loads are relatively heavy and the safe soil pressure is small. Based on economic considerations according to the *Building Design and Construction Handbook by Merritt*, mat foundations are constructed for the following reasons and are judged against the Wellington Condominiums circumstances:

1. Large Individual Footings: A mat foundation is often constructed when the sum of individual footing areas exceeds about ¹/₂ of the foundation area.

Wellington Condominiums Calculation:

- 259' x 121' Building Area = 31,339 SQ FT
- 36 Footings x (20' x 20' Max Footing Area) = 14,400 SQ FT
- (14,400 SQ FT / 31,339 SQ FT) x 100 = 45.95% < 50% SUM

From the calculation, it can be determined that approximately 46% of the footing area is below the rule of thumb value but is within consideration for mat foundation.

2. **Cavities or Compressible Lenses:** Mat foundation used when subsurface exploration indicates that there will be unequal settlement below the foundation due to small cavities or compressible lenses. A mat foundation would distribute the load more evenly and create better conditions for any possible settlement.

Wellington Condominiums Analysis Viewpoint:

- Cavities or Compressible Lenses have not been indicated in the geotechnical reports or have been an issue during construction.
- Minimal value has been placed on cavities or compressible lenses for this analysis.
- 3. **Shallow Settlements:** A mat foundation can be recommended when shallow settlements predominate and the mat foundation would minimize differential settlements.

Wellington Condominiums Analysis Viewpoint:

- Differential Settlement was identified in the geotechnical report and has been a large concern to the project team.
- Large consideration has been placed on how the foundation settlements would be with a mat foundation system.
- 4. **Unequal Distribution of loads:** Large disparity in building loads acting on different areas of the foundation can be subjected to excessive differential settlement with conventional spread footings. Using a mat foundation would tend to distribute the unequal building loads and reduce the differential settlements.



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

Wellington Condominiums Analysis Viewpoint:

- The column and wall loading varies and therefore different column sizes and spread footings are utilized. The largest spread footings are constructed at the corners and center of the foundation.
- Unequal distribution of loads is something to consider but is not a major focus for the design of the Wellington Condominiums mat foundation redesign analysis. Load distribution will be considered in the analysis for completeness.
- 5. **Hydrostatic Uplift:** A mat foundation could be used to resist uplift forces due to a high groundwater table.

Wellington Condominiums Analysis Viewpoint:

- Groundwater at the project site is of huge concern to the project team. Extensive groundwater measures had to be in place before construction could ever begin.
- Any reduction in waterproofing or groundwater measures from the utilization of a mat slab would be of great savings in budget and schedule.

C.3.4.2.C Mat Foundation Design Background

The design background for a mat foundation tends to be very complicated and requires extensive knowledge and experience. Being said there are many articles and programs that engineers use when considering the design of a mat foundation system. Some of the design criteria outlined in the *Building Design and Construction Handbook by Merritt* are as followed:

- 1. Weight of soil excavated for the foundation decreases the pressure on the soil under the mat. If excavated soil weighs more than the building, there is a net decrease in pressure at mat level from that prior to excavation.
- 2. When the mat is rigid, a uniform distribution of soil pressure can be assumed and the design can be based on a statically determinant structure as shown in the Figure 7 below.
- 3. If the centroid of the factored loads does not coincide with the centroid of the mat area, the resulting nonuniform soil pressure should be used in the strength design of the mat.
- 4. Strength-design provisions for flexure, one-way and two-way shear, development length, and serviceability should conform to ACI 318 Building Code Requirements.



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE



Figure 7: Design Conditions for a Rigid Mat Footing

C.3.4.2.D Mat Foundation Design Input Data and Assumptions

A mat foundation design was created through the utilization of PCA MAT® Software by Structure Point. This software specializes in the complicated design of mat foundations. Before utilizing the software and inputting data, information background about the foundation conditions had to be identified.

- Earth Engineering has assumed and indicated in contract documents that the column loads will not exceed 473 kips, and that the wall loads will not exceed 10 kips per lineal foot. Earth Engineering has assumed that no unbalanced moments or lateral loads are imposed on the columns and walls. Based on these assumptions, Earth Engineering estimated that the total settlement to be less than one inch and the differential settlement to be within tolerable limits.
- Concrete
 - Compression Strength: 3 KSI
 - Unit Weight: 145 PCF
 - o Young's Modulus: 3155.92 KSI
 - o Poisson's Ratio: 0.15
- Soil
 - Subgrade Modulus: 50 KCF
 - Allowable Pressure: 3.5 KSF
- Steel
 - Yield Strength: 60 KSI



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

- o Young's Modulus: 29,000 KSI
- Design Parameters
 - o Minimum Reinforcing Ratio (% of gross area): 0.18
 - Top and Bottom Reinforcing
 - X-Direction: 3.25 inches
 - Y-Direction: 3.5 inches
- Column Dimensions (from construction documents)
- Slaved Nodes: Rx Degree of Freedom
 - Loads and Load Combinations
 - o Service
 - o Ultimate

C.3.4.2.E Mat Foundation Design

Once the data has been inputted and assigned to elements in the PCA MAT® Software program, results can be quickly attained. The advantage to this software is analyzing how thick a mat slab has to be to properly support the required loads of the structure. Simply changing the thickness in the input data will update the results for the viewer to see. The goal is to get the thickness of the mat foundation as thin as possible due to the controlling cost of concrete and reinforcement. Also by decreasing the depth of the foundation better control over hydrostatic uplift, load distribution, and settlements will occur.



Figure 8: PCA MAT® Software

For the design analysis the following thickness will be looked at to determine the most appropriate for the Wellington Condominiums mat foundation system: 120", 108", 96", 84", 72", 60", 48", 36", 24", and 12". With each thickness the amount of reinforcing, deflection settlement, and moment capacity will be determined. The best combination of

Sean Flynn – Construction Management

Page 106 of 147



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

the three will result in the selected mat foundation thickness. The chart below shows the results of the analysis using the PCA MAT® Software.

		PCA M	AT® Ana	alysis Results Ch	art	
	Thickness (in)	Max Deflection (in)	Contours	TYP. AS (sq in/ft)	TYP. Rebar Size #	Contours
	120	0.306	Good	2.592	18	
5	108	0.316	Good	2.333	18	
	96	0.328	Good	2.074	14	
-	84	0.343	Good	1.814	14	
T	72	0.361	Good	1.555	11	
	60	0.382	Okay	1.296	11	
	48	0.405	Okay	1.037	10	
	36	0.426	So So	0.778	8	
= ♠	24	0.45	So So	0.518 (mix sizes)	7	
	12	0.545	Bad	0.259 (mix sizes)	5	

From the PCA MAT® Chart, it can be shown that the ideal thickness for the mat foundation lies between 48" and 36". Above the results creates large rebar sizes and thick mat slabs which are unnecessary to carry the structural load. Below the results creates mixed rebar sizes and bad settlement contours. Therefore it is recommended that a 48" mat slab be utilized due to the settlement contours and typical rebar sizes that are commonly found in constructing foundations. This value tends to be on the conservative side of the given results.

~See Attached Appendix for PCA Mat® Contours And Analysis Calculations~

C.3.4.2.F Other Mat Foundation Design Considerations

One of the major concerns addressed on the project site other than poor subsurface conditions was the high water table. As an example in Figure 9, the Boring B-5 Garage Finished Floor Elevation (G.F.F.E.) and groundwater depth is at 429.00 feet and 423.00 feet respectively. With a 4 foot mat foundation there will be an additional 2 feet above the groundwater depth level.

Page 107 of 147



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE



Figure 9: Geotechnical Boring Results from Earth Engineering

More concern by the project team was given for the depth of the groundwater table at B-1, B-6, and B-11. The groundwater table was above the G.F.F.E. and something needed to be done. The project team decided at the beginning of the project to install first the dewatering system and an excellent waterproofing system. This proved to pay dividends when constructing the foundation system. Even though the soil was considered poor, construction workers with the dewatering system were provided a dry area to work in. If the permanent dewatering system was not installed prior to foundation construction, delays and productivity decreases could have resulted. It is in this analysis that the project team did an excellent job concerning waterproofing and the design for the mat foundation concerning groundwater depth should remain the same.

The permanent dewatering system utilizes a gravity flow system with an electrical sump pump backup. The current gravity flow system utilizes a 6" DIA perforated drainage PVC under the 5" slab on grade from a starting elevation of 430.75' to a gravity outfall of 429.71'. The maximum travel distance is approximately 379' with a 0.03 in/ft drainage piping slope. The drainage piping currently runs between column and footings and it is recommended that the piping system remain the same but be dropped 4' to accommodate the mat foundation system. Doing so may result in a greater influx of water and create a greater need for the dewatering and waterproofing system. With this increase in demand

Sean Flynn – Construction Management

Page 108 of 147



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

for water removal may create a possible backlog of additional hydrostatic pressure that cannot be forgotten about. With a possibility of increased hydrostatic pressure with the utilization of the same drainage system comes to the responsibility of the designer as to what to do. Through advice of structural engineers and contractors it was recommended that once you start constructing your foundation that the dewatering system must be in effect to reduce the possibility of high hydrostatic pressure on the foundation system. With a permanent dewatering system installed prior to construction, it will alleviate any potential risk during construction of hydrostatic pressure. The following calculation is provided as to give a rule of thumb to the structural load interaction of the Wellington Condominiums Project:

Allowable Bearing Pressure of Soil Conditions:	3.5 KSF
Square footage of Mat Foundation: 259' x 121'	31,339 SF
Allowable Total Load Transferred to Soil Conditions:	109,687 K
Maximum Column Load: 473 K x 36 Columns	17,028 K
Maximum Wall Load: 10 K/FT x 760 FT	7600 K
Total Mat Foundation Load:	24,628 K

The mat foundation load is less than the allowable mat foundation load; therefore the foundation has enough strength to allow for the prevalent soil conditions. There is a 4.45 safety factor on this analysis which will allow for any additional hydrostatic pressure and uplift from the soil conditions present. With the permanent dewatering system installed prior to foundation construction and continued throughout the project; there is no additional analysis to consider.

C.3.4.2.G Mat Foundation Schedule Implications

The schedule effect to the implementation of the mat foundation system is shown in Figure 10.A along with the original schedule in Figure 10.B.



Sean Flynn – Construction Management



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

Sitework 43 days Mee 1/1660 The 32206 Clear & grub 5 days Mee 1/1660 Fil 1/2006 Stroppoli 5 days Mee 1/1600 Fil 1/2006 Stroppoli 5 days Mee 1/1600 Fil 1/2006 Parking lot 5 days Mee 1/2006 Fil 1/2006 Parking lot 5 days Mee 1/2006 Fil 1/2006 Stewardy Feece 2 days Mee 1/1600 Mee 1/1600 Stewardy Feece 2 days Mee 1/1600 Mee 1/1600 Bill Execution 5 days Mee 1/2006 Fil 1/2006 Bill Execution 5 days Mee 3/2000 Mee 3/2000 Boolder Removal 1 day Mee 3/2000 Mee 3/2000 Dewastering pipe 5 days Mee 3/2000 Mee 3/2000 Stom Seare 6 days Mee 3/2000 Mee 3/2000 Mat Foundation Rebar and Conce 41 days Mee 3/2000 Mee 3/2000 Mat Foundation Rebar and Conce 41 days Mee 3/2000 Mee 3/2000 Mat Foundation Wall Formwork Placement Foundation Rebar and Concett	
Clear & grub 5 days Mon 11000 Fil 12000 3 trip topsoil 5 days Mon 11200 Fil 12000 Parting fol 3 days Mon 112000 Fil 12000 Parting fol 3 days Mon 112000 Fil 12000 Township sporval for bulk excavation 1 day Mon 111000 Mon 111000 Sacurdy Fance 2 days Inn 12000 Fin 122000 Bill Excavation 5 days Thu 122000 Fin 122000 Bill Excavation 1 day Mon 11800 Mon 28000 Boulder Removal 1 day Mon 28000 Mon 28000 Statustrup grap 5 days Thu 22000 Thu 22000 Statustrue 48 days Wei 31100 The 214000 Mat Foundation & Columnas 6 days Mon 311000 Mon 51000 Mat Foundation Rebar and Concel 41 days Mon 51000 Mon 52000 Mat Foundation Vall Formach Place and Concel 10 days The 31000 Mon 52000 Foundation Vall Formachin Columnas Formach Placement Foundation Wall Formachin Placement Foundation Col	
Stro topsel 9 days Mon 102.000 Fit 12700 Parking lot 38 days Mon 102.000 Fit 12700 Parking lot 38 days Mon 102.000 Fit 12700 Parking lot 38 days Mon 102.000 Fit 12700 Store topsel 28 days Mon 102.000 Fit 12700 Bitle transation 5 days Mon 102.000 Fit 12700 Bitle transation 5 days Mon 102.000 Fit 12700 Biolder Removal 1 day Mon 200.00 Fit 12700 Biolder Removal 1 day Mon 200.00 Fit 12700 Store topsel 5 days Mon 102.000 Fit 12700 Biolder Removal 1 day Mon 200.00 Fit 12700 Store topsel 6 days The 200.00 Wed 31.00 Store topsel 6 days Mon 102.00 Mon 05000 Mat Foundation Layout 2 days Mon 112.00 Mon 05000 Mat Foundation Layout 2 days Mon 05000 Mon 05000 Mat Foundation Nale rand Concert 10 days The 310.00 Mon 05000 Foundation Wall Robur and Concert </td <td></td>	
Parking lot 38 days Mont 10000 Thu 3/2306 Tournship approval for bulk escavation 1 day Mon 11/1000 Mon 11/1000 Security Fance 2 days Mon 11/1000 Fn 12/200 Fn 2/2000 Boulder Removal 1 day Mon 12/000 Fn 2/2000 Fn 2/2000 Boulder Removal 1 day Mon 12/000 Fn 2/2000 Beul E/2000 Boulder Removal 1 day Mon 12/000 Fn 2/2000 Beul E/2000 Boulder Removal 1 day Mon 12/000 Mon 22/000 Beul E/2000 Stom Sever 6 days The 2/2000 Mon 12/000 Provide/000 Stom Sever 6 days Mon 11/1000 Mon 11/1000 Mon 11/1000 Feundation & Columns 6 days Mon 11/1000 Mon	
Tormsbip approval for bulk excavation Sacurity Fance Bilk Excavation Bilk Excavation Bi	
Sacurity Fance 2 days Im: 1/2000 Ph 12/300 Hilk Excatation 5 days Mon 10000 Ph 20300 Bolde Removal 1 day Mon 10000 Ph 20300 Bolde Removal 1 day Mon 10000 Ph 20300 Bolde Removal 1 day Mon 10000 Ph 20300 Dewatering pipe 5 days This 2208 Wei 31100 Stom Sever 6 days This 2208 Mon 91000 Substructure 16 days Mon 91000 Mon 91000 Mat Foundation Layout 2 days Mon 91000 Mon 91000 Mat Foundation Layout 2 days Mon 911000 Mon 91000 Mat Foundation Layout 2 days Mon 911000 Mon 911000 Mat Foundation Layout 2 days Mon 911000 Mon 911000 Mat Foundation Layout 2 days The 911400 Mon 911000 Mat Foundation Mat Foundation Rebar and Concer 44 4 days The 911400 Mat Foundation Mat Foundation Mat Park and Conceret Flacem Foundation Wall Formark Placement Foundation Vall Formark Placemen	
Hill Excatation 5. days Mon 10000 Pr. 22000 Boulder Removal 1. day Mon 2808 Beuder Removal Beuder Removal 1. day Mon 2808 Beuder Removal Beuder Removal 6. days Thu 2208 Thu 3208 Stom Sever 6. days Thu 2208 Thu 3208 Foundation & Columno 6. days Men 3/1006 Men 5/1008 Mat Foundation Rebar and Concer 14. days Men 5/1008 Men 5/1008 Mat Foundation Rebar and Concer 41. days Mon 5/1008 Mat Foundation Rebar and Concerter Flacem Foundation Rebar and Concer 10. days Two 5/200 Mon 5/1008 Mat Foundation Columns Formover, Hatement Foundation Columns Formover, Holder 10. days Two 5/2000 Mon 5/2008 Mon 5/2008 Foundation Columns Formover, Holder 5. days Two 5/2000 Mon 5/2008 Foundation Columns Formover, Hatement Foundation Columns Formover, Holder 5. days Two 5/2000 Mon 5/2008 Foundation Columns Formover, Hatement Foundation Columns Formover, Holder 5. days Two 5/2000 Mon 5/2008 Foundation Columas Formover, Hatement	
Boulder Removal 1 say Mon 28006 Devestering pipe 5 days The 22006 Stom Seave 6 days Mon 28008 Stom Seave 6 days Mon 28008 Substructure 149 days Weil 32206 Poundation & Columns 6 days Mon 311306 Foundation Layout 2 days Mon 311306 Mat Foundation Layout 2 days Mon 311306 Foundation Wall Formwork Place 5 days Tive 51000 Mat Foundation Columns Formwork Placement Foundation Columns Formwork Placement Foundation Columns Rebar and Cono 10 days Tive 51000 Mon 52000 Mon 52000 Mon 52000 Elevator Jack Holes 5 days Tive 51000 Under-das Granage system & stone 5 5 days Tive 51000 Under-das Granage system & stone 5 5 days Tive 51000 Somtkin and Conciste mar revice 10 days Tive 51000 Under-das Granage system & stone 5 5 days Tive 51000 Somtkin and Conciste mar revice 10 days Tive 51000	
Decasterop pie 5. days Thi: 72300 Weik 31100 Stom Sener 6 days Thi: 22306 Thi: 32306 Departing piec Substructure 6 days Thi: 32306 Main 51506 Departing piec Substructure 16 days Main 311306 Main 51506 Departing piec Main Foundation Layout 2 days Main 511306 Main 5106 Departing piec Main Foundation Layout 2 days Main 51106 Main 5106 Departing piec Foundation Layout 2 days Main 51106 Main 5106 Departing piec Departing piec Foundation Layout 2 days Main 51106 Main 5106 Main 50106 Main 50106 Main Foundation Vall Formatorh Piace 5 days Tue 511000 Main 52006	
Stom Sever 6 days Th: 22.06 Mon SHEMS Substructure 459 days Weid 22206 Mon SHEMS Foundation & Columns 61 days Mon SHEMS Mon SHEMS Foundation & Columns 61 days Mon SHEMS Mon SHEMS Mail Foundation & Columns 61 days Mon SHEMS Mon SHEMS Mail Foundation Rebar and Concr 41 days Mon SHEMS Mon SHEMS Mail Foundation Rebar and Concr 41 days Mon SHEMS Mon SHEMS Foundation Rebar and Concr 10 days Tre SHEMS Mon SHEMS Foundation Vall Foundation Columns Formwork Placement 10 days Tre SHEMS Mon SHEMS Foundation Columns Formwork Placement 10 days Tre SHEMS Mon SHEMS Foundation Columns Formwork Placement Foundation Columns Formwork Placement 10 days Tre SHEMS Mon SHEMS Foundation Columns Formwork Placement Foundation Columns Formwork Placement 10 days Tre SHEMS Mon SHEMS Foundation Columns Formwork Placement Foundation Columns Formwork Placement 10 days Tre SHEMS Mon SHEMS	
Substructure 148 days Wed 32206 Men 911996 Poundation & Columns 61 days Men 911996 Men 61596 Mult Foundation & Columns 61 days Men 61596 Mail Foundation Layout 2 days Mult Foundation Rebar and Concr 41 days Men 911906 Men 51506 Mail Foundation Rebar and Concrete Flacem Foundation Rebar and Concr 41 days Men 911906 Men 51508 Mail Foundation Rebar and Concrete Flacem Foundation Rebar and Concrete 5 days Tue 51000 Men 51508 Men 51508 Foundation Columns Formerk P 10 days Tue 51000 Mon 52208 Foundation Columns Formerk P Foundation Columns Formerk P 10 days Tue 51000 Mon 52208 Foundation Columns Formerk P Foundation Columns Formerk P 10 days Tue 51000 Mon 52208 Foundation Columns Formerk P Under-data dramage system & stone s 5 days Tue 51000 Mon 52208 Foundation Columns Formerk P Under-data dramage system & stone s 5 days Tue 51000 Mon 52208 Foundation Columns Formerk P Under-data dramage system & stone s<	
Foundation & Columns 61 days Mean 013000 Two 3114000 Mean 025000 Mat Foundation Layeout 2 days Mean 313000 Two 3114000 Mean 025000 Mat Foundation are store Mat Foundation are stor	•
Mat Foundation Layout 2 days Men 2/1300 Tue 3/1408 Mat Foundation Rebar and Concert 4 days Men 2/1300 Mon 5/0308 Foundation Wall Formark Place Foundation Wall Formark Place Foundation Columns Formark P Foundation Columns Formark P Foundatio	
Mel Foundation Rebar and Concert 41 days Mon 311000 Mon 50006 Foundation Wall Formack Place S days Tue 50006 Mon 511506 Foundation Vall Formack Placement Foundation Columns Formack	
Foundation Wall Formwork Place 5 days Tix 55005 Mon 51606 Poundation Wall Rebus and Come 10 days Tix 51000 Mon 52000 Foundation Columns Rebus and Com 10 days Tix 51000 Mon 52000 Poundation Columns Rebus and Come 10 days Tix 51000 Mon 52000 Poundation Columns Rebus and Columns Rebus an	cement
Foundation Wall Rebar and Corro 10 days Two \$11000 Mon 502000 Foundation Columns Formwork P 10 days Two \$11000 Mon 502000 Foundation Columns Formwork P 10 days Two \$10000 Mon 502000 Foundation Columns Rebar and (10 days Two \$11000 Mon 502000 Bierator Jack Holes 5 days Two \$11000 Mon 60500 Understand cranups system & stone s 5 days Two \$10000 Mon 60500 Synthiker and Domesto water service 10 days Wed 202100 Two 37100	1
Foundation Columns Formwork P 10 days Tie 56100 Mon 522:06 Foundation Columns Retar and C 10 days The 522:06 Mon 522:06 Berator Jack Holes 5 days The 51000 Mon 520:06 Understab drankage system & store 5 5 days Tie 51000 Mon 55:06 Sprinkler and Domestic water service 10 days Wed 322:06 Tue 37:06	rete Placement
Poundation Columns Rebar and C 10 days Twe 50200 Mon 60000 Elevator Juck Holes 5 days Twe 51000 Mon 60000 Under-dato dramage system & store 5 days Twe 51000 Mon 6000 C moder-dato dramage system & store 5 days Twe 50000 Mon 6500 SoftMer and Domestic water service 10 days Web 202200 Twe 37000 SoftMer and Domestic water service 10 days Web 202200 Twe 37000	cement
Elevator Jack Holes 9 dans 1 the \$1000 Mon 50200 Under-Jab dramage system & store \$ 5 days 1 tel 50000 Mon 5000 Sofekher and Comestic mater service 10 days Web 20200 Tue 37/00	d Concrete Placemer
Linder-slab drainage system & stone s 5 days Toxi 50000 Mon 0/500 Sprinkler and Domestic water service 10 days Wed 2/2200 Tue 3/7/00	
Sprinkler and Domestic water service 10 days Wed 2/2/06 Tue 3/7/06 Sprinkler and Domestic water service	stone subgrade
Garage Slab 0 days Mon 6/506 Mon 6/506	
Iransfer Slab SS days Tub SS05 Mon 93005	
Foundation waterproofing 5 days Tue 88/08 Mon 8/12/08	
Footing, downspout & condensate dra 10 days Twe 8/13/06 Mon 8/28/06	
Backfill 10 days Tue G/5108 Mon 9/12/08	ondensate drains

Figure 10.A: Mat Foundation System Schedule

ruction	340 days	Mon 1/16/06	Fri 5/4/07	
xterior, shell	335 days	Mon 1/16/06	Fri 4/27/07	
Sitework	49 days	Mon 1/16/06	Thu 3/23/06	Sitework
Clear & grub	5 days	Mon 1/10/00	Fri 1/20/00	Clear & grub
Strip topsoll	5 days	Mon 1/23/08	Fri 1/27/06	Strip topsoil
Parking lot	39 days	Mon 1/30/06	Thu 3/23/06	Parking lot
Township approval for bulk excavation	1 day	Mon 1/16/08	Mon 1/16/06	Township approval for bulk excavation
Security Fence	2 days	Thu 1/26/08	Fri 1/27/08	Security Fence
Bulk Excavation	10 days	Mon 1/30/00	Fri 2/10/00	Bulk Excavation
Boulder Removal	13 days	Mon 2/6/08	Wed 2/22/00	Boulder Removal
Dewatering pipe	5 days	Thu 2/23/06	Wed 3/1/06	Cewstering pipe
Storm Sewer	6 days	Thu 2/23/08	Thu 3/2/08	Storm Sewer
Substructure	132 days	Wed 2/22/06	Thu 8/24/06	
Foundation & Columns	39 days	Mon 3/13/06	Thu 5/4/06	Ti T
Spread and Column Footing Lays	2 days	Mon 3/13/00	Tue 3/14/00	-Spread and Column Footing Layout
Spread Footing Rebar and Concr	5 days	Wed 3/15/08	Tue 3/21/08	-Spread Footing Rebar and Concrete Placement
Column Footing Rebar and Conci	10 days	Fri 3/17/06	Thu 3/30/06	Column Footing Rebar and Concrete Placement
Foundation Wall Formwork Place	5 days	Mon 3/27/08	Fri 3/31/08	- Acundation Wall Formwork Placement
Foundation Wall Rebar and Conc	10 days	Mon 4/3/06	Fri 4/14/08	Foundation Wall Rebar and Concrete Placement
Foundation Columns Formwork P	10 days	Fri 4/7/00	Thu 4/20/00	Foundation Columns Formwork Placement
Foundation Columns Rebar and C	10 days	Fri 4/21/08	Thu 5/4/06	Foundation Columns Retar and Concrete Placement
Elevator Jack Holes	5 days	Fn 4/14/05	Thu 4/20/08	Hevator Jack Holes
Under-slab drainage system & stone s	5 days	Fri 4/28/08	Fri 5/5/08	Ander-slab drainage system & stone subgrade
Sprinkler and Domestic water service	10 days	Wed 2/22/08	Tue 3/7/08	Sprinkler and Domestic water service
Garage Slab	5 days	Fri 5/5/06	Thu 5/11/06	
Transfer Slab	65 days	Fri 5/12/06	Thu 8/10/06	γ_
Foundation waterproofing	5 days	Fn 5/5/06	Thu 5/11/08	Foundation waterproofing
Footing, downspout & condensate drai	10 days	Fri 5/12/08	Thu 6/25/08	Footing, downspout & oondensate drains
Backfill	10 days	Fri 8/11/08	Thu 8/24/08	Backfill
Superstructure	186 days	Fri 8/11/06	Fri 4/27/07	

Figure 10.B: Original Foundation System Schedule

~See Attached Appendix for the Complete Schedule~

Sean Flynn – Construction Management

Page 110 of 147



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

From the schedules the important dates to take notice are highlighted in blue and listed as followed for analysis:

Mat Foundation System:

- Construction: 340 Days
- Substructure: 149 Days
- Foundation and Columns: 61 Days
- Superstructure: 169 Days

Original Foundation System:

- Construction: 340 Days
- Substructure: 132 Days
- Foundation and Columns: 39 Days
- Superstructure: 186 Days

Mon 1/16/06 – Fri 5/4/07 Wed 2/22/06 – Mon 9/18/06 Mon 3/13/06 - Mon 6/5/06 Tue 9/5/06 – Fri 4/27/07

Mon 1/16/06 – Fri 5/4/07 Wed 2/22/06 – Thu 8/24/06 Mon 3/13/06 – Thu 5/4/06 Fri 8/11/06 – Fri 4/27/07

Green – Schedule Pull Back

Key:

Some interesting results have occurred that are worth noting for the comparison between schedules. The construction of the mat foundation in comparison to the original foundation system will result in as followed:

- Construction: Entire Construction of the project will be the same start and finish date with no increase or decrease in project schedule.
- Substructure: The construction of the substructure will increase by 17 days. The substructure construction will start on the same day but finish at a later time.
- Foundation and Columns: Foundation and Columns will increase by 22 days. The foundation and column construction will start on the same day but finish at a later time.
- Superstructure: The superstructure will decrease in time of construction by 17 days. The start time will be pushed back but will finish on the same day as the original schedule.

What this data is revealing is that there is float within the schedule and the utilization of a mat foundation system will not delay the overall project. There is an increase in parts of the schedule but due to superstructure float was able to take on those extra days of construction and still finish on time. Therefore based on these observations, more analysis must be conducted further as to whether or not to utilize a mat foundation system for the Wellington Condominiums Project.



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

C.3.4.2.H Mat Foundation Budget Implications

The current budget for the Wellington Condominiums Foundation system is based on the following estimates:

Original Estimate:

•	Single Slab Column Footings:	\$104, 374
•	Wall Strip Footings:	\$13,070
•	Slab on Grade:	\$73,048
•	Change Orders	\$253,159

Total: \$443,651

Mat Foundation Estimate @ 4' Thickness:

- 2007 RS Means Building Construction Data • Cubic Yards of Mat Foundation: 259' x 121' x 4' 4,643 CY • 2 Crews (C-14C) Totaling: o 2 Foreman o 12 Carpenters • 4 Rodmen (reinf.) o 8 Laborers • 2 Cement Finishers o 2 Gas Engine Vibrators Material Cost: \$174/CY \$807,882 Labor Cost: \$70/CY/Crew x 2 Crews = \$140/CY \$650,020 Equipment: \$0.38/CY/Crew x 2 Crews = \$0.76/CY \$3,529 Total: \$1,461,431 Mat Foundation Estimate @ 3' Thickness: 2007 RS Means Building Construction Data • Cubic Yards of Mat Foundation: 259' x 121' x 3' 3,482 CY • 2 Crews (C-14C) Totaling:
 - o 2 Foreman
 - o 12 Carpenters
 - o 4 Rodmen (reinf.)
 - o 8 Laborers
 - 2 Cement Finishers
 - 2 Gas Engine Vibrators
 - Material Cost: \$174/CY
 - Labor Cost: \$70/CY/Crew x 2 Crews = \$140/CY

Sean Flynn – Construction Management

Page 112 of 147

\$605,868

\$487,480



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

• Equipment: \$0.38/CY/Crew x	2 Crews = \$0.76/CY	\$2,646
	Total:	\$1,095,994

From the estimate analysis, at a minimum 3' mat foundation thickness the cost is 2.5 times over the original foundation estimate. At the preferred 4' mat foundation thickness the cost is 3.3 times over the original foundation estimate. If utilized the 4' mat foundation system, 53% of the total structural system would be put towards the redesign. Also 84% of the original cost would have to be put towards the construction of the mat foundation system.

If the owner were to decide solely on the estimates given here for the project budget as to what system should be utilized. It would not be beneficial to use a mat foundation system based on these estimates.

C.3.4.3 Comparison of the Two Foundation Systems

The comparison of the two foundation systems have been created through a matrix chart based on the owner requirements of which system overall is better for the project.

Compare and Contrast	Orginal Foundation System						Mat Foundation System				
ategories of Interest	Ratings	Total Weight	Weight	Grade	Comment	Ratings	Total Weight	Weight	Grade	Comment	
Material and Equipment	11	3.83	2.07	75.00%	Good	11	3.83	2.49	65.00%	Okay	
Change Orders	4	10.83	5.96	55.00%	Poor	4	10.83	7.04	65.00%	Okay	
Cost	1	13.83	11.76	85.00%	Great	1	13.83	7.61	55.00%	Poor	
Watertable Interaction	3	11.83	7.69	65.00%	Okay	3	11.83	7.69	65.00%	Okay	
Schedule	7	7.83	5.09	65.00%	Okay	7	7.03	5.09	65.00%	Okay	
Subsurface Interaction	2	12.83	7.06	55.00%	Poor	2	12.83	10.91	85.00%	Great	
Load Distribution	6	0.03	5.74	65.00%	Okay	6	0.03	0.39	95.00%	Excellent	
Drainage System	5	9.83	7.37	/5.00%	Good	5	9.83	6.39	65.00%	Okay	
Labor Intensive	8	6.83	4.44	65.00%	Okay	8	6.83	4.44	65.00%	Okay	
Installation	10	4.83	3.14	65.00%	Okay	10	4.83	3.14	65.00%	Okay	
Versatility	12	2.03	2.12	75.00%	Good	12	2.03	1.84	65.00%	Okay	
Quality Control	9	5.83	4.37	/5.00%	Good	9	5.83	4.37	/5.00%	Good	
TOTAL		100 00	67.6		Okay		100 00	69.4		Okay	
Average				70.00%					72.50%		

The comparison and contrast of the two foundation systems have been created through a matrix chart based on what was most important through the owner's perspective on a scale of 1-12. Each system would be graded on how well it performs in each of the 12 categories. For instance, the cost for the original foundation system was deemed as a reasonable price and was commented as being great advantage to the project budget. The mat foundation was deemed as poor due to the high cost imposed onto the project budget.

Sean Flynn – Construction Management



Exton, PA Spring Thesis Research BUILIDING FOR THE FUTURE

The results have indicated that a score of 67.6% and 69.4% for the original and mat foundation system respectively. Both are indicated as an okay system but it is the mat foundation which should be selected by the owner. This provides an interesting perspective in that the mat foundation even though cost was a number one concern and was over three times the original foundation system; the mat foundation should be perused if given the correct amount of funding availability. The advantages of the mat foundation in subsurface interaction and load distribution create just enough of an advantage to spend the extra money on the system. If however other variables were to change; it could give the possibility of the original foundation system being preferred over the mat foundation system. But with the current information provided, if the amount of funding is available, the mat foundation system should be selected for the Wellington Condominiums Project.

