

# Wellington Condominiums

Exton PA

Extraordinary Residences Exceptional Lifestyle



## Design and Construction Team:

**Owner:** The Hankin Group

**General Contractor:** Wellington Commercial Construction

**Construction Manager:** Wellington Commercial Construction

**Architects:** Minno & Wasko Architects and Planner

**Engineers:** Liberty Engineering

## General Scope:

**Size:** 147,069 S.F. 4 Story luxury condominiums w/ Parking Garage

**Building Cost:** \$18.1 million

**Schedule:** September 2005 thru May 2007

**Project Delivery:** Design Build



## Architecture:

- Designed in the tradition of grand estate homes
- Situated at Eagleview community town center
- 8 designs with a choice of décor being "traditional" or "contemporary"
- Designated areas for concerts, shopping, dining and fun
- Building surrounded by landscaped parks and native woods
- Stylish brick and cast stone exterior veneer
- Composite slate roof and membrane roof w/ copper eave drip edge



## M.E.P. Systems:

- Fire protection system includes sprinklers, fire alarms and smoke detectors throughout each residence and public areas
- Building access communication system, telephone, cable and internet ready
- HVAC is an all air gas fired furnace supplying each condominium residence
- Main Electrical Distribution switch board is 1600 Amp, 3 phase, 120/208 V
- The main electrical distribution connects to 4 meter banks which are then broken down to each individual apartments

## Construction and Structural:

- Being built in a very developed commercial neighborhood
- Geotech report indicated site had variance in quality of soils
- Installed permanent dewatering system before actual construction
- Delay in Permits and architectural approvals pushed façade construction to winter
- Foundation utilizes 18" strip and column footings w/ 5" slab on grade
- First floor makes use of a 12" heavily reinforced two way flat plate concrete slab
- Other floors use innovative Hambros Joist 3" slab on deck composite system



## Wellington Features:

- 48 unique floor plans up to 2,300 S.F.
- Great views from large bay windows
- Hardwood floors in all living areas
- Polished Granite Countertops
- Elegant lobby entry





*Wellington Condominiums*  
*Exton, PA*  
**Technical Analysis in Cost and Methods**

# Contents

▣ <b>A. Executive Summary</b>	Page 2
▣ <b>B. Detailed Project Schedule</b>	
B.1 Introduction	Page 3
B.2 Wellington Condominiums Project Schedule	Page 4
B.3 Brief Analysis	Page 5
▣ <b>C. Site Layout Planning</b>	
B.1 Introduction	Page 6
B.2 Superstructure Phased Site Plan	Page 7
B.3 Brief Analysis	Page 8
▣ <b>D. Assemblies Estimate</b>	
B.1 Introduction	Page 9
B.2 Building Envelope Assemblies Estimate	Page 10
B.3 Brief Analysis	Page 11
▣ <b>E. Detailed Structural Systems Estimate</b>	
B.1 Introduction	Page 11
B.2 Detailed Structural Systems Estimate	Page 13
B.3 Brief Analysis	Page 14
▣ <b>F. General Conditions Estimate</b>	
B.1 Introduction	Page 15
B.2 General Conditions Estimate	Page 15
B.3 Brief Analysis	Page 16
▣ <b>Appendices</b>	
A. Backup Estimate Calculations	Page 17
B. Site Plan with Utilities	Page 18



# *Wellington Condominiums*

*Exton, PA*

## **Technical Analysis in Cost and Methods**

### **A. Executive Summary**

A technical analysis in cost and construction methods of the Wellington Condominiums project was performed. An in depth study of the project schedule, site layout, and estimates were completed as follows.

The project schedule explored the details of how the building will be constructed. A focus on preconstruction and construction phases has lead the project to begin on September 26, 2005 and end on May 4, 2007. For preconstruction it takes 355 days to complete the tasks of project management, buyout, shop drawings, and fabrication. The construction phase focuses on completing the substructure, superstructure, exterior shell, interior shell, and fit out in 340 days.

The critical part of the schedule occurs when constructing the transfer slab and superstructure. It took 65 days to construct the transfer slab while the foundation and rest of the superstructure respectively took 60 and 172 days. Lost productivity is resulted from constructing the transfer slab and possible schedule reduction/acceleration and constructability review should be looked at in the near future. To make up for lost productivity and delays, a site layout plan is created for the superstructure phase. Communicating the plan to all and laying out key zones in the project site will increase safety and productivity.

An assemblies estimate for the building exterior was calculated and compared to the actual project estimate. The building exterior assemblies estimate includes: the concrete foundation wall, brick and stone cast façade, and roof. The assemblies estimate and actual project estimate are as followed respectively: \$1,966,198, \$1,958,226 (0.41% estimate difference). The 2006 RS Means Assemblies estimating manual was referenced to calculate the building exterior assemblies estimate.

A detailed estimate was prepared for the entire structural system. The detailed structural systems estimate and actual project estimate was compiled and are as followed: \$2,359,438, \$2,530,307 (0.94% estimate difference). The use of RAM Concept and 2005 Cost Works was utilized to calculate the structural systems estimate.

The general conditions for the Wellington Condominiums project were projected to be at a cost of \$692,725.00. This amounts to a 3.83% cost to the entire construction project. To industry standards this is found to be resonable.



# *Wellington Condominiums*

*Exton, PA*

## **Technical Analysis in Cost and Methods**

## **B. Detailed Project Schedule**

### **B.1 Introduction**

A detailed project schedule was developed for Wellington Condominiums to provide a breakdown of the construction phasing and sequencing. The project schedule begins with preconstruction on September 26, 2005 and ends on May 4, 2007 with exterior landscaping. A highlight breakdown of the project schedule is as followed:

- **Preconstruction:** *355 Days Scheduled From Sept. 26,2005 thru Feb. 5, 2007*
  - Project Management
  - Buyout
  - Shop Drawings
  - Fabrication
  
- **Construction:** *340 Days Scheduled From Jan. 16,2006 thru May 4, 2007*
  - Exterior
    - ◆ Site Work
    - ◆ Parking Lot
  - Substructure
    - ◆ Foundations & Columns
    - ◆ Garage Slab
    - ◆ Transfer Slab
  - Superstructure
    - ◆ Wall Panels & Hambros Composite Deck System
    - ◆ Roof Trusses and Decking
    - ◆ Arriscraft & Brickwork
  - Interior Shell
    - ◆ Non-load Bearing Partitions
    - ◆ MEP Rough-in and Distribution
    - ◆ Drywall & Finishes
  - Fit out
    - ◆ Phase 1
    - ◆ Phase 2



***Wellington Condominiums***  
***Exton, PA***  
**Technical Analysis in Cost and Methods**

**B.2 Detailed Project Schedule**

*See the Following Attached Pages*



Wellington Condominiums Detailed Project Schedule

ID	Task Name	Duration	Start	Finish	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul '0	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul '0	Aug	Sep	Oct	Nov				
1	<b>Preconstruction</b>	<b>355 days</b>	<b>Mon 9/26/05</b>	<b>Mon 2/5/07</b>	[Summary bar]																															
2																																				
3	<b>Project Management</b>	<b>111 days</b>	<b>Mon 9/26/05</b>	<b>Mon 2/27/06</b>	[Summary bar]																															
4	Revised Structural Drawings	11 days	Mon 11/7/05	Mon 11/21/05	[Task bar]																															
5	Re-submit for Permits	0 days	Mon 11/21/05	Mon 11/21/05	[Milestone diamond]																															
6	Subcontractor re-bids	5 days	Tue 11/22/05	Mon 11/28/05	[Task bar]																															
7	Final Estimate & Approval	5 days	Tue 11/29/05	Mon 12/5/05	[Task bar]																															
8	Revised Arch, Strut, MEP drawings	26 days	Mon 1/23/06	Mon 2/27/06	[Task bar]																															
9	Permit Approval	80 days	Mon 9/26/05	Fri 1/13/06	[Task bar]																															
10																																				
11	<b>Buyout</b>	<b>167 days</b>	<b>Tue 12/6/05</b>	<b>Thu 7/27/06</b>	[Summary bar]																															
12	Sitework	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
13	Panels and Trusses	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
14	Hambro	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
15	Concrete	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
16	Masonry	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
17	Windows and Doors	1 day	Wed 7/26/06	Thu 7/27/06	[Task bar]																															
18	Elevator	1 day	Thu 1/12/06	Fri 1/13/06	[Task bar]																															
19	Sprinkler	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
20	Plumbing	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
21	Electric	1 day	Tue 12/6/05	Tue 12/6/05	[Task bar]																															
22	Balconettes	20 days	Thu 6/29/06	Thu 7/27/06	[Task bar]																															
23																																				
24	<b>Shop Drawings</b>	<b>206 days</b>	<b>Wed 12/7/05</b>	<b>Thu 9/21/06</b>	[Summary bar]																															
25	Storm Sewer submittals	15 days	Mon 1/9/06	Fri 1/27/06	[Task bar]																															
26	Panel shops	40 days	Thu 6/1/06	Thu 7/27/06	[Task bar]																															
27	Truss shops	40 days	Thu 7/27/06	Thu 9/21/06	[Task bar]																															
28	Hambro shops	35 days	Thu 6/15/06	Thu 8/3/06	[Task bar]																															
29	Elevator shops	20 days	Thu 2/2/06	Thu 3/2/06	[Task bar]																															
30	Balconette shops	30 days	Thu 7/27/06	Thu 9/7/06	[Task bar]																															

Project: Wellington Condominiums  
Date: 10/30/06

Task: [Blue hatched bar] Progress  
Split: [Dotted line] Milestone

Summary: [Black bar] External Tasks: [Grey bar] Deadline: [Green arrow]

Project Summary: [Grey arrow] External Milestone: [Black diamond]

Wellington Condominiums Detailed Project Schedule

ID	Task Name	Duration	Start	Finish	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul '0	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul '0	Aug	Sep	Oct	Nov	
31	Pan stair shops	20 days	Thu 8/31/06	Thu 8/31/06																													
32	Sprinkler shops	40 days	Wed 12/7/05	Tue 1/31/06																													
34	<b>Fabrication</b>	<b>265 days</b>	<b>Mon 1/30/06</b>	<b>Mon 2/5/07</b>																													
35	Storm Sewer Structure	5 days	Mon 1/30/06	Fri 2/3/06																													
36	Panels	30 days	Thu 7/27/06	Thu 9/7/06																													
37	Trusses	40 days	Thu 9/21/06	Thu 11/16/06																													
38	Hambro Joists	25 days	Thu 8/3/06	Thu 9/7/06																													
39	Balconette fab	40 days	Mon 12/11/06	Mon 2/5/07																													
40	Elevator shop drwg review	2 days	Thu 3/2/06	Mon 3/6/06																													
41	Elevator permit	20 days	Mon 3/6/06	Mon 4/3/06																													
42	Elevator fab	65 days	Thu 11/2/06	Thu 2/1/07																													
43	Pan stair fab	20 days	Thu 8/31/06	Thu 9/28/06																													
44	Sprinkler & Water service material	15 days	Wed 2/1/06	Tue 2/21/06																													
46	<b>Construction</b>	<b>340 days</b>	<b>Mon 1/16/06</b>	<b>Fri 5/4/07</b>																													
48	<b>Exterior, shell</b>	<b>335 days</b>	<b>Mon 1/16/06</b>	<b>Fri 4/27/07</b>																													
49	<b>Sitework</b>	<b>49 days</b>	<b>Mon 1/16/06</b>	<b>Thu 3/23/06</b>																													
50	Clear & grub	5 days	Mon 1/16/06	Fri 1/20/06																													
51	Strip topsoil	5 days	Mon 1/23/06	Fri 1/27/06																													
52	<b>Parking lot</b>	<b>39 days</b>	<b>Mon 1/30/06</b>	<b>Thu 3/23/06</b>																													
53	Fill Parking Lot	35 days	Mon 1/30/06	Fri 3/17/06																													
54	Curb Parking Lot	2 days	Mon 3/20/06	Tue 3/21/06																													
55	Stone subgrade parking lot	1 day	Wed 3/22/06	Wed 3/22/06																													
56	Binder Parking Lot	1 day	Thu 3/23/06	Thu 3/23/06																													
57	Township approval for bulk excav	1 day	Mon 1/16/06	Mon 1/16/06																													
58	Security Fence	2 days	Thu 1/26/06	Fri 1/27/06																													
59	Bulk Excavation	10 days	Mon 1/30/06	Fri 2/10/06																													
60	Boulder Removal	13 days	Mon 2/6/06	Wed 2/22/06																													

Project: Wellington Condominiums  
Date: 10/30/06

Task Progress Summary External Tasks Deadline

Split Milestone Project Summary External Milestone


Wellington Condominiums Detailed Project Schedule

ID	Task Name	Duration	Start	Finish	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov				
61	Dewatering pipe	5 days	Thu 2/23/06	Wed 3/1/06																																
62	Storm Sewer	6 days	Thu 2/23/06	Thu 3/2/06																																
63	<b>Substructure</b>	<b>146 days</b>	<b>Wed 2/22/06</b>	<b>Wed 9/13/06</b>																																
64	<b>Foundation &amp; Columns</b>	<b>30 days</b>	<b>Mon 3/13/06</b>	<b>Fri 4/21/06</b>																																
65	Spread and Column Footing L	2 days	Mon 3/13/06	Tue 3/14/06																																
66	Spread Footing Rebar and Cx	5 days	Mon 3/13/06	Fri 3/17/06																																
67	Column Footing Rebar and C	10 days	Fri 3/17/06	Thu 3/30/06																																
68	Foundation Wall Formwork Pl	5 days	Mon 3/27/06	Fri 3/31/06																																
69	Foundation Wall Rebar and C	10 days	Wed 3/29/06	Tue 4/11/06																																
70	Foundation Columns Formwo	10 days	Fri 4/7/06	Thu 4/20/06																																
71	Foundation Columns Rebar a	10 days	Mon 4/10/06	Fri 4/21/06																																
72	Elevator Jack Holes	5 days	Mon 4/3/06	Fri 4/7/06																																
73	Under-slab drainage system & sto	5 days	Mon 4/17/06	Mon 4/24/06																																
74	Sprinkler and Domestic water serv	10 days	Wed 2/22/06	Tue 3/7/06																																
75	<b>Garage Slab</b>	<b>5 days</b>	<b>Mon 4/24/06</b>	<b>Fri 4/28/06</b>																																
76	W.W.F. Layout	2 days	Mon 4/24/06	Tue 4/25/06																																
77	Concrete Pour Bay 1	1 day	Wed 4/26/06	Wed 4/26/06																																
78	Concrete Pour Bay 2	1 day	Thu 4/27/06	Thu 4/27/06																																
79	Concrete Pour Bay 3	1 day	Fri 4/28/06	Fri 4/28/06																																
80	<b>Transfer Slab</b>	<b>65 days</b>	<b>Thu 6/1/06</b>	<b>Wed 8/30/06</b>																																
81	Formwork Placement and Shi	17 days	Thu 6/1/06	Fri 6/23/06																																
82	Rebar Placement	18 days	Mon 6/26/06	Wed 7/19/06																																
83	Concrete Pour Bay 1	10 days	Thu 7/20/06	Wed 8/2/06																																
84	Concrete Pour Bay 2	10 days	Thu 8/3/06	Wed 8/16/06																																
85	Concrete Pour Bay 3	10 days	Thu 8/17/06	Wed 8/30/06																																
86	Foundation waterproofing	5 days	Mon 4/24/06	Fri 4/28/06																																
87	Footing, downspout & condensate	10 days	Mon 5/1/06	Fri 5/12/06																																
88	Backfill	10 days	Thu 8/31/06	Wed 9/13/06																																
89	<b>Superstructure</b>	<b>172 days</b>	<b>Thu 8/31/06</b>	<b>Fri 4/27/07</b>																																
90	<b>Panels and Hambro, floors 1-4</b>	<b>50 days</b>	<b>Thu 9/7/06</b>	<b>Wed 11/15/06</b>																																

Project: Wellington Condominiums Date: 10/30/06	Task		Progress		Summary		External Tasks		Deadline	
	Split		Milestone		Project Summary		External Milestone			




Wellington Condominiums Detailed Project Schedule



Project: Wellington Condominiums Date: 10/30/06	Task		Progress		Summary		External Tasks		Deadline	
	Split		Milestone		Project Summary		External Milestone			


Wellington Condominiums Detailed Project Schedule



Project: Wellington Condominiums Date: 10/30/06	Task		Progress		Summary		External Tasks		Deadline	
	Split		Milestone		Project Summary		External Milestone			

Wellington Condominiums Detailed Project Schedule

ID	Task Name	Duration	Start	Finish	Aug'	Sep'	Oct'	Nov'	Dec'	Jan'	Feb'	Mar'	Apr'	May'	Jun'	Jul '0	Aug'	Sep'	Oct'	Nov'	Dec'	Jan'	Feb'	Mar'	Apr'	May'	Jun'	Jul '0	Aug'	Sep'	Oct'	Nov'
151	FRAMING & BLOCKING, 1	7 days	Thu 11/16/06	Fri 11/24/06																		Nov										
152	MEP ROUGH, 1	7 days	Thu 1/11/07	Fri 1/19/07																												
153	INPECTION, FITOUT, ROUGH, 1	0 days	Fri 1/19/07	Fri 1/19/07																												
154	INSULATION, 1	1 day	Mon 1/22/07	Mon 1/22/07																												
155	DRYWALL, 1	5 days	Mon 1/22/07	Fri 1/26/07																												
156	TAPE & FINISH, 1	5 days	Mon 1/29/07	Fri 2/2/07																												
157	PAINT, SPRAY, 1	3 days	Mon 2/5/07	Wed 2/7/07																												
158	DOORS, TRIM, CABINETS, 1	10 days	Thu 2/8/07	Wed 2/21/07																												
159	FLOORING, 1	10 days	Mon 2/12/07	Fri 2/23/07																												
160	MEP FINISH, 1	5 days	Thu 2/22/07	Wed 2/28/07																												
161	INSPECTION, FITOUT, FINAL, 2	0 days	Wed 2/28/07	Wed 2/28/07																												
162	APPLIANCES, 1	1 day	Wed 2/28/07	Wed 2/28/07																												
163	PAINT, FINISH, 1	4 days	Mon 2/26/07	Thu 3/1/07																												
164	PUNCHLIST, 1	1 day	Fri 3/2/07	Fri 3/2/07																												
165																																
166	Phase 2	88 days	Mon 11/27/06	Wed 3/28/07																												
167	FRAMING & BLOCKING, 2	7 days	Mon 11/27/06	Tue 12/5/06																												
168	MEP ROUGH, 2	7 days	Mon 1/22/07	Tue 1/30/07																												
169	INPECTION, FITOUT, ROUGH, 2	0 days	Tue 1/30/07	Tue 1/30/07																												
170	INSULATION, 2	1 day	Wed 1/31/07	Wed 1/31/07																												
171	DRYWALL, 2	5 days	Thu 2/1/07	Wed 2/7/07																												
172	TAPE & FINISH, 2	5 days	Thu 2/8/07	Wed 2/14/07																												
173	PAINT, SPRAY, 2	3 days	Thu 2/15/07	Mon 2/19/07																												
174	DOORS, TRIM, CABINETS, 2	10 days	Thu 2/22/07	Wed 3/7/07																												
175	FLOORING, 2	10 days	Thu 3/8/07	Wed 3/21/07																												
176	MEP FINISH, 2	5 days	Thu 3/22/07	Wed 3/28/07																												
177	INSPECTION, FITOUT, FINAL, 2	0 days	Wed 3/28/07	Wed 3/28/07																												
178	APPLIANCES, 2	1 day	Wed 3/28/07	Wed 3/28/07																												
179	PAINT, FINISH, 2	4 days	Thu 3/22/07	Tue 3/27/07																												
180	PUNCHLIST, 2	1 day	Wed 3/28/07	Wed 3/28/07																												



Project: Wellington Condominiums  
Date: 10/30/06

Task Progress Summary External Tasks Deadline   
 Split Milestone Project Summary External Milestone



# Wellington Condominiums

Exton, PA

## Technical Analysis in Cost and Methods

### B.3 Brief Analysis

#### B.3.1 Critical Point in Schedule

The detailed project schedule breaks down how the project will flow throughout construction. The transfer slab is a key transition point to the flow and sequence of the project. It takes the project team 65 days to complete the 12" thick 6,000 PSI strength concrete pour versus only spending 60 days to complete the entire foundation systems. If a schedule reduction or acceleration is needed on this project the transfer slab would be the first sequence that should be looked at. After the completion of the foundation and transfer slab sequence, the 4 story superstructure takes 172 days to complete.

#### B.3.2 Phase 1 and 2

Near the end of completion before handover, a phase 1 and phase 2 are established on the project schedule. Phase 1 and 2 include final framing, rough-in, finishes, and punch list. After the main load bearing walls and MEP rough-in and distributions are installed these phases are then utilized. As seen in the diagram below, the structure is cut into two work zones named phase 1 and phase 2. Phase 1 begins trades on the first floor and then moves floor to floor completing condominiums only in the area highlighted. Phase 2 is scheduled to start and finish 28 days after phase 1. The project team decided to do this to speed up the time for handover and make one of the condominiums a show room for potential home owners. Caution must be taken when trying to accelerate the schedule and setting up phases like this. Home owners will be moving and living in phase 1 potentially while construction is in the process of phase 2. How a worker enters the space and how is each room and floor sequenced are questions that the project team must pay attention to when constructing.




Figure 1: First Floor Phase 1 and 2 – Wellington Commercial Construction



# *Wellington Condominiums*

## *Exton, PA*

### **Technical Analysis in Cost and Methods**

#### **B.3.3 Project Delays**

The project schedule attached is an updated best case scenario for the project to be completed. The project team has faced many challenges and has delayed the schedule numerous times. Some of the reasons why the schedule has been delayed are as followed:

- Poor Subsurface Conditions
- Architect and Local Township Approvals
- Change Orders by Owner
- Learning curve to installing new Hambros Joist Composite Deck System

## **C. Site Layout Planning**

### **C.1 Introduction**

A more in depth study of the superstructure phase was utilized through the use of a site plan. The critical phase of the Wellington Condominiums project is the construction of the first floor transfer slab and installation of a repeated load bearing stud walls and Hambros joist composite deck system. Sixty five days are spent constructing the transfer slab and the project has before been delayed on numerous occasions. At the current time it was imperative for the project team to be efficient and accelerate the schedule to get back on track. A good way of proper site planning and organization is to sequence the work through the use of a site plan




***Wellington Condominiums***  
***Exton, PA***  
**Technical Analysis in Cost and Methods**

**C.2 Superstructure Phased Site Plan**

*See the Following Attached Page*






**Wellington Condominiums Site Layout  
Superstructure Construction Analysis**

Uwchlan Township – Chester County - Pennsylvania

Sean Flynn – Construction Management

October 30, 2006 Revision #001



- Installation Key**
- (1) Metal Stud Walls
  - (2) Hambro Joists
  - (3) Rollbars
  - (4) Plywood
  - (5) W.W.F.
  - (6) 3" Concrete Pour
- Pour 5**

**Wellington Condominium Zones**

- Unloading and Vehicle Traffic Zone
- Storage/Equipment/Offices Zone
- Construction Zone

Note: Please see Site Utilities Plan for a complete layout of utilities.

**Drawing Scale**



# *Wellington Condominiums*

## *Exton, PA*

### **Technical Analysis in Cost and Methods**

## **C.3 Brief Analysis**

### **C.3.1 Key Site Project Zones**

The superstructure phased site plan has three main zones named: the unloading and traffic vehicle zone, the storage/equipment/office zone, and the construction zone. These zones offer different functions to the job site for safety and organization. The proper layout of material/equipment/vehicle pathways and sequencing of work is critical to the success of improving productivity on the project site. Needed equipment, tools, and material are placed in each zone by the management team to ensure that crews do not have to travel from one side of the site to the other. All other materials that are not needed are secured in designated storage areas.

### **C.3.2 Superstructure Sequence**

The superstructure phase can be broken down to three main stages of construction. The first stage is doing the floor pour. A concrete pump is used around the entire structure pouring the 4 bays. The concrete pours work in a counterclockwise fashion from the north east corner of the construction zone. The concrete pump and trucks work around the site as noted in the site layout plan till all pours have been completed. Once the concrete pour is completed a 120 ton crane is then positioned on the north side of the building structure to place load bearing metal stud walls. The walls are sequenced and placed so that the crane can easily pick them up and bolt/weld into place without wasting time. The flow of work in placing the metal studs and future construction work will go from the north to the south side of the structure. After the metal studs are in place the Hambros joist composite deck system can be installed as detailed in the site layout plan. This work flow sequence of concrete pours, stud wall placement, and composite deck system will continued right through to the forth floor. Initially a learning curve for the crew is to be expected with the new composite deck system and work sequence. As construction continues the project team expects productivity to increase and schedule time savings.

### **C.3.3 Critique of Contractor Layout**

The site layout utilized by the contractor at this current stage has worked fairly well. When at the project site, the delivery truck drivers and construction workers felt that the site layout did the job. Delivery trucks come from the north end entrance and get unloaded at the construction zone or the designated unloading and vehicle traffic zone. Once the truck is unloaded they proceed to exit out the west side of the site without having to turn around. Construction workers did not have a problem when it came to parking. Ample parking spaces surround the construction site allowing the flexibility of workers to park wherever they see fit. The project management team reorganized the schedule to build the parking lot before construction started. The general consensus by





# *Wellington Condominiums*

## *Exton, PA*

### **Technical Analysis in Cost and Methods**

many construction workers is that the additional parking lot has made work on the construction site much more productive.

Some of the areas that I can see improvements in are accessibility to floor work zones and waste removal. As noted in the attached site layout plan there are only two ladder access points for workers to reach above grade levels. Both ladders being on the south east side of the structure. The project site should have more ways of easily moving up and down floors while construction is underway. Workers trying to haul equipment back and forth everyday can create issues and lost productivity time. By placing material hoists or more ladders around the structure, it will inhibit more productivity and worker morale. Another issue is waste removal on the project site. The waste containers are located on the south side of the project site. This means that any waste must be hauled to this location for removal. If these waste containers are put on either end of the job site, less hauling would have to be required by equipment.

## **D. Assemblies Estimate**

### **D.1 Introduction**

An assembly's estimate was created for the building envelope system. The estimate includes: the concrete foundation, brick and cast stone façade, doors and windows, and roof skin composition. The estimate was broken down with reference to 2006 RS Means Assemblies Estimating Guide. A location factor was applied to the estimate for Allentown, PA for each category as listed in the attached assemblies estimate.



***Wellington Condominiums***  
***Exton, PA***  
**Technical Analysis in Cost and Methods**

**D.2 Building Envelope Assemblies Estimate**

*See the Following Attached Pages*



Estimating Form		Project Summary	
PROJECT	Wellington Condominiums	TOTAL SITE AREA	5.88 Acres
BUILDING TYPE	Residential	OWNER	Hankin Group
LOCATION	Exton PA	ARCHITECT	Minno & Wasko
DATE OF CONSTRUCTION	Spring '06 - Spring '07	ESTIMATED CONSTRUCTION PERIOD	18 Months
BRIEF DESCRIPTION	Wellington Condominiums is a 4 story luxury complex that houses a parking garage on the ground level. The 147,069 SF condominium project features a concrete substructure followed by a series of Hambros Joist 3" Slab on Deck Composite System. The roof system utilizes a single ply EPDM roofing membrane and slate roof system supporting by metal rafters.		

**Assemblies Estimate - Wellington Condominiums Building Envelope**

Estimating Form				Systems Costs						
Qty	Assembly Number	Description	Unit	Mat.	Inst.	Total	Zip Code Prefix	Type	Release	Note
<b>B20 Exterior Closure</b>										
9,312.000	B20101017600	Conc wall reinforced, 8' high, 12" thick, plain finish, 5000 PSI	S.F.	63,787.20	142,939.20	206,726.40	181	Open	2006	Walls are 12' high, 6000 PSI Strength
670.910	B20101023000	Fit precast conc, 4" thick, 5x18', smooth gray, low rise	S.F.	4,193.19	2,475.66	6,668.85	181	Open	2006	
8,998.600	B20101023150	Fit precast conc, 4" thick, 12x20', smooth gray, low rise	S.F.	79,187.68	9,898.46	89,086.14	181	Open	2006	
14,588.330	B20101305200	Brk vnr/met std bkup, std face, 20gax3-5/8" nlb std, 16" OC sp, mng bnd	S.F.	86,071.15	199,860.12	285,931.27	181	Open	2006	22 Gage studs utilized
350.000	B20201046350	Windows, steel, csmt, insul gl, 5'-11" x 5'-2", 3 lite	Ea.	586,250.00	154,000.00	740,250.00	181	Open	2006	Average window size
221.000	B20302102500	Doors, birch, solid core, single door, hinged, 3'-0" x 7'-0" opening	Opng.	226,525.00	54,587.00	281,112.00	181	Open	2006	
<b>B30 Roofing</b>										
7,289.000	B30101202000	Sgl ply memb, EPDM, 45mils, fully adhered	S.F.	6,195.65	5,758.31	11,953.96	181	Open	2006	
25,018.000	B30101402800	Slate roofing, 4" min slope, shingles, 3/16" thick, 8.0 PSF	S.F.	162,617.00	61,043.92	223,660.92	181	Open	2006	
7,289.000	B30104300700	Flashing, copper, no backing, 16 oz, < 500 lbs	S.F.	22,158.56	26,313.29	48,471.85	181	Open	2006	6" Half round copper gutter
776.000	B30106103300	Gutters, half round, copper, 16 oz thick, 5", mill finish	L.F.	4,462.00	3,360.08	7,822.08	181	Open	2006	
1,395.875	B30106200700	Downspouts, copper, rectangular corr, 3"x4", mill, 16 oz thick	V.L.F.	7,049.17	4,997.23	12,046.40	181	Open	2006	
1.000	B30202100200	Roof hatches, with curb, and 1" fiberglass insulation, 2'-6"x3'-0", al	Opng.	605.00	172.00	777.00	181	Open	2006	
<b>Totals</b>				<b>\$1,249,101.59</b>	<b>\$665,405.27</b>	<b>\$1,914,506.86</b>				
<b>Allentown PA location factor multiplier</b>				x	x	x				
				0.98	1.074	1.027				
				<b>\$1,224,119.56</b>	<b>\$714,645.26</b>	<b>\$1,966,198.55</b>				



# *Wellington Condominiums*

*Exton, PA*

## **Technical Analysis in Cost and Methods**

### **D.3 Brief Analysis**

#### **D.3.1 Assumptions**

List of the following assumptions has been made for the attached assemblies estimate and is as followed:

- Doors and Windows are similar in size and composition
- The building is rectangular in form with no other façade protrusions
- All material and equipment needed for installation are included
- Concrete walls are 12' and not 8' in height
- Metal stud walls are 22 gage not 20 gage in composition
- Copper Gutters are 6" half round not 5" half round

#### **D.3.2 Comparison of Assemblies Estimate v. Actual Project Estimate**

The total amount for the assemblies and actual estimates are listed as followed:

- Assemblies Estimate: \$1,966,198.55 = \$13.37 / SF
- Actual Project Estimate: \$1,958,226.00 = \$13.32 / SF
- Estimate Difference: \$7,972.55 = 0.41%


### **E. Detailed Structural Systems Estimate**

#### **E.1 Introduction**


An estimate for the cost of the entire superstructure was analyzed for the structural systems analyses. To calculate more accurately the amount of formwork, rebar, and concrete utilized on the substructure a program called RAM Concept was utilized. A 3D model of the structural system was developed to calculate more accurately the system. A further constructability review of the transfer slab is of great interest. It is hoped that the program will be utilized on whether or not the slab can be reduced in size and schedule. Below are figures of the RAM Concept program utilized for the detailed structural systems estimate. The superstructure of the building was calculated manually with the guide of 2005 Cost Works software.




*Wellington Condominiums*  
*Exton, PA*  
**Technical Analysis in Cost and Methods**



**Figure 2: Transfer Slab Rebar Placement – RAM**



**Figure 3: Foundation – RAM Concept**



**Figure 4: Transfer Slab – RAM Concept**



***Wellington Condominiums***  
***Exton, PA***  
**Technical Analysis in Cost and Methods**

**E.2 Detailed Structural Systems Estimate**

*See the Following Attached Pages*



**Detailed Structural Estimate for Wellington Condominiums**

Total Unit Costs		Foundations, Substructure, Superstructure	
Qty	CSI Number	Description	Total
<b>Division 3 Concrete - Forms and Accessories</b>			
1.000	31104107750	C.I.P. concrete forms, column, square, steel framed plywood, 24" x 24", rent, 4 uses per month, includes erecting, bracing, stripping and cleaning	\$14,951.04
1.000	31104201000	C.I.P. concrete forms, elevated slab, flat plate, plywood, to 15' high, 1 use, includes shoring, erecting, bracing, stripping and cleaning	\$250,836.35
1.000	31104206500	C.I.P. concrete forms, elevated slab, curb forms, wood, 6" to 12" high, 1 use, includes shoring, erecting, bracing, stripping and cleaning	\$4,578.40
1.000	31104207000	C.I.P. concrete forms, elevated slab, edge forms, to 6" high, 4 use, includes shoring, erecting, bracing, stripping and cleaning	\$1,750.00
1.000	31104559260	C.I.P. concrete forms, walls, steel framed plywood, over 8' to 16' high, based on 100 uses of purchased forms, 4 uses of bracing lumber, includes erecting, bracing, stripping and cleaning	\$66,704.20
1.000	31500800020	Anchor bolts, J-type, 1/2" diameter x 6" long, includes nut and washer	\$1,338.60
1.000	31501701000	Column clamp, adjustable, buy, to 24" x 24"	\$85.00
1.000	31506001500	Shores, reshoring	\$20,912.40
<b>Division 3 Concrete - Reinforcement</b>			
1.000	32101001200	High chairs, for reinforcing steel, individual, no plates, plain, to 3' high, includes material only	\$19,821.00
1.000	32101001500	Bar chair, for reinforcing steel, plain, includes material only	\$14,852.26
1.000	32106000200	Reinforcing steel, in place, columns, #3 to #7, A615, grade 60, incl access. Labor	\$8,465.76
1.000	32106000400	Reinforcing steel, in place, elevated slabs, #4 to #7, A615, grade 60, incl access. Labor	\$67,314.35
1.000	32106000500	Reinforcing steel, in place, footings, #4 to #7, A615, grade 60, incl access. Labor	\$40,692.09
1.000	32106000700	Reinforcing steel, in place, walls, #3 to #7, A615, grade 60, incl access. Labor	\$16,049.42
1.000	32202000200	Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1 (8 x 8) 30 lb. per C.S.F., A185	\$12,748.80
1.000	32202000300	Welded wire fabric, sheets, 6 x 6 - W2.9 x W2.9 (6 x 6) 42 lb. per C.S.F., A185	\$58,268.00
<b>Division 3 Concrete - Cast-In-Place</b>			
1.000	33102200150	Structural concrete, ready mix, normal weight, 3000 psi, includes material only	\$132,168.96
1.000	33102200411	Structural concrete, ready mix, normal weight, 6000 PSI, includes material only	\$207,304.69
0.000	33102201000	Structural concrete, ready mix, high early strength cement, add, includes material only	
1.000	33107000800	Structural concrete, placing, column, square or round, pumped, 24" thick, includes vibrating, excludes material	\$1,820.03
1.000	33107001400	Structural concrete, placing, elevated slab, pumped, less than 6" thick, includes vibrating, excludes material	\$18,764.50
1.000	33107001600	Structural concrete, placing, elevated slab, pumped, over 10" thick, includes vibrating, excludes material	\$14,104.62
1.000	33107002650	Structural concrete, placing, spread footing, pumped, over 5 C.Y., includes vibrating, excludes material	\$8,204.02
1.000	33107003250	Structural concrete, placing, grade beam, pumped, includes vibrating, excludes material	\$1,043.47
1.000	33107004350	Structural concrete, placing, slab on grade, pumped, 4" thick, includes vibrating, excludes material	\$8,267.89
1.000	33107005100	Structural concrete, placing, walls, pumped, 12" thick, includes vibrating, excludes material	\$8,208.07
1.000	33503000250	Concrete finishing, floors, monolithic, machine trowel finish	\$61,705.35
1.000	33503250120	Control joint, concrete floor slab, saw cut in green concrete, 1" depth	\$794.04
<b>Division 5 Metals - Cold Formed Framing</b>			
1.000	54104006400	Partition, galv LB studs, 16 ga x 6" W studs 16" O.C. x 12" H, incl galv top & bottom track, excl openings, headers, beams, bracing & bridging	\$403,447.20
1.000	54204100550	Floor joist, galv CF steel, 12 ga x 12" D, incl joists (2" flange) & fasteners, excl band joists (track), web stiffeners, headers, beams, bridging & bracing, materials only	\$153,159.24
1.000	54204101550	Floor joist, galv CF steel, 12 ga x 12" D, incl fastening to band joists, beams & headers, excl materials, labor only	\$46,305.00
			<b>Total: \$1,664,664.75</b>
			(Addition of 3.9% Total Cost Escalation)
			<b>\$1,729,586.68</b>
			ENR Building Cost Index Inflation from 2005 to 2006
			Allentown, PA Location Factor already in calculations



**Detailed Structural Estimate for Wellington Condominiums**

Wall Strip Footings													Foundations		
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release	
<b>Division 3 Concrete</b>															
7.610	32101001200	High chairs, for reinforcing steel				C	506.07	0.00	0.00	506.07	555.53	181	Open	2005	
7.610	32101001500	Bar chair, for reinforcing steel				C	285.38	0.00	0.00	285.38	312.01	181	Open	2005	
2.445	32106000500	Reinforcing steel, in place, footings, #4 to #7	4 Rodm	2.1	15.238	Ton	1,919.33	1,088.03	0.00	3,007.35	4,034.25	181	Open	2005	
84.56	33102200411	Structural concrete, ready mix, normal weight				C.Y.	7,737.24	0.00	0.00	7,737.24	8,510.96	181	Open	2005	
84.56	33107003250	Structural concrete, placing, grade beam	C20		180	C.Y.	0.00	634.20	409.27	1,043.47	1,509.40	181	Open	2005	
<b>Totals</b>							<b>\$10,448.01</b>	<b>\$1,722.23</b>	<b>\$409.27</b>	<b>\$12,579.50</b>	<b>\$14,922.15</b>				
									ENR Building Cost Index Inflation from 2005 to 2006 Allentown, PA Location Factor already in calculations			(Addition of 3.9% Total Cost Escalation)			
											<b>\$13,070.10</b>				

Single Slab Column Footings													Foundations		
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release	
<b>Division 3 Concrete</b>															
98.000	32101001500	Bar chair, for reinforcing steel				C	3,675.00	0.00	0.00	3,675.00	4,018.00	181	Open	2005	
30.638	32106000500	Reinforcing steel, in place, footings, #4 to #7	4 Rodm	2.1	15.238	Ton	24,050.83	13,633.91	0.00	37,684.74	50,552.70	181	Open	2005	
556.205	33102200411	Structural concrete, ready mix, normal weight				C.Y.	50,892.76	0.00	0.00	50,892.76	55,982.03	181	Open	2005	
556.205	33107002650	Structural concrete, placing, spread footing	C20		150	C.Y.	0.00	4,978.03	3,225.99	8,204.02	11,958.41	181	Open	2005	
<b>Totals</b>							<b>\$78,618.59</b>	<b>\$18,611.94</b>	<b>\$3,225.99</b>	<b>\$100,456.52</b>	<b>\$122,511.14</b>				
									ENR Building Cost Index Inflation from 2005 to 2006 Allentown, PA Location Factor already in calculations			(Addition of 3.9% Total Cost Escalation)			
											<b>\$104,374.32</b>				

Foundation Walls													Substructure		
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release	
<b>Division 3 Concrete</b>															
21,942.170	31104559260	C.I.P. concrete forms, walls	C2		450	SFCA	8,338.02	58,366.17	0.00	66,704.20	108,174.90	181	Open	2005	
14.657	32106000700	Reinforcing steel, in place, walls, #3 to #7	4 Rodm	3	10.667	Ton	11,505.75	4,543.67	0.00	16,049.42	20,886.23	181	Open	2005	
406.340	33102200411	Structural concrete, ready mix, normal weight				C.Y.	37,180.11	0.00	0.00	37,180.11	40,898.12	181	Open	2005	
406.340	33107005100	Structural concrete, placing, walls, pumped	C20		110	C.Y.	0.00	4,977.67	3,230.40	8,208.07	11,783.86	181	Open	2005	
<b>Totals</b>							<b>\$57,023.88</b>	<b>\$67,887.51</b>	<b>\$3,230.40</b>	<b>\$128,141.79</b>	<b>\$181,743.10</b>				
									ENR Building Cost Index Inflation from 2005 to 2006 Allentown, PA Location Factor already in calculations			(Addition of 3.9% Total Cost Escalation)			
											<b>\$133,139.32</b>				

**Detailed Structural Estimate for Wellington Condominiums**

Foundation Columns													Substructure			
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release		
<b>Division 3 Concrete</b>																
4,516.930	31104107750	C.I.P. concrete forms, column, square	C1	440	0.073	SFCA	6,865.73	8,085.30	0.00	14,951.04	21,274.74	181	Open	2005		
1.000	31501701000	Column clamp, adjustable, buy, to 24" x 24"				Set	85.00	0.00	0.00	85.00	93.50	181	Open	2005		
5.879	32106000200	Reinforcing steel, in place, columns, #3 to #7	4 Rodm	1.5	21.333	Ton	4,850.18	3,615.59	0.00	8,465.76	11,758.00	181	Open	2005		
75.520	33102200411	Structural concrete, ready mix, normal weight				C.Y.	6,910.08	0.00	0.00	6,910.08	7,601.09	181	Open	2005		
75.520	33107000800	Structural concrete, placing, column, square	C20	92	0.696	C.Y.	0.00	1,106.37	713.66	1,820.03	2,643.20	181	Open	2005		
<b>Totals</b>							<b>\$18,710.99</b>	<b>\$12,807.26</b>	<b>\$713.66</b>	<b>\$32,231.91</b>	<b>\$43,370.53</b>					
ENR Building Cost Index Inflation from 2005 to 2006										(Addition of 3.9% Total Cost Escalation)						
Allentown, PA Location Factor already in calculations										<b>\$33,488.95</b>						

Slab on Grade													Substructure			
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release		
<b>Division 3 Concrete</b>																
307.200	32202000200	Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1	2 Rodm	31	0.516	C.S.F.	8,140.80	4,608.00	0.00	12,748.80	17,203.20	181	Open	2005		
484.920	33102200150	Structural concrete, ready mix, normal weight				C.Y.	38,405.66	0.00	0.00	38,405.66	42,246.23	181	Open	2005		
484.920	33107004350	Structural concrete, placing, slab on grade	C20	130	0.492	C.Y.	0.00	5,018.92	3,248.96	8,267.89	11,880.54	181	Open	2005		
30,720.000	33503000250	Concrete finishing, floors, monolithic	1 Cefi	550	0.015	S.F.	0.00	10,752.00	0.00	10,752.00	17,510.40	181	Open	2005		
509.000	33503250120	Control joint, concrete floor slab	C27	2,000	0.008	L.F.	0.00	96.71	35.63	132.34	193.42	181	Open	2005		
<b>Totals</b>							<b>\$46,546.46</b>	<b>\$20,475.63</b>	<b>\$3,284.59</b>	<b>\$70,306.69</b>	<b>\$89,033.79</b>					
ENR Building Cost Index Inflation from 2005 to 2006										(Addition of 3.9% Total Cost Escalation)						
Allentown, PA Location Factor already in calculations										<b>\$73,048.65</b>						

Transfer Slab													Superstructure			
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release		
<b>Division 3 Concrete</b>																
29,045.000	31104201000	C.I.P. concrete forms, elevated slab, flat plate	C2	470	0.102	S.F.	118,503.60	74,064.75	0.00	192,568.35	255,596.00	181	Open	2005		
776.000	31104206500	C.I.P. concrete forms, elevated slab, curb forms	C1	180	0.178	SFCA	1,171.76	3,406.64	0.00	4,578.40	7,022.80	181	Open	2005		
388.000	31500800020	Anchor bolts, J-type, 1/2" diameter x 6" long	1 Carp	90	0.089	Ea.	372.48	966.12	0.00	1,338.60	2,056.40	181	Open	2005		
29,045.000	31506001500	Shores, reshoring	2 Carp	1,400	0.011	S.F.	11,327.55	9,584.85	0.00	20,912.40	28,173.65	181	Open	2005		
290.450	32101001200	High chairs, for reinforcing steel				C	19,314.93	0.00	0.00	19,314.93	21,202.85	181	Open	2005		
290.450	32101001500	Bar chair, for reinforcing steel, plain				C	10,891.88	0.00	0.00	10,891.88	11,908.45	181	Open	2005		
56.330	32106000400	Reinforcing steel, in place, elevated slabs	4 Rodm	2.9	11.034	Ton	49,288.75	18,025.60	0.00	67,314.35	85,903.25	181	Open	2005		
1,143.000	33102200411	Structural concrete, ready mix, normal weight				C.Y.	104,584.50	0.00	0.00	104,584.50	115,042.95	181	Open	2005		
1,143.000	33107001600	Structural concrete, placing, elevated slab	C20	180	0.356	C.Y.	0.00	8,572.50	5,532.12	14,104.62	20,402.55	181	Open	2005		
29,045.000	33503000250	Concrete finishing, floors, monolithic	1 Cefi	550	0.015	S.F.	0.00	10,165.75	0.00	10,165.75	16,555.65	181	Open	2005		
509.000	33503250120	Control joint, concrete floor slab	C27	2,000	0.008	L.F.	0.00	96.71	35.63	132.34	193.42	181	Open	2005		
<b>Totals</b>							<b>\$315,455.44</b>	<b>\$124,882.92</b>	<b>\$5,567.75</b>	<b>\$445,906.11</b>	<b>\$564,057.97</b>					
ENR Building Cost Index Inflation from 2005 to 2006										(Addition of 3.9% Total Cost Escalation)						
Allentown, PA Location Factor already in calculations										<b>\$463,296.45</b>						

**Detailed Structural Estimate for Wellington Condominiums**

Metal Stud Framing		Superstructure												
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release
<b>Division 5 Metals</b>														
13,936.000	54104006400	Partition, galv LB studs, 16 ga x 6" W studs	2 Carp	51	0.314	L.F.	262,693.60	140,753.60	0.00	403,447.20	529,568.00	181	Open	2005
<b>Totals</b>							<b>\$262,693.60</b>	<b>\$140,753.60</b>	<b>\$0.00</b>	<b>\$403,447.20</b>	<b>\$529,568.00</b>			
ENR Building Cost Index Inflation from 2005 to 2006 Allentown, PA Location Factor already in calculations										(Addition of 3.9% Total Cost Escalation)				
										<b>\$419,181.64</b>				

Hambro Joist System and Components		Superstructure												
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release
<b>Division 5 Metals</b>														
25526.54	54204100550	Floor joist, galv CF steel, 12 ga x 12" D				L.F.	153,159.24	0.00	0.00	153,159.24	167,198.84	181	Open	2005
2,700.000	54204101550	Floor joist, galv CF steel, 12 ga x 12" D	2 Carp	30	0.533	Ea.	0.00	46,305.00	0.00	46,305.00	78,300.00	181	Open	2005
<b>Totals</b>							<b>\$153,159.24</b>	<b>\$46,305.00</b>	<b>\$0.00</b>	<b>\$199,464.24</b>	<b>\$245,498.84</b>			
ENR Building Cost Index Inflation from 2005 to 2006 Allentown, PA Location Factor already in calculations										(Addition of 3.9% Total Cost Escalation)				
										<b>\$207,243.35</b>				

Deck Slabs		Superstructure												
Qty	CSI Number	Description	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Total	Total Incl. O&P	Zip Code Prefix	Type	Release
<b>Division 3 Concrete</b>														
29,134.000	31104201000	C.I.P. concrete forms, elevated slab, flat plate	C2	470	0.102	S.F.	14,567.00	14,567.00	0.00	58,268.00	98,181.58	181	Open	2005
1,000.000	31104207000	C.I.P. concrete forms, elevated slab, edge forms	C1	500	0.064	L.F.	170.00	1,580.00	0.00	1,750.00	2,860.00	181	Open	2005
1,165.360	32202000300	Welded wire fabric, sheets, 6 x 6 - W2.9 x W2.9	2 Rodm	29	0.552	C.S.F.	39,622.24	18,645.76	0.00	58,268.00	76,331.08	181	Open	2005
1,183.880	33102200150	Structural concrete, ready mix, normal weight				C.Y.	93,763.30	0.00	0.00	93,763.30	103,139.63	181	Open	2005
1,183.880	33102201000	Structural concrete, ready mix				C.Y.	10,000%	0.00	0.00	0.00	0.00	181	Open	2005
1,183.880	33107001400	Structural concrete, placing, elevated slab	C20	140	0.457	C.Y.	0.00	11,424.44	7,340.06	18,764.50	27,229.24	181	Open	2005
116,536.000	33503000250	Concrete finishing, floors, monolithic	1 Cefl	550	0.015	S.F.	0.00	40,787.60	0.00	40,787.60	66,425.52	181	Open	2005
2,036.000	33503250120	Control joint, concrete floor slab	C27	2,000	0.008	L.F.	0.00	386.84	142.52	529.36	773.68	181	Open	2005
<b>Totals</b>							<b>\$148,122.64</b>	<b>\$87,391.64</b>	<b>\$7,482.58</b>	<b>\$272,130.75</b>	<b>\$374,940.73</b>			
ENR Building Cost Index Inflation from 2005 to 2006 Allentown, PA Location Factor already in calculations										(Addition of 3.9% Total Cost Escalation)				
										<b>\$282,743.85</b>				



# *Wellington Condominiums*

*Exton, PA*

## **Technical Analysis in Cost and Methods**

### **E.3 Brief Analysis**

#### **E.3.1 Assumptions**

A list of the following assumptions has been made for the attached structural estimate and is as followed:

- Concrete is 6000 PSI strength not 5000 PSI strength
- No vapor barriers/insulation/waterproofing/non load bearing walls
- No stairways or elevators
- Foundation wall forms include temporary shoring
- No expansion joints, inserts, sleeves, chases, splicing
- No metal roof framing – design and built by specialty company
- Accessories/tools found in general conditions
- No Waste was included in calculations
- Balcony reinforcing similar to other parts of composite deck
- Not including steel W members assume part of metal stud framing
- The second, third, and forth floor the same
- No detail connections required for joist members
- Footings on the same grade and reinforcing

#### **E.3.2 Comparison of Detailed Estimate v. Actual Project Estimate**

The total amount for the detailed and actual estimates are listed as followed:

- Detailed Estimate: \$1,966,198.55 = \$13.37 / SF
- Actual Project Estimate: \$2,530,307.00 = \$17.20 / SF
- Estimate Difference: \$564,108.45 = 3.12%

The results are different due to the fact the detailed estimate performed did not take into consideration waste or the need of such things like detailed connections or splices. The detailed estimate is a near perfect representation of everything performing up to expectations without delays or problems. Just the structural miscellaneous metals on the project were alone budgeted for \$200,000.00. To compare more accurately the estimates, if add a factor of 20% for waste, detailed connections, and miscellaneous metals the totals are as followed:

- Detailed Estimate: \$2,359,438.26 = \$16.04 / SF
- Actual Project Estimate: \$2,530,307.00 = \$17.20 / SF
- Estimate Difference: \$170,868.74 = 0.94%



**Wellington Condominiums**  
*Exton, PA*  
**Technical Analysis in Cost and Methods**

**F. General Conditions Estimate**

**F.1 Introduction**

An estimate for the general conditions was assembled for the Wellington Condominiums project. Part of the estimate includes the following costs: management team, inspections, permits, temporary signs, temporary utilities, construction trailers, tools, and punch list. What is not included in the general conditions are consultants and geotechnical services. These costs are paid for by the owner of the project and not on the general conditions.

**F.2 General Conditions Estimate**

**General Conditions Estimate for Wellington Condominiums**

<b>General Conditions</b>				
Description	Quantity	Unit	Unit Cost	Total
SR. PROJECT MANAGER	35	WKS	\$3,500.00	\$122,500
SUPERINTENDENT	60	WKS	\$3,000.00	\$180,000
LABORER	52	WKS	\$800.00	\$41,600
ASSISTANT SUPERINTENDENT	30	WKS	\$2,500.00	\$75,000
SURVEYING	1	L.S	\$22,000.00	\$22,000
INSPECTIONS	1	L.S	\$30,000.00	\$30,000
TWP BLDG PERMIT	1	L.S	\$44,405.00	\$44,405
FITOUT PERMIT	48	EACH	\$400.00	\$19,200
TEMPORARY UTILITIES	1	L.S	\$30,000.00	\$30,000
TEMPORARY SIGNS	1	EACH	\$2,500.00	\$2,500
CONSTRUCTION TRAILERS	14	MTH	\$300.00	\$4,200
OFFICE EXPENSES (BLUE PRINTS)	116,000	S.F.	\$0.22	\$25,520
TRASH REMOVAL (DUMPSTERS)	60	EACH	\$500.00	\$30,000
EQUIP & TOOL RENTALS	1	L.S	\$20,000.00	\$20,000
MATERIALS & SUPPLIES	12	MTH	\$200.00	\$2,400
FINAL SITE CLEAN-UP	1	EACH	\$5,000.00	\$5,000
FINAL BUILDING CLEAN-UP	48	EACH	\$400.00	\$19,200
PUNCH LIST	48	EACH	\$400.00	\$19,200
<b>Total:</b>				<b>\$692,725.00</b>



# *Wellington Condominiums*

*Exton, PA*

## **Technical Analysis in Cost and Methods**

### **F.3 Brief Analysis**

#### **E.3.2 Comparison of General Conditions Estimate v. Industry Standards**

The total general condition cost for the Wellington Condominium project is \$692,725.00. The percentage of the total construction dedicated to the general conditions is 3.83%. The project staff in technical assignment #1 was used to calculate the general conditions. The 3.83% of total construction cost that the general conditions accumulate are reasonable in today's construction industry.



***Wellington Condominiums***  
***Exton, PA***  
**Technical Analysis in Cost and Methods**

**A. Appendix A – Backup Estimate Calculations**

*See the Following Attached Pages*



**Wellington Condominiums Takeoffs**

Single Slab Column Footings				Takeoffs						
Dimensions				Volume (in^3)	Concrete (CY)	Rebar (LFT)	Formwork (SFCA)	Rebar (lbs.)	Rebar (Tons)	
Length (in.)	x	Width (in.)	x							Depth (in.)
198		198		18	705672	15.125	1633.5	0	1703.741	0.85187
204		204		18	749088	16.05556	1734	0	1808.562	0.904281
195		195		18	684450	14.67014	1584.375	0	1652.503	0.826252
186		186		18	622728	13.34722	1441.5	0	1503.485	0.751742
201		201		18	727218	15.58681	1683.375	0	1755.76	0.87788
195		195		18	684450	14.67014	1584.375	0	1652.503	0.826252
204		204		18	749088	16.05556	1734	0	1808.562	0.904281
198		198		18	705672	15.125	1633.5	0	1703.741	0.85187
147		147		18	388962	8.336806	900.375	0	939.0911	0.469546
216		216		18	839808	18	1944	0	2027.592	1.013796
234		234		18	985608	21.125	2281.5	0	2379.605	1.189802
183		183		15	502335	10.76678	1395.375	0	1455.376	0.727688
198		198		18	705672	15.125	1633.5	0	1703.741	0.85187
183		183		15	502335	10.76678	1395.375	0	1455.376	0.727688
234		234		18	985608	21.125	2281.5	0	2379.605	1.189802
216		216		18	839808	18	1944	0	2027.592	1.013796
147		147		18	388962	8.336806	900.375	0	939.0911	0.469546
222		222		24	1182816	25.35185	2053.5	0	2141.801	1.0709
204		204		18	749088	16.05556	1734	0	1808.562	0.904281
234		234		18	985608	21.125	2281.5	0	2379.605	1.189802
159		159		21	530901	11.37905	1053.375	0	1098.67	0.549335
234		234		18	985608	21.125	2281.5	0	2379.605	1.189802
204		204		18	749088	16.05556	1734	0	1808.562	0.904281
186		186		24	830304	17.7963	1441.5	0	1503.485	0.751742
222		222		21	1034964	22.18287	2053.5	0	2141.801	1.0709
222		222		18	887112	19.01389	2053.5	0	2141.801	1.0709
222		222		18	887112	19.01389	2053.5	0	2141.801	1.0709
189		189		18	642978	13.78125	1488.375	0	1552.375	0.776188
213		213		15	816642	17.50347	1890.375	0	1971.661	0.985831
186		186		15	518940	11.12269	1441.5	0	1503.485	0.751742
213		213		18	816642	17.50347	1890.375	0	1971.661	0.985831
189		189		18	642978	13.78125	1488.375	0	1552.375	0.776188
222		222		18	887112	19.01389	2053.5	0	2141.801	1.0709
222		222		21	1034964	22.18287	2053.5	0	2141.801	1.0709
<b>Totals:</b>					<b>556.21</b>	<b>58751</b>	<b>61277</b>	<b>30.638</b>		



Wellington Condominiums Takeoffs

Hambros Joists			Takeoffs		
Joists	FT	IN	LFT	# OF JOISTS	TOTAL LFT
J9	27	2	27.16667	2	54.33333
J10	27	2	27.16667	6	163
J11	23		23	2	46
J12	19		19	2	38
J13	18		18	2	36
J14	19	4	19.33333	5	96.66667
J15	15	3.5	15.29167	6	91.75
J16	18	9	18.75	2	37.5
J17	22	9	22.75	2	45.5
J18	26	9	26.75	2	53.5
J19	26	3.5	26.29167	11	289.2083
J21	26	3.5	26.29167	4	105.1667
J22	11	9.5	11.79167	2	23.58333
J23	11	9.5	11.79167	6	70.75
J24	11	9	11.75	12	141
J25	11	9	11.75	2	23.5
J26	17		17	6	102
J27	17	4.5	17.375	12	208.5
J28	20	1.25	20.10417	4	80.41667
J65	20	0.25	20.02083	2	40.04167
J29	13	5.5	13.45833	2	26.91667
J30	13	5.5	13.45833	18	242.25
J31	11	5.5	11.45833	2	22.91667
J23	11	5.5	11.45833	3	34.375
J25	11	2.5	11.20833	5	56.04167
J32	11	2.5	11.20833	4	44.83333
J25	11	2.5	11.20833	2	22.41667
J33	15	2	15.16667	6	91
J34	15	10.625	15.88542	12	190.625
J28	20	0.625	20.05208	2	40.10417
J29	13	5.5	13.45833	2	26.91667
J30	13	5.5	13.45833	14	188.4167
J35	13	5.5	13.45833	4	53.83333
J28	20	0.625	20.05208	2	40.10417
J23	11	9.5	11.79167	3	35.375
J25	11	4.5	11.375	5	56.875
J25	11	2.625	11.21875	2	22.4375
J7	12		12	6	72
J67	15	6	15.5	1	15.5
J36	19	11	19.91667	2	39.83333
J37	19	3.5	19.29167	8	154.3333
J38	17	7.5	17.625	6	105.75
J68	25	11.5	25.95833	1	25.95833
J39	25	11.5	25.95833	5	129.7917
J40	21	10.5	21.875	6	131.25
J41	22	6	22.5	8	180
J42	20	4	20.33333	2	40.66667
J43	20	4	20.33333	6	122
J44	7	2	7.166667	2	14.33333
J45	10	5.5	10.45833	6	62.75
J30	13	5.5	13.45833	23	309.5417
J46	20	9.625	20.80208	1	20.80208
J47	21	9	21.75	2	43.5
J52	18	7.5	18.625	3	55.875
J48	15	5.5	15.45833	3	46.375
J49	15	5.5	15.45833	3	46.375
J50	12	8	12.66667	24	304
J45	10	8.625	10.71875	2	21.4375
J2	6	3.25	6.270833	1	6.270833
J53	9	8.75	9.729167	3	29.1875
J54	5	9.25	5.770833	3	17.3125
J55	12	11.625	12.96875	3	38.90625
J56	9	0.625	9.052083	1	9.052083
J24	11	8	11.66667	9	105
J57	18	4	18.33333	2	36.66667
J58	10		10	12	120
J56	9	0.625	9.052083	1	9.052083
J24	11	8	11.66667	9	105
J26	16	11.375	16.94792	1	16.94792
J52	18	6	18.5	2	37
J48	15	4	15.33333	4	61.33333
J49	15	4	15.33333	3	46
J45	10	5.5	10.45833	3	31.375
J30	13	5.5	13.45833	8	107.6667
J46	21	9	21.75	1	21.75
J47	21	9	21.75	2	43.5
J52	18	9.5	18.79167	3	56.375
J48	15	5.5	15.45833	3	46.375
J49	15	5.5	15.45833	3	46.375
J44	7	2	7.166667	2	14.33333
J45	10	3.5	10.29167	4	41.16667
J67	19	11	19.91667	1	19.91667
J1	9	5.625	9.46875	2	18.9375
J2	6	1.625	6.135417	19	116.5729
J3	7	8.625	7.71875	3	23.15625
J4	8	1.625	8.135417	12	97.625
J5	7	4	7.333333	3	22
J6	9	0.625	9.052083	10	90.52083
J8	15	7	15.58333	4	62.33333
<b>TOTAL LFT:</b>					6381.6
X					
<u>4 FLOORS</u>					
<b>25527 LFT</b>					



# Wellington Condominiums

## Exton, PA

### Technical Analysis in Cost and Methods

## Backup Estimate Calculations

Notes

50G → 300 PSI 6'20' days → strength  
 → ASTM A615 Grade 60 → Reinforcing  
 → Mesh ASTM A185

Concrete → 600 PSI @ 28 days  
 → Reinforcing A615 Grade 60

Wall Studs → 16" on center  
 → 4" x 6" depth  
 → 16" G-Base min.  
 → 2 Studs on wall edges

Joints → D-500 steel joint & rebar

- Assume walls est. straight  
 - Not including outside system (min)  
 - Not including stair elevators towers & no structural system  
 - Assume form for foundation walls include support

Foundation Notes

Concrete Notes

col/formed Metal Framing Notes

First Floor  
 formwork horizontal ✓ (wood)  
 vertical → metal supports w/plywood  
 need 4x4" of frame

→ No waste included - 5"

### General Notes



**Wellington Condominiums**  
**Exton, PA**  
**Technical Analysis in Cost and Methods**

Wall Footings → perimeter #5 @ 10 Freeze 3' below surface min

4 #4  
 Perimeter =  $6224'' \text{ "cont."} + 2908'' = 9132 \text{ in} = 761 \text{ LF}$

CY  $(761 \text{ LF})(3')(1') = 2283 \text{ ft}^3 = \boxed{84.56 \text{ cy}}$

Rebar (#4)  $(761 \text{ LF}) \times 4 = \boxed{3044 \text{ LF \#4}}$   
 (#5)  $913.2 \text{ LF} \times \#5 @ 3' \text{ long} = \boxed{2739.6 \text{ LF \#5}}$

#4 0.668  $\text{lb/ft}$   
#5 1.043  $\text{lb/ft}$

Forms None

WALL STRIP

Wall Strip Calculations



**Wellington Condominiums**  
**Exton, PA**  
**Technical Analysis in Cost and Methods**

(3)  $l \times w \times d$   
 $198'' \times 198'' \times 18'' \Rightarrow 6,000 \text{ psi}$  3" Below frost line no

Single slab Column Footing  
 #5  $\Rightarrow .31 \text{ in}^2/\text{bar}$ , 1.043  $\frac{l}{A}$

$l = \left( \left( \frac{l}{4} \right) \times 2 \right) \times l = \frac{l^2}{2}$

$l = \frac{l^2}{24} = l A \text{ rebar req.}$

$\left( \frac{l \times w \times d}{46656} \right) = CV$   
 (in. for dm.)

Concrete 408.38  $\text{ft}^3 \Rightarrow 15.125 \text{ cy}$

rebar 163.5  $\text{ft} = \frac{(198'')^2}{24}$

formwork None required

Spread Footings

**Column Spread Footings**



**Wellington Condominiums**  
**Exton, PA**  
**Technical Analysis in Cost and Methods**

**Wall** 12" thick

**CY**

**FW** **SFCA** → sides will be included in waste

3112" x 173" (4) ⇒ 14954.89 ft<sup>2</sup>

1454" x 173" (4) ⇒ 6987.28 ft<sup>2</sup>

21942.17 ft<sup>2</sup>

**rebar**

(#4) 6224" + 2908" = 9132" perimeter ⇒ **761 ft**

→ 15 levels of #4 x 2 bars x 761 ft = **21942.17 lft**

→ 761 sets of 2 #4 rebar req @ 173" high = **21942.17 lft**

**total #4 req:** **43884.34 lft**

**#4** ⇒ 0.668 lb./ft

Foundation Wall



# Wellington Condominiums

Exton, PA


## Technical Analysis in Cost and Methods

column

20 #4 → Assume all column similar (typ.)  
 → Assume all #4 → changes size


#3 ties @ 12" on outside & inside


#3 ⇒ 0.376 l<sup>3</sup>/ft  
 #4 ⇒ 0.668 l<sup>3</sup>/ft



Rebar for 16x30 (17)

20 #4 @ 173" = 3460 in = 288.33 l<sup>3</sup>/column


 #3 15 times 7.67 l<sup>3</sup> req./loop ⇒ 115 l<sup>3</sup>/column

 #3 15 times 5.17 l<sup>3</sup> req./loop ⇒ 77.5 l<sup>3</sup>/column

= 1.637 ton, 36754, 0.24769 = 2.252 ton

rebar for 16x34 (17)

26 #4 @ 173" ⇒ 374.83 l<sup>3</sup>/column

 #3 15 times 8.33 l<sup>3</sup> req./loop ⇒ 125 l<sup>3</sup>/column


#3 15 times 5.5 l<sup>3</sup> req./loop ⇒ 82.5 l<sup>3</sup>/column


= 2.128 ton, .3995, .6367 = 2.7917 ton

Rebar for 16x46 (4)

3e2bar: 461.33 l<sup>3</sup>/column #4

155 l<sup>3</sup>/column #3

 0.61634 ton

 0.11656 ton = 0.8363 ton

Foundation Columns



# Wellington Condominiums

Exton, PA

## Technical Analysis in Cost and Methods

(SOG)

5" ↓

6' ↑

44' →

21' →

259' - 4" →

121' - 2" →

→ Reinforcing w/ 6x6 - W2.1 x W2.1 W.W.F.

(CY) 484.92 cy

(Rebar) → W.W.F → need 924 6'x6' W.W.F

(Form) None req. → walls across forms later poured

SOG

Slab on Grade



# Wellington Condominiums

Exton, PA

## Technical Analysis in Cost and Methods

Slab  $206'0'' \times 120'2'' \Rightarrow 31964.33 \text{ ft}^2$

- (CY)  $3'' \Rightarrow 295.97 \text{ yd concrete}$
- (FW) <sup>bottom</sup> plywood 4' wide need 7991.08 lft @  
 $4' \times 8'$  need 999 pieces
- (sides)  $\rightarrow$  use  $2'' \times 4''$  for sides  $\rightarrow$  1000 lft of  $2'' \times 4''$   
 for  $3''$  concrete
- (Rebar)  $\rightarrow$  support Bracing  $\rightarrow$  every  $3' 6'' - 4' 6''$   
 $\sim$  need 2700 braces to do floor
- WWF  $6 \times 6 - W 2.9 / W 2.9$   
 $f_y = 60 \text{ ksi}$   
 $\sim$  890 sheets of WWF
- $\rightarrow$  Not including balcony reinforcing

89'  $\uparrow$  29' (width)  
 $\rightarrow$

---

prefabricated  
 Metal Stud framing (top) (bearing)

- 802 ft  $\rightarrow$  interior part. TP
- 848 ft  $\rightarrow$  int. part. d. w.
- 530 ft  $\rightarrow$  double part.
- 532 ft  $\rightarrow$  interior corridor / elevator
- 472 ft  $\rightarrow$  exterior

3484 ft of metal stud wall

METAL STUD

Load Bearing Metal Studs







***Wellington Condominiums***  
***Exton, PA***  
**Technical Analysis in Cost and Methods**


**B. Appendix B – Full Site Plan with Utilities**

*See the Following Attached Page*





Drawing Scale



Wellington Condominiums - Site Plan Utilities  
 Uwchlan Township - Chester County - Pennsylvania

Sean Flynn - Construction Management

October 30, 2006 Revision #002