

**Tyler Swartzwelder**  
**Construction Management**  
**Faculty Advisor: Dr. Messner**  
**Canton Crossing Tower**  
**1501 S. Highland Avenue**  
**Baltimore, Maryland 21224**



## Existing Construction Conditions

### Table of Contents

A. Executive Summary.....	Page 2
B. Project Schedule Summary.....	Pages 3-4
C. Building Systems Summary.....	Pages 5-16
D. Project Cost Evaluation.....	Pages 17-24

## Executive Summary

The Canton Crossing Tower is the first of 14+ buildings being built in Hale Properties' Planned Unit development of the 65 acre campus in Canton. The southeastern portion of Baltimore City is changing from an industrial area to a thriving commercial area where individuals can "live, work, and play." From the architect; "this project is one of the most significant projects to be developed in Baltimore since the Inner Harbor Development created by the Rouse Company and will contain over \$150 million in development to the area." ([www.wbcm.com](http://www.wbcm.com))

In the following technical assignment, topics such as schedule, cost, and existing conditions were all analyzed. A better understanding for the project as a whole was gained. A few items and issues that stood out during research as discussed below.

The GMP developed for the impressive 17-story tower was somewhat deceiving to an outsider looking in. The contract the owner had with CM was merely for the core and shell construction of the building. After completion of the core and shell, the tenant space on each floor was bid out as a separate construction project. Great communication between the owner, CM, and tenant GC's allowed this situation to remain a positive.

The only major hang-up the team faced with the 18-month schedule early was the existing soil conditions. The site, at one time, had been used as an Exxon Terminal that handled heavy-weight soils classifying the soils as contaminated. An interesting and educational issue arose that brought upon a Corrective Action Plan (CAP). The CAP declares that each person working in the soils must complete a 40 hr hazardous training class, as well as the soils must be transferred offsite once removed. Obviously this made a big impact on the already difficult schedule.

## **Project Schedule Summary**

\*\*Corresponding Primavera Schedule is shown on the following page

The key schedule element in the construction of the foundation was the condition of the existing soils. Since the soils were classified as contaminated and had to be transported offsite, the schedule could potentially be affected. Every individual who worked on the excavation and foundation system crews had to go through a 40-hour Hazardous Material course.


The initial schedule allowed steel erection to be completed at exactly one floor per week. Also, immediately following the steel, the metal decking and concrete were being placed. The demanding pace forced steel crew sizes to be increased, as well as extra safety measures to be followed during the structure's erection. The erection of the structure directly affected the building close-in milestone. This milestone had to be reached before any finish work could begin.

The finish work subcontractors, due to the demanding schedule, were forced to work together. Good communication through weekly superintendent meetings and accurate two-week look ahead schedules was a key to the success of construction.

Canton Crossing Tower

Classic WBS Layout

04-Oct-06 17:02



TASK filter: All Activities

Page 1 of 1

Summary

Actual Work (blue bar) Remaining Work (red bar) Critical Remaining Work (black bar) Milestone (diamond)

© Primavera Systems, Inc.

## Building Systems Summary

### Primary Engineering Systems

#### Architecture (Design and Functional Components):

The Canton Crossing Tower is the first of many new additions to the 65-acre Canton Crossing campus. The campus is located in the Southeastern portion of Baltimore City just outside of Baltimore's Inner Harbor, known as Canton. Developer, Edwin F. Hale Sr. of Hale Properties, envisions Canton Crossing as "The City within the City". The tower spearheads the construction of the campus that will ultimately consist of more than



1 million square feet of Class-A office space, 250,000 square feet of retail space, 500 condominiums, a 450-unit upscale hotel, and a marina pier. The tower itself has been designed

as a 17-story building that will house over 475,000 square feet of commercial space.

The octagonal shaped building's exterior architectural features are highlighted by the hipped roof with a metal roofing cap that towers 77' above top floor. The core and shell design provides nearly 30,000 square feet of rentable office space per floor. To maximize the buildings leasable space and accompany the unique hipped roof design, a 2-story Utility Distribution Center (UDC) was built across the street from the tower. The UDC houses the main mechanical and electrical systems that power the building.

With its unique location, the tower provides breathtaking views of Baltimore's Inner Harbor, as well the city's entire skyline. Even as Canton Crossing continues to grow, the Canton Crossing Tower will remain the tallest building throughout the campus. Since it is easily visible from busy locations such as the Inner Harbor, Fort McHenry, and Interstate 95 & 895, the Canton Crossing Tower is sure to put Canton on the map.

### **Building Envelope:**

The building envelope of the tower is quite unique. The tower has an octagonal shaped shell. The four largest sides of the building are comprised of precast concrete panels with thin face brick and 6" deep aluminum window wall systems. The top of



these four sides are completed with a triangular peak which is home to the 1<sup>st</sup> Mariner Bank name and symbol in gold. Two of the smaller sides are the grand entrances, located on either side of the building. These walls are designed with a 7 1/2" deep aluminum curtain wall system. The final two sides of the tower are designed the same as the four large ones with the 6" deep aluminum window wall systems. The four smaller sides are all capped off with balconies on the 17<sup>th</sup> floor.

The roof of the Canton Crossing Tower is what makes this high-rise building distinctive. The hipped roof design towers 77' above the top floor. Each of the four hips is covered by a standing seam metal roof. In between the four hips, the core is covered

by insulated aluminum panels that then meet the standing seam metal roof cap. The peak of the 17-story building is complimented by a flag pole.

### **Construction:**

The site for Canton Crossing Tower caused dilemmas for the construction team from day one. The site, the former location of an Exxon terminal, was bid as a clean site but was far from it. The soil on the site was classified as contaminated



soil and required a Corrective Action Plan (CAP) for the remediation of light non-aqueous phase liquids (LNAPL). The plan included the excavation and transportation of the contaminated soils to an offsite location. Also, before anyone was permitted to work in the contaminated soils they must first complete a 40 hour Hazardous Awareness Training.

Once the project broke ground the concrete piles began to be placed. The steel structure was erected at a very rapid pace. The construction manager followed a demanding schedule of one floor per week. The one floor per week included all of the following; structural steel placed, metal decking placed, and the suspended concrete slab



poured. Also, as a safety measure, 75% of the above floor metal decking had to be placed before work began on the floor below. At times the schedule

seemed in jeopardy, but by the aggressive management of many individuals the schedule was able to be attained.

The site logistics were in the favor of the construction team for this project. The large site footprint made steel staging a manageable task. Other positive site features were the two surrounding public roadways running on either side of the tower. These, along with the immediate access to Interstate 95, gave some leeway to the delivery methods. Two tower cranes were used for the steel erection and the concrete slabs were placed by pump. The construction team also had two material hoists that ran the length of the 17-story tower during construction. These hoists were crucial to the project because with no elevators, production would have been seriously affected.

As the contract with the owner was for simply the core and shell of the building, the tenant fit-out brought the most challenging aspect of managing the project. Gilbane, the base building CM, was not awarded any of the tenant's CM contracts. Therefore while Gilbane was attempting to complete base building, tenant hired CM's were beginning their work on the rented floors. Intense coordination and good cooperation had to be implemented for the parties to work side by side.

### **Electrical:**

The tower's electric systems begin at the Central Plant building where the power is housed. In the electrical room of the plant is the Main Service Switchgear (13.2 kV) and the substation with two 3500 kVA transformers. The power is transferred to the power through 2 – 9-way ductbanks, one for normal power and one for emergency power. The 15 kV switchgear located in the Ground Floor Electrical Room of the tower is where the



13.8 kV normal open loop feeders enter from the Central Plant Ductbanks. The power runs vertically through the entire building through 7 main busways, with one more optional plug-in busway. The busways run through electrical rooms that are located on each side of the tower's core. The one room houses a lighting busway (600A, 480/277V,




30, 4W), computer busway (1600A, 480V, 30, 3W), emergency life safety busway (600A, 480/277V, 30, 4W), and an emergency standby busway (600A, 480/277V, 30, 4W).

The opposite electrical room houses the HVAC busway (2000A,

480/277V, 30, 4W), computer busway (1600A, 480V, 30, 3W), lighting busway (1600A, 480/277V, 30, 4W), and the optional standby busway (800A, 480V, 30, 4W). Each electrical room is also equipped with 3 transformers and six electrical panels. On the 18<sup>th</sup> floor, the electrical systems floor, the busways come to six ATS's, two main substations, and an emergency substation.

### **Lighting:**

The tower's interior lighting fixture schedule is mostly comprised of 277 V recess mounted fluorescent lamps. The lighting of the building is served



via 480/277, 3-phase, 4 wire panels. On the ground floor, the lighting was designed with more of an architectural purpose. This floor's lighting ranges from polished brass wall mounted fixtures to ceiling recessed compact fluorescent downlights. The typical floors contain 2'x2' parabolic fluorescent fixtures in the core areas and 4' heavy duty industrial fluorescents in the tenant shell areas. On the exterior hardscape of the tower, pole mounted light fixtures, in-grade up lights, and bollard lights combine to beautify the surrounding area.

### **Mechanical:**



The mechanical design in the tower is based on two air handling units located on each floor. The units are constant volume vertical air units (8500 cfm), each consisting of mixing box, chilled water cooling coil

and fan. The feeds from these units are predominantly run down each corridor in the ceiling space of the tower's core. The ducts from the corridor also branch out to the shell area.

The shell is equipped with 8 different VAV boxes. Due to the tower being a tenant fit out building, the ducts are run to the shell and then capped off. This allows tenants to design and construct the mechanical system for their unique spaces. The mechanical

room floor, located on the 19<sup>th</sup> floor, is where the two Energy Recovery Ventilators (ERVs) are positioned. The two ERV units are fed from the ventilation air supply and return ducts that run vertically up the building through the designed duct shafts located beside the mechanical rooms. The Central Plant designed to power the building will house the 2500 ton chiller, three hot water boilers, and two cooling towers. The plant has been designed for future expansion of the Canton campus as well, for example, locations for 3 additional 2500 ton chillers and 3 more hot water boilers.

### **Structural:**

The structural system in the Canton Crossing Tower starts with a foundation comprised of precast, prestressed concrete piles. The 20” square piles, which use 7000 psi concrete, are situated underneath pile caps.



These pile caps are located on the column grid and each covers roughly 4-10 piles.

The structure of the tower is made up of a composite steel framing system. Each floor has 3” composite metal decking with a 6-1/4” thick lightweight concrete (3500 psi). The reinforcing used is the new high strength billet steel. A typical bay in the tenant shell space, sized at 37’ x 43’3”, is laid out with beams at W18x35 and girders ranging from W24x62 to W33x118. In the core area, beams are typically W16x26 and W16x31 while the girders range from W14x22 to W40x249. With floor heights at 13’4”, the columns


are all designed as W14's. The weights of the columns vary from 82 lb/ft to 605 lb/ft. The columns ultimately rest on top of the pile caps at the foundation level.

The primary lateral system in the building are braced frames, both concentrically braced and eccentrically braced. Moment frames are also used as a lateral system around the perimeter of the building. The lower level of the hipped roof system has a typical beam size of W16x26 and a typical girder size of W24x76. The upper level of the roof use W12x26 beams and W33x118 girders.

The steel of the building was placed using two tower cranes positioned on the North and South ends of the towers exterior



perimeter. The height of the tower cranes were 340 ft & 380 ft respectively. They have a concrete foundation with eight precast piles under each. The pieces of the cranes, known as "towers", were each approximately 20' tall. To remain structurally safe, the max free standing towers are nine or 180'. Once the cranes were above the 180' height limit, they had to be tied into the building structure.





## Additional Engineering and Engineering Support Systems

### Fire Protection:



The tower was designed as a wet sprinkler system except in the loading dock area where a dry system was installed. The fire pump was reduced in size through value engineering to a 750 gpm pump. Each 20-story stairwell contains a 6” standpipe. A jockey pump is

used to maintain the pressure in the building at 175 psi. The Fire Command Center is located on the Ground Floor near the West Entrance and houses the Fire Alarm Panel, Fireman’s Override Panel, Fire Annunciator Panel, etc. Each typical floor, including core and shell, is equipped with manual pull stations, fire alarm strobes, ceiling mounted smoke detectors, and ceiling mounted fire alarm speakers.



### Transportation:

The building consists of 8 traction elevators, four on each side of the lobby. One of the eight elevators will be used as a service elevator with a capacity of 4,500 lbs and speed of 700 f.p.m. The service elevator will stop on all floors up to the 19<sup>th</sup> floor. The other 7 elevators are strictly passenger elevators with a capacity of 3,500 lbs and a speed of 700 f.p.m. These elevators will stop on all floors up to the 17<sup>th</sup> floor. The elevator pits

are approximately 8'4" deep with a sump pump in each pit. The 20<sup>th</sup> floor of the tower houses the elevator machine room.



### **Telecommunications:**

Due to the 17-story office tower being designed as a tenant fit-out, the telecommunications aspect of the base building is somewhat minute. The Main Telecommunications Room on the ground floor is where the 12-way incoming ductbank enters from the Central Plant. Each of the typical floors is equipped with two Tele/Data Rooms. Under base building contract, these rooms are built so that each tenant may come in and fit-out their own telecommunications system.

The security system of the building is important because the main tenant of the tower is 1<sup>st</sup> Mariner Bank. The owner opted to hold the contract with the security subcontractor as opposed to Gilbane holding that contract. The tower is inaccessible to the public after hours, with a 24-hour security crew on board. The exterior entrances are equipped with a telecom system for entry during non-working hours. Each interior floor has been set up with four security cameras that monitor the entire core area.

### **Additional Building Systems Summary Form**

#### **Demolition Required**

No demolition was required for the Canton Crossing Tower.

## Cast in Place Concrete

The cast in place concrete for the composite floor slabs is lightweight with a minimum compressive strength of 3500 psi. The 3” metal decking will act as the horizontal formwork for the concrete, while the steel toe plate around the perimeter will act as the vertical formwork. The concrete is to be poured in strips perpendicular to the steel girders. The cast in place concrete is placed by the pump method.



## Precast Concrete

The architectural precast panels that were designed for the tower were constructed by The Shockey Precast Group at their plant in Winchester, Virginia. The panels were then transferred by tractor and trailer to the construction site as needed for erection. The two tower cranes were used for the erection of the precast panels.

Precast connections were detailed by Shockey. The connections were a combination of L-shaped steel angles for lateral support, with bearing connection plates embedded in the concrete. The angles were attached to the structure columns and welded to embedded plates in the precast.



## **Masonry**

The masonry used in the tower was very minimal. At locations where masonry was used, it was non-load bearing.

## **Support of Excavation**

The building required a minimal amount of excavation, therefore the only excavation support system needed was around the elevator pits where sheeting and surring was used.

There was no dewatering system used on the project due to the minor excavation.





## Project Cost Evaluation

### **Building Details**

Size (total square feet) = 519,401 ft<sup>2</sup>

Number of stories = 17 stories occupied, 3 equipment and machine floors

### **Actual Building Construction Cost**

Construction Cost = \$ 42,199,783

- Note – Not including land costs, sitework, permitting, etc.

Construction Cost/Sq. Ft. = \$81.25/Sq. Ft.

### **Total Project Costs**

Total Cost = \$ 51,525,571

- Note – The total cost include is for the construction of the core and shell of the tower, as well as the overhead, profit, fee, and also including contingency.

Total Cost/Sq. Ft. = \$99.20/Sq. Ft.

### **Building Systems Cost**

*Site Work* = \$ 3,653,940

Cost/Sq. Ft. = \$ 7.03/Sq. Ft.

*Electrical* = \$ 4,290,094

Cost/Sq. Ft. = \$ 8.26/Sq. Ft.

*Mechanical* = \$ 7,557,051

Total Mechanical/Sq. Ft. = \$ 14.55/Sq. Ft.

Plumbing/HVAC = \$ 7,099,100

Cost/Sq. Ft. = \$13.67/SF

Fire Protection = \$ 457,951

Cost/Sq. Ft. = \$0.88/SF

*Structural* = \$ 13,713,806

Total Structural/SF = \$ 26.40/SF

Concrete = \$ 5,010,455

Cost/SF = \$ 9.65/SF

Masonry = \$ 35,300

Cost/SF = \$ 0.07/SF

Steel = \$ 8,668,051

Cost/SF = \$16.69/SF

## Parametric D4Cost Estimate

\*\*Corresponding *D4Cost 2002* Estimate is shown on the following page

The D4Cost Database did not have any specific projects that matched Canton Crossing Tower closely, so the True Averaging Method was used on multiple similar projects. The five projects selected from the D4Cost Database were chosen because of their similarities to the Canton Crossing Tower. The subjects chosen were all office buildings, with the size of each varying greatly. The overall selection process was based on the square footage and number of stories with direct comparison to the cost. The spreadsheet shown below for reference gives the building names, square footages, number of stories, and costs.

<b>Building Name</b>	<b>Square Footage</b>	<b>No. of Stories</b>	<b>Total Cost</b>
Grand Tower	305,000 sq. ft.	15	\$ 18,495,942
Preston Pointe	105,768 sq. ft.	8	\$8,242,378
Ha-Lo Headquarters	267,334 sq. ft.	7	\$ 37,643,382
Willow Oaks III	407,042 sq. ft.	7	\$ 16,757,728
Westchase Corporate	308,500 sq. ft.	6	\$10,492,634

The results yielded for Canton Crossing Tower:

*Total Cost = \$ 46,616,960*

Canton Crossing Tower - Oct 2004 - MD - Baltimore

Prepared By: <b>Tyler Swartzwelder</b> <b>Penn State University</b> <b>236 South Barnard Street Apt 2</b> <b>State College, PA 16801</b> Fax: Building Sq. Size: <b>519401</b> Bid Date: No. of floors: <b>20</b> No. of buildings: Project Height: 1st Floor Height: 1st Floor Size:	Prepared For: <b>Dr. John Messner</b> <b>Penn State University</b>  <b>University Park, PA 16801</b> Fax: Site Sq. Size: <b>145667</b> Building use: <b>Office</b> Foundation: <b>CAI</b> Exterior Walls: <b>PRE</b> Interior Walls: <b>GYP</b> Roof Type: <b>MET</b> Floor Type: <b>CON</b> Project Type: <b>NEW</b>
--	---

Division	Percent	Sq. Cost	Amount
<b>00 Bidding Requirements</b>	<b>1.94</b>	<b>1.75</b>	<b>906,400</b>
Bidding Requirements	1.94	1.75	906,400
<b>01 General Requirements</b>	<b>8.23</b>	<b>7.39</b>	<b>3,838,154</b>
General Requirements	8.23	7.39	3,838,154
<b>02 Site Work</b>	<b>2.46</b>	<b>2.21</b>	<b>1,145,367</b>
Site Work	2.46	2.21	1,145,367
<b>03 Concrete</b>	<b>19.79</b>	<b>17.76</b>	<b>9,227,138</b>
Concrete	19.79	17.76	9,227,138
<b>04 Masonry</b>	<b>2.04</b>	<b>1.83</b>	<b>949,142</b>
Masonry	2.04	1.83	949,142
<b>05 Metals</b>	<b>12.56</b>	<b>11.28</b>	<b>5,856,836</b>
Metals	12.56	11.28	5,856,836
<b>06 Wood &amp; Plastics</b>	<b>0.43</b>	<b>0.38</b>	<b>198,982</b>
Wood & Plastics	0.43	0.38	198,982
<b>07 Thermal &amp; Moisture Protection</b>	<b>1.60</b>	<b>1.44</b>	<b>748,166</b>
Thermal & Moisture Protection	1.60	1.44	748,166
<b>08 Doors &amp; Windows</b>	<b>13.32</b>	<b>11.95</b>	<b>6,208,780</b>
Doors & Windows	13.32	11.95	6,208,780
<b>09 Finishes</b>	<b>7.35</b>	<b>6.59</b>	<b>3,424,314</b>
Finishes	7.35	6.59	3,424,314
<b>10 Specialties</b>	<b>1.57</b>	<b>1.41</b>	<b>733,660</b>
Specialties	1.57	1.41	733,660
<b>11 Equipment</b>	<b>0.02</b>	<b>0.02</b>	<b>9,044</b>
Equipment	0.02	0.02	9,044
<b>12 Furnishings</b>	<b>0.63</b>	<b>0.57</b>	<b>294,686</b>
Furnishings	0.63	0.57	294,686
<b>13 Special Construction</b>	<b>0.01</b>	<b>0.01</b>	<b>6,670</b>
Special Construction	0.01	0.01	6,670
<b>14 Conveying Systems</b>	<b>4.43</b>	<b>3.97</b>	<b>2,062,865</b>
Conveying Systems	4.43	3.97	2,062,865
<b>15 Mechanical</b>	<b>8.77</b>	<b>7.87</b>	<b>4,088,216</b>
Mechanical	8.77	7.87	4,088,216
<b>16 Electrical</b>	<b>4.53</b>	<b>4.07</b>	<b>2,113,677</b>
Electrical	4.53	4.07	2,113,677
<b>21 Fire Suppression</b>	<b>0.75</b>	<b>0.67</b>	<b>350,243</b>
Fire Suppression	0.75	0.67	350,243

<b>22</b>	<b>Plumbing</b>	<b>0.54</b>	<b>0.49</b>	<b>252,966</b>
	Plumbing	0.54	0.49	252,966
<b>23</b>	<b>HVAC</b>	<b>3.74</b>	<b>3.36</b>	<b>1,744,241</b>
	HVAC	3.74	3.36	1,744,241
<b>26</b>	<b>Electrical</b>	<b>2.89</b>	<b>2.59</b>	<b>1,346,284</b>
	Electrical	2.89	2.59	1,346,284
<b>31</b>	<b>Earthwork</b>	<b>0.52</b>	<b>0.47</b>	<b>243,727</b>
	Earthwork	0.52	0.47	243,727
<b>32</b>	<b>Exterior Improvements</b>	<b>1.27</b>	<b>1.14</b>	<b>590,545</b>
	Exterior Improvements	1.27	1.14	590,545
<b>33</b>	<b>Utilities</b>	<b>0.59</b>	<b>0.53</b>	<b>276,856</b>
	Utilities	0.59	0.53	276,856
<b>Total Building Costs</b>		<b>100.00</b>	<b>89.75</b>	<b>46,616,960</b>
<b>Total Site Costs</b>		<b>100.00</b>	<b>0.00</b>	<b>0</b>
<b>Total Project Costs</b>		<b>--</b>	<b>--</b>	<b>46,616,960</b>

## **RS Means Square Foot Estimate**

**\*\*Source: *RS Means SQFT Cost – 27<sup>th</sup> Annual Addition – 2006 (Page 180)***

**\*\*Corresponding *RS Means* Data is shown on the following page**

The following Square Foot Estimate was completed through the RS Means source listed above. The tower was placed under the Commercial/Industrial/Institutional section as an Office, 11-20 Story. The Exterior Wall selection was chosen to be Precast Concrete Panel with Exposed Aggregate. The perimeter and story height adjustments were not necessary for the tower's estimate. The cost per square foot of floor area was found through interpolation to be \$108.85. In order to make the estimate more accurate, the additional costs of the elevators and smoke detectors were estimated from the Common Additives section.

### *Floor Area*

- Cost per square foot of floor area = \$108.85
- Square Foot Cost = \$108.85\*519,401 sq. ft. = \$ 56,536,798.85

### *Elevators*

- 7 – 3500# capacity elevators with 17 stops @ \$302,850 = \$ 2,119,950.00
- 1 – 4500# capacity elevator with 20 stops @ \$327,500 = \$ 327,500.00

### *Smoke Detectors*

- 3 – Ceiling Type per floor (20 floors) @ \$164.00 = \$ 9,840.00
- 6 – Duct Type per floor (20 floors) @ \$430.00 = \$ 51,600.00

***Total Cost Estimate = \$ 59,045,689***



519,401

**Costs per square foot of floor area**

Exterior Wall	S.F. Area	120000	145000	170000	200000	230000	260000	400000	600000	800000
	L.F. Perimeter	420	450	470	490	510	530	600	730	820
Double Glazed Heat Absorbing Tinted Plate Glass Panels	Steel Frame	135.10	130.10	126.00	122.30	119.55	117.40	111.20	107.85	105.70
	R/Conc. Frame	135.25	129.15	124.35	119.95	116.70	114.25	107.00	103.00	100.60
Face Brick with Concrete Block Back-up	Steel Frame	134.55	129.20	125.00	121.20	118.40	116.25	110.05	106.60	104.55
	R/Conc. Frame	127.45	122.20	118.10	114.40	111.70	109.55	103.50	100.10	98.15
Precast Concrete Panel With Exposed Aggregate	Steel Frame	136.75	131.10	126.70	122.75	119.80	117.55	111.00	107.40	105.20
	R/Conc. Frame	129.95	124.40	120.10	116.25	113.35	111.10	104.75	101.15	99.00
Perimeter Adj., Add or Deduct	Per 100 L.F.	7.45	6.15	5.25	4.50	3.90	3.45	2.25	1.40	1.15
Story Hgt. Adj., Add or Deduct	Per 1 Ft.	3.05	2.65	2.35	2.10	1.85	1.75	1.25	1.05	.90

For Basement, add \$30.00 per square foot of basement area

The above costs were calculated using the basic specifications shown on the facing page. These costs should be adjusted where necessary for design alternatives and owner's requirements. Reported completed project costs, for this type of structure, range from \$77.10 to \$188.05 per S.F.

**Common additives**

Description	Unit	\$ Cost	Description	Unit	\$ Cost
Clock System	Each	14,500	Escalators, Metal	Each	105,300
20 room	Each	35,300	32" wide, 10' story height	Each	123,400
50 room			20' story height	Each	110,800
Directory Boards, Plastic, glass covered	Each	560	48" wide, 10' story height	Each	128,900
30" x 20"	Each	1300	20' story height		
36" x 48"	Each	530	Glass	Each	103,800
Aluminum, 24" x 18"	Each	610	32" wide, 10' story height	Each	123,400
36" x 24"	Each	820	20' story height	Each	110,800
48" x 32"	Each	1900	48" wide, 10' story height	Each	128,900
48" x 60"	Each		20' story height	Each	
Elevators, Electric passenger, 10 stops	Each	252,500	Smoke Detectors	Each	164
3000# capacity	Each	254,500	Ceiling type	Each	430
4000# capacity	Each	259,500	Duct type		
5000# capacity	Each	7050	Sound System	Each	2025
Additional stop, add			Amplifier, 250 watts	Each	166
Emergency Lighting, 25 watt, battery operated	Each	259	Speaker, ceiling or wall	Each	315
Lead battery	Each	765	Trumpet	Outlet	272
			TV Antenna, Master system, 12 outlet	Outlet	173

## **Comparison of Actual Costs and Estimates**

*Total Actual Cost = = \$ 51,525,571*

*D4Cost 2002 Parametric Estimate = \$ 46,616,960*

*RS Means Square Foot Estimate = \$ 59,045,689*

After both estimates were compiled and compared to the actual cost, a significant difference was shown. The D4 Cost estimate came in roughly 10% lower than the actual cost. D4 Cost's database has a limited number of source projects to select from. During the Canton Crossing Tower estimate, a few of the source buildings used had a smaller number of floors and square footage. The selection process for the source buildings used dealt with building use, size, number of floors, and building cost. The program then adjusted the time and location factors for construction. With more of a selection in the database of source projects, a more accurate estimate would have been possible.

The RS Means Square Foot Estimate came in 13% higher than the actual cost. The main reason for this drastically high estimate is that RS Means does not allow the estimate to be core and shell construction only with tenant fit out spaces. With the estimate incorporating the tenant areas under the same price, there is going to be a significant increase in the final number. The additives section of RS Means did help the estimate become more accurate, but this estimate is almost irrelevant to Canton Crossing Tower due to the tenant fit out situation.

Also, the demanding 18-month schedule probably is not typical of a building this size. Neither estimate took into account the duration of construction. The two estimate types used are for preliminary estimating only, but proved they could be useful to an individual who wanted to get a quick and basic idea of their potential costs.



**Tyler Swartzwelder**  
**Construction Management**  
**Faculty Advisor: Dr. Messner**  
**Canton Crossing Tower**  
**1501 S. Highland Avenue**  
**Baltimore, Maryland 21224**



## Technical Assignment 1: Construction Project Management

### Table of Contents

- A. Site Plan of Existing Conditions...Pages 2-4
- B. Local Conditions.....Pages 5-6
- C. Client Information.....Pages 7-8
- D. Project Delivery System.....Pages 9-11
- E. Staffing Plan.....Pages 12-13




**CANTON CROSSING TOWER**  
 1501 S. CLINTON ST  
 BALTIMORE, MD 21224

**SITE PLAN OF EXISTING CONDITIONS**

TECH ASSG #1 - 10/6/06  
 TYLER SWARTZWELDER  
 CM OPTION - DR. MESSNER

**DWG - 1.0**







MARB

TRAILERS

S. CLINTON STREET


HAZARDOUS AREA

S. HIGHLAND AVENUE

## Local Conditions

The site of construction for the Canton Crossing Tower is located in the Southeastern part of Baltimore City, otherwise known as Canton. The existing site and adjacent site locations of the Canton Crossing Tower were classified as an industrial area and were previously vacant. In order for the rezoning from industrial to commercial to occur, Hale Properties had to submit a Planned Unit Development (PUD) to Baltimore City. Once approved by the city, the rezoning occurred and construction development began. The tower building was the first of 14+ buildings being built in the 65 acre campus. The methods of construction, as well as the architectural style, used on the tower building will be the beginning of the new style of the Canton Crossing Campus.

The site logistics plan for construction of the tower was favorable to the General Contractor. There is no demolition required onsite before construction, and the existing active utilities are water main and overhead electric. The lot the building sits on is roughly 1.23 acres. Directly adjacent to this lot is a 1.47 acre lot that is available for trailers, steel staging and laydown areas, and dumpsters. Across the street from these lots is a 3+ acre empty lot that can easily hold more trailers, as well as the construction parking for the




project. On the opposite side of the street, an existing 2 story warehouse building (also owned by Hale Properties), is the location of the General Contractor's office.

The existing soil conditions became a major issue for the whole construction team in the construction of the tower. A large portion of the Canton Crossing Campus was previously the site of an Exxon Terminal that handled heavy-weight fuel oils. Due to impacts from the terminal, all of the soils on the site have been classified as contaminated. Therefore a Corrective Action Plan (CAP) had to be implemented for the excavation and off-site transportation of the petroleum saturated soils.

The Geotechnical Engineering Study by D.W. Kozera indicates site soils are underlain by a layer of man-made fill, which is then underlain by recent alluvial deposits. Also, since the site is part of the Atlantic Coastal Plain Physiographic Province, the site soils are also underlain by the Potomac Group deposits of the Cretaceous age. These deposits lie above the bedrock that is approximately 200' below ground.

## Client Information

The owner of the Canton Crossing Tower, Hale Properties, built the tower as the first building in their Planned Unit Development (PUD). The company, founded by Edwin F. Hale, Sr. in 1978, is a developer, owner and manager of east coast real estate. Hale Properties' vision is to completely change the



existing industrial area of Canton, into a thriving area where individuals can “live, work, and play.” The team’s PUD had to gain approval from the city of Baltimore before the development of Canton Crossing could occur.

The cost of the project was set between the Owner (Hale Properties) and the General Contractor (Gilbane) as a Guaranteed Maximum Price of nearly \$52 million. The existing offices of Hale Properties are located directly adjacent to the new construction lot of the tower. This made it very easy for both parties, the Owner and the GC, to control quality issues. Both teams embraced the convenient location and used it to their advantage throughout construction. Issues such as first delivery inspections, mock-ups, color schemes for finishes, etc. could be discussed by both teams and decisions were made in a more timely fashion. The schedule of construction was critical to the owner’s interests for the major factor of tenant fit-outs. The sooner the GC could complete the core and shell of the tower, the sooner the new tenants could begin their fit outs. Hale Properties watched the schedule rather closely because of the amount of money that



could potentially be lost due to late tenant move-in. Rather than this issue becoming a problem, both teams worked vigorously together as one to assure a beneficial occupancy date as close to the original as possible. The building requiring over 20 stories of steel



erection caused safety to be a pivotal factor in the successful completion of the tower. From the very start, Hale Properties did everything possible to help Gilbane implement their Project Safety Plan. At no point did the schedule, cost,

and/or quality of the building take precedence over safety.

The sequencing of construction of this project is of utmost interest to the owner because of tenant fit-outs. The first step in the process is the completion of the core and shell of the building. To speed up the tenant move in dates, the Owner decided to allow the tenant space GC's to begin working simultaneously with Gilbane. Most importantly, the core and shell GC (Gilbane) must have their Certificate of Occupancy from the Baltimore City Fire Marshall before the tenants could apply for their own. The Certificate of Occupancy was the key factor to completing the tower on schedule and to the owner's satisfaction. This was made possible through exceptional communication lines being drawn between Hale Properties, Gilbane, and tenant fit out GC's. Also, the tremendous cooperation from the Baltimore City Fire Marshall was imperative.



## Project Delivery System

The construction of the Canton Crossing tower is being delivered as a Construction Management at Risk with a Guaranteed Maximum Price contract with the owner. The CM at Risk delivery method was chosen to help alleviate some of the duties, such as managing the subcontractors, from the Hale Properties staff team. The GMP contract is typical for Gilbane and was what their team proposed.

The contract between Hale Properties and Gilbane was a GMP of nearly \$52 million and schedule duration of 18 months. The lump sum contracts that Gilbane holds with the subcontractors specify all of the following; list of contract documents, scope of work (inclusions and exclusions), bid breakdown, unit rates, construction milestones, termination conditions, change order process, bonds and insurance, paid when paid conditions, etc.


The Owner-CM contract was based on a prior relationship between Gilbane's Regional Manager and Hale Properties Owner Mr. Hale. Gilbane did not bid the project with the other GC's; instead they negotiated with the owner through the design phases (SD, DD, & CD) by providing estimates and value engineering ideas. At the completion of the Construction Documents, Gilbane then submitted a GMP to be reviewed and approved by the owner. The subcontractor's were selected through a process that reviewed several of the low bids. The process consisted of scope review meetings, ENR rating analysis, and bond qualifications. Through all of these parameters a subcontractor was chosen, meaning the low bidder was not always chosen.

The owner held the builder's risk insurance for the project, which almost immediately was put into effect. After a barge of precast piles tipped over, the insurance teams were

called into action, specifically the builder's risk. The cost of the materials was paid in full by the insurance group. Gilbane carried general liability, automobile, comprehensive, and worker's compensation insurance, but was not required to be bonded. Instead the executives, through a solid relationship with the owner, guaranteed the work on the job. Gilbane requires each subcontractor to have a performance and payment bond, and on this project those bonds accounted for the majority of the contract. This allowed Mr. Hale to save some expenses and not require Gilbane to be bonded. Each subcontractor also had to provide general liability insurance, excess liability insurance, automobile insurance, and worker's compensation insurance. The subcontractors also held Hale Properties and Gilbane as additional insurers in their umbrella.

The CM at Risk delivery method used for the tower was appropriate because Gilbane needed control over the subcontractors to complete the intense 18 month schedule. However, since Gilbane was involved in the design phase, there is a possibility that a Design-Build delivery could have been beneficial to them. With a Design-Build delivery the project would have had the opportunity to be fast tracked. Typically design-build gives the owner less control of the design issues, which Hale Properties was not interested in. Also, a Design-Build-Finance approach was mentioned during negotiation but decided against by the team. Overall, the CM at Risk with a GMP contract seemed to be successful.


# Canton Crossing Tower Organizational Chart





## Staffing Plan

Gilbane was a part of the project team from the schematic design phase. The Preconstruction Department provided many services to the owner including, estimating, constructability at all design phases, purchasing, and overall budget management and control. The preconstruction team included the Principle in Charge, Estimating, Purchasing, as well as the Project Executive. At the point construction began the operations team from Gilbane took over. The Project Executive was in charge of the operations team. From there, the Project Manager and Superintendent had control of their respective teams. The PM was responsible for many things including cost reporting, owner correspondence, and schedule updating. The Assistant Project Manager was the first in command to the PM, assisting with the duties as well as managing the Project Engineers. The Superintendent of the project was in charge of the schedule for construction, site logistics, safety, among many other things. Gilbane opted to have an MEP Superintendent on the project team to alleviate some of the duties of the Superintendent. The Project Executive, PM, and Assistant PM all worked hand in hand with the Accountant to for the task of cost reporting.

# Gilbane Staffing Plan for Canton Crossing



	Full Time Canton Crossing Employee
	Main Office Personnel