### **Andrew Rhodes**

The Pennsylvania State University Architectural Engineering – Mechanical

# **The Hilton Baltimore Convention Center Hotel**



# 7.0 Construction Management Breadth

### **Purpose**

The purpose of the Construction Management Breadth is to shorten the construction time of the guest room towers of the HBCCH. Currently, the guest room towers are scheduled to take 51 weeks for completion once all structural elements are completed. The construction time will be completed through the use of a Short Interval Production Schedule (SIPS).

#### Justification

Short Interval Production Schedules thrive on efficiency and organization of work rather than speed. As a result, they are perfectly suited for construction jobs with repetitive work. Repetition reduces the learning curve of construction work, so workers become more efficient and skilled as they repeat tasks over and over during the completion of a project. Floors 4-19 of the HBCCH, the guest room towers, are essentially the same floor plan stacked on top of each other, making them a perfect candidate for a SIPS. SIPS also eliminate trade stacking, improve predictability and job-tracking, and help to better job site communication.

#### **Method of Analysis**

In order to complete the SIPS, the construction activities carried out on each floor of the guest room towers had to be determined. Once the activities were determined, each one had to be assigned a production rate. Production rates were assigned with the help of industry professionals. Next, related trades that logically work together were combined and overlapped, breaking the construction of each floor of the guest room tower into a list of finalized tasks. These tasks were then arranged into a resource-loaded, time-scaled bar graph, the SIPS. The finalized SIPS can be seen in Figure-17 below. Overall, the SIPS created for this report decreases the construction time of the guest room towers to 47 weeks. This means that four full weeks of construction time are saved.

Floor# ы ω 4 ÿ4 ο. -4 **...** 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 VWC GUESTROOMS (COMPLETE), MILLWORK AND SHELVING VWC CORRIDORS, DOORS COMPLETE, STOCK PLUMBING AND ELECTRIC FIXTURES ELECTRICAL FIXTURES, DROP SPRINKLER HEADS WALL LAYOUT
HVAC/PLUMB ROUGH-IN
FIRE PROTECTION ROUGH-IN
FRAME, DOOR FRAME CORR. START FIXTURES AND FURNISHINGS HOOK UP VFCUS, TILE BATHROOMS WIRE VFCUS, TILE BATHROOMS FRAME VFCU'S, TAPE VFCU'S ELECTRICAL IN WALL COMPLETE, FCU COMPLETE INSULATE, FRAME AT FCU ENCLOSURES ELECTRICAL HOMERUNS, OA DUCT RISERS ELECTRICAL ROUGH-IN, WIRING TO FCUS OWNER SIGN-OFF SET PLUMBING FIXTURES, TEST ELECTRIC VWC GUESTROOMS (START) PAINT - PRIME & 1ST FINISH COAT PRIME & TEXTURES CEILINGS INSPECTIONS, WALL INSULATION, INSULATE PIPING DRYWALL & TAPE 41 42 43 44 45 46

Figure-17: Completed SIPS