

FINAL REPORT

WWW.ENGR.PSU.EDU/AE/THESIS/PORTFOLIOS/2008/JMD503/

CITY VISTA.

BUILDING 2. 5TH AND K STREET . WASHINGTON D. C.



JULIE DAVIS
AE482 : SENIOR THESIS
STRUCTURAL OPTION
DR. MEMARI
APRIL 9, 2008



CITY VISTA BUILDING 2

460 L STREET WASHINGTON D.C.

General Info

PROJECT TEAM

- *Owner:* L5K LLC.
- *Architect:* Tortis Gallas
- *Structural Engineer:* SK&A
- *MEP:* GHT Limited
- *Contractor:* Davis

Size

- 11 Stories
- 324,296 sqft

Occupancy

- *Residential :* 149 Condos



JULIE DAVIS | STRUCTURAL OPTION

Architecture

Materials:

- Grey & Buff colored brick
- Champagne gold metal panels : penthouse and pedestrian bridge
- Precast stone panels

Architectural Statement:

- *Horizontal Element:* strong roof overhang
- *Vertical Elements:* protruding glass and crème colored brick vertical components
- *Narrowing Element:* building narrows at street level for to provide a more intimate appearance.



Structural

Foundation System:

- Slab on grade construction with grade beams and a deep foundation system of augured cast in place *piles* drilled 60-65 feet below grade

Framing System:

- Cast in place concrete with *Post tension floor slabs*
- Conventional reinforcement for balconies
- (4) Shear walls

Pedestrian Bridge:

- *Steel* framing with moment connection
- Composite slab
- Flat rubber asphalt roofing system
- Composite beam construction where bridge connects to Building 2

Roof System:

- Post tension slab with ridged polystyrene insulation and ballast



Construction Management

Construction Date

- *Start:* December 2005
- *Finish:* December 2007

Delivery Method:

- *Design-Bid-Build:* with Davis construction as the single prime contractor

Crane:

- Crane footing: incorporated into building foundation system as the bridge footings



MEP

Mechanical System:

- (2) Roof Top Units-208 V/3 phase 4000CFM,
- Heat Pumps – 208V/1 phase located in central locations varies from 600-1500 CFM
- Thru-the-wall heating *gas heating units* in condos: Gas Powered

Electrical System:

- (2) 3000A 208/120V Systems
 - 1→ Lobby via sub-panels
 - 2→ Condos via 3000 A bus duct
- 230 KW diesel emergency generator
- *Contract Amount* = \$3,000,000



JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

TABLE OF CONTENTS

EXECUTIVE SUMMARY

<i>Executive Summary</i>	4
<i>Acknowledgements</i>	5

EXISTING CONDITIONS

<i>Architectural</i>	6
<i>Architectural Layout</i>	7-8
<i>Building Systems</i>	9-10
<i>Structural System</i>	10-11
<i>System Advantages / Disadvantage</i>	12

PROPOSAL

<i>Problem Statement</i>	13
<i>Proposed Solution</i>	13-14

LOADING CONDITIONS

<i>Loading</i>	15-16
----------------	-------

PRELIMINARY ANALYSIS

<i>Hollow Core vs. Solid slab</i>	17-18
<i>Topping vs. no topping</i>	18
<i>Ridged vs. Flexible Diaphragm</i>	19
<i>Expansion Joints</i>	19
<i>Tendons</i>	20

DESIGN CONSIDERATIONS

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

<i>Optimization of members</i>	21
<i>Basic design data</i>	21-22
<i>PRE CAST DESIGN</i>	
<i>New floor plan</i>	22
<i>Hollow core selection</i>	23
<i>Interior beams</i>	23
<i>Exterior beams</i>	24
<i>Columns</i>	25
<i>Member check</i>	25
<i>DESIGN CHECK</i>	
<i>Gravity system issues</i>	26-27
<i>Connection issues</i>	28-29
<i>Diaphragm issues</i>	29
<i>Foundation issues</i>	30-31
<i>LATERAL CHECK</i>	
<i>Existing conditions</i>	31
<i>Flexure check</i>	32
<i>Shear Check</i>	33
<i>Reinforcing Summary</i>	34
<i>Drift</i>	35-36
<i>BREADTH #1: CONSTRUCTIBILITY</i>	
<i>Erection</i>	37-38
<i>Leads</i>	49-40
<i>Cost</i>	41-42
<i>Schedule</i>	43-44
<i>BREADTH#2: ARCHITECTURAL ALTERATIONS</i>	
<i>Floor Plan</i>	45-48
<i>Section</i>	48-49

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

CONCLUSION

<i>Results</i>	<i>50-52</i>
<i>Recommendation</i>	<i>52</i>

REFERENCES

<i>References</i>	<i>53</i>
-------------------	-----------

APPENDIX #1: SEISMIC

APPENDIX #2: GRAVITY DESIGN

APPENDIX #3: GRAVITY DETAILING

APPENDIX #4: LATERAL ANALYSIS

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

EXECUTIVE SUMMARY



City Vista, Building 2 is a mixed use complex located in downtown Washington D.C. Currently the building's gravity system is a flat plate post tension slab, tendons are unbounded and span in both directions. Slabs are supported by a grid of (52) cast in place columns. Resisting lateral forces are (4) cast in place shear walls. The building is supported with a deep foundation system consisting of over 270 augured cast in place piles and a 4" slab on grade. Building 2 is 324,298 sqft and 128'-5" tall at sections taken through the mechanical penthouse.

Developers in the D.C market buildings are driven by the 130'-0" height restrictions. Buildings

are designed to maximize rentable space and minimize construction time while keeping the building under the 130 ft height restriction. With a post tension system floor to ceiling height is optimized while creating a finished ceiling with the underside of the slab.

Considering the competitive market, societies interest in "green" design, the finished ceiling incorporated into structural system and height restriction I have propose to redesign the post tensioned gravity system to a pre-cast system. Potentially a pre-cast system presents faster erection, possible leads certification and similar if not the same floor to ceiling height

Before design began preliminary analysis and design consideration were formulated. Different pre-cast construction systems were compared and contrast. Issues concerning cost, shipping, fireproofing, optimization of member and connections were considered.

After preliminary analysis a hollow core floor system with 2" composite topping, interior inverted T-beams, exterior L-beams, and conventionally pre-cast columns was choose. A new column grid was created with span to depth ratios in mind. A lateral check was then conducted using E-tabs to verify the stability of the (4) shear walls. Cost, schedule and initial leads analysis was performed along with architectural alterations to accommodate the new column grid.

After design was complete it was concluded that a pre-cast system would produce a building within the height limit, with a fast erection time, and finished ceiling if incorporated into the preliminary design phase of the project. The current architectural layout was conducive to the irregularly shaped bays that a post tension system allows. The new column grid creates awkward spaces within some condo layout.

Structurally the lateral system was not adequate after redesign to support the seismic base shear. This was un-expected because the building only increased in height by 3ft and weight by 3000 kips.

Economically the post tension system is cheaper after the cost analysis was done and it was discovered that the post tension system is \$2,000,000 cheaper. After examining these results it is obvious this is a result of the beams added to the gravity system.

After completing the gravity, lateral, and constructability analysis it is concluded that in the D.C. building market a post tension building is more economical and provides more rentable space. I feel the pre-cast building could be optimized with longer spans but this would result in larger floor to ceiling heights and a heavier building and ultimately this redesign was driven by building height

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

ACKNOWLEDGEMENTS

My parents for all the encouragement and support they have given me over the past 5 years. Also for giving me the opportunity to come to Penn State and pursue my dream of being an architectural engineer.

My Fellow Classmates the past 5 years would not have been the same without every single one of you. Thank you for all the good memories, encouragement and help you have given me over the past 5 years.

The Penn State University A.E Faculty for the endless hours of instruction over the past 5 years. Without your knowledge and expertise I would never have been able to grasp the concepts of structural engineering.

Dr. Memari my thesis mentor for taking the time to grade all my work and guiding me through the thesis experience.

I would like to thank *Davis Construction* for supplying the plans, cad files, and building information

Special thanks to *Brian Polesmak* of Davis Construction for taking time out of his schedule to answer any questions I had pertaining to the construction of the building.

Waild Choueiri from S.K.A. engineering for his insight into thesis topics and answering all questions I had about the current structural system and proposed pre-cast system.

EXISTING CONDITIONS

City Vista is a three building mixed used complex in downtown Washington D.C. Building 2, is strictly residential and contains 149 condos along with a community room, library, steel frame pedestrian bridge, and outdoor patio.




Figure #1 : Site Plan of City Vista



Figure #2 : Rendering of City Vista Building #2 courtesy of Torti Gallas and Partners,

This 11 story 324,298 square foot post tension building reaches a height of 110'-6" and 128'-5" at sections that include the mechanical penthouse. Construction of Building 2 began in 2005 and was completed in 2007. City Vista was designed by world renowned architects Torti Gallas and Partners. The architecture uses strong vertical and horizontal elements of glass and brick. For example, the skyline is a powerful horizontal statement through the use of metal roof overhangs extending several feet past the building's façade. The horizontal elements are counteracted with protruding glass and crème colored vertical brick components throughout the building's façade. At ground level the building narrows for a more intimate feel.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

ARCHITECTURAL LAYOUT



Key

- Elevator Shaft
- Corridor
- Stair Well
- Utility Rooms

Figure #3: Typical floor layout

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI




Figure #4: North/South Building Section

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

BUILDING ENVELOPE

Typical wall construction is 4" metal gauge studs, 1/2" sheathing, air space, and face brick, or floor to ceiling glass curtain walls. The penthouse uses 8" CMU back up wall, with a metal panel façade. Roof construction is a post tension roof slab, covered with ridged polystyrene insulation then sealed with a standing seam metal roofing system.




Figure #5: Typical Wall section at roof and floor

ELECTRICAL SYSTEM

Building 2 is fed by (2) 3000A 208/120V systems. The first system services the lobby via sub panels, and the second services the condos via a 3000 amp bus duct. The panel boards services corridor lighting, fire alarm equipment, and mechanical rooms. The bus duct feeds into a 120/208 volts, 3 phase, 600 amps, meter center at each floor and then is sent to individual 120/208 volt, 125 amp, 1 phase panel board located in each apartment. A 4 cycle 230 KW diesel emergency generator with a 50 gallon fuel tank is located on the roof. The generator operates the fire alarm system, fire pumps, elevators, and emergency lighting in the event of a power outage.

LIGHTING SYSTEM

All indoor public areas are lit by fluorescent 120V parabolic recessed lighting fixtures and wall sconces. The pedestrian bridge's architectural features can be seen at night by the 150W T10 halogen pendant fixtures. Condo units are equipped with a combination of fluorescent and incandescent surface and track lighting by Sea Gull Lighting. Fluorescent lighting is used in the kitchen of each condo, with a combination of (2) bulb 32W T-8 fixtures and track lighting with canopy style magnetic transformers. All other fixtures are incandescent with varying wattages depending on the rooms use.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

MECHANICAL SYSTEM

On the roof are (2) 100% outside air rooftop units containing an indirect gas furnace, condensing unit, and compressor. Each unit is 208V/ 3 phase and pushed 4000 cfm of outside air. Public areas are serviced with 208V/ 3 phase split system heat pumps with cooling, reverse cycle heating and electrical heating capability. Each residential units contained its own through the wall gas heating units. This unit also used for cooling. Each individual unit is 208V/1 phase with variable CFM depending on the unit size.

FIRE PROTECTION

The building is 100% sprinkled with an automotive wet and dry sprinkling system. The dry system is located in areas that are not heated (i.e. loading deck). Stairwells walls have a 2 hr fire rating and are sprayed from top and bottom. Upon detection of smoke, water, and heat, the fire alarm system is activated and unlocks fire access doors, turns off corridor electrical units, and activates pressurized fans for towers. Building 2 construction is predominantly built with a 2 hour fire rating.

TRANSPORTATION

Building 2 has (2) elevators located in the building's central core. Both elevators are electric traction elevators with a capacity of 3,500 lbs. Elevators are controlled by the fire system and are equipped with emergency power. There are also (2) stairwells located at each end of the building.

CONSTRUCTION MANAGMENT

City Vista is a design-bid-build contract, with Davis Construction as the prime contractor. Truland Systems Corporation did all electrical and fire protection, work and Miller and Long performed all concrete work. Construction began in December 2005 and is set to end in December 2007. A tower crane was used during construction, whose footings double as a mat foundation for the steel pedestrian bridge connecting the 2 buildings.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

CODE

Design of City Vista was govern by the following codes:

- *District of Columbia Building Code*
- *ACI 318-89 : Building Code Requirements for Structural Concrete*
- *ACI 530-99 : Building Code Requirements for Masonry Structures*
- *Post Tensioning Institute Standards*
- *ASCE 7-05 : American Society Of Civil Engineers 2005 edition*

STRUCTURAL SYSTEM

Foundation System:

Building 2's foundation system is a 4" slab on grade with a deep foundation system. Drilled at a depth of 60-65' below grade there are over 250 16" diam. augured cast in place piles. This foundation system was chosen due to the median to stiff clay located up to 22' below grade. Piles have an assumed service capacity of 125 tons and typically are reinforced with 1 #8 x 15'-0" LG. Piles under shear walls are reinforced at 25' with 4-#8 vert. and #4 ties. The slab is thickening at interior CMU walls and location of increased service loads. Grade beams at a width of 1'-0" are placed around the buildings perimeter at varying depths.


Floor System:

A two way post-tension slab is used for all floors. The tendons are unbounded and span in both directions with a minimum of (2) tendons above columns. Banded tendons are used north to south and uniform tendons east to west. Bundle size varies but is restricted to a minimum of 4 tendons per bundle. The 7 1/2" slab is reinforced two-ways with #4@24" bottom mesh reinforcement and #5 top bars at various locations. Rebar is also provided around the perimeter. Where tendons and rebar intersect chairs should be placed with #4 ties for lateral stability. Tendons stressing will be done with a hydraulic jack, anchorage blockouts are grouted and tendons cut 1" from slab edge, stressing sequence is as follows;

1. Stress 50% banded tendons
2. Stress 50% of uniform tendons
3. Stress remaining 50% banded tendons
4. Stress remaining 50% uniform tendons

Figure #6: Typical floor section

Blue: Uniformly distributed tendon
 Red: Banded Tendons



Balconies are conventionally reinforced with #4 @ 12" O.C and 2-#5 top & bottom.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

Roof System:

Post-tension roof slab is to be 10" deep with #5@24" reinforcing. A 1 ½" galvanized metal roof deck placed on top continuous over 3 spans. This is followed by an asphalt membrane, ridged insulation and ballast

The flat plate post tension slab is supported by a grid of (52) cast in place gravity concrete columns. Columns have an f'_c of 5000 psi and take some lateral forced but predominately support gravity loads. Cold form metal studs are used for most wall construction with the exception of stairwells, mechanical rooms and storage areas which are masonry construction.

Lateral System:

The lateral system consists of (4) concrete shear walls, three of which surround the elevator shaft (i.e. the central core).

Shear Walls: Shear wall footings are to be reinforced at a depth of 25'-0" with vertical bars and ties. Typical shear wall reinforcing is #4@12" vertical and horizontal, 8#8 in the middle and #3 ties in various arrangements. An F'_c of 5000 and F_y of 60,000 are used in each shear wall.




Figure #7: Current Building Layout

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

Advantages Post Tension:

1. Shallower floor plenum: Post tension building can reduce floor to ceiling height.
2. Reduction in materials: PT slabs require less rebar and are generally thinner so less concrete is needed.
3. Longer clear spans: PT slabs allow long continuous spans resulting in fewer columns which ultimately results in a lighter building.
4. Strength: Higher ultimate strength because of bond between concrete and strands.

Disadvantages Post Tension:

1. Cable Integrity: Cables can distress over time, although this is not a common problem
2. Remodeling: If the building is renovated in the future the floor slab can only be punctured once exact locations of tendons are known.
3. Shorting issues: As a result of PT ability to hold shrinkage cracks together tightly when shorting occurs large tension cracks can occur around perimeter of building.

PROBLEM

City Vista's presents designers with several challenges due to its design and location as a result many structural systems are not feasible for use at City Vista.

1. City Vista is located in Washington D.C where there is a height limit of 130 ft. Currently Building 2 is 110'-0" not including the mechanical penthouse. At sections that include the penthouse the building is 128'-6". It will be a challenge to stay within the 130' limit.
2. Because a flat plate system is used the underside of the floor slab is already a finished ceiling. When choosing alternate floor systems this should be taken into consideration.

When considering alternative structural solutions for City Vista, cost and construction time were as much a concern as floor to ceiling height. Washington D.C. construction business is very demanding and the faster and cheaper the construction the better.

PROPOSED SOLUTION

Taking into consideration the height restriction and competitive market, I propose a precast gravity system for City Vista. This system would consist of hollow precast floor planks with a slab thickness between 8-10 inches which keeps City Vista well within the height requirement. The current lateral system will be examined for stability after the gravity system is redesigned using precast inverted T-beams, hollow core planks and conventionally reinforced columns. Using a pre-cast system could potentially present faster erection time, a cheaper bottom line, possible LEED certification, and the same floor to ceiling height.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

Advantages Pre-Cast:

1. Construction Time: Since pouring and curing is done offsite construction is significantly faster than other systems.
2. Efficiency of Members: Because members are poured and cured in controlled environments defects are limited.
3. Lightweight: Pre-cast components have good span to weight ratios, resulting in shallower foundation systems. And for this redesign the existing foundation will require little if any alterations.
4. Fireproofing: No fireproofing needed if pieces are designed with fire codes in mind.

Disadvantages Pre-Cast:

1. Lead Time: Since construction is done off site, a pre-cast system requires more planning so materials arrive on time.
2. Size Restrictions: Planks and beams come in standard sizes; therefore column grid will be restricted.




Figure #8 : Proposed typical bay for the new pre-cast system

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

LOADING CONDITIONS

The original loading conditions specified by ASCE07-05 are as follows:

DEAD LOAD

7 ½" Post Tension Slab	150 PCF
Beams	VARIES
Façade #1 (4" Brick, 8" CMU)	95 PSF
Façade #2 (4" Brick, Glass, Cold form)	35 PSF
Walls	
<i>Superimposed Dead Loads:</i>	
Partitions	20 PSF
Mechanical/Electrical	5 PSF

LIVE LOAD

Residential Units:	40 PSF
Lobbies/Corridors:	100 PSF
Balconies:	100 PSF
Mechanical/Storage:	125 PSF
Canopy:	60 PSF
Public Areas:	100 PSF
Snow:	30 PSF
Elevator Rooms:	150 PSF

Roof:

Live:

Ordinary flat Roof = 20PSF

Live Load Reduction :

$$L_r = L_0 R_1 R_2$$

$$R_1 = 1.2 - 0.001 A_t$$

$$R_2 = 1.2 - 0.05 F$$

Equipment:

*100% outside air rooftop units
 Units @ 4000lbs a piece
 Dimension :*

Snow:

$$P_f = 0.7 C_e C_s I P_g$$

$$(0.7)(1.0)(1.0)(1.0)(30) = 21PSF$$

Snow Drift				Leeward		Windward			
	H _c (ft)	Lu _T (ft)	Lu _B (ft)	H _d (ft)	W (ft)	H _d (ft)	W (ft)	γ	P _d (PSF)
A	10.58	27	84	1.7	6.8	1.51	6.04	17.9	30.43
B	10.58	15.667	163	1.3	5.2	2.32	9.28	17.9	41.528
C	10.58	9.5	29.58	1.3	5.2	0.9	3.6	17.9	23.27
D	10.58	25.5	23.4	1.3	5.2	0.9	3.6	17.9	23.27
E	10.58	9.5	24.8	1.3	5.2	0.9	3.6	17.9	23.27
F	17.83	55.5	40.2	1.9	7.6	1.125	4.5	17.9	34.01
G	17.83	22	36	1.3	5.2	1	4	17.9	23.27
H	17.83	22	46	1.3	5.2	1.2	4.8	17.9	23.27
I	17.83	14.8	42	1.3	5.2	1.2	4.8	17.9	23.27
J	17.83	55.5	70.4	1.9	7.6	1.4	5.6	17.9	34.01
K	10.58	25.5	123	1.3	5.2	2.6	10.4	17.9	46.54
L	10.58	9.5	35.3	1.3	5.2	1.35	5.4	17.9	24.165
M	10.58	9.5	31.8	1.3	5.2	1.35	5.4	17.9	24.165

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI




Figure #9: Snow Drift Diagram

Design Data:
 $P_g = 30 \text{ PSF}$
 $P_d = \gamma * W$
 $W = \text{Larger } W$
 $\gamma = 0.13P_g + 14$




Figure #10: Typical loading diagram, Residential floors

Areas highlighted in blue are CORRIDORS : LL=100PSF
 All other areas RESIDENTIAL = 40PPSF
 100 PSF **** may not be reduced****

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

PRELIMINARY ANALYSIS

To begin analysis decisions were made to optimize performance of the precast system. Many sources were used to determine the design criteria:


1. PCI Handbook 6th Edition
2. ACI 318-03
3. Several Manufacturers of Precast (Hanson, Nitterhouse, and Hollowcore)
4. PCI Manual for the design of hollow core slabs

The following topics were considered and a decisions was made with regards to the overall constructability, fire rating, mechanical and electrical requirements, erection time, seismic requirements, slab thickness, and


1. Hollow Core vs. Solid flat slab
2. Topping vs. No Topping
3. Ridged vs. Flexible Diaphragm
4. Expansion joints vs. No expansion joints
5. Tendons Considerations

1. Hollow core vs. solid flat slabs

Solid flat slabs perform similar to cast in place solid slabs. Optimized when used for short spans of 12-24 feet and floor depth of 4-16 inches. This system provides a smooth underside so it can be used as a finished ceiling. The slabs have a fire rating of between ½ -2 hours depending construction. Mechanical and electrical fittings can be embedded during casting. Deflections are easily controlled with this system, and depending on the manufacturer a 2 inch reinforced concrete topping could be required.




Hollow core slabs are utilized in intermediate spans of 12-40 feet and depths of 4-16 inches. The continuous voids reduce weight and provide space to run electrical and mechanical equipment. If designed properly the voids can be engineered as a passive solar system. Floor covering can be applied directly to the planks or a concrete topping can be applied. The concrete topping is ½ to 2" in width and can be non-structural or structural composite concrete. The underside of the plank can be utilized as a finished ceiling. Depending thickness a 1 to 4 hour fire rating can also be accomplished with hollow precast planks. A hollow core system also provides excellent sound transmission, fast onsite construction, durability, and precision casting is an added bonus.



JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Conclusion *Hollow Core Slab*: For the redesign of City Vista I would like to accomplish spans of up to 20+ feet, as little interference with other trades, fast erection, and adequate fire rating. As a result I have chosen a hollow core system which is optimized when used for intermediate spans, has better fire rating than the flat slab, and is friendlier to the space requirements of other trades.



Selling factor: Longer spans, mechanical and electrically friendly, and sound absorption.

2. Concrete vs. No concrete topping

Topping: Using a composite topping will provide added stiffness and strength with a min. topping thickness of 2 inches, and $f'c$ between 3000-4000 psi. The added topping weight can cause significant deflection, camber can be included in the original design to combat this. Diaphragm design can also be simplified with the use of a composite topping. When the shear between the planks and topping is limited to 80 psi the topping can contain all the diaphragms reinforcing. This will eliminate the need to keyhole and grout all the planks to one another.

Un-topped: (PCI 3.8.4.5) An un-topped system may be used if the shear strength is proven to meet ACI requirements. This system usually requires a reinforced perimeter and grouted joints to achieve required shear strength. An untopped system is also inherently lighter, which could potentially reduce base shear. Un-topped systems still consist of a 3/4" leveling concrete slab.

Dead Load Comparison for Hollow Core Planks	
Plank Size	Dead Load (PSI)
6 in	0.350
6 in Topped	0.564
8 in	0.446
8 in Topped	0.568
10 in	0.527
10 in Topped	0.789
12 in Topping	0.848
Topping=60mm which is approx. 2.3"	
** Information based on data from Hanson Precast and is converted from metric so answers are approx. **	

Figure #11: Dead load comparison between topped & un-topped

Minimum Cover to Achieve Fire Resistance				
Plank Size	60 Min	120 Min	180 Min	240 Min
6"	-	1"	2.5"	3"
8"	-	-	1"	2"
10"	-	-	-	1"
12"	-	-	-	-
** Information based on data from Hanson Precast and is converted from metric so answers are approx. **				

Figure #12: Required thickness to achieve specific fire ratings

Conclusion: A *topped composite slab* is industry standard. I will design for a 2" composite slab, although if the additional strength isn't needed I will only apply a 3/4" topping to level the floor. The 2" topping will result in additional camber consideration.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

3. Ridged vs. Flexible Diaphragm

Ridged diaphragm distributes horizontal forces to vertical elements proportionate to their relative stiffness. In a ridged system deflections of the diaphragm have little effect on the overall system. In high seismic zones a stiff ridged diaphragm is ideal and requires much less analysis. Chord requirements (Chord: the tension or compressive elements creating a flange for the diaphragm used to develop flexural integrity) for this system are larger than a flexible system, but potentially creates a safer distribution of forces.

Flexible diaphragms are used mainly for distribution of story shear when the lateral deformation is twice the average story drift. To keep elastic analysis simple a factor of $2R/5$ is applied. This system is less demanding on vertical elements with smaller chord requirements, and smaller shear and moment diagrams, although the stability of the floor can be unsafe compared to a ridged system.




Figure #13. Ridged Diaphragm : You can see deformation of the diaphragm is limited. For a pre-cast system this is ideal.




Figure #14: Flexible Diaphragm: You can see large deformations are experienced in the diaphragm.


Courtesy of the University of Virginia : [urban.arch.virginia.edu/~km6e/arch721/content/lectures/lec-03/home.html]

Conclusion: A ridged diaphragm will be used, this system will be provide simpler analysis, performs better in seismic zones and is inherently stronger and safer.

5. Expansion joints vs. No expansion Joints

Expansion joint requirements are specified in (PCI FIG 3.10.20)

Maximum Seasonal Climatic Temp. Change: 50°



Conclusion: No expansion joints needed. Max building length is 179'-4"

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

7. Tendons:

Prestressed vs. Non-Prestressed

Prestressed concrete members achieve higher span to depth ratio and better resistance to cracking. Conventionally reinforced is only used in small construction projects where small loads are experienced.

Post tension vs. Pre-tensioned

Post-tension tendons are placed in conduits during casting then tensioned in the field after erection and grouted. They are placed in conduits so they do not bond to concrete during curing. Post tensioning is usually used in conjunction with pre-tensioning when a component cannot sustain the full stressing before stripping, or to stop cracking during production.

Conclusion: *Pre-tensioned*, 270ksi low relaxation (7) wire strands, 2-3 strands per bundle and varying diameters.

Strand placement: The number of depressions: varies from 0-2. (2) points of inflection can potentially create a higher capacity. Depending on fire rating thicker cover is required.

Debonding: When there is an area of high stress concentration and as a result pragmatic cracking occurs, which could cause failure. In prestensioned concrete there are areas of high stress at the edges. The tendons begin to separate from the concrete causing cracking and a decrease in capacity.

DESIGN CONSIDERATION

When determining preliminary framing dimensions the following were considered:

1. Framing Dimensions
2. Span to Depth Ratio
3. Connection Concepts
4. Mechanisms for control of volume change
5. Optimization of member sizes
6. Basic Design Data

Framing Dimensions: Select modular dimensions from standard pieces. Optimize this selection by choosing the least amount of components that satisfy structural, architectural, cost, production, shipping, and erection requirements.

Optimization of Members:

Beams: Due to the height restriction in Washington D.C. choosing a beam depth is the first concern. Therefore, a T-Beam is the most sufficient, depending the size of the beam 8-16 inches could be added to the floor slab. The column to beam connection creates a moment due to eccentricity. To minimize or subtract this spans should of equal length and loading. Other ways to optimize member are:

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

1. Maximize repetitive and modular dimensions for plan layout and member dimensions.
2. Use simple spans whenever possible.
3. Minimize the number of different member types and sizes.
4. Minimize the number of different reinforcing patterns in the particular member type.

Columns: Because this is a condominium building space is money. As a result smaller column sizes are desired.

Span to Depth Ratio

Hollow-core floor slabs	30 to 40
Hollow-core roof slabs	40 to 50
Stemmed floor slabs	25 to 35
Stemmed roof slabs	35 to 40
Beams	10 to 20

Architectural: City Vista is a condominium building whose previous gravity system used longer spans and less columns than a precast system. The column grid was also skewed to accommodate the architectural plan. When planning a new column layout it will be a challenge to create a uniform grid while considering the open architectural plan. Although additional columns will reduce column sizes.

Cost Info

Hollow Core Planks	\$ 8.15 (8" plank 20 ft span)
Beams	\$ 143.00 (12x16 T beam 20 ft span)
Columns	\$ 69.00 (14 ft 14x14 column)

Figure #15: All info is from RSM and only includes material cost

Transportation:

Weight:

No Permit: 20 Tons of Material
 Permit: up to 100 Tons
 Washington D.C.:

Dimensions:

No Permit: 8ft x 40ft
 Permit: 13.5ft x 70ft
 Washington D.C.: 13.5':tall 8': wide (2' overhang limit)
 -Per load permits available but expensive

<i>Permit Restriction:</i>	Limited to Monday: After Noon Friday: Until Noon M-F: Not during rush hour (8-9 am & 5-6pm)
----------------------------	---

Connection Concepts: Pre-Cast connections can be complicated, as a result during preliminary design connection options should be examined.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Erection Connections:

Wet Cast: Allows for many types of anchors because they are installed during casting.

Dry Cast: Limited to shallow anchors because anchors are inserted with grout after production and curing.

Member Connections:

Beams connect to columns using hanger. These connections are expensive, provide little bearing area, and are susceptible to fabrication errors although, these connections work well in areas where floor to ceiling height is an issue.

Control of volume change: Once preliminary design has been established charts located in the PCI handbook should be used to establish totally shortening/expansion due to creep and shrinkage. These strains will be used when designing connections.

Basic design data:

1. Occupancy of the structure : Residential | R-2
2. Fire ratings
 - TYPE: II
 - Walls: 2 Hours
 - Floors: 2 hours
 - Cover: Concrete topping 2 → 2.5"

Min Slab Thickness: 6 inches
 Slab Width: 8" (6" plank 2" topping)

PRELIMINARY DESIGN

Preliminary Column Layout:




Figure #16: New column grid with old overlaid

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

MEMBER SELECTION:


Hollow Core Planks:

Planks were selected from manufacturer Nitterhouse [www.nitterhouse.com]. This company was chosen because it services the D.C. area and has a good reputation for quality.


USE: 4' x 6" hollow core planks with 2" topping (2 hr fire rating) 7-1/2" Ø strands

(See Appendix #2 for Calculations)

PHYSICAL PROPERTIES	
$A_c=253 \text{ in}^2$	Precast $S_{bc} = 370 \text{ in}^3$
$I_c=1519 \text{ in}^4$	Topping $S_{tc}= 551 \text{ in}^3$
$Y_{bc}=4.10 \text{ in}$	$W_t=195 \text{ plf}$
$Y_{tc}=1.90 \text{ in}$	$W_t=48.75 \text{ psf}$



Exterior-Beams: (See Appendix #2 for full calculations)
 20LB20/ 98-S: (9) 1/2"Ø low relaxation strands – straight



PROPERTIES 20LB20:	
$A=304 \text{ in}^2$	$S_b= 1,163 \text{ in}^3$
$I=10,160 \text{ in}^4$	$S_t= 902 \text{ in}^3$
$h_1=12 \text{ in}$	$f'_c=5000 \text{ psi}$
$h_2=8 \text{ in}$	$f_{pu}=270 \text{ ksi}$
$C_t= 11.26 \text{ in}$	$A_{sp}= 9(0.153)= 1.377 \text{ in}^2$
$C_b= 8.74 \text{ in}$	$P_o= 278.8 \text{ Kips}$
$W_t=317 \text{ plf}$	
$e=6.33 \text{ ''}$	


Beam Designation	$W_u \text{ plf}$	TRAIL SIZE
LB-1	1147.3	20LB20
LB-2	1147.3	20LB20
LB-3	1147.3	20LB20
LB-4	1147.3	20LB20
LB-5	353.0	20LB20
LB-6	353.0	20LB20
LB-7	1558.5	20LB20
LB-8	1558.5	20LB20
LB-9	1270.8	20LB20
LB-10	1270.8	20LB20
LB-11	353.0	20LB20
LB-12	353.0	20LB20
LB-13	353.0	20LB20
LB-14	353.0	20LB20
LB-15	353.0	20LB20
LB-16	353.0	20LB20

Beam Designation	$W_u \text{ Plf}$	Trail Size
LB-16	353.0	20LB20
LB-17	353.0	20LB20
LB-18	353.0	20LB20
LB-19	1059.0	20LB20
LB-20	1059.0	20LB20
LB-21	353.0	20LB20
LB-22	353.0	20LB20
LB-23	353.0	20LB20
LB-24	353.0	20LB20
LB-25	353.0	20LB20
LB-26	353.0	20LB20
LB-27	353.0	20LB20
LB-28	353.0	20LB20
LB-29	353.0	20LB20
LB-30	353.0	20LB20
LB-31	353.0	20LB20


JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Interior Beams: (See Appendix #2 for calculations)
 12RB16 / 58-S: (8) 1/2" ϕ low relaxation strands - straight



28IT20 / 98-S: (9) 1/2" ϕ low relaxation strands – straight
 28IT24 / 188 -S: (18) 1/2" ϕ low relaxation strands – straight



PROPERTIES 12RB20:

A=192in²
 I=4096 in⁴ f_c=5000psi
 h=16 in f_{pu}=270ksi
 S = 512 in³ A_{sp}= 5(0.153)= 0.765 in²
 b = 12 in P_o= 154.9Kips
 Wt=200 plf
 e = 5"
 d=8"

PROPERTIES 28IT24:

A=480 in² Y_b= 9.60in
 I=20,275 in⁴ S_b= 2,112 in³
 h₁=12 in S_t= 1,408 in³
 h₂=12 in f_c=5000psi
 C_t = 14.4 in f_{pu}=270ksi
 C_b= 9.60 in A_{sp}= 18(0.153)= 2.754 in²
 Wt=500 plf P_o= 557.6 Kips
 e =6.87"

PROPERTIES 28IT20:

A=368 in² Y_b= 7.91in
 I=11,688 in⁴ S_b= 967 in³
 h₁=12 in S_t= 1,478 in³
 h₂=8 in f_c=5000psi
 C_t = 12.09in f_{pu}=270ksi
 C_b= 7.91 in A_{sp}= 9(0.153)= 1.377 in²
 Wt=383 plf P_o= 278.8 Kips
 e =5.47"

Interior Beams		
DESIGNATION	W _u plf	TRAIL SIZE
TB-1	2665.15	28IT24
TB-2	2665.15	28IT24
TB-3	2665.15	28IT24
TB-4	2665.15	28IT24
TB-5	2797.29	28IT24
TB-6	-	28IT24
TB-7	3855.00	28IT20
TB-8	3855.00	28IT20
TB-10	2797.29	28IT24
TB-11	4692.99	28IT20
TB-12	2915.77	28IT20
TB-13	2915.71	28IT20
TB-14	2118.00	28IT20
TB-15	2733.40	28IT20
TB-16	*	28IT24
TB-17	2829.49	28IT20
TB-18	2733.40	28IT24
TB-19	*	28IT24
TB-20	2319.49	28IT20
TB-21	2733.40	28IT24
TB-22	*	28IT24
TB-23	2738.76	28IT24
TB-24	2733.40	28IT24
TB-25	*	28IT24
TB-26	3202.36	28IT24
TB-27	2733.40	28IT24
TB-28	*	28IT24
TB-29	2734.46	28IT24
TB-30	2733.40	28IT20
TB-31	*	28IT24
TB-32	2734.46	28IT24
TB-33	2331.74	28IT28
TB-34	2331.74	28IT28
RB-1	1563.20	12RB16
RB-2	2316.25	12RB16
RB-3	485.44	12RB16
RB-4	513.57	12RB16
RB-5	513.57	12RB16
RB-6	2316.25	12RB16
RB-7	*	12RB16
RB-8	545.00	12RB16
RB-9	*	12RB16

* Designate beams with special loading conditions. Analysis for these beams can be seen in Appendix #2

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Columns

A summary of the column sizing and loading can be found in appendix #2. Columns were sized every 4 floors to accommodate both the decrease in gravity loads and the ability to cast columns to span 2 stories. Columns were designed and then checked in PCA column.

The following columns were selected:


16"x16" | $f_c = 5000$ psi | 4-#8 Bars

18"x18" | $f_c = 5000$ psi | 4-#9 Bars

20"x20" | $f_c = 5000$ psi | 4-#9 Bars

24"x24" | $f_c = 5000$ psi | 4-#11 Bars

FINAL LAYOUT / MEMBER CHECK



Highlighted pre-cast members are either worst case scenarios or special loading conditions and detailed checked were done for the following: (results can be seen in appendix #2)

1. Flexure
2. Shear
3. Transfer Stress
4. Pre-Stress Losses
5. Serviceability
6. Deflection and Camber

1: *Hollow Core Planks*: Corridor Loading

2: *Hollow Core Planks*: Residential Loading

3: *Exterior L-Beam*: Special loading condition

4: *Exterior L-Beam*: Special loading conditions


5: *Interior T-Beam*: Combined loading conditions (LL 40-100)

6: *Interior T-Beam*: Combined loading conditions (LL 40-100)

PRELIMINARY CHECK

GRAVITY SYSTEM ISSUES:

Floor Section: Due to pre-cast construction the floor depth and composition has changed. Initially City Vista was a 7 ½" flat plate slab. Now it is an 8" slab with beams framing in every bay.



Load Distribution:

ISSUE: If load is not applied to the center of a plank the plank has the tendency to twist and deflect, grouting forces neighboring beams to take some of the deflections. Shear forces are now created causing torsion and now the system act as a 2 way slab that transfers bending moment .

SOLUTION: The 2" composite topping will create a monolithic slab so forces will be distributed between planks. Also no significant point loads are seen by the hollow core planks, therefore load distribution won't be an issue

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Creep and Shortning:

Creep occurs over time by continuous loading, causing pre-stress losses, deflection, and stresses in non bearing members. Concrete shortens as it cures. These factors and others were considered in the pre-stress losses calculations found in appendix #3.

$TOTAL STRAIN = 4.43E-4 + 150E-6 = \underline{5.93 \times 10^{-4}}$
 $TOTAL SHORTNING = 5.93E-4(12)(26) = \underline{0.185 \text{ in}}$

CONNECTIONS:

Column to Foundation: Currently City Vista Building 2 is slab on grade construction with augured piles. Columns sit on pedestal pile caps 48" deep and 4'-6" to 12'-6" in length. For the new pre-cast system I am proposing the current augured pile pedestal system with the addition of base plates and anchors to secure the pre-cast columns. (For calculations see Appendix #3) The following calculations were done for a column C18 a 20"x20" column.





Figure #18 :Typical detail as per PCI 6th edition


JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Hollow Core to Beam: Both the L-Beam and T-Beam use ledgers to support the hollow core planks, therefore the ledgers must be reinforced to support the load. A bearing pad is placed on ledgers to help distribute the load. Uneven loading on T-beams create torsion, a remedy is additional reinforcing in the ledgers. (All calculations in Appendix #3) Bearing pads are to be 1/2" past edge, and hollow core planks are required to bear a minimum of 3 in or $l_n/180$ past ledge.



Beam to Column: Beams will be poured with dapped ends to connect to columns with hanger connections. Hangers are the most expensive and prone to errors during production. Although in a situation where floor to ceiling height is tight it is the best option to minimize space. Corbels may be easier to manufacture and erect, but take up considerably more space. Reinforcing will be added for direct shear, flexure, tension, and diagonal. All calculations are located in Appendix #3.



JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI




Figure #21 : Typical hanger detail as found in PCI 6th edition.

The actual hanger and bolts have not been designed. In this exercise only the reinforcing relating directly to the T, L and R beams manufacturing.

Full calculations can be found in appendix #3

DIAPHRAM

In the pre-design stages a composite topping was selected for its load distribution, additional strength, connection of planks, and fire rating. When the horizontal stress between the topping and hollow core planks is limited to 80 psi the diaphragm can be contained in the topping eliminating keyways and grouting in hollow core planks.

If Horizontal Shear: $VQ/I < 80 \text{ PSI}$; the chords struts and drags can all be contained with-in the topping. The actual design of the diaphragm is out of the realm of knowledge, and is not included in the scope of this gravity analysis.


JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

FOUNDATION CAPACITY:

The current foundation system will be compatible with the pre-cast system as well. The new system may require additional pile caps but not many. The new system is 3,000 kips heavier than the PT system, so additional piles will need to be added, although this will be accounted for by the additional pile caps and pedestal footings for the 5 additional columns.

PT System



Pre-cast System.

The maximum column load is 984 kips, therefore all the columns in the new system fall into one of the four pile cap categories. The only alteration to the foundation system will be the column to pedestal connections shown in the connection section on page 27.

LATERAL CHECK

The new floor system created a slightly taller and heavier building; therefore new seismic and wind calculations were formulated. A lateral check was then conducted for lateral stability. PCA Column was used flexural strength, shear reinforcing and building drift was also examined. The (4) walls were not expected to need any alteration due to only a 3' increase in wall height and 3000 kip increase in weight. [For more detail see appendix #4]




Figure #22: Shear Wall Locations, Size, and Reinforcing

Load Combinations : Strength Design

[ASCE 7-05 2.3.2 & 12..2.3]

- #1 : 1.4D
- #2: 1.2D + 1.6L + 0.5S
- #3: 1.2D + 1.6S + 0.8W
- #4: 1.2D + 1.6W + L + 0.5S
- #5: **(1.2+0.2S_{ds})D + ρE + L + 0.2S**
- #6: 0.9D + 1.6W + 1.6H
- #7: **(0.9 - 0.2S_{ds})D + ρE + 1.6H**

→ ρ [Design Category D, H/L<1] 1.0
 S_{ds} = .163

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

FLEXURE CHECK




Figure #23: Interaction Diagram for Shear Wall #2 & Wall #4
Pu = 1,401.9 Kips
Mu = 9,806.8 Kip-ft
COMBO 50
Reinforcing: #8 @ 12" O.C (Floor 1-2)
#5 @ 12" O.C (floors 3-11)




Figure #24 : Interaction Diagram for Shear Wall #3
Pu = 264.57 Kips
Mu = 7,144 Kip-ft
COMBO 48
Reinforcing: #5 @ 12" O.C




Figure #25 : Interaction Diagram for Shear wall # 1
Pu = 162.3 Kips
Mu = 2,035.7 Kip-Ft
COMBO 48
Reinforcing: #5 @ 12" O.C

Combo 48 = 0.867D + 1.0 Quake X(-)Y eccentricity
Combo 50 = 0.867D + 1.0 Quake Y(-) X eccentricity

All shear walls are adequate in flexure. Shear walls #1 and #3 reinforcing were consistent with the original schedule (see appendix #4). Shear walls #2 and #4 were not and needed larger reinforcing for the first 2 stories.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

SHEAR CHECK

Controlling Factors : From code

(2) Curtain of Reinforcing needed when : $V_u \geq 2A_{cv}\sqrt{f'_c} = 20.36$ kips
 Boundary Element needed when: $P_u/P_o \leq 0.30$
 Wall Thickness $\geq l_u/16 = 7.5'' < 12''$ OK

Wall #1

Combo 30 : 1.233 D + 1.0L + 0.2S + 1.0 Quake X (-) Y eccentricity
 $63.8 > 20.36$: Use 2 Curtains

Reinforcing: #4 @ 12" O.C $A_s = 0.20 * 2$ curtains = $0.40 \text{ in}^2 > 0.36 \text{ in}^2$ Required
 Boundary Element : $0.0328 < 0.30$ None Required

Wall #2&4:

Combo 48 : 0.867D + 1.0 Quake X(-)Y eccentricity
 $272.48 > 20.36$: Use 2 Curtains

Reinforcing: #5 @ 12" O.C $A_s = 0.31 * 2$ curtains = $0.62 \text{ in}^2 \geq 0.62 \text{ in}^2$ Required
 Boundary Element: $0.79 < 0.30$ None Required

Wall #3:

Combo 30 : 1.233 D + 1.0L + 0.2S + 1.0 Quake X (-) Y eccentricity
 $400.288 > 20.36$: Use 2 Curtains

Reinforcing: #4 @ 12" O.C $A_s = 0.20 * 2$ curtains = $0.40 \text{ in}^2 \geq 0.36 \text{ in}^2$ Required
 Boundary Element: $0.34 > 0.30$ Required 4 ft each side





Figure #26 : Typical Shear wall Detail


Again shear walls #1 and #3 were consistent with the original reinforcing schedule (see appendix #4) specified by the engineer. Shear walls #2 and #4 were not and required larger reinforcing. Bars were increasing from #4 to #5. This was expected after flexural reinforcing was increased.

Wall Reinforcing Summary


Wall #1 :



Wall #2&4:



Wall #3 :



For full reinforcing detail and the existing reinforcing schedule see appendix #4

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

DRIFT CHECK

An E-tabs serviceability model was created to check the displacement and story drift. $P\Delta$ effects were taken into consideration during E-Tab's analysis, with the non-iterative mass base method. Seismic base shear controlled, therefore seismic displacement was examined. Story drift and displacement values are taken from the E-Tabs output. To comply with ASCE7-03 story drift was multiplied by an amplification factor (C_d) and then divided by the importance factor (I_e) before comparing it to the story drift limit (Δ_b) specified in *ASCE7-03 Table 12.12-1*. In the charts below story drift and δ_{ei} (story displacement) are taken from the E-Tabs output. δ_i is the amplified displacement.

$$\text{Story Drift Requirement} = (\delta_e - \delta_e)C_d / I_e \leq \Delta$$

Story	Wall #3			Wall #1			Quake X Direction		
	Story Drift	δ_{ei}	δ_i	Drift	δ_{ei}	δ_i	Total Story Drift (δt)	Δ_b	$\delta t \leq \Delta_b$
11	0.26	1.17	0.91	0.26	1.17	0.91	1.82	2.40	OK
10	0.26	1.16	0.90	0.259	1.17	0.91	1.81	2.40	OK
9	0.26	1.16	0.90	0.258	1.16	0.90	1.81	2.40	OK
8	0.26	1.15	0.89	0.255	1.15	0.89	1.79	2.40	OK
7	0.25	1.11	0.86	0.247	1.11	0.86	1.73	2.40	OK
6	0.23	1.05	0.82	0.234	1.05	0.82	1.64	2.40	OK
5	0.21	0.96	0.75	0.214	0.96	0.75	1.50	2.40	OK
4	0.19	0.85	0.66	0.188	0.85	0.66	1.32	2.40	OK
3	0.15	0.69	0.54	0.153	0.69	0.54	1.07	2.40	OK
2	0.11	0.51	0.40	0.1137	0.51	0.40	0.80	2.40	OK
1	0.07	0.32	0.25	0.0715	0.32	0.25	0.50	3.12	OK

Symbol Key

δ_{ei} = Elastic displacement taken from E-Tabs model

$\delta_i = [C_d \delta_{ei} / I_e]$ Amplified displacement

$\Delta_b = 0.020h_{sk}$ Allowable story drift


Story	Wall #2&4			Quake Y Direction		
	Story Drift	δ_{ei}	δ_i	Total story Drift (δt)	Δ_b	$\delta t \leq \Delta_b$
11	0.54	2.43	1.89	3.78	2.40	NG
10	0.53	2.39	1.86	3.71	2.40	NG
9	0.52	2.34	1.82	3.64	2.40	NG
8	0.51	2.30	1.79	3.57	2.40	NG
7	0.48	2.16	1.68	3.36	2.40	NG
6	0.44	1.98	1.54	3.08	2.40	NG
5	0.43	1.94	1.51	3.01	2.40	NG
4	0.41	1.85	1.44	2.87	2.40	NG
3	0.39	1.76	1.37	2.73	2.40	OK
2	0.25	1.13	0.88	1.75	2.40	OK
1	0.165	0.74	0.58	1.155	3.12	OK

Both the X and Y direction met displacement and drift requirement

Total Displacement: **X = 1.82 in OK**


Y = 3.78 in NG

Displacement Summary




Wall #1 : Deformed shape under seismic forces in the X direction.

Wall Adequate



Wall #2 & 4 : Deformed shape under seismic forces in the Y direction

Wall Inadequate



Wall #3 : Deformed shape under seismic forces in the X direction

Wall Adequate

After examination of the lateral system it can be concluded that shear walls #2 and 4 are inadequate and will need to be redesigned. Even after thickening these walls to 16" the walls were unable to resist seismic displacement. This was partly expected after reinforcing was increased to support flexure and shear in both walls. To correct this problem an increase in length or different placements of the (2) walls will need to be examined further.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

BREADTH#1: CONSTRUCTABILITY

There are several constructability issues with the redesign of City Vista.

1. *ERECTION:* With pre-cast the erection of the structural system is much different from post tension. Members are set in place with a crane. This process caused forces in the member which can sometimes affect the design.
2. *LEEDS:* Pre-cast concrete allows for easier obtainment of a Leeds rating. An in-depth analysis was not performed, although advantages are discussed showing that LEEDS certification is more feasible with a pre-cast building.
3. *COST:* A Cost analysis was done to compare the gravity system cost of the PT and pre-cast system.
4. *SCHEDULING:* A simple schedule was also assembled to show potential time savings the precast system could provide.

ERECTION



Currently a saddle jib tower crane is being used at City Vista. After examining the cut sheets it is sufficient for erection of the pre-cast members.


Concerns:

Design of pre-cast members is influenced by storage and stripping, the number of pick points and location of the crane. All these variables create forces in the member need to be considered during design. For example the figure below shows a two point pick using a spreader beam.


Predominantly line lifts will be used to assemble City Vista since all components have long spans and thin depths. As a result the inclined lines created by the two pick point creates a moment due to $p\Delta$ affects. Eccentric moments created by picks not at the center of the member are also an issue. As a safe practice a minimum **safety factor of 1.2** is applied to all pre-cast products, this factor accounts for stripping and dynamic forces.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI



Smooth erection at City Vista: Building 2 superstructure is erected before Building 1, as a result a lay down area is available (see diagram below). Currently the crane is located between the two buildings on the pedestrian bridge footings which double as crane footing.



JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

LEED POTENTIAL

LEEDS ASSESMENT

Sustainability is the development that meets the needs of the present without compromising the ability of future generations to meet their own needs.

Pre-Cast concrete is a sustainable practice because it uses:

1. Integrated design
2. Materials efficiency
3. Reduces waste, site disturbance, and noise

Integrated design, when you examine a building as a whole not as individual parts. By doing this you can concentrate on energy efficiency, durability, environmental impacts, and cost.

Material efficiency is the combination of reducing energy and emissions created by building materials.

Reductions, is reducing the amount of material and toxic waste created when buildings are built.

WHY?

- *Operation Cost*: \$0.60-1.50 sqft vs. \$1.80 sqft of conventional buildings.
- Lower energy cost translates into smaller cooling equipment → lower first cost for equipment.
- Green design first cost ranges from 0-2% more than conventional buildings.
- This 2% increase → 10 times the initial cost in operation cost.

HOW?

- Material savings when precast panels are used for interior walls. This eliminates the need for drywall and additional framing.
- Eliminate duct work when hollow core planks voids are used as ducts.
- Concrete is a durable material therefore reducing maintenance.

LEED RATING AT CITY VISTA:

As discussed above a pre-cast building can obtain 23/26 points required for green certification, but exactly how is this accomplished by simply changing the method of concrete casting from onsite post tension to offsite pre-tension.

- **Material Recourses**: Precast components can be reused when building is renovated or demolished, reducing air and land pollution caused by demolition. Corrosion resistance which in return means less maintenance. This is because precast is made under ideal circumstances so things like steel cover are carefully monitored.
- **Sustainable site**: The heat island effect is minimized by concrete because pre-cast concrete provides a reflective surface.
- **Production**: Pre-cast plants create little waste. About 2.5% of the volume used in production is disposed of, and 95% of the water used is reused for other process. Steel formworks are also reused over and over again.
- **Recycled Content**: Concrete is a recycled material, and reinforcing bars are 90% recycled material. 95% of the waste water and steel formworks are reused

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

- **Energy:** Hollow core plank voids can be used as a passive solar system. This can be done by using the voids themselves as ducts changing the planks thermal mass. Energy reduction during production can be accomplished through the use of slag cement or silica fume. These items would be waste if not utilized in concrete products.
- **Local Materials:** Most suppliers are within 200 miles of the site.
- **Reuse:** At the end of the useful life of the building pre-cast pieces can be unassembled and reused.

LEEDS SUMMARY	
Sustainable Site	
Site Development, restore habitat	1
Site Development, maximize open space	1
Heat island effect	1
Energy and Atmosphere	
Prerequisite: Minimum Energy Performance	
Optimize Energy Performance	1-10
Material and Resources	
Reuse, maintain 75% existing shell	1
Reuse, maintain 25% existing shell	1
Construction waste management divert 50% by wt. or vol.	1
Construction waste management divert 75% by wt. or vol.	1
Recycled Content (10% of material on project, based on cost)	1
Recycled Content (20% of material on project based on cost)	1
Local/Regional material (minimum of 10%, based on cost)	1
Local/Regional material (minimum of 20%, based on cost)	1
Indoor Environmental Quality	
Construction Indoor air quality , during construction	1

Innovation and Design Process	
High volume supplementary cementitious materials	1
Apply for other credits demonstrating performance	1
Apply for other credits demonstrating performance	1
Apply for other credits demonstrating performance	1
LEED accredited professional	1
TOTAL	23

Figure 27 #: LEED Checklist for pre-cast building , courtesy of www.PCL.org

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

COST ANALYSIS:

Pre-Cast Gravity System Cost Analysis:

Pre-Cast System		Page 1 of 1					
Quantity	Assembly Number	Description	Unit	Ext. Material O&P	Ext. Installation O&P	Extended Total O&P	Labor Type
84.85	80102152000	Concrete beam, precast, 12" x 15", 200 PLF, 15...	L.F.	\$ 4,072.80	\$ 1,694.58	\$ 5,727.38	Standard Union
84.847	80102152800	Concrete beam, precast, 12" x 15", 200 PLF, 20...	L.F.	\$ 5,387.78	\$ 1,092.83	\$ 6,480.61	Standard Union
510	010102141000	Concrete T beam, precast, 24" x 20", 360 PLF, ...	L.F.	\$ 111,100.00	\$ 0,445.00	\$ 111,625.00	Standard Union
273.5	010102145750	Concrete T beam, precast, 24" x 20", 665 PLF, ...	L.F.	\$ 60,495.00	\$ 5,016.00	\$ 65,508.00	Standard Union
70.97	0101021503000	Concrete I beam, precast, 12" x 20", 300 PLF, 1...	L.F.	\$ 0,202.50	\$ 1,385.05	\$ 1,587.55	Standard Union
224.58	80102152000	Concrete I beam, precast, 12" x 20", 300 PLF, 2...	L.F.	\$ 26,091.28	\$ 3,095.96	\$ 29,148.24	Standard Union
235.94	80102154000	Concrete I beam, precast, 12" x 28", 495 PLF, 2...	L.F.	\$ 32,599.72	\$ 2,597.70	\$ 35,157.42	Standard Union
79,401.64	010102002800	Precast concrete planks, 2" topping, 0' total thic...	S.F.	\$ 240,275.37	\$ 135,910.36	\$ 376,185.73	Standard Union
940	010102071500	Precast concrete column, 20" sq. tied, eccentric...	V.L.F.	\$ 01,700.00	\$ 0,030.00	\$ 80,410.00	Standard Union
300	80102071300	Precast concrete column, 18" sq. tied, eccentric...	V.L.F.	\$ 28,888.88	\$ 3,888.88	\$ 35,888.88	Standard Union
				\$ 583,934.47	\$ 169,412.48	\$ 753,346.95	

Pre-Cast System : a typical floor
 Materials: \$583,934.00
 Installation: \$ 169,412.00
TOTAL : \$ 753,347.00 / FLOOR

Analysis was done using the program cost works by RSMears. Values were drawn from Commercial/ New construction cost book released in 2008. A stand union labor was assumed and no mark ups were included.

Total Cost :
 [\$753,347 * 6] + [\$647,372*5] =
 ** The two different floor prices take into consideration the double height columns **
Approx. TOTAL = \$ 7,756,942.00

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

Post Tension Gravity System cost Analysis:

Page 1 of 1

Quantity	Assembly Number	Description	Unit	Ext. Material OMP	Ext. Installation OMP	Extended Total OMP	Labor Type
324,298	010102294200	Mid plate, concrete, 1" slab, 18" column, 20"x20"	S.F.	\$ 1,857,704.00	\$ 2,990,076.26	\$ 4,027,781.16	Standard Union
5,820	010100004000	Cast-in-place concrete column, 24" square, bed...	V.L.F.	\$ 303,000.00	\$ 761,000.00	\$ 1,133,000.00	Standard Union
				\$ 1,999,312.00	\$ 3,151,112.00	\$ 5,150,425.80	

PT. System : a typical floor

Materials: \$18,120.00
 Installation: \$ 286,465.00

TOTAL : \$ 604,584.00 / FLOOR

Analysis was done using the program cost works by RSMeans. Values were drawn from Commercial/ New construction cost book released in 2008. A stand union labor was assumed and no mark ups were included.

Approx. TOTAL = \$ 5,150,425.00

The post tension system cost considerably less. This is due to the additional beams needed to support the hollow planks. The post tensioned slab and planks with topping price is competitive with one another. The same can be said when comparing the pre-cast and cast in place conventionally reinforced columns. Economically a post tensioned flat plate building is considerably cheaper.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI

SCHEDULE


Pre-Cast System:

Typical erection of pre-cast is 400m² /week of pre-cast = 62,000 in² /week

Typical Floor :

Member	Quantity	Total Area
<i>Column #1 [20x20]</i>	24	66.69 in ²
<i>Column #2 [16x16]</i>	10	17.68 in ²
<i>Column #3 [24x24]</i>	23	92 in ²
<i>L-Beams</i>	31	9424 in ²
<i>T-Beams</i>	34	16 320 in ²
<i>R-Beams</i>	9	1728 in ²
<i>Planks</i>	200	50,600 in ²
TOTAL		<u>78,249 in²</u>

A two floor schedule was done in Microsoft project to reflect this erection pace, while taking into consideration the double floor column height. This analysis shows erection pace of 2 floor in **9 Days**.



Pre-Cast erection saves about 5.5 days in the schedule. Not a significant difference when considering the higher cost of the system.

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI


Post Tension System: Courtesy of Davis Construction

Activity ID	Activity Description	Orig Dur	Rem Dur	Early Start	Early Finish	Total Float
Building 2						
<i>Concrete Structure</i>						
Level 1						
02010010	Bldg 2 - Sitework / Foundations & SOG	80*	80*	29DEC05	20APR06	0
02010020	Install Test Piles	5	5	29DEC05	05JAN06	0
02010022	Install Test Probes, Test reports & Mobilize	14	14	06JAN06	25JAN06	0
02010024	Install Tower Crane Foundation	8	8	09FEB06	20FEB06	36
02010028	Erect Tower Crane	2	2	21FEB06	22FEB06	36
02010030	Start Auger Cast Piles - Bldg 2	0	0	26JAN06		0
02010035	Install Auger Cast Piles	20	20	26JAN06	22FEB06	0
02010040	Start Concrete Foundations - Bldg 2	0	0	23FEB06		0
02010045	F,R&P Pile Caps & Grade Beams	25	25	23FEB06	29MAR06	0
02010050	Selective Demo/Cut Site	25	25	24FEB06	30MAR06	0
02010055	Foundations / Slab on Grade - Bldg 2	41*	41*	23FEB06	20APR06	0
02010060	F,R&P Foundation Walls & Cols	25	25	03MAR06	06APR06	0
02010070	Backfill Foundation	10	10	10MAR06	06APR06	0
02010080	Rough-in Underground Plumbing	10	10	10MAR06	06APR06	0
02010085	Inspect Underground Plumbing	5	5	07APR06	13APR06	0
02010090	Rough-in Underground Electric	10	10	10MAR06	06APR06	0
02010095	Inspect Underground Electric	5	5	07APR06	13APR06	0
02010100	Prep & Pour Slab-on-Grade	5	5	14APR06	20APR06	0
02010110	Slab-on-Grade Complete - Bldg 2	0	0		20APR06	0
Level 2						
02020090	Start Concrete Structure - Bldg 2	0	0	21APR06		0
02020095	Concrete Structure (1st - Roof) - Bldg 2	60*	60*	21APR06	17JUL06	0
02020100	F,R&P Slabs, Walls & Cols - 2nd	7	7	21APR06	01MAY06	0
Level 3						
02030100	F,R&P Slabs, Walls & Cols - 3rd	5	5	02MAY06	08MAY06	0
Level 4						
02040100	F,R&P Slabs, Walls & Cols - 4th	5	5	09MAY06	15MAY06	0
Level 5						
02050100	F,R&P Slabs, Walls & Cols - 5th	5	5	16MAY06	22MAY06	3
Level 6						
02060100	F,R&P Slabs, Walls & Cols - 6th	5	5	23MAY06	30MAY06	5
Level 7						
02070100	F,R&P Slabs, Walls & Cols - 7th	5	5	31MAY06	06JUN06	8
Level 8						
02080100	F,R&P Slabs, Walls & Cols - 8th	5	5	07JUN06	13JUN06	12
Level 9						
02090100	F,R&P Slabs, Walls & Cols - 9th	5	5	14JUN06	20JUN06	15
Level 10						
02100100	F,R&P Slabs, Walls & Cols - 10th	5	5	21JUN06	27JUN06	16
Level 11						
02110100	F,R&P Slabs, Walls & Cols - 11th	5	5	28JUN06	05JUL06	16
Roof						
02RF0100	F,R&P Slabs, Walls & Cols - Main/PH Roof	8	8	06JUL06	17JUL06	16
02RF0195	Concrete Top-Out - Bldg 2	0	0		17JUL06	16
02RF0198	Dismantle Tower Crane 1 (NE)	0	0		05APR07	0


On average the current structure is assembled at a rate of 1 floor per week

BREADTH #2: ARCHITECTURAL ALTERATIONS

The hardest part about coordinating the existing architecture plans and the new column grid was the acquiring of the cad files. The cad files were not acquired until very late in the design process as a result there were small discrepancies between the plan created by hand in cad for analysis and the actual CAD files. The column grid was overlaid on a typical floor then 3 problem areas were chosen and architectural alterations were made. A section is also included showing the altered floor to ceiling height and ceiling appearance with the addition of T-Beams.



AREA 1




Existing Plan

Area 1 is a one bedroom/den combo layout is shown on the left with the new column grid in blue. It is evident that a 16" x 16" column circled in blue, location is unacceptable. The column creates a tight unusable space between it and the neighboring walls. Alterations were necessary to maximize the rentable space, and correct the flow issue created by the column.

SQFT approx. = 780 sqft

Photo courtesy of Lowes developers
www.cityvistadc.com. [Figure N.T.S]




Area 1 Alterations

The floor plan was essentially mirrored to accommodate the column. Column C44 is now located within the wall between the kitchen and master bedroom. All spaces were kept to their original dimensions as shown above.

Fig # : New proposed floor plan for apt units 112, 212, 312, 412, 512, 612, 712, 812, 912, 1012, and 1112. [Figure N.T S]

AREA 2



Existing Plan


Area 2 is part of a one bedroom condo, layout is shown on the left with the new column grid in blue. (2) Columns are in critical locations and the floor plan needs alterations.

SQFT approx. = 650 sqft

Photo courtesy of Lowes developers
www.cityvisatdc.com [Figure N.T S]

JULIE DAVIS
STRUCTURAL OPTION
 APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
 ADVISOR: DR. MEMARI




Area 2 Alterations

Unlike area 1 area 2 has (2) obstructions, as a result it was difficult to redesign the space to optimize both the window space and the rentable space. A decision had to be made between a smaller closet, or eliminating the awkward cubby between column C25 and the wall. Closet space is a definite plus for renters, so closet space was not reduced. It was decided the “cubby” space could be used as bookshelf or bench area.

Fig # : New proposed floor plan for apt units 102, 202, 302, 402, 502, 602, 702, 802, 902, 1002, and 1102 .
 [Figure N.T S]

AREA 3



Existing Plan


Area 3 is a two bedroom condo, layout is shown on the left with the new column grid in blue.

SQFT approx.= 1000 sqft

Photo courtesy of Lowes developers
www.cityvisatdc.com [Figure N.T S]

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI



Area 3 Alterations

Area three was the most difficult area to alter to accommodate the new column grid. Columns run down the center of the main living space. Column C3 is blocking the edge of glass curtain walls reducing its span from 9'-9" to 8'-9".

Fig # : New proposed floor plan for apt units 104, 204, 304, 404, 504, 604, 704, 804, 904, 1004, and 1104 [Figure N.T S]

SECTION

Currently City Vista uses varying ceiling height to add volume and create a separation between spaces in the condos as seen in figure #28. The underside of the slab in the new design is a grid of



exposed pre-cast beams. This grid could be used to further develop the volume or other architectural interest in the ceiling, or a finished ceiling could be built under the beams. In general there is one grid line of beams running though each condo.

Floor to ceiling height was changed to accommodate the new system. A new north/south section is shown in figure #29. This section can be compared with figure #4 on page 6.

Figure #28 : Typical condo in City Vista Building 2 courtesy of The Lower enterprise www.cityvistadc.com




Figure #29 : New floor to ceiling heights

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

CONCLUSION

After closely examining the pre-cast gravity system I would not suggest it for this application. If it was incorporated during preliminary design I feel it would have better success, although still a PT system is more efficient and economic for an open plan condominium building with a height restriction.

Column Grid:

In the D.C. market the height restriction and overwhelming demand for rentable space control the design. The PT system provides a less restrictive column grid. The irregularity in column placement the post tension system allows is very conducive to architectural plans where column placement cannot govern. The pre-cast system does provide considerably smaller columns, but the requirement for a rectangular bay is an architectural issue no matter how it is laid out. Both systems use conventionally reinforced columns. The P.T column grid consists of (52) 28"x15" cast in place columns, mostly irregularly shaped bays are used. Typically bay sizes are in the range of 20ft x 22 ft. The pre-cast grid uses strict rectangular bays arranged to reduce the eccentric moment created by the hanger connection, (57) columns are needed decreasing in size every 4 floors.

Floor System:

The 7 ½" flat plate is about as efficient as they come for achieving small floor to ceiling height. The pre-cast system does provide more convenient for electrical and mechanical system because the hollow cores in the planks can double as conduits. The post tension system restricts the other trades because conduits, rebar, and tendons must fit inside the 7 ½" slab.

During redesign member, spans, and connection types were chosen to minimize the story height, although in the end an additional 8" was added to each story increasing the overall building height to 130'-6" at sections when the penthouse is considered. This is 6" over the height restriction in Washington D.C. The mechanical penthouse has a 17'-10" floor to ceiling height. In my analysis the possibility of decreasing this height was not considered, although it could be a possibility and the max building height could be obtained.

Building Weight:

The building weight did increase by approximately 3000 kips. The diaphragm (hollow core planks and 2" topping, weight = 73.75PSF) was lighter than the 93.75 PSF post tension slab although with the addition of T, R and L-beam each floor gained about 275 kips of additional dead weight. The composite topping contributed 25 PSF of the 73.75 PSF dead load. A ¾" leveling topping could have been used reducing the dead weight, but it was not because the composite topping presented more benefits to the overall serviceability of City Vista. The 2" topping benefits include: fireproofing, load distribution, diaphragm reinforcing and seismic capabilities. The additional mass did in return affect the story shear and displacement of the building.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

Lateral System:

The lateral system was inadequate to support the building in the event of an earthquake. This was unsuspected due to the small height and weight increase in the building. Shear walls 2&4 used to resist lateral forces in the Y direction were significantly inadequate. The displacement was well above the minimum and walls were heavily reinforced compared to the walls used to resist forces in the X direction. Further investigation of this problem is needed before a decision can be made to either relocate or increase wall length. This is outside the scope of my thesis although it needs to be resolved before a final decision could be made by the developer to use a pre-cast system.

A possible explanation for the failure of shear walls 2 and 4 could be the modeling method in E-Tabs. The gravity system was assumed to take minimum of none of lateral forces. This may not have been the original assumption when the walls were originally designed. Another may be the simplification made to the model during analysis. Instead of drawing the entire gravity system in E-Tabs weightless floor diaphragms were modeled and then assigned a uniform mass to account for the planks, beams, and columns.

Constructability:

Both systems present constructability issues. A post tensioned system is dependent on weather during pours. Many admixtures and construction procedures have been created to combat this, although it is a concern. Pre-cast is not weather depend, although it requires a more intensive pre-design process. Considerable lead time is needed for the manufacturing and designing of the pre-cast members by the manufacturer. This limits last minute architectural and structural design changes.

Transportation of pre-cast members is crucial to erection. Laws and traffic in Washington D.C. restrict transportation of members. Shipping is restricted to Monday after noon to Friday before noon. During these times traffic patterns in down town D.C. are still an issue. In some instances pre-cast requires special permits for oversize loads or roadways to be closed to accommodate wide members. During design this was considered and no member in the new gravity system requires a permit.

Post tension system present shortening and cable integrity issues during erection and curing of the structure. Cables have the capability of rupturing during tensioning and blowing out entire bays. During curing the concrete tends to shrink creating tension cracks around the perimeter of the floor plates. Pre-cast is cured in a warehouse before transportation to site, therefore shrinking is not as big of a concern during curing.

If erection of the pre-cast system is not done correctly structural integrity could be in jeopardy. Connections between members must be executed to resisted lateral forces and distribute load correctly. The composite topping makes this procedure easier by creating a monolithic slab. Hangers connection are a concern due to high probability of manufacturing mistakes.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

Cost:

The post tension gravity system cost considerably less than the pre-cast. Like building weight this is a result of the beams needed to support the planks. The post tensioned slab and planks with topping prices are competitive with each other. The same with the pre-cast and cast in place conventionally reinforced columns. If a strictly economical approach is taken the post tensioned system is about 2 million dollars cheaper when materials and installation was considered.

Pre-Cast System: \$ **7,756,942.00**

Post Tension System: \$ **5,150,425.00**

Architecturally:

Architects Tortis Gallas uses an open plan for condos at City Vista. This system requires long clear spans so kitchen/ living room/ dining areas are not obstructed by columns. As seen in the architectural portion of the report, several floor plans are redesigned to accommodate for the new column grid, although even with alterations the rectangular grid is inadequate to support the open plan condos. The T-Beams does present architectural interest but may not be what the architect had in mind during design.

Recommendation:

As a result a pre-cast system would have been more successful if incorporated during preliminary design. Condos could still use an open plan if designed around rectangular bays. Although, it is very difficult to incorporate rectangular bays after a design for irregular bays is in place. To accommodate the current plan beam sizes would need to be increased resulting in larger member, a heavier building, and larger floor to ceiling heights.

JULIE DAVIS
STRUCTURAL OPTION
APRIL 9, 2008

CITY VISTA
WASHINGTON D.C.
ADVISOR: DR. MEMARI

REFERENCES:

Pre-Cast Design:

- PCI 6th edition
- Hollow core handbook :
http://www.pci.org/view_file.cfm?file=MNL-126-981.PDF
- Nitterhouse Pre-cast products.
<http://Nitterhouse.com>

Leeds:

- PCI Sustainability article:
http://www.pci.org/publications/designers_notebook/dn_view.cfm?ascent_id=47
- U.S Green Building Council:
<http://www.usgbc.org/DisplayPage.aspx?CategoryID=19>

Cost:

- RS-Means Cost Works:
<http://www.rsmeans.com/>

Appendix #1

SESMIC AND WIND CALCULATIONS

REVEISED BUILDING

<i>Seismic Calculations</i>	2
<i>Seismic Diagrams</i>	3
<i>Wind Calculations</i>	4
<i>Wind Diagrams</i>	5-6

Seismic (ASEC7-05 : Chapter 11-12)

Site Classification : D
 Design Category: B
 Occupancy Category: II
 Building Height : 128'-0"
 Seismic Use Group: Group Importance Factor: 1.0

Table 12.8-1 $C_u = 1.7$ [$S_{D1} \leq 0.1$]

Table 12.8-2; $C_T = 0.02$ $x = 0.75$

$T_a = C_t H_n^x = (0.02)(113)^{0.75} = 0.69$

T : Fundamental Period of Structure = $C_u T_a = (1.7)(0.69) = 1.17$

T_L = [Fig 22-15] Long-Period transition period = 8 Sec

Table 12.2-1: Ordinary plain concrete shear walls $R = 5.0$
 $\Omega = 2.5$
 $C_D = 4.5$

$$C_S = \begin{cases} S_{DS}/(R/I) = (0.163)/(5/1) = 0.0326 \\ S_{D1}/T(R/I) = (0.08)/(1.17(5/1)) = 0.013 \\ S_{D1}T_L/(T^2(R/I)) = (1.292*8)/(1.292^2(5/1)) = 1.24 \end{cases}$$

Building Weight

(W) = DEAD LOAD + 20% SNOW LOAD + ROOFTOP UNITS+20PSF PARTITION

Building Weight Summary

Floors	Plank (psf)	Partitions	2" Topping (psf)	Area	Total (Kips)	Beams (Kips)	Shear (Kips)	Columns (Kips)	Walls (Kips)
1	48.75	20	25	15405	1444	566.82	92.76	225	101
2	48.75	20	25	15405	1444	566.82	92.48	215.4	193
3	48.75	20	25	15405	1444	566.82	92.48	215.4	184
4	48.75	20	25	15405	1444	566.82	92.48	215.4	184
5	48.75	20	25	15405	1444	566.82	92.48	215.4	184
6	48.75	20	25	15405	1444	566.82	92.48	215.4	184
7	48.75	20	25	15405	1444	566.82	92.48	215.4	184
8	48.75	20	25	15405	1444	566.82	92.48	215.4	184
9	48.75	20	25	15405	1444	566.82	92.48	215.4	184
10	48.75	20	25	15405	1444	566.82	92.48	215.4	184
11	48.75	20	25	15405	1444	566.82	92.48	215.4	92
Pent	78.75	20	25	1738	215	41.82	92.48	25.6	337.7
TOTAL					16101	6276.84	1017.6	2404.4	2195.7

Additional Weight:

Rooftop Units = 8 Kips

Snow = 102.8 Kips

TOTAL BUILDING WEIGHT = 28,076 Kips

Base Shear: $V = C_s W = 0.0326 * 28,076 = 915.27$ Kips

Overtopping Moment = 73,601.43 Kip-Ft

Latitude / Longitude :
 RESULTS FROM SOFTWARE :

$S_s = 0.153$

$S_1 = 0.05$

$F_a = 1.6$ (Table 11.4-1)

$F_v = 2.4$ (Table 11.4-2)


$S_{m_s} = F_a S_s = 0.2448g$

$S_{m_1} = F_v S_1 = 0.12g$

$SD_s = 0.163g$

$SD_1 = 0.08g$

Seismic Loading								
K = 1.1	Level	W_x	H_x	$W_x H^{1.1}$	$C_{vx}(k)$	F_x (kips)	V_x (kips)	M_x (kip-Ft)
11	12	2321	113.46	422670.75	0.17	155.39	155.39	17630.10
10	11	2321	103.46	381878.20	0.15	140.39	295.78	14524.70
9	10	2321	93.46	341478.60	0.14	125.54	421.32	11732.73
8	9	2321	83.46	301509.75	0.12	110.84	532.16	9251.02
7	8	2321	73.46	262018.02	0.11	96.33	628.49	7076.07
6	7	2321	63.47	223100.47	0.09	82.02	710.50	5205.70
5	6	2321	53.47	184755.06	0.07	67.92	778.43	3631.75
4	5	2321	43.47	147124.07	0.06	54.09	832.51	2351.17
3	4	2321	33.48	110392.39	0.04	40.58	873.10	1358.73
2	3	2321	23.48	74721.06	0.03	27.47	900.57	644.99
1	2	2248	13.47	39273.60	0.02	14.44	915.00	194.48
Overturning Moment								73601.43 Kip-Ft
Base Shear								915.00 Kips



Wind: (ASCE7-05 : Chapter 6)

General Info:

Rigid Building $T = 0.76 \text{ Sec} < 1 \text{ Sec}$
 Exposure Category = B
 Enclosure Category = Enclosed Building
 Basic Wind Speed: $V = 90 \text{ mph}$
 Importance Factor : $I = 1.0$
 Mean Roof Height = $128'-0''$

$p = qGC_p - q_i(GC_{pi})$

Calculations:

K_z : Table 6-3

K_{zt} : 1.0

K_d : Table 6-4 / Building Main wind force resisting System = 0.85

$$G = 0.925 (1 + 1.7gI_z Q) / (1 + 1.7 * gI_z) \left\{ \begin{array}{l} \mathbf{N-S} = 0.854 \\ \mathbf{W-E} = 0.867 \end{array} \right.$$

$$I_z = c(33/z)^{1/6} = 0.3(33/76.8)^{1/6} = 0.38$$

$$Z = 0.6h = 76.8\text{ft}$$

[Table 6-2] $Z_{min} = 30$

$$c = 0.30$$

$$\epsilon = 1/3$$

$$\ell = 320$$

$$Q = \left\{ \begin{array}{l} \mathbf{W-E} = 0.909 \\ \mathbf{N-S} = 0.888 \end{array} \right.$$

$$L_z = \ell / (z/33)^\epsilon = 320 / (76.8/33)^\epsilon = 423.9$$

$$g_q = 3.4$$

$$g_v = 3.45$$

C_{pi} : FIG 6-5 = +/- 0.18

C_p : FIG 6.6 \longrightarrow **W-E**: LEEWARD = -0.5 ($L/B = .616$)

WINDWARD = 0.8

N-S: LEEWARD = -0.3 ($L/B = 1.6$)


WINDWARD = 0.8

$GC_{pi} = +/- 0.18$	
East/West	$C_{P \text{ Windward}} = 0.80$ $C_{P \text{ Leeward}} = -0.50$
	$C_{P \text{ Side}} = -0.70$
North/South	$C_{P \text{ Windward}} = 0.80$ $C_{P \text{ Leeward}} = -0.30$ $C_{P \text{ Side}} = -0.70$


Roof:	
East/West	$C_{P \text{ Windward}} = 0-h/2 \rightarrow -1.3$ $C_{P \text{ Windward}} = >h/2 \rightarrow -0.7$
North/West	$C_{P \text{ Windward}} = 0-h/2 \rightarrow -1.3$ $C_{P \text{ Windward}} = >h/2 \rightarrow -0.7$

Wind From W-E								
Windward		Leeward		TOTAL	Area (ft ²)	P (kips)	Shear	Moment
h	P	h	p					
0-15	15.73	0-15	-17.29	33.02	2700	89.154	829.52	0.00
20	16.7	20	-17.29	33.99	900	30.591	740.37	611.82
25	17.49	25	-17.29	34.78	900	31.302	709.78	782.55
30	18.27	30	-17.29	35.56	900	32.004	678.47	960.12
40	19.44	40	-17.29	36.73	1800	66.114	646.47	2644.56
50	20.42	50	-17.29	37.71	1800	67.878	580.36	3393.90
60	21.2	60	-17.29	38.49	1800	69.282	512.48	4156.92
70	21.99	70	-17.29	39.28	1800	70.704	443.20	4949.28
80	22.77	80	-17.29	40.06	1800	72.108	372.49	5768.64
90	23.35	90	-17.29	40.64	1800	73.152	300.38	6583.68
100	23.94	100	-17.29	41.23	1800	74.214	226.17	7421.40
116	24.92	120	-17.29	42.21	3600	151.956	151.96	18234.72
Base Shear=						830 Kips		
Moment=						55507.59	Ft Kips	

Wind From N-S								
Windward		Leeward		TOTAL	Area (ft ²)	P(Kips)	Shear	Moment
h	P	h	p					
0-15	15.49	0-15	-12.02	27.51	1665	45.80415	436.4853	0
20	16.45	20	-12.02	28.47	555	15.80085	390.6812	316.017
25	17.22	25	-12.02	29.24	555	16.2282	374.8803	405.705
30	18	30	-12.02	30.02	555	16.6611	358.6521	499.833
40	19.15	40	-12.02	31.17	1110	34.5987	341.991	1383.948
50	20.11	50	-12.02	32.13	1110	35.6643	307.3923	1783.215
60	20.89	60	-12.02	32.91	1110	36.5301	271.728	2191.806
70	21.66	70	-12.02	33.68	1110	37.3848	235.1979	2616.936
80	22.43	80	-12.02	34.45	1110	38.2395	197.8131	3059.16
90	23	90	-12.02	35.02	1110	38.8722	159.5736	3498.498
100	23.58	100	-12.02	35.6	1110	39.516	120.7014	3951.6
120	24.55	120	-12.02	36.57	2220	81.1854	81.1854	9742.248
Base Shear =						437 Kips		
Moment=						29448.97	Ft-Kips	



Wind Loading Diagram East - West



Wind Loading Diagram North - South

Appendix #2
GRAVITY SYSTEM

FLOOR PLAN

Typical Floor Plan 3

HOLLOW CORE

Specs 4

Design Check 5-10

EXTERIOR BEAMS

Design 11

Specs 12

Design check 13-17

INTERIOR BEAMS

Design 18

Specs 19-20


Design Check 21-24

COLUMNS

Specs 25

Design 26-27

PCA column check 28




Prestressed Concrete 6"x4'-0" Hollow Core Plank

2 Hour Fire Resistance Rating With 2" Topping

PHYSICAL PROPERTIES Composite Section	
$A_c = 253 \text{ in.}^2$	Precast $S_{sc} = 370 \text{ in.}^3$
$I_c = 1519 \text{ in.}^4$	Topping $S_{sc} = 551 \text{ in.}^3$
$Y_{bc} = 4.10 \text{ in.}$	Precast $S_{sc} = 799 \text{ in.}^3$
$Y_c = 1.90 \text{ in.}$	Wt. = 195 PLF
	Wt. = 48.75 PSF

DESIGN DATA

1. Precast Strength @ 28 days = 6000 PSI
2. Precast Strength @ release = 3500 PSI.
3. Precast Density = 150 PCF
4. Strand = 1/2"Ø 270K Lo-Relaxation.
5. Strand Height = 1.75 in.
6. Ultimate moment capacity (when fully developed)...
 - 4-1/2"Ø, 270K = 67.5 k-ft
 - 7-1/2"Ø, 270K = 104.2 k-ft
7. Maximum bottom tensile stress is $7.5\sqrt{f_c} = 580 \text{ PSI}$
8. All superimposed load is treated as live load in the strength analysis of flexure and shear.
9. Flexural strength capacity is based on stress/strain strand relationships.
10. Deflection limits were not considered when determining allowable loads in this table.
11. Topping Strength @ 28 days = 3000 PSI. Topping Weight = 25 PSF.
12. These tables are based upon the topping having a uniform 2" thickness over the entire span. A lesser thickness might occur if camber is not taken into account during design, thus reducing the load capacity.
13. Load values to the left of the solid line are controlled by ultimate shear strength.
14. Load values to the right are controlled by ultimate flexural strength or fire endurance limits.
15. Load values may be different for IBC 2000 & ACI 318-99. Load tables are available upon request.
16. Camber is inherent in all prestressed hollow core slabs and is a function of the amount of eccentric prestressing force needed to carry the superimposed design loads along with a number of other variables. Because prediction of camber is based on empirical formulas it is at best an estimate, with the actual camber usually higher than calculated values.



SAFE SUPERIMPOSED SERVICE LOADS		IBC 2003 & ACI 318-02 (1.2 D + 1.6 L)																		
Strand Pattern		SPAN (FEET)																		
		11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29
4 - 1/2"Ø	LOAD (PSF)	227	187	360	306	268	229	194	165	141	120	102	86	73	61	50	XXXX			
7 - 1/2"Ø	LOAD (PSF)	367	305	495	455	418	387	340	312	275	243	215	189	167	147	130	114	97	83	70

NITTERHOUSE
CONCRETE PRODUCTS

2655 Molly Pitcher Hwy, South, Box N
Chambersburg, PA 17201-0813
717-267-4505 Fax 717-267-4518

This table is for simple spans and uniform loads. Design data for any of these span-load conditions is available on request. Individual designs may be furnished to satisfy unusual conditions of heavy loads, concentrated loads, cantilevers, flange or stem openings and narrow widths. The allowable loads shown in this table reflect a 2 Hour & 0 Minute fire resistance rating.

05/14/07

6F2.0T

HOLLOW CORE CHECKS:

Pre-cast	$F'_c = 6000\text{psi}$ $F'_{ci} = 3500\text{psi}$ $E_c = 4463\text{ksi}$	$E_c = 33(145)^{1.5}\sqrt{6000} = 4463\text{ksi (11.2.2)}$ $E_{ci} = 33(145)^{1.5}\sqrt{3500} = 3408\text{ksi}$ $F_{se} = 170\text{ksi}$
Topping	$F'_c = 5000\text{psi}$ $E_c = 4074\text{ksi}$	
Service loads :	$F_{ti} = 7.5\sqrt{f'_c} = 580\text{psi}$ $F_{ci} = 0.6(f'_c) = 3600\text{psi}$	
Allowable @ transfer:	$F_t = 3\sqrt{f'_{ci}} = +180\text{psi}$ $F_c = 0.6f'_{ci} = -2160\text{psi}$	

1

Corridor Design Check

Span = 16.33'
Length = 17'
Slab Thickness: 6" plank + 2" topping = 8"

LOADING:
Topping W = 25PSF
LL = 100PSF
Super = 20PSF

Span-Depth : $17/.667 = 25.5 < 40$ OK

Plank by Nitterhouse: www.nitterhouse.com

-6"x4' Hollowcore plank 2 hour rating w/ 2" topping

$A_c = 253\text{in}^2$
 $I_c = 1519\text{in}^4$
 $T_{bc} = 4.10\text{in}$
 $Y_{tc} = 1.90\text{in}$
 $D_p = 6"$
 $W_t = 48.75\text{psf}$
 $S_T = 799\text{in}^3$
 $S_B = 307\text{in}^3$

1. Preliminary Design Loads :

$W = 1.2(20) + 1.6(100) = 184\text{psf}$
6" Slab+ 2" Topping and 7-1/2"Ø strands

Capacity = 189 psf
M Capacity = 104.2 k-ft

2. Transfer Stresses: 7-1/2" Ø 270ksi low relaxation strands

$A_{sp} = 7(0.153) = 1.071\text{in}^2$
 $e = 2.25"$
 $L = 17"$
 $W_u = 1.2*(48.75+25)*4\text{ft} = 354\text{plf}$
 $M_D = (295)(17^2)/8 = 10.6\text{ft-kips} \rightarrow 127\text{in-kips}$
 $P_o = 0.6A_{ps}F_{pu} = (1.071)(270)(0.60) = 173.5\text{Kips}$
 $P_i = 0.153*270*.75*7 = 216.87$

CHECK

$F_c = P_o/A \pm P_o e/S \pm M_D/S =$
 $F_{TOP} = 0.685 - 0.708 + 0.15 =$
 $F_{BOT} = 0.685 + 1.055 - 0.41 =$

$= 0.127\text{KSI} \leq F_{ti}$ OK
 $= 1.33\text{KSI} \leq F_{ci}$ OK

3. Prestress Losses:

$P_i=216.87\text{kips}$	$f_{pu}=270\text{ksi}$
$P_e=P_i-R_{A_{ps}}$	$f_{pi}= P_i/A_{ps} = /1.071$
$R= ES+CR+SH+RE$	$f_{pu}/f_{pi}=0.749$
$E_c=33(145)^{1.5}\sqrt{6000} =4463\text{ksi}$	$A_g=384\text{in}^2$
$E_{ci}=33(145)^{1.5}\sqrt{3500}=3408\text{ksi}$	$I_g=2048\text{in}^3$
$R.H.= 75\%$	$e = 2.25''$
$V/S= 384/884= 4.36$	

Elastic Shortening: $K_{es}E_{ps}F_{cir}/E_{ci} = (1)(28.5E3)(0.82)/3400 = 6.80 \text{ KSI}$
 $F_{cir} = K_{cir}(P_i/A_g + P_i e^2/I_g) - M_g e/I_g$ ($M_g=1.2(48.75+25)*4*18^2/8$) = 153.5 in-kips
 $= 0.9[(216/384)+(216*2.25^2)/2048] - (153.5*2.25/2048) = 0.82\text{ksi}$
= 6.80 KSI

Concrete Creep: $K_{cr}(E_{ps}/E_c)(f_{cir}-f_{cds}) = 2(28.5E3/4400)(.78 -.16) = 7.6 \text{ kips}$
 $f_{cds}=M_{sd}e/I_g = (153.5*2.25)/2048 = 0.16 \text{ Kips}$
= 7.64 KSI

Shrinkage: $(8.2E-6)K_{sh}E_{ps}(1-0.06V/S)(100-RH) = (8.2E-6)(1.0)(28.5E3)(1-0.06(4.36))(100-75) =$
= 4.31 KSI

Steel Relaxation: $R.E=(K_{re}-J)(SH+CR+ES)C = (5000-0.040(6.80+7.64+4.31))1.441 =$
 $K_{re}=5000 \quad J=0.040 \quad C= 1+9(0.749-.7) = 1.441$
= 3.0 KSI
 TOTAL LOSSES AT MIDSPAN = 6.80+7.64+4.31+3.0 = 21.75 KSI → 10%

4. Service Load Stresses:

$M_{Sustained} = 222.8 \text{ in-kips}$
 $M_{Service} = 153.5 \text{ in-kips}$
 $P=0.75A_{ps}F_{pu} = (.75)(7)(41.3)(1-.10) = 195.1 \text{ Kips}$

CHECK:

$F = P/A \pm P_e/S \pm M_{Ser} * e/S \pm$ OR $\pm M_{Sus} * e/S =$
 $F_{TOP/Service} = 0.77-0.55+1.0$ **= 1.22 KSI < F_{Ci} OK**
 $F_{TOP/Sustainable} = 0.77-0.55+2.4$ **= 2.62 KSI < F_{Ci} OK**
 $F_{BOT} = 0.77 + (0.55-2.4)(799/511)$ **= -2.1 KSI > $-F_t$ OK**

5. Flexure Check:

PCI 6th edition FIG 4.12.3
 $M_u = 104.2 \text{ kip-ft}$
 $f_{se} \geq 0.5f_{pu} \quad [140 \geq 135]$
 Bonded YES

$-\phi M_n \geq M_u$
 $C\omega_{pu} = 1.13(1.071*270,000)/(48*6*6000) + (8/6)(0) = 0.189$
 $f_{ps} = 250\text{ksi}$

$$\phi M_n = \phi A_{sp} f_{ps} (d_p - a/2)$$

$$a = A_{sp} f_{ps} / 0.85 f'_{cb} = 1.071 * 250 / 0.85 * 6 * 48 = 1.09$$

$$c = 1.09 / 0.75 = 1.46$$

$$1.46 / 6 = .24 < 0.375 \rightarrow \phi = 0.9$$

$$\phi M_n = 0.9 * 1.071 * 250 * [6 - 1.46 / 2] =$$

$$\underline{105.82 \text{ kip-ft} > 104.2 \text{ kip-ft} \text{ OK}}$$

$$-\phi M_n > 1.2 M_{cr}$$

P: from part 4

$$e = 2.25''$$

$$1.2 M_{cr} = 1.2 (P/A + Pe/S_b + 7.5 \sqrt{f'_c}) * S_b =$$

$$1.2 (.762 + 0.543 + .581) * 370 =$$

$$\underline{83.7 \text{ kip-ft} < 105.82 \text{ kip-ft} \text{ OK}}$$

6. Shear Check

PCI 6th edition: FIG 4.12.5

$$\phi V_n \geq V_u$$

$$x = 50 d_b = 50 (.5) = 25''$$

$$x / \ell = 25'' / 23 * 12 = 0.09$$

$$d = 6.981 \quad bw = 18''$$

$$V_u = 4.6 \text{ Kips}$$

$$M_u = 222.8 \text{ in-kips}$$

$$V_n = V_c$$

$$V_c = (0.6 \sqrt{f'_c} + 700 * V_{ud} / M_u) b_w d = [46.47 + 700 (4.6 * 6.981 / 222)] b_w d$$

$$V_c = .147 b_w d$$

$$\phi V_n = \phi 2 \sqrt{f'_c} b_w d = 14.6 \text{ Kips}$$

$$\underline{14.6 \text{ Kips} \geq 18.56 \text{ Kips} \text{ OK}}$$

7. Deflections

Hollow core design handbook Table 2.4.1

Deflection :

$$\Delta_{\text{TOPPING}} = 5 * .025 * 4 * 17^4 * 1728 / 384 * 4463 * 529 = 0.079''$$

$$\text{Long Term} = (0.079)(2.30) = 0.182''$$

$$\Delta_{\text{SUPERIMPOSED}} = 5 * .02 * 4 * 17^4 * 1728 / 384 * 4463 * 2048 = .016''$$

$$\text{Long Term} = (.016)(3) = 0.05''$$

$$\text{Live Deflection} = (100/20)(.05) = 0.25''$$

Multiplied from Table 2.4.1 of Hollow core design paper

$$\Delta_{\text{FINAL}} = -.079 - .016 - .25 = \underline{-0.336''}$$

$$\text{Camber: } P_o e l^2 / 8EI - 5w l^4 / 384EI$$

$$\text{Initial Camber} = [173.5 * 2.25 * (17 * 12)^2 / 8 * 3408 * 1519] - [5 * .195 * 17^4 * 1728 / 384 * 3408 * 1519]$$

$$0.39'' - 0.1'' = 0.49''$$

$$\text{Erection Camber} = 0.39(1.80) - 0.1(1.85) = 0.517''$$

$$\text{Final Camber} = 0.39(2.45) - 0.1(2.70) = 0.68''$$

$$\text{Camber} = \underline{0.68''}$$

$$\text{TOTAL} = \Delta_{\text{CAMBER}} - \Delta_{\text{DEFLECTION}} = 0.68 - 0.336 = \underline{0.344''}$$

$$\text{Limit} = L / 360 = 17 * 12 / 360 = 0.567''$$

$$\underline{0.344'' < 0.567'' \text{ OK}}$$

2

Residential Design Check

Span = 16.67

Length = 18"

Slab Thickness: 6" plank + 2" topping = 8"

LOADING:

Topping W=25PSF

LL=20PSF

Super=20PSF

Span-Depth : $18/.667 = 26 < 40$ OK

Plank by Nitterhouse: www.nitterhouse.com

-6"x4' Hollowcore plank 2 hour rating w/ 2" topping

$A_c = 253 \text{ in}^2$

$I_c = 1519 \text{ in}^4$

$T_{bc} = 4.10 \text{ in}$

$Y_{tc} = 1.90 \text{ in}$

$D_p = 6"$

$W_t = 48.75 \text{ psf}$

1. Preliminary Design Loads :

$W = 1.2(20) + 1.6(40) = 88 \text{ psf}$

6" Slab+ 2" Topping and 7-1/2"Ø strands

Capacity = 165 psf

M Capacity = 104.2 k-ft

2. Transfer Stresses: 7-1/2" Ø 270ksi low relaxation strands

$$A_{sp} = 7(0.153) = 1.071 \text{ in}^2$$

$$e = 2.25"$$

$$L = 17"$$

$$W_u = 1.2(48.75 + 25) = 88.5 \text{ psf} \cdot 4 \text{ ft} = 354 \text{ plf}$$

$$M_d = (354)(18^2)/8 = 14.3 \text{ ft-kips} \rightarrow \underline{171.6 \text{ in-kips}}$$

$$P_o = 0.75 A_{ps} F_{pu} = (1.071)(270)(0.60) = 173.5 \text{ Kips}$$

$$P_i = 0.153 \cdot 270 \cdot 0.75 \cdot 7 = 216.87$$

CHECK

$$F_c = P_o/A \pm P_o e/S \pm M_D/S =$$

$$F_{TOP} = 0.685 - 0.708 + 0.22$$

$$F_{BOT} = 0.685 + 1.055 - 0.56$$

$$= \underline{0.195 \leq F_{ti} \text{ OK}}$$

$$= \underline{1.10 \leq F_{ci} \text{ OK}}$$

3. Prestress losses

$$\text{Elastic Shortening: } K_{es} E_{ps} F_{cir} / E_{ci} = (1)(28.5E3)(0.91)/3400 = 7.57 \text{ KSI}$$

$$F_{cir} = K_{cir} (P_i/A_g + P_i e^2/I_g) - M_{ge}/I_g \quad (M_g = 48.75 + 25 \cdot 4 \cdot 18^2/8) = 171.6 \text{ in-kips}$$

$$= 0.9 [(216.87/384) + (216.87 \cdot 2.25^2)/2048] - (171.6 \cdot 2.25/2048) = 0.91$$

$$= \underline{7.57 \text{ KSI}}$$

$$\text{Concrete Creep: } K_{cr} (E_{ps}/E_c) (f_{cir} - f_{cds}) = 2(28.5E3/4400)(.91 - .24) = 8.6 \text{ kips}$$

$$f_{cds} = M_{sde}/I_g = (218 \cdot 2.25)/2048 = \underline{0.24 \text{ Kips}}$$

$$= \underline{8.67 \text{ KSI}}$$

$$\text{Shrinkage: } (8.2E-6)K_{sh}E_{ps}(1-0.06V/S)(100-RH) = (8.2E-6)(1.0)(28.5E5)(1-0.06(4.36))(100-75) =$$

$$= 4.31 \text{ KSI}$$

$$\text{Steel Relaxation: } R.E=(K_{re}-J)(SH+CR+ES)C = (5000-0.040(7570+8679+4310))1.441 =$$

$$K_{re}=5000 \quad J=0.040 \quad C=1+9(0.749-.7) = 1.441$$

$$= 3.815 \text{ KIS}$$

$$\text{TOTAL LOSSES AT MIDSPAN} = 7.757+8.679+4.310+3.815= 24.5 \text{ KSI} \rightarrow 11.3\%$$

4. Service Load Stresses:

$$M_{\text{Sustained}} = 343 \text{ in-kips}$$

$$M_{\text{Service}} = 218.7 \text{ in-kips}$$

$$P=0.75A_{ps}F_{pu} = 216.87(1-.113)= 192.3 \text{ Kips}$$

CHECK:

$$F = P/A \pm Pe/S \pm M_{\text{Ser}}*e/S \pm \text{OR} \pm M_{\text{Sus}}*e/S =$$

$$F_{\text{TOP/Service}} = 0.760-0.54+0.61$$

$$= 0.83 \text{ KSI} < F_{ci} \quad \text{OK}$$

$$F_{\text{TOP/Sustainable}} = 0.760-0.54+0.96$$

$$= 1.18 \text{ KSI} < F_{ci} \quad \text{OK}$$

$$F_{\text{BOT}} = 0.760 + (0.54-0.96)(799/551)$$

$$= 0.103 \text{ KSI} > -F_t \quad \text{OK}$$

5. Flexure Check:

PCI 6th edition FIG 4.12.3

$$M_u = 104.2 \text{ kip-ft}$$

$$f_{se} \geq 0.5f_{pu} \quad [140 \geq 135]$$

Bonded YES

$$-\phi M_n \geq M_u$$

$$C\omega_{pu} = 1.13(1.071*270,000)/(48*6*6000) + (8/6)(0) = 0.189$$

$$f_{ps} = 250 \text{ ksi}$$

$$\phi M_n = \phi A_{sp} * f_{ps} (d_p - a/2)$$

$$a = A_{sp} * f_{ps} / 0.85f'_{cb} = 1.071*250/0.75*6*48 = 1.23$$

$$c = 1.23/0.75 = 1.64$$

$$1.64/6 = .27 < .0375 \rightarrow \phi = 0.9$$

$$\phi M_n = 0.9*1.071*250*[6-1.23/2] =$$

$$108.13 \text{ kip-ft} > 104.2 \text{ kip-ft} \quad \text{OK}$$

$$-\phi M_n > 1.2M_{cr}$$

P: from part 5

$$e = 2.25''$$

$$1.2M_{cr} = 1.2(P/A + Pe/S_b + 7.5\sqrt{f'_c}) * S_b =$$

$$1.2(.762+0.543+.581)*370 =$$

$$83.7 \text{ kip-ft} < 108.13 \text{ kip-ft} \quad \text{OK}$$

6. Shear Check

PCI 6th edition FIG 4.12.5

$$\phi V_n \geq V_u$$

$$x = 50d_b = 50(.5) = 25''$$

$$x/\ell = 25''/18 \times 12 = 0.12$$

$$d = 6.981$$

$$bw = 18''$$

$$V_u = 6.35 \text{ Kips}$$

$$M_u = 28.5 \text{ Kip-ft} = 343 \text{ Kip-in}$$

$$V_n = V_c$$

$$V_c = (0.6\sqrt{f'_c} + 700 \cdot V_{ud}/M_u) b_w d = [46.47 + 700(6.35 \cdot 6.981/343)] b_w d$$

$$V_c = 136.9 b_w d$$

$$\phi V_n = \phi 2\sqrt{f'_c} b_w d =$$

$$\underline{14.6 \text{ Kips} \geq 6.35 \text{ Kips OK}}$$

7. Composite Deflections :

Hollow core design handbook Table 2.4.1

Deflection:

$$\Delta_{\text{TOPPING}} = 5 \cdot 0.025^4 \cdot 18^4 \cdot 1728 / 384 \cdot 4463 \cdot 529 = 0.100''$$

$$\text{Long Term} = (0.100)(2.30) = 0.23''$$

$$\Delta_{\text{SUPERIMPOSED}} = 5 \cdot 0.02^4 \cdot 18^4 \cdot 1728 / 384 \cdot 4463 \cdot 2048 = .0206''$$

$$\text{Long Term} = (.0206)(3) = 0.0618''$$

$$\text{Live Deflection} = (100/20)(.0206) = 0.13''$$

$$\Delta_{\text{FINAL}} = -.23 - .0618 - .13 = \underline{-0.422''}$$

**Multiplied from Table 2.4.1 of Hollow core design paper **

Camber: $[P_{\text{oe}} l^2 / 8EI - 5wl^4 / 384EI]$

$$\text{Initial Camber} = [173.5 \cdot 2.25 \cdot (18 \cdot 12)^2 / 8 \cdot 3408 \cdot 1519] - [5 \cdot .195 \cdot 18^4 \cdot 1728 / 384 \cdot 3408 \cdot 1519]$$

$$0.43'' - 0.0889'' = 0.34''$$

$$\text{Erection Camber} = 0.43(1.80) - 0.0889(1.85) = 0.93''$$

$$\text{Final Camber} = 0.43(2.45) - 0.0889(2.70) = 0.813''$$

$$\text{Camber} = \underline{0.813''}$$

$$\text{TOTAL} = \Delta_{\text{CAMBER}} - \Delta_{\text{DEFLECTION}} = 0.813 - 0.422 = \underline{1.391''}$$

$$\text{Limit} = L/360 = 18 \cdot 12 / 360 = 0.6''$$

$$\underline{0.391'' < 0.6'' OK}$$

EXTERIOR BEAMS


<i>DESIGNATION</i>	<i>Span</i>	<i>Trib W (ft)</i>	<i>1.2* Dead (psf)</i>	<i>1.6*Live (psf)</i>	<i>Wu psf</i>	<i>Wu plf</i>	<i>TRAIL SIZE</i>
LB-1	26.8	6.5	112.5	64	176.5	1147.3	20LB20
LB-2	26.8	6.5	112.5	64	176.5	1147.3	20LB20
LB-3	26.8	6.5	112.5	64	176.5	1147.3	20LB20
LB-4	26.8	6.5	112.5	64	176.5	1147.3	20LB20
LB-5	13.2	2	112.5	64	176.5	353.0	20LB20
LB-6	16	2	112.5	64	176.5	353.0	20LB20
LB-7	14.4	8.83	112.5	64	176.5	1558.5	20LB20
LB-8	14.4	8.83	112.5	64	176.5	1293.6	20LB20
LB-9	17.6	7.2	112.5	64	176.5	1270.8	20LB20
LB-10	23	7.2	112.5	64	176.5	1270.8	20LB20
LB-11	19.58	2	112.5	64	176.5	353.0	20LB20
LB-12	11.25	2	112.5	64	176.5	353.0	20LB20
LB-13	6.6	2	112.5	64	176.5	353.0	20LB20
LB-14	22.16	2	112.5	64	176.5	353.0	20LB20
LB-15	17	2	112.5	64	176.5	353.0	20LB20
LB-16	17	2	112.5	64	176.5	353.0	20LB20
LB-17	17	2	112.5	64	176.5	353.0	20LB20
LB-18	12.16	2	112.5	64	176.5	353.0	20LB20
LB-19	32	6	112.5	64	176.5	1059.0	20LB20
LB-20	32	6	112.5	64	176.5	1059.0	20LB20
LB-21	12.16	2	112.5	64	176.5	353.0	20LB20
LB-22	17	2	112.5	64	176.5	353.0	20LB20
LB-23	17	2	112.5	64	176.5	353.0	20LB20
LB-24	17	2	112.5	64	176.5	353.0	20LB20
LB-25	17	2	112.5	64	176.5	353.0	20LB20
LB-26	17	2	112.5	64	176.5	353.0	20LB20
LB-27	17	2	112.5	64	176.5	353.0	20LB20
LB-28	17	2	112.5	64	176.5	353.0	20LB20
LB-29	18	2	112.5	64	176.5	353.0	20LB20
LB-30	17	2	112.5	64	176.5	353.0	20LB20
LB-31	13.167	2	112.5	64	176.5	353.0	20LB20

DESIGN CHECKS

<i>DESIGNATION</i>	<i>Load (plf)</i>	<i>Self (plf)</i>	ϕM_n (kip-ft)	ϕV_n (kip)	M_u (kip-ft)	V_u (kip)	$\phi M_n \geq M_u$	$\phi V_n \geq V_u$
LB-1	2318	317	187.30	27.96	103.00	15.37	OK	OK
LB-2	2318	317	187.30	27.96	103.00	15.37	OK	OK
LB-3	2318	317	187.30	27.96	103.00	15.37	OK	OK
LB-4	2318	317	187.30	27.96	103.00	15.37	OK	OK
LB-5	6556	317	128.51	38.94	7.69	2.33	OK	OK
LB-6	6556	317	188.81	47.20	11.30	2.82	OK	OK
LB-7	6556	317	152.94	42.48	40.40	11.22	OK	OK
LB-8	6556	317	152.94	42.48	33.53	9.31	OK	OK
LB-9	5131	317	178.81	40.64	49.21	11.18	OK	OK
LB-10	2768	317	164.73	28.65	84.03	14.61	OK	OK
LB-11	4105	317	-	-	-	-	OK	OK
LB-12	6566	317	93.49	33.24	5.58	1.99	OK	OK
LB-13	6566	317	32.18	19.50	1.92	1.16	OK	OK
LB-14	3345	317	-	-	-	-	OK	OK
LB-15	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-16	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-17	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-18	6566	317	109.22	35.93	6.52	2.15	OK	OK
LB-19	2768	317	318.87	39.86	135.55	16.94	OK	OK
LB-20	2768	317	318.87	39.86	135.55	16.94	OK	OK
LB-21	6566	317	109.22	35.93	6.52	2.15	OK	OK
LB-22	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-23	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-24	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-25	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-26	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-27	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-28	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-29	5131	317	187.02	41.56	14.30	3.18	OK	OK
LB-30	5131	317	166.82	39.25	12.75	3.00	OK	OK
LB-31	6566	317	128.06	38.90	7.65	2.32	OK	OK

L-BEAMS

Normal Weight Concrete



$f'_c = 5,000$ psi
 $f_{pu} = 270,000$ psi
 1/2 in. diameter
 low-relaxation strand

Designation	h in.	h ₁ /h ₂ in./in.	A in. ²	I in. ⁴	y _b in.	S _b in. ³	S _t in. ³	wt plf
20LB20	20	12/8	304	10,160	8.74	1,163	902	317
20LB24	24	12/12	384	17,568	10.50	1,673	1,301	400
20LB28	28	16/12	432	27,883	12.22	2,282	1,767	450
20LB32	32	20/12	480	41,600	14.00	2,971	2,311	500
20LB36	36	24/12	528	59,119	15.82	3,737	2,930	550
20LB40	40	24/16	608	81,282	17.47	4,653	3,608	633
20LB44	44	28/16	656	108,107	19.27	5,610	4,372	683
20LB48	48	32/16	704	140,133	21.09	6,645	5,208	733
20LB52	52	36/16	752	177,752	22.94	7,749	6,117	783
20LB56	56	40/16	800	221,355	24.80	8,926	7,095	833
20LB60	60	44/16	848	271,332	26.68	10,170	8,143	883

1. Check local area for availability of other sizes.
2. Safe loads shown include 50% superimposed dead load and 50% live load. 800 psi top tension has been allowed, therefore, additional top reinforcement is required.
3. Safe loads can be significantly increased by use of structural composite topping.

Key

- 6566 – Safe superimposed service load, plf.
- 0.3 – Estimated camber at erection, in.
- 0.1 – Estimated long-time camber, in.

Table of safe superimposed service load (plf) and cambers (in.)

Designation	No. Strand	y _c (end) in. y _c (center) in.	Span, ft																				
			16	18	20	22	24	26	28	30	32	34	36	38	40	42	44	46	48	50			
20LB20	98-S	2.44	6566	5131	4105	3345	2768	2318	1961	1674	1438	1243	1079										
		2.44	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.0	1.1	1.2										
20LB24	108-S	2.80	9577	7495	6006	4904	4066	3414	2896	2479	2137	1854	1617	1416	1244	1097	969						
		2.80	0.3	0.3	0.4	0.5	0.5	0.6	0.7	0.8	0.9	0.9	1.0	1.0	1.1	1.1	1.2	1.2	1.3	1.3			
20LB28	128-S	3.33			8228	6733	5596	4711	4009	3443	2979	2595	2273	2000	1768	1567	1394	1243	1110	992			
		3.33			0.4	0.4	0.5	0.6	0.6	0.7	0.8	0.9	0.9	1.0	1.1	1.1	1.2	1.2	1.2	1.3	1.3		
20LB32	148-S	3.71					8942	7446	6281	5356	4611	4001	3495	3071	2712	2406	2143	1914	1715	1540	1386		
		3.71					0.4	0.5	0.5	0.6	0.7	0.7	0.8	0.9	1.0	1.0	1.1	1.2	1.2	1.3	1.3		
20LB36	168-S	4.25							9457	7988	6823	5883	5113	4476	3941	3489	3103	2771	2483	2231	2011	1816	
		4.25					0.2	0.2	0.2	0.2	0.2	0.2	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.2	
20LB40	188-S	4.89									9812	8386	7235	6293	5513	4858	4305	3832	3425	3073	2765	2495	2257
		4.89					0.4	0.5	0.6	0.6	0.7	0.8	0.8	0.9	1.0	1.0	1.1	1.1	1.2	1.1	1.2	1.2	
20LB44	198-S	5.05											8959	7803	6845	6042	5363	4783	4284	3851	3474	3143	2850
		5.05												0.5	0.6	0.6	0.7	0.8	0.8	0.9	0.9	1.0	1.1
20LB48	218-S	5.81												9226	8100	7158	6360	5678	5092	4584	4140	3751	3408
		5.81												0.5	0.6	0.6	0.7	0.8	0.8	0.9	0.9	1.0	1.1
20LB52	238-S	6.17													9634	8521	7578	6774	6082	5482	4958	4499	4094
		6.17													0.6	0.6	0.7	0.7	0.8	0.9	0.9	1.0	1.0
20LB56	258-S	6.64														9954	8860	7927	7124	6427	5820	5287	4816
		6.64													0.6	0.7	0.7	0.8	0.8	0.9	1.0	1.0	1.0
20LB60	278-S	7.33															9989	8173	7380	6688	6080	5544	
		7.33																0.7	0.7	0.8	0.9	0.9	1.0

EXTERIOR BEAM DESIGN

3

BEAM LB-11

20LB20 / 98-S: (9) 1/2"Ø low relaxation strands
 - straight
 $f'_c=5000\text{psi}$ $f_{pu}=270\text{ksi}$
 $E_c=33(145)^{1.5}\sqrt{5000}=4074\text{ ksi}$
 $F_{se}=170\text{ksi}$
 $f_{pu}=270\text{ksi}$

LOADING CONDITION:

Self 20LB20 = 317plf

Self TB18 = 500 plf

$W_u = 166.4\text{ PSF}$ OR 2929.5 PLF

Span-Depth : $19.58/1.67 = 11.7 < 40$ OK

$P(\text{TB18}) = ((2.829 + .5) * 18.83) / 2 = 31.4\text{ Kips}$

** Detailed loading conditions See spreadsheets**

Loading Capacity: 4105 PLF

Moment Capacity: $M_n = 196.75\text{ Ft-Kips}$

Shear Capacity: $V_n = 40.2\text{ Kips}$

Beam Properties

$L = 19.58\text{ ft}$

$A = 304\text{ in}^2$

$I = 10,160\text{ in}^4$

$Y_{bc} = 8.74\text{ in}$


$S_t = 902\text{ in}^3$

$S_b = 1163\text{ in}^3$

$h_1 = 12$ $h_2 = 8\text{ in}$

$wt = 317\text{ plf}$

1. Flexure and Shear




Using Stadd-Pro:

$V_u: 30.7\text{ Kips}$

$M_u: 76.92\text{ kip-ft}$

$\phi M_n \geq M_u$ OK

$\phi V_n \geq V_u$ OK



2. Transfer Stresses:

9-1/2" Ø 270ksi low relaxation strands

Service loads : $F_{ti} = 7.5\sqrt{f'_c} = 580 \text{ psi}$
 $F_{ci} = 0.6(f'_c) = 3600 \text{ psi}$
Allowable @ transfer: $F_t = 3\sqrt{f_{ti}} = +180 \text{ psi}$
 $F_c = 0.6f'_{ci} = -2160 \text{ psi}$

$A_{sp} = 9(0.153) = 1.37 \text{ in}^2$ $e = 6.33''$ $ct = 11.26''$ $cb = 8.74''$ $L = 19.58''$ USING STADD $M_D = 658 \text{ kip-in}$ $M_L = 264 \text{ kip-in}$ $P_o = 0.153 * 270 * .75 * 9 = 278.8$ $I = 8000 \text{ in}^4$
--

CHECK

$$F_c = P_o/A \pm P_o eC/I \pm M_D C/I =$$

$$F_{TOP} = -0.92 + 2.48 - 0.92 =$$

$$F_{BOT} = -0.92 - 1.93 + 0.71 =$$

$$= 0.64 \text{ KSI} \leq F_{ti} \text{ OK}$$

$$= 2.14 \text{ KSI} \geq -F_{ci} \text{ OK}$$

3. Pre-Stress Losses

**** Pre-Stress loss assumption of 15%**** [this is conservative full calculations were done for hollow core planks yielding losses of 10-11%]

$$P_e = (1 - 0.15)278.8 = 236.9 \text{ Kips}$$

CHECK:

$$F = P_e/A \pm P_e eC/I \pm M_D C/I \pm M_L C/I$$

$$F_{TOP} = -0.78 + 1.66 - 0.92 - 0.26 =$$

$$F_{BOT} = -0.78 - 1.28 + 0.71 + 0.23 =$$

$$= -0.30 \text{ KSI} \geq -F_{ti} \text{ OK}$$

$$= 1.3 \text{ KSI} \leq F_{ci} \text{ OK}$$

4. Cracking Moment

Case #1: $M = P_e e + P_o I/A_c$: zero stress at bottom

$$M_{cr} = 278.8 * 6.33 + 236.98 * 10106 / 304 * 11.26 = 483.8 \text{ ft-kips} < 196.75 \text{ ft-kips OK}$$

Case #2: $M = \text{Case\#1} + f_r I/C$: cracking at bottom

$$M_{cr} = 483.8 + (530 * 10106 / 8.74) = 534.86 \text{ ft-kips} < 196.75 \text{ ft-kips OK}$$

4

BEAM LB-14

20LB20/ 98-S: (5) 1/2"Ø low relaxation strands - straight
 $f'_c=5000\text{psi}$ $f_{pu}=270\text{ksi}$
 $E_c=33(145)^{1.5}\sqrt{5000}=4074\text{ ksi}$
 $F_{se}=170\text{ksi}$
 $f_{pu}=270\text{ksi}$

LOADING CONDITION:

LL=40 PSF
 Super D=5 PSF
 Self 12RB16 = 250plf
 Self TB18 = 300plf
 $W_u = 176.5\text{ PSF OR } 353\text{ PLF}$
 Span-Depth : $22.16/1.33 = 16.66 < 40$ OK
 $P(\text{TB-24}) = ((2.733+.5)*25.5)/2 = 41.22\text{ Kips}$
 ** Detailed loading conditions See spreadsheets**

Loading Capacity: 3345 PLF


Moment Capacity: $M_n = 205.3\text{ Ft-Kips}$

Shear Capacity: $V_n = 37.0\text{ Kips}$

Beam Properties


$L=22.16\text{ ft}$
 $A= 304\text{ in}^2$
 $I = 10,160\text{ in}^4$
 $Y_{bc} = 8.74\text{ in}$
 $St = 902\text{ in}^3$
 $S_b=1163\text{ in}^3$
 $H1=12'' H2=8''$
 $wt = 317\text{ plf}$

1. Flexure and Shear



Using Stadd-Pro:

$V_u: 35.5\text{ Kips}$
 $M_u: 175.75\text{ Kip-Ft}$
 $\phi M_n \geq M_u$ **OK**
 $\phi V_n \geq V_u$ **OK**



2. Transfer Stresses:

9-1/2" Ø 270ksi low relaxation strands

$$\begin{aligned} \text{Service loads : } \quad F_{ti} &= 7.5\sqrt{f'_c} = 580 \text{ psi} \\ & F_{ci} = 0.6(f'_c) = 3600 \text{ psi} \\ \text{Allowable @ transfer: } F_t &= 3\sqrt{f'_{ci}} = +180 \text{ psi} \\ & F_c = 0.6f'_{ci} = -2160 \text{ psi} \end{aligned}$$

$$\begin{aligned} A_{sp} &= 9(0.153) = 1.377 \text{ in}^2 \\ e &= 6.33" \quad ct = 11.26" \quad cb = 8.74" \\ L &= 22.16' \\ \text{From Stadd} \\ M_D &= 1245 \text{ in-kips} \\ M_L &= 864 \text{ in-kips} \\ P_o &= 0.153 \cdot 270 \cdot 75 \cdot 9 = 278.8 \\ I &= 10160 \text{ in}^4 \end{aligned}$$

CHECK

$$F_c = P_o/A \pm P_o eC/I \pm M_D C/I =$$

$$F_{TOP} = -0.91 + 1.95 - 1.37 =$$

$$F_{BOT} = -0.91 - 1.52 + 1.07 =$$

$$= -0.33 \text{ KSI} \leq F_{ti} \text{ OK}$$

$$= 1.36 \text{ KSI} \geq -F_{ci} \text{ OK}$$

5. Pre-Stress Losses

**** Pre-Stress loss assumption of 15%**** [this is conservative full calculations were done for hollow core planks yielding losses of 10-11%]

$$P_e = (1 - 0.15)278.8 = 236.98 \text{ Kips}$$

CHECK:

$$F = P_e/A \pm P_e eC/I \pm M_D C/I \pm M_L C/I$$

$$F_{TOP} = -0.77 + 1.66 - 1.37 - 0.95 = -1.43$$

$$F_{BOT} = -0.77 - 1.28 + 1.07 + 0.743 =$$

$$= -1.43 \text{ KSI} \geq -F_c \text{ OK}$$

$$= -237 \text{ KSI} \leq -F_{ci} \text{ OK}$$

6. Cracking Moment

Case #1: $M = P_e e + P_o I / A_c$: zero stress at bottom

$$M_{cr} = 278.8 \cdot 6.33 + 236.98 \cdot 10106 / 304 \cdot 11.26 = \underline{483.8 \text{ ft-kips}} > 205.3 \text{ ft-kips OK}$$

Case #2: $M = \text{Case\#1} + f_r I / C$: cracking at bottom

$$M_{cr} = 483.8 + (530 \cdot 10106 / 8.74) = \underline{534.86 \text{ ft-kips}} > 205.3 \text{ ft-kips OK}$$

INTERIOR BEAMS

DESIGNATION	Span	Trib W (ft)	1.2° Dead (psf)	1.6° Live (psf)	KLL	AT	Lr	Wu psf	Wu psf	TRAIL SIZE
TB-1	26.8	15.1	112.5	64	2	404.68	64	176.50	2665.15	281T24
TB-2	26.8	15.1	112.5	64	2	404.68	64	176.50	2665.15	281T24
TB-3	26.8	15.1	112.5	64	2	404.68	64	176.50	2665.15	281T24
TB-4	26.8	15.1	112.5	64	2	404.68	64	176.50	2665.15	281T24
TB-5	26.8	17.5	112.5	64	2	469.00	47	159.85	2797.29	281T24
TB-6	26.8	-	-	-	-	-	-	-	-	281T24
TB-7	18.125	10.5	112.5	64	2	469.00	47	159.85	2797.29	281T24
TB-8	18.125	10.5	112.5	64	2	469.00	47	159.85	2797.29	281T24
TB-10	26.8	17.5	112.5	160	2	215.25	156	268.17	4692.99	281T20
TB-11	12.3	17.5	112.5	64	2	317.19	54	166.62	2915.77	281T20
TB-12	18.125	17.5	112.5	64	2	317.24	54	166.61	2915.71	281T20
TB-13	18.128	17.5	112.5	64	2	211.92	63	176.50	2118.00	281T20
TB-14	17.66	12	112.5	64	2	442.00	48	160.79	2733.40	281T20
TB-15	26	17	112.5	64	2	442.00	48	160.79	2733.40	281T20
TB-16	22	*	112.5	64	2	320.11	54	166.44	2829.49	281T20
TB-17	18.83	17	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-18	26	17	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-19	22	*	112.5	64	2	293.75	56	168.11	2319.49	281T20
TB-20	18.83	15.6	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-21	26	17	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-22	22	*	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-23	25.5	17	112.5	64	2	433.50	49	161.10	2738.76	281T24
TB-24	26	17	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-25	22	*	112.5	64	2	524.48	46	158.14	3202.36	281T24
TB-26	25.9	20.25	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-27	26	17	112.5	64	2	442.00	48	160.79	2733.40	281T24
TB-28	22	*	112.5	64	2	440.30	48	160.85	2734.46	281T24
TB-29	25.9	17	112.5	64	2	442.00	48	160.79	2733.40	281T20
TB-30	26	17	112.5	64	2	442.00	48	160.79	2733.40	281T20
TB-31	22	*	112.5	64	2	440.30	48	160.85	2734.46	281T24
TB-32	25.9	17	112.5	64	2	466.56	47	159.93	2331.74	281T28
TB-33	32	14.58	112.5	64	2	466.56	47	159.93	2331.74	281T28
TB-34	32	14.58	112.5	64	2	466.56	47	159.93	2331.74	281T28
RB-1	17.66	8.5	112.5	160	2	124.70	130	242.72	485.44	12R816
RB-2	14.67	8.5	112.5	160	2	35.32	144	256.79	513.57	12R816
RB-3	17.66	2.00	112.5	64	2	28.00	144	256.79	513.57	12R816
RB-4	14.00	2.00	112.5	64	2	28.00	144	256.79	513.57	12R816
RB-5	14.00	2.00	112.5	64	2	86.42	160	272.50	2316.25	12R816
RB-6	10.17	8.50	112.5	160	2	86.42	160	272.50	2316.25	12R816
RB-7	10.67	*	112.5	160	2	21.34	160	272.50	545.00	12R816
RB-8	10.67	2.00	112.5	160	2	21.34	160	272.50	545.00	12R816
RB-9	10.67	*	112.5	160	2	21.34	160	272.50	545.00	12R816

* : Wu found by hand due to loading combinations

* : These beams are the same in decks analysis can be found in appendix 2

* : Mu and Vu were found in STADD due to loading conditions


BLUE: Beams checked for structural integrity

Green: Beam which additional reinforcing for column and hollow core bearing is designed for in Appendix #3

DESIGN CHECKS							
<i>DESIGNATION</i>	<i>Load (plf)</i>	<i>∅ Mn (kip-ft)</i>	<i>∅ Vn (kip)</i>	<i>Mu (kip-ft)</i>	<i>Vu(kip)</i>	<i>∅Mn≥Mu</i>	<i>∅Vn≥Vu</i>
TB-1	3374	272.63	40.69	239.28	35.71	OK	OK
TB-2	3374	272.63	40.69	239.28	35.71	OK	OK
TB-3	3374	272.63	40.69	239.28	35.71	OK	OK
TB-4	3374	272.63	40.69	239.28	35.71	OK	OK
TB-5	3374	272.63	40.69	251.14	37.48	OK	OK
TB-6	3374	272.63	40.69	261.90	42.30	OK	OK
TB-7	5078	187.67	41.42	158.30	34.94	OK	OK
TB-8	5078	187.67	41.42	158.30	34.94	OK	OK
TB-10	3374	272.63	40.69	251.14	37.48	OK	OK
TB-11	6511	110.82	36.04	88.75	28.86	OK	OK
TB-12	5076	187.60	41.40	205.00	30.70	OK	OK
TB-13	5076	187.66	41.41	119.77	26.43	OK	OK
TB-14	5076	178.10	40.34	82.57	18.70	OK	OK
TB-15	3374	256.59	39.48	230.97	35.53	OK	OK
TB-16	4882	265.82	48.33	199.80	39.50	OK	OK
TB-17	5078	202.56	43.03	125.41	26.64	OK	OK
TB-18	3374	256.59	39.48	230.97	35.53	OK	OK
TB-19	4882	265.82	48.33	199.80	39.50	OK	OK
TB-20	5076	202.48	43.01	102.80	21.84	OK	OK
TB-21	3374	256.59	39.48	230.97	35.53	OK	OK
TB-22	4882	265.82	48.33	199.80	39.50	OK	OK
TB-23	3374	246.82	38.72	222.61	34.92	OK	OK
TB-24	3374	256.59	39.48	230.97	35.53	OK	OK
TB-25	4882	265.82	48.33	199.80	39.50	OK	OK
TB-26	3374	254.62	39.32	268.52	41.47	OK	OK
TB-27	3374	256.59	39.48	230.97	35.53	OK	OK
TB-28	4882	265.82	48.33	199.80	39.50	OK	OK
TB-29	3374	254.62	39.32	229.29	35.41	OK	OK
TB-30	3374	256.59	39.48	230.97	35.53	OK	OK
TB-31	4882	253.62	50.72	199.80	39.50	OK	OK
TB-32	3374	254.62	39.32	229.29	35.41	OK	OK
TB-33	2976	342.84	42.85	298.46	37.31	OK	OK
TB-34	2976	342.84	42.85	298.46	37.31	OK	OK
RB-1	2772	97.26	22.03	60.94	13.80	OK	OK
RB-2	2772	67.11	18.30	62.31	16.99	OK	OK
RB-3	2772	97.26	22.03	18.92	4.29	OK	OK
RB-4	2772	61.12	17.46	12.58	3.59	OK	OK
RB-5	2772	61.12	17.46	12.58	3.59	OK	OK
RB-6	3553	41.32	16.26	29.93	11.77	OK	OK
RB-7	3553	45.51	17.06	*	*	OK	OK
RB-8	3553	45.51	17.06	7.76	2.91	OK	OK
RB-9	3553	45.51	17.06	*	*	OK	OK

RECTANGULAR BEAMS

Normal Weight Concrete



$f'_c = 5,000$ psi
 $f_{pu} = 270,000$ psi
 ½ in. diameter
 low-relaxation strand

Section Properties							
Designation	b in.	h in.	A in. ²	I in. ⁴	y_b in.	S in. ³	wt plf
12RB16	12	16	192	4,096	8.00	512	200
12RB20	12	20	240	8,000	10.00	800	250
12RB24	12	24	288	13,824	12.00	1152	300
12RB28	12	28	336	21,952	14.00	1568	350
12RB32	12	32	384	32,768	16.00	2048	400
12RB36	12	36	432	46,656	18.00	2592	450
16RB24	16	24	384	18,432	12.00	1536	400
16RB28	16	28	448	29,269	14.00	2091	467
16RB32	16	32	512	43,691	16.00	2731	533
16RB36	16	36	576	62,208	18.00	3456	600
16RB40	16	40	640	85,333	20.00	4267	667

1. Check local area for availability of other sizes.
2. Safe loads shown include 50% superimposed dead load and 50% live load. 800 psi top tension has been allowed, therefore, additional top reinforcement is required.
3. Safe loads can be significantly increased by use of structural composite topping.

Key


- 3553 – Safe superimposed service load, plf.
- 0.4 – Estimated camber at erection, in.
- 0.2 – Estimated long-time camber, in.

Table of safe superimposed service load (plf) and cambers (in.)

Designation	No. Strand	y_c (end) in. y_c (center) in.	Span, ft															
			16	18	20	22	24	26	28	30	32	34	36	40	42	44	46	48
12RB16	58-S	3.00	3553 2772 2212 1799 1484 1239 1045															
			0.4 0.5 0.6 0.8 0.9 1.0 1.1															
			0.2 0.2 0.2 0.2 0.3 0.3 0.3															
12RB20	88-S	3.00	0165 4825 3807 3138 2620 2201 1808 1600 1380 1198 1046															
			0.4 0.5 0.6 0.7 0.9 1.0 1.1 1.3 1.4 1.5 1.7															
			0.2 0.2 0.3 0.3 0.4 0.4 0.4 0.5 0.5 0.5 0.5															
12RB24	108-S	3.60	8950 7018 5636 4613 3835 3230 2749 2362 2045 1782 1562 1375 1216 1079 960															
			0.4 0.4 0.5 0.7 0.8 0.9 1.0 1.1 1.3 1.4 1.5 1.6 1.8 1.9 2.0															
			0.2 0.2 0.3 0.3 0.3 0.4 0.4 0.5 0.5 0.6 0.6 0.6 0.6 0.7 0.8															
12RB28	128-S	4.00	9781 7866 6448 5370 4532 3866 3329 2890 2525 2220 1962 1741 1552 1387 1244 1118 1006															
			0.4 0.5 0.6 0.7 0.8 0.9 1.0 1.2 1.3 1.4 1.5 1.7 1.8 1.9 2.0 2.1 2.2															
			0.2 0.2 0.3 0.3 0.4 0.4 0.5 0.5 0.6 0.6 0.7 0.7 0.7 0.8 0.8 0.8															
12RB32	138-S	4.77	8320 6936 5859 5005 4316 3752 3284 2892 2561 2278 2034 1823 1639 1477 1334															
			0.5 0.6 0.7 0.8 0.9 1.0 1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8 1.9															
			0.2 0.3 0.3 0.3 0.4 0.4 0.4 0.5 0.5 0.5 0.5 0.6 0.6 0.6 0.6															
12RB36	158-S	5.07	9015 7624 6521 5631 4902 4298 3792 3364 2999 2684 2411 2173 1964 1780															
			0.5 0.6 0.7 0.8 0.9 1.0 1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8															
			0.2 0.3 0.3 0.4 0.4 0.4 0.5 0.5 0.6 0.6 0.6 0.6 0.7 0.7															
16RB24	138-S	3.54	9397 7547 6177 5136 4325 3682 3164 2739 2387 2092 1843 1629 1446 1287 1149 1027															
			0.4 0.5 0.6 0.8 0.9 1.0 1.1 1.2 1.4 1.5 1.6 1.7 1.8 1.9 2.0 2.1															
			0.2 0.2 0.3 0.3 0.4 0.4 0.5 0.5 0.5 0.6 0.6 0.6 0.6 0.6 0.6															
16RB28	148-S	3.71	8730 7272 6137 5237 4510 3915 3423 3010 2660 2362 2105 1883 1688 1518 1368															
			0.5 0.6 0.7 0.8 0.9 1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8 1.9 1.9															
			0.2 0.2 0.3 0.3 0.3 0.4 0.4 0.4 0.4 0.4 0.4 0.4 0.4 0.4 0.4 0.3															
16RB32	188-S	4.67	9340 7891 6741 5813 5054 4425 3897 3451 3070 2742 2458 2210 1992 1800															
			0.6 0.7 0.8 0.9 1.0 1.1 1.2 1.3 1.5 1.6 1.7 1.8 1.9 2.0															
			0.3 0.3 0.4 0.4 0.5 0.5 0.5 0.6 0.6 0.6 0.7 0.7 0.7 0.7															
16RB36	208-S	5.40	9948 8505 7343 6391 5603 4942 4383 3905 3494 3138 2827 2555 2314															
			0.6 0.7 0.8 0.9 1.0 1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8															
			0.3 0.3 0.4 0.4 0.4 0.5 0.5 0.5 0.6 0.6 0.6 0.6 0.6															
16RB40	228-S	6.00	9122 7949 6976 6160 5470 4881 4374 3935 3552 3215 2918															
			0.7 0.8 0.9 1.0 1.1 1.2 1.3 1.4 1.5 1.6 1.7															
			0.3 0.4 0.4 0.4 0.5 0.5 0.5 0.5 0.6 0.6 0.6															

INVERTED TEE BEAMS

Normal Weight Concrete



Section Properties								
Designation	h in.	h ₁ /h ₂ in./in.	A in. ²	I in. ⁴	y _b in.	S _{b₃} in.	S _{t₃} in.	wt plf
28IT20	20	12/8	380	11,800	7.04	1,470	687	383
28IT24	24	12/12	480	20,275	9.60	2,112	1,408	500
28IT28	28	16/12	528	32,078	11.09	2,892	1,897	550
28IT32	32	20/12	576	47,372	12.07	3,778	2,477	600
28IT36	36	24/12	624	68,101	14.31	4,759	3,140	650
28IT40	40	24/16	736	93,503	15.83	5,907	3,869	767
28IT44	44	28/16	784	124,437	17.43	7,139	4,683	817
28IT48	48	32/16	832	161,424	19.08	8,460	5,582	867
28IT52	52	36/16	880	204,884	20.76	9,869	6,558	917
28IT56	56	40/16	928	255,229	22.48	11,354	7,614	967
28IT60	60	44/16	976	312,866	24.23	12,912	8,747	1,017

$f'_c = 5,000$ psi
 $f_{pu} = 270,000$ psi
 ½ in. diameter
 low-relaxation strand

1. Check local area for availability of other sizes.
2. Safe loads shown include 50% superimposed dead load and 50% live load. 800 psi top tension has been allowed, therefore, additional top reinforcement is required.
3. Safe loads can be significantly increased by use of structural composite topping.

Key

- 6511 – Safe superimposed service load, plf.
- 0.2 – Estimated camber at erection, in.
- 0.1 – Estimated long-time camber, in.

Table of safe superimposed service load (plf) and cambers (in.)

Designation	No. Strand	y _c (end) in. y _c (center) in.	Span, ft																	
			16	18	20	22	24	26	28	30	32	34	36	38	40	42	44	46	48	50
28IT20	98-S	2.44 2.44	6511	6076	4846	3280	2711	2202	1805	1417	1061	1100	1020							
28IT24	188-S	2.73 2.73	9612	7504	5997	4882	4034	3374	2850	2427	2081	1795	1555	1351	1178	1029				
28IT28	138-S	3.08 3.08	8303	6822	5087	4750	4031	3451	2876	2582	2252	1873	1735	1536	1362	1197	1061			
28IT32	158-S	3.47 3.47	9049	7521	5333	5389	4628	4006	3490	3057	2691	2379	2110	1876	1673	1495	1337			
28IT36	168-S	3.50 3.50	9832	8295	7075	6092	5287	4619	4060	3587	3183	2835	2534	2271	2040	1836				
28IT40	198-S	4.21 4.21	8638	7440	6460	5647	4966	4390	3898	3474	3107	2767	2508	2258						
28IT44	208-S	4.40 4.40	9186	7989	6997	6165	5462	4861	4344	3898	3505	3162	2859							
28IT48	228-S	4.55 4.55	9719	8525	7523	6676	5953	5330	4791	4320	3907	3542								
28IT52	248-S	5.17 5.17	9987	8823	7838	6998	6274	5647	4100	4619	4196									
28IT56	268-S	5.23 5.23	9307	8319	7469	6731	6088	5524	5026											
28IT60	288-S	5.57 5.57	9645	8668	7820	7081	6432	5859												

5

INTERIOR BEAMS DESIGN

BEAM TB-6

Beam TB-6
 28IT24/ 188-S: (18) ½"Ø low relaxation strands
 – straight
 $f'_c=5000\text{psi}$ $f_{pu}=270\text{ksi}$
 $E_c=33(145)^{1.5}\sqrt{5000}=4074\text{ ksi}$
 $F_{se}=170\text{ksi}$
 $f_{pu}=270\text{ksi}$

LOADING CONDITION:

Self 28IT24 = 500plf

Wu = differs

Span-Depth : $26.67/2 = 13.35 < 40$ OK

** Detailed loading conditions See spreadsheets**

1.Flexure and Shear

$M_u = 261.9\text{ ft-Kips} < .9M_n$ OK

$V_u = 42.3\text{ Kips} < .9V_n$ OK

2.Transfer Stresses:

10-1/2" Ø 270ksi low relaxation strands

Service loads : $F_{ti} = 7.5\sqrt{f'_c} = 580\text{psi}$
 $F_{ci} = 0.6(f'_c) = 3600\text{ psi}$
 Allowable @ transfer: $F_t = 3\sqrt{f'_{ci}} = +180\text{psi}$
 $F_c = 0.6f'_{ci} = -2160\text{psi}$

Loading Capacity: 3374 PLF

Moment Capacity: $M_n = 299\text{ Ft-Kips}$

Shear Capacity: $V_n = 45\text{ Kips}$

Beam Properties

$A = 480\text{in}^2$

$L = 26'-8"$

$I = 20,275\text{ in}^4$

$c = \text{in}$

$h_1 = 12"$ $h_2 = 12"$

$St = 1408\text{ in}^3$

$S_b = 2112$

$W_t = 500\text{ plf}$

$A_{sp} = 18(0.153) = 2.75\text{ in}^2$
 $e = 6.87"$ $ct = 14.4"$ $cb = 9.6"$
 $L = 26.8"$
 From Stadd
 $M_D = 1537.2\text{ ft-kips}$
 $M_L = 1605\text{ ft-kips}$
 $P_o = 0.153 \cdot 270 \cdot .75 \cdot 18 = 557.68\text{K}$

CHECK

$F_c = P_o/A \pm P_o eC/I \pm M_D C/I =$

$F_{TOP} = -1.16 + 2.72 - 0.09 =$

$F_{BOT} = -1.16 - 1.82 + 0.06 =$

$= 1.47\text{ KSI} \leq F_{ti}$ OK

$= -2.92\text{ KSI} \geq -F_{ci}$ OK

3.Pre-Stress Losses

** Pre-Stress loss assumption of 15%** [this is conservative full calculations were done for hollow core planks yielding losses of 10-11%]

$P_e = (1 - 0.15)557.68 = 474\text{ Kips}$

CHECK:

$$F = P_e/A \pm P_e eC/I \pm M_D C/I \pm M_L C/I$$

$$F_{TOP} = -0.98 + 2.31 - 1.09 - 1.13 =$$

$$F_{BOT} = -0.98 - 1.54 + 0.72 + 0.75 =$$

$$= -0.89 \text{ KSI} \geq F_c \text{ OK}$$

$$= -1.05 \text{ KSI} \leq F_{ci} \text{ OK}$$

4. Cracking Moment

Case #1: $M = P_e e + P_o I / A_c$: zero stress at bottom
 $M_{cr} = 474 * 6.87 + 557 * 20275 / 480 * 14.4 = 434.7 \text{ kip-ft}$

Case #2: $M = \text{Case\#1} + f_r I / C$: cracking at bottom
 $M_{cr} = 434.7 + (530 * 20275 / 9.6) = 527.9 \text{ kip-ft}$

6

Beam RB-22

Beam RB-23
 28IT24/ 188-S: (10) 1/2" \emptyset low relaxation strands
 - straight
 $f'_c = 5000 \text{ psi}$ $f_{pu} = 270 \text{ ksi}$
 $E_c = 33(145)^{1.5} \sqrt{5000} = 4074 \text{ ksi}$
 $F_{se} = 170 \text{ ksi}$
 $f_{pu} = 270 \text{ ksi}$

LOADING CONDITION:
 Self 28IT24 = 500 plf
 $W_u = \text{differs}$
 Span-Depth : $22/2 = 12 < 40$ OK
 ** Detailed loading conditions See spreadsheets**

1. Flexure and Shear

$$M_u = 199.8 \text{ ft-Kips} < .9M_n \text{ OK}$$

$$V_u = 39.7 \text{ Kips} < .9V_n \text{ OK}$$

2. Transfer Stresses:

18-1/2" \emptyset 270ksi low relaxation strands

Service loads : $F_{ti} = 7.5 \sqrt{f'_c} = 580 \text{ psi}$
 $F_{ci} = 0.6(f'_c) = 3600 \text{ psi}$
 Allowable @ transfer: $F_t = 3 \sqrt{f'_c} = +180 \text{ psi}$
 $F_c = 0.6 f'_{ci} = -2160 \text{ psi}$

Loading Capacity: 7882 PLF

Moment Capacity: $M_n = 269.4 \text{ Ft-Kips}$

Shear Capacity: $V_n = 38.5 \text{ Kips}$

Beam Properties

$A = 480 \text{ in}^2$

$L = 26'-8"$

$I = 20,275 \text{ in}^4$

$c = \text{in}$

$h_1 = 12"$ $h_2 = 12"$

$S_t = 1408 \text{ in}^3$

$S_b = 2112$

$W_t = 500 \text{ plf}$

$$A_{sp} = 18(0.153) = 2.75 \text{ in}^2$$

$$e = 6.87" \quad ct = 14.4" \quad cb = 9.6"$$

$$L = 22"$$

From Stadd

$$M_D = 1388 \text{ ft-kips}$$

$$M_L = 1008 \text{ ft-kips}$$

$$P_o = 0.153 * 270 * .75 * 18 = 557.6 \text{ K}$$

CHECK

$$F_c = P_o/A \pm P_o eC/I \pm M_D C/I =$$

$$F_{TOP} = -1.16 + 2.72 - 0.082 =$$

$$= 1.47 \text{ KSI} \leq F_{ti} \text{ OK}$$

$$F_{BOT} = -1.16 - 1.82 + 0.054 = -$$

$$= -3.03 \text{ KSI} \geq -F_{ci} \text{ OK}$$

3. Pre-Stress Losses

**** Pre-Stress loss assumption of 15%**** [this is conservative full calculations were done for hollow core planks yielding losses of 10-11%]

$$P_e = (1 - 0.15)557.6 = 473.966 \text{ Kips}$$

CHECK:

$$F = P_e/A \pm P_e eC/I \pm M_D C/I \pm M_L C/I$$

$$F_{TOP} = -0.98 + 2.31 - 0.98 - 0.71 =$$

$$= -0.36 \text{ KSI} \geq F_c \text{ OK}$$

$$F_{BOT} = -0.98 - 1.54 + 0.65 + 0.47 =$$

$$= -1.4 \text{ KSI} \leq F_{ci} \text{ OK}$$

4. Cracking Moment


Case #1: $M = P_e e + P_o I / A_c$: zero stress at bottom

$$M_{cr} = 474 * 6.87 + 557 * 20275 / 480 * 14.4 = \underline{434.7 \text{ kip-ft}}$$

Case #2: $M = \text{Case\#1} + f_r I / C$: cracking at bottom

$$M_{cr} = 434.7 + (530 * 20275 / 9.6) = \underline{527.9 \text{ kip-ft}}$$

Column Sizing Charts from PCI 6th edition



Column Sizing [Fig 2.7.1 PCI handbook 6th edition]

Per Floor		Level 1-4			Level 5-9			
<i>Designation</i>	<i>Pu(kips)</i>	<i>Mu(k-ft)</i>	ϕ <i>Pn(kips)</i>	ϕ <i>Mn(k-ft)</i>	<i>TRIAL</i>	ϕ <i>Pn(kips)</i>	ϕ <i>Mn(k-ft)</i>	<i>TRIAL</i>
C1	21.7	-17.51	217.07	-175.12	16x16 f'c=5000psi 4-#8	130.24	-105.07	16x16 f'c=5000psi 4-#8
C2	39.2	0.00	392.43	0.00	16x16 f'c=5000psi 4-#8	235.46	0.00	16x16 f'c=5000psi 4-#8
C3	39.2	0.00	392.43	0.00	16x16 f'c=5000psi 4-#8	235.46	0.00	16x16 f'c=5000psi 4-#8
C4	39.2	0.00	392.43	0.00	16x16 f'c=5000psi 4-#8	235.46	0.00	16x16 f'c=5000psi 4-#8
C5	21.7	-43.67	217.07	-436.74	24x24 f'c=5000psi 4-#11	130.24	-262.04	18x18 f'c=5000psi 4-#11
C6	47.2	19.35	471.91	193.47	16x16 f'c=5000psi 4-#8	283.15	116.08	16x16 f'c=5000psi 4-#8
C7	84.8	0.00	848.22	0.00	18x18 f'c=5000psi 4-#9	508.93	0.00	16x16 f'c=5000psi 4-#8
C8	84.8	0.00	848.22	0.00	18x18 f'c=5000psi 4-#9	508.93	0.00	16x16 f'c=5000psi 4-#8
C9	84.8	0.00	848.22	0.00	18x18 f'c=5000psi 4-#9	508.93	0.00	16x16 f'c=5000psi 4-#8
C10	47.3	-21.79	472.77	-217.86	20x20 f'c=5000psi 4-#9	283.66	-130.72	16x16 f'c=5000psi 4-#8
C11	49.8	36.93	498.48	369.30	24x24 f'c=5000psi 4-#11	299.09	221.58	18x18 f'c=5000psi 4-#11
C12	97.0	5.57	969.62	55.74	20x20 f'c=5000psi 4-#9	581.77	33.45	16x16 f'c=5000psi 4-#8
C13	80.3	0.00	803.41	0.00	18x18 f'c=5000psi 4-#9	482.05	0.00	16x16 f'c=5000psi 4-#8
C14	79.5	0.00	794.79	0.00	18x18 f'c=5000psi 4-#9	476.87	0.00	16x16 f'c=5000psi 4-#8
C15	55.6	-15.32	555.99	-153.20	18x18 f'c=5000psi 4-#9	333.60	-91.92	16x16 f'c=5000psi 4-#8
C16	18.3	-5.58	182.55	-55.81	16x16 f'c=5000psi 4-#8	109.53	-33.48	16x16 f'c=5000psi 4-#8
C17	50.4	37.29	503.87	372.89	24x24 f'c=5000psi 4-#11	302.32	223.74	18x18 f'c=5000psi 4-#11
C18	78.6	-7.37	786.26	-73.68	18x18 f'c=5000psi 4-#9	471.76	-44.21	16x16 f'c=5000psi 4-#8
C19	62.3	0.00	623.24	0.00	16x16 f'c=5000psi 4-#8	373.94	0.00	16x16 f'c=5000psi 4-#8
C20	6.8	5.10	67.57	51.04	16x16 f'c=5000psi 4-#8	40.54	30.63	16x16 f'c=5000psi 4-#8
C21	6.2	-0.10	61.56	-1.05	16x16 f'c=5000psi 4-#8	36.94	-0.63	16x16 f'c=5000psi 4-#8
C22	54.1	-5.50	540.66	-55.01	18x18 f'c=5000psi 4-#9	324.40	-33.00	16x16 f'c=5000psi 4-#8
C23	26.7	-10.16	267.39	-101.63	16x16 f'c=5000psi 4-#8	160.43	-60.98	16x16 f'c=5000psi 4-#8
C24	56.4	-11.33	564.03	-113.30	18x18 f'c=5000psi 4-#9	338.42	-67.98	16x16 f'c=5000psi 4-#8
C25	36.0	-3.15	360.13	-31.46	16x16 f'c=5000psi 4-#8	216.08	-18.88	16x16 f'c=5000psi 4-#8
C26	18.1	-7.19	180.78	-71.89	16x16 f'c=5000psi 4-#8	108.47	-43.14	16x16 f'c=5000psi 4-#8
C27	47.4	35.20	474.18	352.05	24x24 f'c=5000psi 4-#11	284.51	211.23	18x18 f'c=5000psi 4-#11
C28	98.5	9.62	984.81	96.15	20x20 f'c=5000psi 4-#9	590.89	57.69	16x16 f'c=5000psi 4-#8
C29	65.0	-0.42	650.36	-4.23	16x16 f'c=5000psi 4-#8	390.22	-2.54	16x16 f'c=5000psi 4-#8
C30	47.4	35.20	474.18	352.05	24x24 f'c=5000psi 4-#11	284.51	211.23	18x18 f'c=5000psi 4-#11
C31	98.5	9.62	984.81	96.15	20x20 f'c=5000psi 4-#9	590.89	57.69	16x16 f'c=5000psi 4-#8
C32	60.1	-3.71	601.04	-37.10	18x18 f'c=5000psi 4-#9	360.63	-22.26	16x16 f'c=5000psi 4-#8
C33	32.2	-11.63	321.83	-116.28	16x16 f'c=5000psi 4-#8	193.10	-69.77	16x16 f'c=5000psi 4-#8
C34	4.0	4.16	40.16	41.57	16x16 f'c=5000psi 4-#8	24.10	24.94	16x16 f'c=5000psi 4-#8
C34a	5.0	3.13	50.47	31.34	16x16 f'c=5000psi 4-#8	30.28	18.81	16x16 f'c=5000psi 4-#8
C35	47.4	35.21	474.31	352.13	24x24 f'c=5000psi 4-#11	284.59	211.28	18x18 f'c=5000psi 4-#11
C36	98.5	9.61	984.94	96.07	20x20 f'c=5000psi 4-#9	590.96	57.64	16x16 f'c=5000psi 4-#8
C37	75.7	6.68	756.86	66.77	18x18 f'c=5000psi 4-#9	454.11	40.06	16x16 f'c=5000psi 4-#8
C38	47.4	35.20	474.18	352.05	24x24 f'c=5000psi 4-#11	284.51	211.23	18x18 f'c=5000psi 4-#11
C39	98.5	9.62	984.81	96.15	20x20 f'c=5000psi 4-#9	590.89	57.69	16x16 f'c=5000psi 4-#8
C40	68.6	1.99	686.49	19.86	18x18 f'c=5000psi 4-#9	411.89	11.92	16x16 f'c=5000psi 4-#8
C41	42.3	-15.28	422.59	-152.83	16x16 f'c=5000psi 4-#8	253.55	-91.70	16x16 f'c=5000psi 4-#8
C42	47.4	35.20	474.18	352.05	24x24 f'c=5000psi 4-#11	284.51	211.23	18x18 f'c=5000psi 4-#11
C43	98.5	9.62	984.81	96.15	20x20 f'c=5000psi 4-#9	590.89	57.69	16x16 f'c=5000psi 4-#8
C44	73.9	5.50	739.20	55.00	18x18 f'c=5000psi 4-#9	443.52	33.00	16x16 f'c=5000psi 4-#8
C45	46.5	-20.20	464.74	-202.04	20x20 f'c=5000psi 4-#9	278.84	-121.23	16x16 f'c=5000psi 4-#8
C46	47.4	35.21	474.31	352.13	24x24 f'c=5000psi 4-#11	284.59	211.28	18x18 f'c=5000psi 4-#11
C47	96.0	7.93	959.75	79.27	20x20 f'c=5000psi 4-#9	575.85	47.56	16x16 f'c=5000psi 4-#8
C48	95.1	-8.59	950.51	-85.88	20x20 f'c=5000psi 4-#9	570.30	-51.53	16x16 f'c=5000psi 4-#8
C49	46.5	-20.20	464.74	-202.04	20x20 f'c=5000psi 4-#9	278.84	-121.23	16x16 f'c=5000psi 4-#8
C50	52.6	39.42	525.71	394.15	24x24 f'c=5000psi 4-#11	315.43	236.49	18x18 f'c=5000psi 4-#11
C52	48.3	-28.28	483.20	-282.80	24x24 f'c=5000psi 4-#11	289.92	-169.68	18x18 f'c=5000psi 4-#11
C53	47.0	31.34	469.57	313.45	24x24 f'c=5000psi 4-#11	281.74	188.07	18x18 f'c=5000psi 4-#11
C55	24.6	18.23	246.47	182.27	18x18 f'c=5000psi 4-#9	147.88	109.36	16x16 f'c=5000psi 4-#8
C56	23.0	-14.01	230.16	-140.11	16x16 f'c=5000psi 4-#8	138.10	-84.06	16x16 f'c=5000psi 4-#8
C57	25.1	16.76	250.77	167.58	18x18 f'c=5000psi 4-#9	150.46	100.55	16x16 f'c=5000psi 4-#8
C58	24.1	-11.93	240.77	-119.30	16x16 f'c=5000psi 4-#8	144.46	-71.58	16x16 f'c=5000psi 4-#8

Column Sizing [Fig 2.7.1 PCI handbook 6th edition]

Level 10-11

<i>Designation</i>	Φ <i>Pn (kips)</i>	Φ <i>Mn (k-ft)</i>	<i>TRIAL</i>
C1	43.41	-70.05	16x16 f'c=5000psi 4-#8
C2	78.49	0.00	16x16 f'c=5000psi 4-#8
C3	78.49	0.00	16x16 f'c=5000psi 4-#8
C4	78.49	0.00	16x16 f'c=5000psi 4-#8
C5	43.41	-174.69	18x18 f'c=5000psi 4-#11
C6	94.38	77.39	16x16 f'c=5000psi 4-#8
C7	169.64	0.00	16x16 f'c=5000psi 4-#8
C8	169.64	0.00	16x16 f'c=5000psi 4-#8
C9	169.64	0.00	16x16 f'c=5000psi 4-#8
C10	94.55	-87.14	16x16 f'c=5000psi 4-#8
C11	99.70	147.72	18x18 f'c=5000psi 4-#11
C12	193.92	22.30	16x16 f'c=5000psi 4-#8
C13	160.68	0.00	16x16 f'c=5000psi 4-#8
C14	158.96	0.00	16x16 f'c=5000psi 4-#8
C15	111.20	-61.28	16x16 f'c=5000psi 4-#8
C16	36.51	-22.32	16x16 f'c=5000psi 4-#8
C17	100.77	149.16	18x18 f'c=5000psi 4-#11
C18	157.25	-29.47	16x16 f'c=5000psi 4-#8
C19	124.65	0.00	16x16 f'c=5000psi 4-#8
C20	13.51	20.42	16x16 f'c=5000psi 4-#8
C21	12.31	-0.42	18x18 f'c=5000psi 4-#11
C22	108.13	-22.00	16x16 f'c=5000psi 4-#8
C23	53.48	-40.65	16x16 f'c=5000psi 4-#8
C24	112.81	-45.32	16x16 f'c=5000psi 4-#8
C25	72.03	-12.59	16x16 f'c=5000psi 4-#8
C26	36.16	-28.76	16x16 f'c=5000psi 4-#8
C27	94.84	140.82	18x18 f'c=5000psi 4-#11
C28	196.96	38.46	16x16 f'c=5000psi 4-#8
C29	130.07	-1.69	16x16 f'c=5000psi 4-#8
C30	94.84	140.82	18x18 f'c=5000psi 4-#11
C31	196.96	38.46	16x16 f'c=5000psi 4-#8
C32	120.21	-14.84	16x16 f'c=5000psi 4-#8
C33	64.37	-46.51	16x16 f'c=5000psi 4-#8
C34	8.03	16.63	16x16 f'c=5000psi 4-#8
C34a	10.09	12.54	16x16 f'c=5000psi 4-#8
C35	94.86	140.85	18x18 f'c=5000psi 4-#11
C36	196.99	38.43	16x16 f'c=5000psi 4-#8
C37	151.37	26.71	16x16 f'c=5000psi 4-#8
C38	94.84	140.82	18x18 f'c=5000psi 4-#11
C39	196.96	38.46	16x16 f'c=5000psi 4-#8
C40	137.30	7.94	16x16 f'c=5000psi 4-#8
C41	84.52	-61.13	16x16 f'c=5000psi 4-#8
C42	94.84	140.82	18x18 f'c=5000psi 4-#11
C43	196.96	38.46	16x16 f'c=5000psi 4-#8
C44	147.84	22.00	16x16 f'c=5000psi 4-#8
C45	92.95	-80.82	16x16 f'c=5000psi 4-#8
C46	94.86	140.85	18x18 f'c=5000psi 4-#11
C47	191.95	31.71	16x16 f'c=5000psi 4-#8
C48	190.10	-34.35	16x16 f'c=5000psi 4-#8
C49	92.95	-80.82	16x16 f'c=5000psi 4-#8
C50	105.14	157.66	18x18 f'c=5000psi 4-#11
C52	96.64	-113.12	16x16 f'c=5000psi 4-#8
C53	93.91	125.38	18x18 f'c=5000psi 4-#11
C55	49.29	72.91	16x16 f'c=5000psi 4-#8
C56	46.03	-56.04	16x16 f'c=5000psi 4-#8
C57	50.15	67.03	16x16 f'c=5000psi 4-#8
C58	48.15	-47.72	16x16 f'c=5000psi 4-#8

Full column checks, and columns loading can be obtained upon request. PCA Column was used to check columns on level 1-4 interaction diagrams are on the next page.

PCA Column: Interaction diagrams for columns on ground level.




Fig 1: 24x24" Column w/ 4-#11




Fig 2: 18"x18" Column w/ 4-#9




Fig 3: 20"x20" Columns w/ 4-#9




Fig 4: 18"x18" Column w/ 4-#8

Appendix #3

GRAVITY SYSTEM DETAILING

CREEP & STRAIN

<i>Volume Calculations</i>	3
----------------------------	---

CONNECTIONS

<i>Column to Foundations</i>	4
<i>Plank to Beam</i>	5
<i>T&L Beam to Column</i>	6-7

VOLUME CHANGE:

PCI 6th edition: Fig 3.10.13-3.10.16

Location: Washington D.C

Normal Weight Beam 12RB24

10 -1/2" diam. 270 low relaxation strands

Length 26 ft

$A_{ps} = 0.153 \times 10 = 1.53 \text{ in}^2$

$P_o = 1.53 \times 270 \times 0.75 \times (1 - 0.15) = 263.35 \text{ kips}$

$P_o/A = 914.5 \text{ psi}$

$V/S = 4 \text{ in}$

$F'_c = 5000 \text{ psi}$

R.H = 75%

Design Temp. Change = 50°F

At 60 Days :

Creep Strain: 169×10^{-6}

Shrinkage Strain: 354×10^{-6}

Creep correction factor: 1.325

Relative humidity correction (creep): 0.96

Relative humidity correction (shrinkage): 0.9

Volume-to-surface ratio correction (creep): 0.48

Volume-to-surface ratio correction (shrinkage): 0.46

$\begin{aligned} \text{Creep} &= 169 \times 10^{-6} \times 0.96 \times 0.48 \times 1.325 = 1.03 \times 10^{-4} \\ \text{Shrinkage} &= 354 \times 10^{-6} \times 0.93 \times 0.46 = 1.512 \times 10^{-4} \\ \text{Total Strain} &= 2.546 \times 10^{-4} \\ \text{Total Shortening} &= 2.546 \times 10^{-4} (26)(12) = \mathbf{0.079 \text{ in}} \end{aligned}$

At final

Creep Strain: 315×10^{-6}

Shrinkage Strain: 560×10^{-6}

Creep correction factor: 1.325

Volume-to-surface ratio correction (creep): 0.77

Volume-to-surface ratio correction (shrinkage): 0.75

Temperature Strain = 150×10^{-6}

$\begin{aligned} \text{Creep} &= 3.08 \times 10^{-4} \\ \text{Shrinkage} &= 3.906 \times 10^{-4} \\ \text{Total} &= 6.98 \times 10^{-4} \\ \text{Difference} &= 6.98 \times 10^{-4} - 2.546 \times 10^{-4} = \mathbf{4.43 \times 10^{-4}} \end{aligned}$
--

$$\text{TOTAL STRAIN} = 4.43\text{E-}4 + 150\text{E-}6 = \mathbf{5.93 \times 10^{-4}}$$

$$\text{TOTAL SHORTNING} = 5.93\text{E-}4 (12)(26) = \mathbf{0.185 \text{ in}}$$

COLUMN TO FOUNDATION CONNECTION

A 20"x20" column located in the corner with type "P2" column cap details

Column C18

Factored Axial Load : 790 Kips

Column $f'_c=5000$

Pedestal $f'_c= 4000$ psi

Base plate & Anchor bolts= 36ksi

Reinforcing bars=60ksi

$\Phi=1.0$

$\phi T_u = 200A_g = .2(20^2) = 80$ Kips or 20 Kips/Bolt

Base Plate Thickness: $t = \sqrt{((T_u(4)x)/(\Phi B F_y))}$

$B=13.79$ in

$X=3.71$ in

$T = \sqrt{20(4)(3.71)/(1.0)(13.79)(36)} = 0.77$ in

USE \longrightarrow **1" Plate**

Deformed Anchors:

$A_s = T_u / \phi F_y = 1.33$ in²

Try \longrightarrow $[8(0.2) = 1.6 > 1.33$ OK] **(8)-1/2"**

Anchor Bolts:

[Fig 6.16.3] 1" Diam Bolts $A=0.785$ in² Tension=25.6 Kips Shear = 13.7 Kips

$4(25.5) = 102.4 > 80$ OK

$[h_{ed} < 11]$ Hooked anchor bolts

$N_p = 1.2 f'_c e_d d_o C_{crp} \longrightarrow N_p = 20$ Kips

$E_n = 3.97$ in

$C_{crp} = 1.0$ [concrete assumed uncracked]

Spacing 15.5in $< 3h_{ef}$ [Fig 6.5 $D_o = 1.0$]

Breakout :

$C_{bs} = 3.33 \lambda \sqrt{f'_c / h_{ef}} = 3.33(1)(\sqrt{4000 / 6.683}) = 80.6$ psi



$A_n = 36(36) = 1296$ in²

$\Psi = 0.7 + 0.3(10.25 / 1.5 * 6.83) = 1.0$

C_{crb} (Designed for corner cracking) = 0.8

$N_{cb} = C_{bs} A_n C_{ceb} \Psi_{ed} = 83.6$ Kips < 102.4 OK

Detail of Column Connection to Column Cap



BEAM – HOLLOW CORE CONNECTION

TB-15 : Evenly loaded

$V_u = 5.46$

$N_u = 0.2$

$V_u = 1.09$

$\lambda = 1.0$

$d_e = 4\text{in}$

$d = 11\text{in}$

$b = 12\text{in}$

$b_l = 20\text{in}$

$h = 24\text{in}$

$h_l = 12\text{in}$

$F_y = 60\text{ksi}$

$b_t = 8\text{in}$

$F'_c = 5000\text{psi}$

$s = 48\text{in}$

$d_e = Bt/2 = 4\text{in}$

$S > bt + hl = 16''$

$d_e < 2(b_l - b) + bt + bl = 44''$

Eq: 4.5.1.2 $\phi V_n = \phi \lambda v_f' c h_l [2(b_l - b) + b_t + h_l + 2d_e]$

$0.75 * 1.0 * \sqrt{5000} * 12 [2(20 - 12) + 8 + 1 + 2 * 4] = 21 > 5.46 \text{ OK}$

Shear Span $a = \frac{3}{4}(b_l - b) = \frac{3}{4}(20 - 12) = 6\text{in}$

Flexural Reinforcing : $A_s = 1/\phi f_y [V_u(a/d) + N_u(h/d)]$

$1/(\phi * 60) (5.46(6/11) + 1.09(24/11)) = 0.11 \text{ in}^2$

Spacing = $6h_l > s/2 > 12\text{in}$ [lesser of these 3]

Longitudinal Reinforcing :

Attach ledger to web $A_{sh} = V_u/\phi f_y(m)$

M: Table 2.5.4.1

$h_l/h = 0.5$

$b_l/b = 1.667$

$M = 1.19$

$A_{sh} = [5.48/\phi * 60] 1.19 = 0.145 \text{ in}^2$

$A_l = 200(b_l - b)d_l/f_y = 0.29 \text{ in}^2$

Additional reinforcing due to e:

$V_{ue} = 5.46 * 5 = 27.3$

$A_{wl} = V_{ue}/2\phi f_y D_w = 27.3/2 * \phi * 60 * 10.5 = 0.028 \text{ in}^2$

$A_{wl} = \#3$

USE :

$A_{wv} : \#3$

$A_l : 1-\#3 \text{ top \& 1-\#3 bot}$

$A_{sh} : \#3 \text{ bars @ } 12'' \text{ O.C}$

$A_s : \#3 \text{ Bars @ } 12'' \text{ O.C}$

with 2 additional bars at the beam end to provide reinforcing for stems placed near the end

BEAM TO COLUMN

301: Dapped ends

28IT24

$V_u \leq \Phi V_n$

$V_u = 42.41$ Kips

$N_u = 0.2V_u = 0.2(42.41) = 8.48$ kips

$f'_c = 5000$

$F_y = 60,000$

1. Flexure in extended end

Shear span $a = 6''$ $d = 15''$

$$A_s = 1/\Phi f_y [V_u(a/d) + N_u(h/d)] = 1/.75 * 60 [42.41 * (6/15) + 8.48(24/15)] = \underline{0.62 \text{ in}^2}$$

2. Direct Shear :

$$\mu = 1000 \lambda b h \mu / V_u = 1000 * 1 * 28 * 24 * 1.4 / 42.41 * 1000 = 3.4$$

$$A_s = 2V_u / 3\Phi F_y \mu_e + N_u / \Phi f_y = 0.373 \text{ in}^2 < 0.62 \text{ in}^2$$

$$\underline{A_s: \text{USE} \rightarrow 2 \#4 \text{ } A_s = 0.62 \text{ in}^2}$$

$$A_h = 0.5(A_s - A_n) = 0.5(0.62 - 0.188) = 0.216 \text{ in}^2$$

$$V_{u\text{MAX}} = 1000 \lambda^2 A_c r = 1000(1)(18)(16.75) = 226 \text{ Kips} > 42.41 \text{ OK}$$

$$\underline{A_h: \text{USE} \rightarrow 2 \#4 \text{ } A_h = .4 \text{ in}^2}$$

3. Diagonal tension at re-entrant corner

$$A_{sh} = V_u / \Phi f_y = 0.94 \text{ in}^2$$

$$\underline{A_{sh}: \text{USE} \rightarrow 4 \#5 \text{ } A_{sh} = 1.24 \text{ in}^2}$$

$$\underline{A_{sh}': \text{USE} \rightarrow 5 \#4 \text{ } A_{sh} = 1 \text{ in}^2}$$

4. Diagonal Tension in extended end:

$$\text{Concrete capacity} = 2\lambda \sqrt{f'_c} b d = 55.15 \text{ kips}$$

$$A_v = 1/2 f_y [V_u / \Phi - 2bd\lambda \sqrt{f'_c}] = 0.011 \text{ in}^2$$

USE \rightarrow Stirrup

$$\Phi V_n = \Phi (A_v f_y + A_h f_y + 2\lambda \sqrt{f'_c} b d) =$$

$$\Phi V_n > V_u$$

Anchorage: A_s Design Aid 11.2.9:


$$F_y = 60000 \quad f'_c = 5000 \quad l_d =$$

#5 Bars: $L_d = 21 \text{ in}$

$$A_{sh}' \quad L_d = 17'' \quad \text{Extension} = H - d + l_d = 24 - 14.4 + 17 = 26.6''$$

$$A_s \quad L_d = 17'' \quad \text{Extension} = 26.6''$$

$$A_h \quad L_d = 17'' \quad \text{Ex} = 26.6''$$



Shown above is the typical reinforcing for a dapped end beam from PCI 6th edition. The numbers represent the 5 modes of failure resulting from direct shear and diagonal tension.

Appendix #4

LATERAL CHECK

ETABS

<i>Existing Reinforcing</i>	2
<i>Input</i>	3-5
<i>Output</i>	5-7
<i>Shear Wall Reinforcing Details</i>	7-8

Existing Shear wall reinforcing : A different numbering system was used during my analysis wall numbers on the left is the alternate numbering used for the lateral check.

LEVEL		WALL #1					WALL #2					WALL #3					WALL #4								
		V	H	M	TICS (SIZE/ARRANGEMENT #)	TICS (SIZE/ARRANGEMENT #)	V	H	M	TICS (SIZE/ARRANGEMENT #)	TICS (SIZE/ARRANGEMENT #)	V	H	M	TICS (SIZE/ARRANGEMENT #)	TICS (SIZE/ARRANGEMENT #)	V	H	M	TICS (SIZE/ARRANGEMENT #)	TICS (SIZE/ARRANGEMENT #)				
7th FLOOR	ELEV. WACHIM DUL	#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1
6th FLOOR		#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1
5th FLOOR		#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1
4th FLOOR		#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1
3rd FLOOR		#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1
2nd FLOOR		#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1
1ST FLOOR		#4012"	#4012"	5#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	10#6	#3/ARRANGEMENT #2	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1	#4012"	#4012"	8#6	#3/ARRANGEMENT #1

Wall # 1

Wall #3

Wall #2

Wall #4

INPUT

Additional Mass: was added to each diaphragm to account for the planks, beams, topping, and partitions = $(22377.84/11)/386)15405*12 = \underline{4.6E-6}$

F22 : Was changed from 1 to 0.5 for the concrete in the shear walls to account for the cracked section

P-Delta : affects were included in the analysis with a non-iterative (mass based) method

Dynamic analysis: was also included considering all 12 modes.




Figure #1: A snapshot of a typical floor that was input into E-Tabs for analysis

Load Combinations (Strength): The following load combinations were put into E-Tabs to determine reinforcing in all shear walls.

#1 : 1.4D

#2: 1.2D + 1.6L + 0.5S

#3: 1.2D + 1.6S + 0.8W

#4: 1.2D + 1.6W + L + 0.5S

#5: $(1.2+0.2S_{ds})D + \rho E + L + 0.2S$

#6: 0.9D + 1.6W + 1.6H

#7: $(0.9 - 0.2S_{ds})D + \rho E + 1.6H$

$$\rho = 1.0$$


$$S_{ds} = 0.163$$

(50) Load Combinations Inputted into E-Tabs once all combos were considered

- | | |
|--------------------------------------|--|
| 1. 1.4D | |
| 2. 1.2D + 1.6L + 0.5S | |
| 3. 1.2D + 1.6S + 0.8 Wind | |
| 4. 1.2D + 1.6S + 0.8 Wind2 | |
| 5. 1.2D + 1.6S + 0.8 Wind3 | |
| 6. 1.2D + 1.6S + 0.8 Wind4 | |
| 7. 1.2D + 1.6S + 0.8 Wind5 | |
| 8. 1.2D + 1.6S + 0.8 Wind6 | |
| 9. 1.2D + 1.6S + 0.8 Wind 7 | |
| 10. 1.2D + 1.6S + 0.8 Wind 8 | |
| 11. 1.2D + 1.6S + 0.8 Wind 9 | |
| 12. 1.2D + 1.6S + 0.8 Wind 10 | |
| 13. 1.2D + 1.6S + 0.8 Wind 11 | |
| 14. 1.2D + 1.6S + 0.8 Wind 12 | |
| 15. 1.2D + 1.6Wind + L + 0.5S | |
| 16. 1.2D + 1.6Wind2 + L + 0.5S | |
| 17. 1.2D + 1.6Wind3 + L + 0.5S | |
| 18. 1.2D + 1.6Wind4 + L + 0.5S | |
| 19. 1.2D + 1.6Wind5 + L + 0.5S | |
| 20. 1.2D + 1.6Wind6 + L + 0.5S | |
| 21. 1.2D + 1.6Wind7 + L + 0.5S | |
| 22. 1.2D + 1.6Wind8 + L + 0.5S | |
| 23. 1.2D + 1.6Wind9 + L + 0.5S | |
| 24. 1.2D + 1.6Wind10 + L + 0.5S | |
| 25. 1.2D + 1.6Wind11 + L + 0.5S | |
| 26. 1.2D + 1.6Wind12 + L + 0.5S | |
| 27. 1.233D + 1.0QuakeX + L + 0.2S | |
| 28. 1.233D + 1.0QuakeY + L + 0.2S | |
| 29. 1.233D + 1.0QuakeXeY + L + 0.2S | |
| 30. 1.233D+ 1.0QuakeXenY + L + 0.2S | |
| 31. 1.233D + 1.0QuakeYeX + L + 0.2S | |
| 32. 1.233D + 1.0QuakeYenX + L + 0.2S | |
| 33. 0.9D + 1.6Wind | |
| 34. 0.9D + 1.6Wind 2 | |
| 35. 0.9D + 1.6Wind 3 | |
| 36. 0.9D + 1.6Wind 4 | |
| 37. 0.9D + 1.6Wind 5 | |
| 38. 0.9D + 1.6Wind 6 | |
| 39. 0.9D + 1.6Wind 7 | |
| 40. 0.9D + 1.6Wind 8 | |
| 41. 0.9D + 1.6Wind 9 | |
| 42. 0.9D + 1.6Wind 10 | |
| 43. 0.9D + 1.6Wind 11 | |
| 44. 0.9D + 1.6Wind 12 | |
| 45. 0.867D +1.0 Quake X | |
| 46. 0.867D + 1.0 Quake Y | |
| 47. 0.867D + 1.0 Quake XeY | |
| 48. 0.867D+ 1.0 Quake XenY | |
| 49. 0.867D + 1.0 Quake YeX | |
| 50. 0.867D + 1.0 Quake YenX | |

WIND: Because seismic controls wind values were calculated in E-Tabs

E1 = 0.15(108)
E2 = 0.15(179)



SEISMIC: Was calculated as seen in **appendix #1** and then input by hand for each of the 6 cases.

OUTPUT

Controlling Combination:

Combo 50 = 0.867D+1.0Quake Y (-) X eccentricity : Controls in Flexure

Combo 48 = 0.0867D + 1.0 Quake Y(-)X eccentricity : Controls in Flexure and Shear

Combo 30 = 1.22D +1.0L +1.0 Quake X (-) Y eccentricity: Controls in Shear




Figure #2: Deformed shape after analysis of seismic displacement in the X direction.

Wall #1 Output: (Units Kip-in)

Uniform Reinforcing Pier Section - Design (UBC97)							
Story ID: STORY1 Pier ID: SHEAR1 X Loc: 44.66667 Y Loc: 35.33333 Units: Kip-ft							
Flexural Design for P-M2-M3 (RLLF = 1.000)							
Station	Required	Current	Flexural	Pu	M2u	M3u	Pier
Location	Reinf Ratio	Reinf Ratio	Combo				Ag
Top	0.0025	0.0047	COMB14	143.046	0.000	0.000	11.000
Bottom	0.0034	0.0047	COMB12	162.274	0.000	2035.736	11.000
Shear Design							
Station	Rebar	Shear	Pu	Mu	Vu	Capacity	Capacity
Location	in^2/ft	Combo				phi Vc	phi Vn
Top Leg 1	0.360	COMB12	143.046	1177.897	63.819	100.970	215.018
Bot Leg 1	0.360	COMB12	162.274	2035.736	63.819	66.752	180.800
Boundary Element Check							
Station	B-Zone	B-Zone	Pu	Mu	Vu	Pu/Po	
Location	Length	Combo					
Top Leg 1	Not Needed	COMB8	203.432	0.000	0.000	0.0293	
Bot Leg 1	Not Needed	COMB8	230.777	0.000	0.000	0.0328	

Values input into PCA column for flexural check


Wall #2&4 Output: (Units Kip-in)

Uniform Reinforcing Pier Section - Design (UBC97)							
Story ID: STORY2 Pier ID: SHEAR2 X Loc: 470 Y Loc: 1655 Units: Kip-in							
Flexural Design for P-M2-M3 (RLLF = 1.000)							
Station	Required	Current	Flexural	Pu	M2u	M3u	Pier
Location	Reinf Ratio	Reinf Ratio	Combo				Ag
Top	0.0165	0.0035	COMB14	-1026.284	0.000	75371.383	2489.763
Bottom	0.0198	0.0035	COMB14	-1180.360	0.000	93602.479	2489.763
Shear Design							
Station	Rebar	Shear	Pu	Mu	Vu	Capacity	Capacity
Location	in^2/ft	Combo				phi Vc	phi Vn
Top Leg 1	0.562	COMB14	-1026.284	75371.383	266.690	56.123	266.690
Bot Leg 1	0.589	COMB14	-1180.360	93602.479	266.690	46.313	266.690
Boundary Element Check							
Station	B-Zone	B-Zone	Pu	Mu	Vu	Pu/Po	
Location	Length	Combo					
Top Leg 1	Not Needed	COMB14	-1026.284	75371.383	266.690	0.0797	
Bot Leg 1	Not Needed	COMB14	-1180.360	93602.479	266.690	0.0886	

Wall #3 Output: (Unit Kip-in)


Uniform Reinforcing Pier Section - Design (UBC97)							
Story ID: STORY1 Pier ID: SHEAR3 X Loc: 48.16667 Y Loc: 144.4167 Units: Kip-ft							
Flexural Design for P-M2-M3 (RLLF = 1.000)							
Station Location	Required Reinf Ratio	Current Reinf Ratio	Flexural Combo	Pu	M2u	M3u	Pier Ag
Top	0.0033	0.0045	COMB12	234.037	0.000	5070.183	18.000
Bottom	0.0051	0.0045	COMB12	264.572	0.000	7144.829	18.000
Shear Design							
Station Location	Rebar in ² /ft	Shear Combo	Pu	Mu	Vu	Capacity phi Vc	Capacity phi Vn
Top Leg 1	0.360	COMB12	234.037	5070.183	400.288	219.938	453.218
Bot Leg 1	0.360	COMB12	264.572	7144.829	400.288	219.938	453.218
Boundary Element Check							
Station Location	B-Zone Length	B-Zone Combo	Pu	Mu	Vu	Pu/Po	
Top Leg 1	4.115	COMB8	3530.436	0.000	0.000	0.3072	
Bot Leg 1	4.445	COMB8	4040.927	0.000	0.000	0.3439	

REINFORCING DETAILS



TIE ARRANGEMENT #1 (8 BARS)

(TYPICAL AT EACH END)



TIE ARRANGEMENT #2 (10 BARS)


(TYPICAL AT EACH END)

NOTE:
SEE SHEAR WALL SCHEDULES FOR SIZE OF TIES AND
LOCATION OF TIE ARRANGEMENTS.

TYPICAL TIE ARRANGEMENT DETAILS

SCALE: 3/4" = 1'-0"






NOTES:

1. SEE KEY PLANS FOR SHEAR WALL DESIGNATION NUMBERS.
2. PROVIDE CORNER BARS WITH CLASS "B" SPLICES TO MATCH "H" BARS SHOWN ON SCHEDULE.
3. WHERE POSSIBLE, EXTEND "H" HORIZ. BARS INTO ADJACENT PERPENDICULAR WALL AND HOOK.
4. SEE SHEAR WALL SCHEDULES FOR FURTHER INFORMATION.

TYPICAL SHEAR WALL DETAIL

SCALE: 3/4" = 1'-0"

1
2-S2.01



TYPICAL CORNER DETAIL

SCALE: 3/4" = 1'-0"

3
2-S2.01