

AE 481W

Technical Assignment 2: Cost and Schedule Analysis



Jonathan Revtai
Construction Management
Consultant: Dr. Riley
Bakery Square – Building 1
10/24/2008



**JONATHAN
REVTAI**
CONSTRUCTION
MANAGEMENT

PROJECT SIZE
378,000 SF
PROJECT COST
\$24 MILLION
START DATE
03.17.2008
END DATE
05.21.2009
DELIVERY METHOD
CM AT RISK

BUILDING 1 AT BAKERY SQUARE

P OWNER/ DEVELOPER
R BAKERY SQUARE
O HOLDINGS, L.P.
J ARCHITECT
E ASTORINO
C CM AT RISK
T P.J. DICK INC.
E
A
M

BUILDING 1 IS PART OF THE BAKERY SQUARE PROJECT BUILT AROUND THE RENOVATION OF THE 1918 NABISCO FACTORY. THIS FACILITY INCLUDES RETAIL SPACES, A FITNESS CENTER, RESTAURANTS, AND A PARKING GARAGE. THE PARKING GARAGE STRUCTURE IS BUILT AROUND ALL OF THE OTHER SPACES INCLUDING A CAST-IN-PLACE SWIMMING POOL ON LEVEL TWO. FACADE FINISHES WILL BE PROVIDED DURING FIT OUT, AND HAVE NOT BEEN FINALIZED.

PITTSBURGH, PA

MEP

ROOF TOP UNITS ARE USED TO CONDITION THE RETAIL FITNESS SPACES, WHILE WALL UNITS ARE USED IN THE PARKING GARAGE SECTION. PLUMBING IS LIMITED TO BATHROOMS

WWW.ENGR.PSU.EDU/AE/THESIS/PORTFOLIOS/2009/JAR5015

ELECTRICAL

THE FITNESS CENTER IS FED BY A SEPARATE SWITCH BOARD FROM THE REST OF THE BUILDING. THE FEED TO EACH SWITCHBOARD IS A 3 PHASE, 480 V CONNECTION.

STRUCTURAL

PRECAST CONCRETE IS USED FOR MOST OF THE SUPERSTRUCTURE. STRUCTURAL STEEL IS USED FOR AN OUTSIDE BRIDGE, AND A HANGING MEZZANINE IN THE FITNESS CENTER. THE FOUNDATIONS ARE BUILT WITH AUGER CAST PILES.



EXECUTIVE SUMMARY

The detailed construction schedule produced for Technical Assignment II shows activities by trade. The schedule is sorted into each category. The schedule runs from March 24, 2008 to August 31, 2009. The parking garage is to be completed by May 21, 2009. The fit-out for the fitness center extends the schedule into the end of August.

Site layout planning has made key issues apparent. Underground utilities are not an obstruction, but overhead electrical lines could interfere with the crane's swing path. Vehicular movement and parking is relocated several times due to changing site conditions and the ongoing renovation of Building #3. The precast storage compartments and office trailer must be moved during precast erection. This problem could be fixed by locating their trailers east of the building to avoid interfering with the path of the crane. Office trailers will need to be placed onsite when Building #3 renovation is completed.

The result of the detailed structural estimate for Building #1 is a square foot cost of \$27.87. This can be broken down into square foot material, labor, and equipment costs of \$17.75, \$4.39, and \$0.99 respectively. The overall structural cost was calculated to be \$10,665,120. Cost breakdown were found to be material costs of \$6,793,727, labor costs of \$1,678,740, and equipment costs \$378,643 respectively. A similar building assembly estimate from R.S. Means would cost \$24.45/ SF. This might be a little low because of the special items in Building #1 such as the elevated CIP pool, the hanging steel mezzanine, and the combination of such a diverse structural system.

Calculation of the general conditions estimate for Building #1 resulted in a total cost \$923,250. This is roughly 3.5% of the \$24,000,000 GMP set for Building #1. The number may be a little lower than expected because P.J. Dick is constructing four other buildings on the Bakery Square site.

By attending the PACE seminar, I was able to better understand the state of the industry when it comes to BIM. I plan on focusing my research in that area and made contact with Jason, Coleman, and Dragana for that purpose.

Table of Contents

Executive Summary.....	1
Detailed Project Schedule	3
Site Layout Planning	7
Excavation Phase	7
Superstructure Phase	8
Finishes Phase	8
Detailed Structural Systems Estimate.....	13
General Conditions Estimate	15
Critical Industry Issues.....	17
MEP Coordination	17
Document Control	17
File-Sharing	17
PACE Reflection	17
Appendix A.....	19
Appendix B.....	30
• Table 1 - Building 1 - Project Milestones	3
• Table 2 - Building 1 - Critical Phase Issues	7
• Table 3 - Takeoff Assumptions	13
• Table 4 - Estimate Assumptions.....	13
• Table 5 - Cost Breakdown.....	14
• Table 6 - Square Foot Estimate	14
• Table 7 - General Conditions Estimate	16
• Table 8 - BIM Breakout Recap	17
• Table 9 - Key Contacts	18
• Figure 1 - Detailed Construction Schedule	4
• Figure 2 - Excavation Snapshot	7
• Figure 3 - Superstructure Snapshot.....	8
• Figure 4 - Finishes Snapshot	9
• Figure 5 - Site Plan – Excavation Phase	10
• Figure 6 - Site Plan - Superstructure Phase	11
• Figure 7 - Site Plan - Finishes Phase.....	12

DETAILED PROJECT SCHEDULE

A detailed construction schedule has been developed from the summary schedule to show activities that reflect the actual construction of Building 1 at Bakery Square. Important phasing includes the foundation and underground work, bridge construction, finishes, and the precast sequencing that starts at the West end of the building and moves east in three stages. Milestone events have also been included in the schedule.

Building 1 - Project Milestones		
Description	Early Start	Early Finish
Start Precast Erection	July 16, 2008	
Precast Seq. 1 Complete		October 3, 2008
Precast Seq. 2 Complete		November 21, 2008
Precast Seq. 3 Complete		January 6, 2009
Install Permanent Power		March 4, 2009
Building Enclosure		February 3, 2009
Parking Garage Complete		May 21, 2008

• Table 1 - Building 1 - Project Milestones

Each construction phase has been broken down further into activities that were grouped into areas assigned to different trades. Precast erection, CIP concrete, masonry, and steel are some examples of trade categories.

Activity ID	Activity Name	Original Duration	Remaining Duration	Schedule % Complete	Start	Finish	Total Float	2008												2009						
								Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May					
Bakery Square - Building #1								376																		
001	Start Precast Erection West to East	0	0	100%	16-Jul-08		0	◆ Start Precast Erection West to East																		
002	Precast Sequence 1 - West Complete	0	0	100%		03-Oct-08		◆ Precast Sequence 1 - West Complete																		
003	Deliver W30 & W33 Beams	0	0	100%	22-Oct-08			◆ Deliver W30 & W33 Beams																		
004	Precast Squence 2 - Center Complete	0	0	0%		21-Nov-08		◆ Precast Squence 2 - Center Complete																		
005	Precast Sequence 3 - East Complete	0	0	0%		06-Jan-09		◆ Precast Sequence 3 - East Complete																		
006	Install Permanent Power to Building 1	30	30	0%	22-Jan-09	04-Mar-09		Install Permanent Power to Building 1																		
007	Urban Active Fit-out	130	130	0%	03-Mar-09	31-Aug-09																				
008	Parking Garage Complete	0	0	0%		21-May-09		◆																		
Foundations								88																		
013	Test Piles	8	8	100%	24-Mar-08	02-Apr-08		Test Piles																		
014	Auger Cast Piles - Bridge	2	2	100%	18-Apr-08	21-Apr-08		Auger Cast Piles - Bridge																		
015	Pile Caps - Bridge	1	1	100%	12-May-08	12-May-08		Pile Caps - Bridge																		
Foundations - West								66																		
023	Auger Cast Piles - West	20	20	100%	23-Apr-08	20-May-08		Auger Cast Piles - West																		
024	Pile Caps - West	35	35	100%	05-May-08	20-Jun-08		Pile Caps - West																		
025	Grade Beams - West	35	35	100%	05-Jun-08	23-Jul-08		Grade Beams - West																		
026	Foundation Walls @ L2 Line	3	3	100%	09-Jun-08	11-Jun-08		Foundation Walls @ L2 Line																		
027	Foundation Walls @ J2 Line	4	4	100%	16-Jun-08	19-Jun-08		Foundation Walls @ J2 Line																		
028	Foundation Walls @ 7.6 Line	6	6	100%	23-Jun-08	30-Jun-08		Foundation Walls @ 7.6 Line																		
029	Foundation Walls @ Elevator 2	2	2	100%	25-Jun-08	26-Jun-08		Foundation Walls @ Elevator 2																		
Foundations - Center								72																		
020	Auger Cast Piles - Center	35	35	100%	01-Apr-08	09-Jul-08		Auger Cast Piles - Center																		
021	Pile Caps - Center	35	35	100%	21-Apr-08	06-Jun-08		Pile Caps - Center																		
022	Grade Beams - Center	35	35	100%	22-May-08	09-Jul-08		Grade Beams - Center																		
Foundations - East								56																		
016	Auger Cast Piles - East	20	20	100%	27-Mar-08	23-Apr-08		Auger Cast Piles - East																		
017	Pile Caps - East	30	30	100%	14-Apr-08	23-May-08		Pile Caps - East																		
018	Grade Beams - East	30	30	100%	02-May-08	12-Jun-08		Grade Beams - East																		
019	Foundation Walls @ Elevator 1 - East	2	2	100%	13-May-08	14-May-08		Foundation Walls @ Elevator 1 - East																		
Site								110																		
009	Bulk Excavation	10	10	100%	25-Mar-08	07-Apr-08		Bulk Excavation																		
010	Rough Grade Site	30	30	100%	15-Jul-08	25-Aug-08		Rough Grade Site																		
011	Stone Base - Center	5	5	100%	28-Jul-08	01-Aug-08		Stone Base - Center																		
012	Stone Base - East	5	5	100%	04-Aug-08	08-Aug-08		Stone Base - East																		
CIP Concrete								221																		
0030	RFP Pool Columns	7	7	100%	19-May-08	27-May-08		RFP Pool Columns																		
031	Concrete Pool Slab	3	3	100%	17-Jun-08	19-Jun-08		Concrete Pool Slab																		
032	Column - Bridge	6	6	100%	23-Jun-08	30-Jun-08		Column - Bridge																		
033	Bumper Walls - West	3	3	100%	02-Jul-08	04-Jul-08		Bumper Walls - West																		
034	Pool Walls West	7	7	100%	10-Jul-08	18-Jul-08		Pool Walls West																		
035	CIP Walls @ Speedramp - East	7	7	100%	10-Jul-08	18-Jul-08		CIP Walls @ Speedramp - East																		
036	Prep & SOG - West	5	5	100%	06-Oct-08	10-Oct-08		Prep & SOG - West																		
037	Washes & Pour Strips - West	13	13	100%	06-Oct-08	22-Oct-08		Washes & Pour Strips - West																		
038	Washes & Pour Strips - Center	6	6	0%	24-Dec-08	31-Dec-08		Washes & Pour Strips - Center																		
039	Washes & Pour Strips - East	6	6	0%	07-Jan-09	14-Jan-09		Washes & Pour Strips - East																		
040	Topping Slab Lvl 2	5	5	0%	14-Jan-09	20-Jan-09		Topping Slab Lvl 2																		
041	Composite Slab Lvl 2	5	5	0%	14-Jan-09	20-Jan-09		Composite Slab Lvl 2																		
042	Prep & SOG - Stair Twrs & Mech Rms - East	5	5	0%	16-Jan-09	22-Jan-09		Prep & SOG - Stair Twrs & Mech Rms - East																		
043	Topping Slab @ Lvl 4	5	5	0%	22-Jan-09	28-Jan-09		Topping Slab @ Lvl 4																		
044	Composite Slab @ Lvl 4	5	5	0%	22-Jan-09	28-Jan-09		Composite Slab @ Lvl 4																		
045	Pavement @ Access Drive	5	5	0%	17-Mar-09	23-Mar-09		Pavement @ Access Drive																		
Precast								128																		
050	Mobilize Precast Crane	5	5	100%	09-Jul-08	15-Jul-08		Mobilize Precast Crane																		
Precast - West								58																		
051	Erect Precast Stair 5 - West	5	5	100%	16-Jul-08	22-Jul-08		Erect Precast Stair 5 - West																		
052	Erect Precast Bay 15 - 14.1 - West	8	8	100%	23-Jul-08	01-Aug-08		Erect Precast Bay 15 - 14.1 - West																		
053	Erect Precast Bay 14.1 - 13.6 - West	7	7	100%	04-Aug-08	12-Aug-08		Erect Precast Bay 14.1 - 13.6 - West																		

█ Actual Work
 █ Critical Remaining Work
 Summary
█ Remaining Work
 ◆ Milestone

SITE LAYOUT PLANNING


Three separate site layout plans were developed from the Existing Conditions Site Plan. Each plan describes a critical phase of the project in more detail. Excavation, Superstructure, and Finish phase site plans were constructed because these were the three most important areas of interest. Below are the critical issues for each phase.

Building 1 – Critical Phase Issues		
Excavation	Superstructure	Finishes
Existing Utilities	Crawler Crane	Material Hoist
Railroad Tracks	Overhead Electrical	Building #2
Adjacent Buildings	Material Storage	
P.J. Dick Site Office		Trailers
Truck Path		
Parking Area		
Dumpsters		

• Table 2 - Building 1 - Critical Phase Issues

Excavation Phase

During the excavation phase of the project, major concerns are efficiency and underground obstructions. A circular path was established onsite to allow trucks easy access to, from, and around the site.




• Figure 2 - Excavation Snapshot

Underground utilities were not a concern for the contractor because all lines are run outside of the property line. Existing railroad tracks were buried onsite, but the exact location of the rails was unknown. Foundations for Building #1 lock into the existing foundations for Building #3, and great care must

be taken while excavating around them. The contractor's office was located inside Building #3 because of their concurrent renovation work on that building. This eliminated the need for an office trailer onsite.

Superstructure Phase

Crane movement and usage is the most critical issue for the superstructure phase. A Manitowoc 999 crane started erection at the West end of the building and will work east to complete the structure. Overhead power lines have been tagged and must be watched while erected the West Garage. The path for vehicular movement was altered to avoid foundations and allow longer trailers an easy path through the site. The precast subcontractor's storage containers and office trailer were placed within the footprint of Building #1. They are not currently in the crane's path, but they will have to be moved in order to continue erection on the center portion of the building. A better location for the trailers might have been at the east end of the site next to the material storage location. Parking has been moved because site grading must occur at the east end of Building #3.




• Figure 3 - Superstructure Snapshot


Finishes Phase

Work paths and efficiencies are again key issues for the finishes phase. Two material hoists will be erected. They will primarily be used to install the elevators and the infill steel around them, but while in place they can be used to lift materials

up to the upper levels of the building. Since renovation work on Building #3 will be complete at this point, office trailers will need to be used and dumpsters will be moved closer to Building #1.



• Figure 4 - Finishes Snapshot



Legend

- Electrical (Orange line)
- Gas (Yellow line)
- Water (Blue line)
- Dumpster (Green rectangle)
- Gang Box (Grey rectangle)
- Utility Pole (Black dot)
- Porta-John (White rectangle with black outline)


Autodesk® Revit®

www.autodesk.com/revit

Jonathan Revtai
Building #1

No.	Description	Date

Site Plan - Excavation Phase		
Project number	Tech Report I	C102
Date	10/23/08	
Drawn by	Revtai	Scale 1" = 50'-0"
Checked by	Revtai	



Autodesk® Revit®

www.autodesk.com/revit


Jonathan Revtai
Building #1

No.	Description	Date

Site Plan - Superstructure Phase

Project number	Tech Report I
Date	10/23/08
Drawn by	Revtai
Checked by	Revtai

C103
Scale 1" = 50'-0"



Autodesk® Revit®

www.autodesk.com/revit

Jonathan Revtai
Building #1

No.	Description	Date

Site Plan - Finish Phase		
Project number	Tech Report I	C104
Date	10/23/08	
Drawn by	Revta	
Checked by	Revta	
Scale		1" = 50'-0"

DETAILED STRUCTURAL SYSTEMS ESTIMATE

Structural system costs were calculated for the detailed systems estimate. This system was divided into four separate parts of work including foundations, typical precast bays, typical steel bays, and non-typical items.

Takeoff Assumptions	
Foundations	Auger Cast Piles were bored to an average depth of 32'
	A singular 10' long #8 bar reinforces each pile
	Plywood forms are used 4 times
	10% waste included
Typical Precast	Columns bisected by grid line count as 1/2
	Interior Lite Walls are considered T-Beams
	10% waste included on non-precast items
Typical Steel	Columns bisected by grid line count as 1/2
	Beams bisected by grid line count as 1/2
	13% waste included
Non-Typical	Plywood forms are used 4 times
	Steel grouped into similar sizes
	Plywood forms - columns used 4 times, 1 time for all else
	13% waste included for steel
	10% waste included for all else

• Table 3 - Takeoff Assumptions

Cost data was gathered from R.S. Means and from there calculations were made to find the cost per each of the sections mentioned above. Estimate assumptions were tailored specifically for Building #1.

Estimate Assumptions	
Location	Pittsburgh, Pennsylvania 15206
Cost Book	Commercial New Construction
Labor Type	Standard Union
Data Release	Year 2008 Quarter 1
Sub Markup	5%
GC O&P	4%

• Table 4 - Estimate Assumptions

Cost Break Down					
Description	Area (SF)	Material Cost	Labor Cost	Equipment Cost	Total Cost
Foundation	57,394	2,640,568	1,277,868	199,817	5,206,041
Precast	295,695	3,355,066	291,820	152,646	4,369,651
Steel	10,277	264,134	22,793	11,053	341,558
Non-Typical	19,321	533,959	86,258	15,127	747,869
Total	382,688	6,793,727	1,678,740	378,643	10,665,120

• Table 5 - Cost Breakdown

Square Foot Estimate			
Material Cost/SF	Labor Cost/SF	Equipment Cost/SF	Total Cost/SF
\$ 17.75	\$ 4.39	\$ 0.99	\$ 27.87

• Table 6 - Square Foot Estimate

For more estimate information see **Appendix A**.

GENERAL CONDITIONS ESTIMATE

The general conditions estimate is based on a general contractor with a 4% fee. Adjustments were made for the percent of time involved in on this project that has an overall duration of 14 months. Overall General Condition cost equal \$923,250. Based on a \$24,000,000 jobs this comes out to be about 3.5% of the total. This may be a little lower than expected because many of these items are shared with Building #3. Since P.J. Dick is hired to construct 5 building at Bakery Square they are able to save money in the general conditions portion of their price. See table on next page.

General Conditions Estimate			
Item	Description	Duration	Cost
010020	Mobilization	1 time	\$110,200
010010	Demobilization	1 time	\$ 4,300
011002	Senior Project Manager	7 months (50%)	\$84,200
011004	Superintendent	14 months	\$146,700
011013	Project Engineer	14 months	\$68,100
011018	Safety Engineer	3 months (20%)	\$12,600
011021	Secretary	7 months (50%)	\$ 31,100
011030	PX	3 months (20%)	\$40,000
011031	Intern	6 months	\$25,000
012300	Permits	1 time	\$ 83,400
012400	Accounting	-	\$ 18,000
013000	Survey/Layout	14 months	\$25,500
015000	Office	14 months	\$21,500
015100	Field Communication	14 months	\$44,000
015200	Office Equipment	14 months	\$4,750
015310	Job Office Supplies	14 months	\$2,400
015320	Overnight Mail & Postage	14 months	\$2,900
016000	Utilities	14 months	\$53,200
016200	Winter Protection	3 months	\$6,250
016300	Temp Heat	3 months	\$16,000
017000	Safety	14 months	\$3,100
018000	Clean up	14 months	\$67,500
018500	Dumpsters	14 months	\$19,500
019010	Small Tools	14 months	\$4,250
019020	Photographs	14 months	\$700
019030	Project Signs	14 months	\$600
019040	Plans and Specs	1 time	\$10,000
019060	Parking	14 months	\$2,000
019100	Temp. Fence & Gates	14 months	\$13,000
019170	Snow Removal	3 months	\$2,500
Total			\$923,250

• Table 7 - General Conditions Estimate

For more general conditions information see **Appendix B**.

CRITICAL INDUSTRY ISSUES

I attended the Building Information Modeling (BIM) breakout session during the PACE Roundtable Meeting. The main topic of discussion was the implementation of BIM on the project and organizational level. Key issues such as document control, 3-D MEP coordination, file-sharing, software, process, and training were discussed.

MEP Coordination

MEP Coordination was the first topic and is considered by most to be a “low-hanging fruit” that most companies start to pursue when implementing BIM.

Document Control

From there the conversation headed toward document control and what needed to be done in order to safely implement BIM. Possible solutions for security integrity included Constructware, an online database, improved technical departments, and the ability to lock or checkout files.

File-Sharing

Problems often occur during file-sharing due to lack of a central file type. This issue was brought up and questions were asked about an Industry Foundation Classes (IFC) file type. A universal file type such as IFC would allow data to be transferred more accurately between software programs.

BIM Breakout Recap
BIM – Information in a model is the new goal
Most companies should start with a pilot project
Information transfer is complicated between programs
An execution strategy should be implemented
A Design-Build delivery system works best at this time
Modeler should consider design intent and subcontractor involvement

• Table 8 - BIM Breakout Recap

PACE Reflection

It surprised me how little the industry members knew about BIM. I thought that I was quite inexperienced about the topic, but during the discussion I realized that the professionals attending the session were there hoping to learn how to implement the program.

A couple of issues could possibly be applied to my project. 3-D MEP coordination would be helpful on a small scale for the underground utilities being installed for Building #1. An investigation of document control could also be administered for Building #1 because P.J. Dick is already using Constructware. Training and implementation process could also be investigated because P.J. Dick is just starting to use BIM for their jobs.

Key Contacts		
Contact	Affiliation	Reason
Coleman Walker	Haskell	Very interested in BIM – Haskell is a design/build firm which is very well suited for BIM
Jason Reece	Balfour Beatty	Has had much experience in implementing BIM – especially in area of 3-D coordination
Dragana Nikolic	Penn State	Involved in CIC research

• Table 9 - Key Contacts

APPENDIX A

Detailed Estimate Information

Building 1 Foundation

Unit Cost Estimate

**6425 Penn Ave.
Pittsburgh PA 15206**

Data Release : Year 2008 Quarter 1

Quantity	Unit	LineNumber	Description	Ext. Mat. O&P	Ext. Labor O&P	Ext. Equip. O&P	Ext. Total O&P
15858	V.L.F.	024551000085	Uncased drilled concrete piers, cast in place augered piles, 18" diameter, priced using 200 piles, 60' long, unless specified otherwise, excludes pile caps or mobilization, casing or reinforcing	\$ 329,687.82	\$ 186,172.92	\$ 210,435.66	\$ 726,296.40
12816	Lb.	024551001500	Cast-in place adds for drilled concrete piers, for reinforcing, 4000 psi concrete, 7 ga.	\$ 13,072.32	\$ -	\$ -	\$ 13,072.32
1418	C.Y.	033102200150	Structural concrete, ready mix, normal weight, 3000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments	\$ 151,612.56	\$ -	\$ -	\$ 151,612.56
379	C.Y.	033107004050	Structural concrete, placing, pile caps, over 10 CY, includes vibrating, excludes material	\$ -	\$ 4,737.50	\$ 1,546.32	\$ 6,283.82
379	C.Y.	033102200150	Structural concrete, ready mix, normal weight, 3000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments	\$ 40,522.68	\$ -	\$ -	\$ 40,522.68
1418	C.Y.	033107003250	Structural concrete, placing, grade beam, pumped, includes vibrating, excludes material	\$ -	\$ 23,552.98	\$ 7,699.74	\$ 31,252.72
1.65	Ton	032106000500	Reinforcing steel, in place, footings, #4 to #7, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 1,581.41	\$ 1,928.07	\$ -	\$ 3,509.48

2544	Ton	032106000550	Reinforcing steel, in place, footings, #8 to #18, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 2,313,208.32	\$ 1,728,342.72	\$ -	\$ 4,041,551.04
11727	SFCA	031104303150	C.I.P. concrete forms, pile cap, square or rectangular, plywood, 4 use, includes erecting, bracing, stripping and cleaning	\$ 11,375.19	\$ 53,357.85	\$ -	\$ 64,733.04
3069	SFCA	031104304150	C.I.P. concrete forms, pile cap, triangular or hexagonal plywood, 4 use, includes erecting, bracing, stripping and cleaning	\$ 3,467.97	\$ 16,940.88	\$ -	\$ 20,408.85
4.86	Ton	032106000100	Reinforcing steel, in place, beams and girders, #3 to #7, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 4,896.84	\$ 7,395.95	\$ -	\$ 12,292.79
29.95	Ton	032106000150	Reinforcing steel, in place, beams and girders, #8 to # 18, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 30,177.02	\$ 27,184.12	\$ -	\$ 57,361.14
6943	SFCA	031104350150	C.I.P. concrete forms, grade beam, plywood, 4 use, includes erecting, bracing, stripping and cleaning	\$ 6,387.56	\$ 30,757.49	\$ -	\$ 37,145.05

Total

\$ 2,905,989.69 \$ 2,080,370.48 \$ 219,681.72 \$ 5,206,041.89

Typical Garage Bay - 1 Level

Unit Cost Estimate

6425 Penn Ave.
Pittsburgh PA, 15206

Data Release : Year 2008 Quarter 1

Quantity	Unit	LineNumber	Description	Ext. Mat. O&P	Ext. Labor O&P	Ext. Equip. O&P	Ext. Total O&P
64	L.F.	034102100300	Precast column, small, square, to 24' high, 3000 psi, includes material only	\$ 3,294.72	\$ 2,268.80	\$ 791.04	\$ 6,354.56
4216	S.F.	034107500200	Precast tees, double, floor, 60' span, prestressed	\$ 37,564.56	\$ 3,414.96	\$ 1,222.64	\$42,202.16
2	Ea.	034101000250	Precast beam, L shaped, 40' span, 24" x 52", includes material only	\$ 6,682.50	\$ 850.74	\$ 297.44	\$ 7,830.68
1	Ea.	034101002300	Precast beam, tee shaped, 30' span, 24" x 52", includes material only	\$ 4,182.75	\$ 425.37	\$ 148.72	\$ 4,756.84
5.3	C.Y.	033102200460	Structural concrete, ready mix, normal weight, high early, 3000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments	\$ 597.58	\$ -	\$ -	\$ 597.58
0.16	Ton	032106000400	Reinforcing steel, in place, elevated slabs, #4 to #7, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 173.01	\$ 135.66	\$ -	\$ 308.67
3.93	C.S.F.	032202000300	Welded wire fabric, sheets, 6 x 6 - W2.9 x W2.9 (6 x 6) 42 lb. per C.S.F., A185	\$ 85.01	\$ 166.59	\$ -	\$ 251.60
Total				\$ 52,580.13	\$ 7,262.12	\$ 2,459.84	\$62,302.09

Typical Steel Bay

Unit Cost Estimate

6425 Penn Ave.
Pittsburgh PA, 15206

Data Release : Year 2008 Quarter 1

Quantity	Unit	LineNumber	Description	Ext. Mat. O&P	Ext. Labor O&P	Ext. Equip. O&P	Ext. Total O&P
46.33	L.F.	051202607050	Column, structural, 2-tier, W10x68, A992 steel, incl shop primer, splice plates, bolts	\$ 3,983.45	\$ 233.04	\$ 92.66	\$ 4,309.15
27.12	L.F.	051206401100	Structural steel member, 100-ton project, 1 to 2 story building, W12x14, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 480.57	\$ 152.96	\$ 60.75	\$ 694.27
307.36	L.F.	051206403300	Structural steel member, 100-ton project, 1 to 2 story building, W18x35, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 13,579.16	\$ 2,335.94	\$ 685.41	\$16,600.51
76.84	L.F.	051206403900	Structural steel member, 100-ton project, 1 to 2 story building, W18x55, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 5,328.85	\$ 611.65	\$ 180.57	\$ 6,121.07
4.66	S.F.	051205600450	Steel plate, structural, for connections & stiffeners, 3/4" T, shop fabricated, incl shop primer	\$ 163.80	\$ -	\$ -	\$ 163.80
28.25	L.F.	051206404900	Structural steel member, 100-ton project, 1 to 2 story building, W24x55, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 1,959.14	\$ 185.04	\$ 54.24	\$ 2,198.42
Total				\$ 25,494.97	\$ 3,518.63	\$ 1,073.63	\$30,087.22

Non-typical elements

Unit Cost Estimate

6425 Penn Ave.
Pittsburgh PA 15206

Data Release : Year 2008 Quarter 1

Quantity	Unit	LineNumber	Description	Ext. Mat. O&P	Ext. Labor O&P	Ext. Equip. O&P	Ext. Total O&P
66	L.F.	051206406100	Structural steel member, 100-ton project, 1 to 2 story building, W30x99, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 8,276.40	\$ 399.96	\$ 117.48	\$ 8,793.84
66	L.F.	051206406700	Structural steel member, 100-ton project, 1 to 2 story building, W33x118, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 9,843.90	\$ 408.54	\$ 120.12	\$ 10,372.56
66	L.F.	051206406900	Structural steel member, 100-ton project, 1 to 2 story building, W33x130, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 10,847.10	\$ 424.38	\$ 124.74	\$ 11,396.22
66	L.F.	051206407140	Structural steel member, 100-ton project, 1 to 2 story building, W33x201, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 16,803.60	\$ 436.92	\$ 128.04	\$ 17,368.56
131	L.F.	051206408100	Structural steel member, 100-ton project, 1 to 2 story building, W36x300, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 49,780.00	\$ 922.24	\$ 271.17	\$ 50,973.41
131	L.F.	051206407920	Structural steel member, 100-ton project, 1 to 2 story building, W36x260, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 42,935.25	\$ 922.24	\$ 271.17	\$ 44,128.66

147	L.F.	051206400520	Structural steel member, 100-ton project, 1 to 2 story building, W8x35, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 6,494.46	\$ 1,323.00	\$ 526.26	\$ 8,343.72
180	L.F.	051206400620	Structural steel member, 100-ton project, 1 to 2 story building, W10x15, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 3,411.00	\$ 1,488.60	\$ 590.40	\$ 5,490.00
24	L.F.	051206400700	Structural steel member, 100-ton project, 1 to 2 story building, W10x22, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 672.72	\$ 198.48	\$ 78.72	\$ 949.92
116	L.F.	051206401100	Structural steel member, 100-ton project, 1 to 2 story building, W12x14, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 2,055.52	\$ 654.24	\$ 259.84	\$ 2,969.60
217	L.F.	051206401900	Structural steel member, 100-ton project, 1 to 2 story building, W14x26, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 7,113.26	\$ 1,087.17	\$ 431.83	\$ 8,632.26
271	L.F.	051206402700	Structural steel member, 100-ton project, 1 to 2 story building, W16x26, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 8,883.38	\$ 1,344.16	\$ 533.87	\$ 10,761.41
23	L.F.	051206402900	Structural steel member, 100-ton project, 1 to 2 story building, W16x31, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 906.89	\$ 126.73	\$ 50.60	\$ 1,084.22
1413	L.F.	051206403300	Structural steel member, 100-ton project, 1 to 2 story building, W18x35, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 62,426.34	\$ 10,738.80	\$ 3,150.99	\$ 76,316.13
59	L.F.	051206403520	Structural steel member, 100-ton project, 1 to 2 story building, W18x46, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 3,419.05	\$ 448.40	\$ 131.57	\$ 3,999.02

20	L.F.	051206403700	Structural steel member, 100-ton project, 1 to 2 story building, W18x50, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 1,263.60	\$ 159.20	\$ 47.00	\$ 1,469.80
36	L.F.	051206403900	Structural steel member, 100-ton project, 1 to 2 story building, W18x55, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 2,496.60	\$ 286.56	\$ 84.60	\$ 2,867.76
70	L.F.	051206403960	Structural steel member, 100-ton project, 1 to 2 story building, W18x86, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 7,581.00	\$ 566.30	\$ 166.60	\$ 8,313.90
358	L.F.	051206404100	Structural steel member, 100-ton project, 1 to 2 story building, W21x44, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 19,897.64	\$ 2,455.88	\$ 719.58	\$ 23,073.10
64	L.F.	051206404300	Structural steel member, 100-ton project, 1 to 2 story building, W21x50, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 4,043.52	\$ 439.04	\$ 128.64	\$ 4,611.20
79	L.F.	051206404500	Structural steel member, 100-ton project, 1 to 2 story building, W21x62, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 6,192.02	\$ 556.16	\$ 162.74	\$ 6,910.92
28	L.F.	051206404700	Structural steel member, 100-ton project, 1 to 2 story building, W21x68, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 2,407.44	\$ 197.12	\$ 57.68	\$ 2,662.24
38	L.F.	051206404900	Structural steel member, 100-ton project, 1 to 2 story building, W24x55, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 2,635.30	\$ 248.90	\$ 72.96	\$ 2,957.16
86	L.F.	051206405300	Structural steel member, 100-ton project, 1 to 2 story building, W24x68, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 7,394.28	\$ 563.30	\$ 165.12	\$ 8,122.70

82	L.F.	051206405500	Structural steel member, 100-ton project, 1 to 2 story building, W24x76, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 7,867.90	\$ 537.10	\$ 157.44	\$ 8,562.44
104	L.F.	051206406500	Structural steel member, 100-ton project, 1 to 2 story building, W30x116, A992 steel, shop fabricated, incl shop primer, bolted connections	\$ 15,215.20	\$ 650.00	\$ 191.36	\$ 16,056.56
313	C.Y.	033102200300	Structural concrete, ready mix, normal weight, 4000 PSI, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments	\$ 35,594.36	\$ -	\$ -	\$ 35,594.36
203	C.S.F.	032202000200	Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1 (8 x 8) 30 lb. per C.S.F., A185	\$ 3,432.73	\$ 8,055.04	\$ -	\$ 11,487.77
191	C.S.F.	032202000200	Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1 (8 x 8) 30 lb. per C.S.F., A185	\$ 3,229.81	\$ 7,578.88	\$ -	\$ 10,808.69
323	C.Y.	033102200300	Structural concrete, ready mix, normal weight, 4000 PSI, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments	\$ 36,731.56	\$ -	\$ -	\$ 36,731.56
19052	S.F.	053103000300	Metal decking, steel, cellular units, galvanized, over 15 Sq, 2" D, 18-18 ga	\$ 152,797.04	\$ 43,057.52	\$ 2,095.72	\$ 197,950.28
323	C.Y.	033107001400	Structural concrete, placing, elevated slab, pumped, less than 6" thick, includes vibrating, excludes material	\$ -	\$ 6,954.19	\$ 2,254.54	\$ 9,208.73
313	C.Y.	033107004350	Structural concrete, placing, slab on grade, pumped, up to 6" thick, includes vibrating, excludes material	\$ -	\$ 7,177.09	\$ 2,363.15	\$ 9,540.24

144	C.Y.	033102200400	Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments	\$ 16,796.16	\$ -	\$ -	\$ 16,796.16
6	C.Y.	033107000400	Structural concrete, placing, column, square or round, pumped, 12" thick, includes vibrating, excludes material	\$ -	\$ 300.48	\$ 97.80	\$ 398.28
90	C.Y.	033107001600	Structural concrete, placing, elevated slab, pumped, over 10" thick, includes vibrating, excludes material	\$ -	\$ 1,494.90	\$ 488.70	\$ 1,983.60
48	C.Y.	033107005350	Structural concrete, placing, walls, pumped, 15" thick, includes vibrating, excludes material	\$ -	\$ 1,190.40	\$ 392.64	\$ 1,583.04
6.72	Ton	032106000400	Reinforcing steel, in place, elevated slabs, #4 to #7, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 7,266.34	\$ 5,697.62	\$ -	\$ 12,963.96
3.11	Ton	032106000700	Reinforcing steel, in place, walls, #3 to #7, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 2,980.72	\$ 2,552.35	\$ -	\$ 5,533.06
1.65	Ton	032106000250	Reinforcing steel, in place, columns, #8 to #18, A615, grade 60, incl labor for accessories, excl material for accessories	\$ 1,662.51	\$ 1,757.68	\$ -	\$ 3,420.19
562	SFCA	031104105650	C.I.P. concrete forms, column, square, plywood, 12" x 12", 4 use, includes erecting, bracing, stripping and cleaning	\$ 466.46	\$ 4,349.88	\$ -	\$ 4,816.34
1834	S.F.	031104201000	C.I.P. concrete forms, elevated slab, flat plate, plywood, to 15' high, 1 use, includes shoring, erecting, bracing, stripping and cleaning	\$ 8,968.26	\$ 10,472.14	\$ -	\$ 19,440.40
130	L.F.	031104551000	C.I.P. concrete forms, wall, corbel/haunch, add to wall form, to 12" wide, 1 use, includes erecting, bracing, stripping and cleaning	\$ 319.80	\$ 2,328.30	\$ -	\$ 2,648.10

1922	SFCA	031104552000	C.I.P. concrete forms, wall, job built, plywood, to 8' high, 1 use, includes erecting, bracing, stripping and cleaning	\$ 5,823.66	\$ 13,953.72	\$ -	\$ 19,777.38
------	------	--------------	--	-------------	--------------	------	--------------

Total **\$ 586,932.78** **\$ 144,503.61** **\$ 16,433.07** **\$747,869.45**

APPENDIX B

General Conditions Information

Item	Description	Duration	Unit Cost	Cost
10020	Mobilization	1 time	-	\$110,200
10010	Demobilization	1 time	-	\$4,300
11002	Senior Project Manager	7 months (50%)	\$12,028.57	\$84,200
11004	Superintendent	14 months	\$10,478.57	\$146,700
11013	Project Engineer	14 months	\$4,864.29	\$68,100
11018	Safety Engineer	3 months (20%)	\$4,200	\$12,600
11021	Secretary	7 months (50%)	\$4,442.86	\$31,100
11030	PX	3 months (20%)	\$13,333	\$40,000
11031	Intern	6 months	\$4,166.67	\$25,000
12300	Permits	1 time	-	\$83,400
12400	Accounting	-	-	\$18,000
13000	Survey/Layout	14 months	\$1,821.43	\$25,500
15000	Office	14 months	\$1,535.71	\$21,500
15100	Field Communication	14 months	\$3,142.86	\$44,000
15200	Office Equipment	14 months	\$339.29	\$4,750
15310	Job Office Supplies	14 months	\$171.43	\$2,400
15320	Overnight Mail & Postage	14 months	\$207.14	\$2,900
16000	Utilities	14 months	\$3,800.00	\$53,200
16200	Winter Protection	3 months	\$2,083	\$6,250
16300	Temp Heat	3 months	\$5,333	\$16,000
17000	Safety	14 months	\$221.43	\$3,100
18000	Clean up	14 months	\$4,821.43	\$67,500
18500	Dumpsters	14 months	\$1,392.86	\$19,500
19010	Small Tools	14 months	\$303.57	\$4,250
19020	Photographs	14 months	\$50.00	\$700
19030	Project Signs	14 months	\$42.86	\$600
19040	Plans and Specs	1 time	-	\$10,000
19060	Parking	14 months	\$142.86	\$2,000
19100	Temp. Fence & Gates	14 months	\$928.57	\$13,000
19170	Snow Removal	3 months	\$833	\$2,500
Total				\$923,250