# Waynesburg Central High School

Central Greene School District

Waynesburg, Tennsylvania



## **Project Team**

Owner: Central Greene School District

**Construction Manager:** Foreman Program and Construction Managers

Architect and Engineers: Foreman Architects and Engineers



## **Project Overview**

Estimated Project Cost: \$17,000,000
Size, Addition: 24,000 square feet
Renovation: 154,000 square feet

•Number of Stories: 2

• Delivery Method: CM Agency, with Multiple Primes

•Project Dates:

Phase 1: 10 Dec. 2007 – 24 Nov. 2008 Phase 1A: 24 Dec. 2007 – 31 Dec. 2007 Phase 2: 10 Dec. 2007 - 15 Aug. 2008 Phase 3: 15 May 2008 - 15 Sep. 2008 Phase 3A: 06 June 2008 – 22 Aug. 2008 Phase 3B: 06 June 2008 – 15 Oct. 2008 Phase 4: 15 July 2008 – 27 Aug. 2008 Phase 5: 01 Dec. 2008 - 13 Mar. 2009 Phase 6: 20 Mar. 2009 - 01 June 2009 Phase 6A: 15 May 2009 – 15 Aug. 2009 Phase 7: 15 May 2009 - 28 Aug. 2009 Phase 7A: 05 June 2009 - 28 Aug. 2009

## **Project Structure**

- Pre-cast concrete column and beam structure
- Masonry infill with load bearing masonry walls
- •Open web structural steel joists for roof structure
- Pre-cast concrete docs plank over boiler room
- Foundation comprised of grade beams and footers



# **Project Architecture**

#### **Additions:**

- Exposed Architectural pre-cast concrete columns
- Brick veneer with a grape vine joint
- New TPO roof system on building

#### **Renovations and Additions:**

- Columns protrude with beams creating sunshades
- Consistent style maintained on additions
- Operable punch out windows
- Natural day lighting through use of skylights



# **Project Infrastructure**

#### **Mechanical Additions:**

- •215 ton Air cooled chiller
- Prepackaged rooftop air units

#### **Mechanical Renovations:**

•4 pipe unit ventilators (UV) replace old UV system

#### **Electrical Service:**

•Main Service: 277/480V, 3 Phase, 4 Wire

Main Breaker: 3000A, 3 PhaseSecondary Service: 208Y/120V

40 types of luminaires in the building