Technical Report 2



Student Health Center

Penn State University

Prepared By: Jacob Brambley (Structural Option)

Prepared For: Dr. Richard Behr

Table of Contents

Executive Summary	3
Introduction	4
Structural Systems	4
Foundation	4
Floor System/Beams	4
Columns	5
Roof/Penthouse Level	5
Lateral System	6
Code and Design Requirements	9
Design Codes and References	9
Deflection Criteria	9
Material Properties	10
Loads	11
Alternate Floor Systems	12
Composite Steel System (Existing)	12
Two-Way Flat Slab	13
Two-Way Post Tensioned Slab	14
Prestressed Hollow Core Plank on Steel	15
Comparison	15
Conclusion	16
Appendix	17
A: Existing Building Layout	
B: Existing Composite Steel System	18
C: Two-Way Flat Slab	22
D: Two-Way Post Tensioned Slab	
E: Prestressed Hollow Core Plank on Steel	35

Executive Summary

The Student Health Center (SHC) is a five story building on the Penn State campus that serves as a health care services and hospital facility. After completion in the fall of 2008, this building now houses University Health Services and Counseling and Psychological Services, two departments of Penn State's Division of Student Affairs.

The facility is 77 feet in height from the first level and is approximately 64,000 SF in area. It has a brick façade rising from the ground with large curtain wall on the south side the building. The structure is held up primarily by a steel frame. The overall structure sits on a mini-pile foundation through use of pile caps, piers, and grade beams. Composite steel with concrete slab on deck is use for the floor system throughout the SHC.

This technical report will explore three alternate floor systems to the concrete slab on deck already in place at the SHC. A two-way post tensioned slab, a two-way flat slab, and a hollow core concrete plank on steel beam system are the alternate floors being examined. The characteristics of the four systems will be compared and plausible alternatives to the existing system will be determined. These characteristics include cost, serviceability, constructability, self weight, as well as others. A typical interior bay was chosen as the basis for comparison. Conclusions were then drawn from this analysis as to which floor system would be a viable replacement to the composite steel with concrete deck.

As end result of this analysis, the two-way post tensioned slab and the two-way flat plate slab seem to be possible alternatives to the current system. The costs are similar to the system in place and the total floor thickness is significantly smaller. The self-weight of these proposed floors are higher creating a great load on the foundation. Also, the current partially-restrained steel frame cannot be used for these systems. Therefore, the impact of both on the foundation and an alternative for the lateral system would need to be addressed in a further report to truly confirm system efficiency.



Introduction

Located on Penn State campus, the Student Health Center serves as the center of health services for the college. The five story, 64,000 SF building was built in such a way as to bring in natural sunlight and create a healthy atmosphere for office workers and patients. The façade of the SHC is composed of the curtain wall as well as face brick accented with stone bands. The brick façade at the base of the building helps it fit in with the master plan of the rest of the university.

A composite steel floor system is utilized in the SHC and the purpose of this report is to explore three other floor systems and see how they would fit in the current building layout. By the end of this report, there will be a better idea of the viability of the current floor and the best options available if the floor construction was changed.

Structural Systems

Foundation:

The foundation of the SHC is composed of grade beams and piers that are supported by mini-piles with pile caps. The mini-piles are arranged in configurations of 1-5 piles per pile cap. They are to be at a depth of 45 feet and have an 80 ton allowable capacity. The partially-restrained moment frame employed in this building is either connected directly to a pile cap or to a concrete pier. The depth of these mini-piles will counteract the moment of the partially-restrained moment frame caused by lateral loads.

Floor System / Beams:

The floor system used in the SHC is composed of 3 1/4" lightweight concrete fill on 2"-20 gage galvanized composite floor deck LOK floor for a total slab thickness of 5 1/4". Also included are $3/4\phi \times 4$ " long shear studs equally spaced along the entire lengths of all interior beams and girders that are not part of the partially-restrained moment frame. The shear studs are not on the moment frame because the beams on the frame cannot be too rigid so that they can deform. This composite floor deck is supported by steel W-shape beams spanning between steel columns.


Columns:

The P.R. moment frame consists of W14 steel columns running from the foundation up to the roof level. Columns that are not part of the P.R. moment frame range in size and shape. Round HSS shapes are used both with and without concrete fill, as well as square HSS shapes and W shapes to resist gravity loads.

Roof / Penthouse Level:

The roof system is composed of 5 1/4" normal weight concrete fill on 3"-20 gage galvanized composite floor deck LOK floor for a total slab thickness of 8 1/4". The main roof is at the 6th level with a screen wall around the rooftop mechanical equipment. There is also a green roof around the perimeter of the main roof level (*Fig. 1*). On the north end of the building, at the 5th level, there is another green roof (*Fig. 2*) that is nearly 20 feet wide and runs the length of the building.

Fig. 1 – Green Roof on Main Roof







Fig 2 – Green Roof on 5th Floor

Lateral System:

A partially-restrained moment frame is used to resist lateral loads on the SHC. These frames are to have Flexible Moment Connections (FMC) designed by the steel fabricator per Part 11 of the AISC- Load & Resistance Factor Design Manual. A typical beam to column flange connection for these frames is detailed below (Fig. 3). There are eight partially-restrained frames employed in this building, with seven running in the north/south direction, and one in the east/west direction (Fig. 4). These frames run vertically up to the 5th Level or Main Roof Level of the building depending on the location. Frames are shown below in elevation (Fig. 5-7).



GENERAL NOTES:

- General Notes:

 1. Per the General Structural Sieel Notes, all connections are to be by the Steel Fabricator and are to conform to the latest standards of the associated that the steel fabricator and are to conform to the latest standards of the associated that the steel construction" (Lird or asd design).

 2. The Typical Detail Shown is one of Several pre-qualified Flexible Moment Connections (Partially Restrained) per part 11 of the asc "Manual of Steel Construction Load Resistance Factored Design". The Steel Fabricator has the Option to Propose other pre-qualified Flexible Moment Connections as required to Adequately Resist the Given Wind and Seismic Beam end Moments.
- THE STEEL FABRICATOR IS TO USE THIS "TYPICAL" IN CONJUNCTION WITH THE P.R. MOMENT FRAME ELEVATIONS FOUND ON DRAWINGS \$6.0, \$6.1 AND \$6.2.
- PLIK. MOMENT HAWAE ELEVATIONS FOUND ON DRAWINGS S6.0, S6.1 AND S6.2.

 4. THE STEEL FABRICATOR IS TO SUBMIT FOR OUR REVIEW PER THE GENERAL STRUCTURAL STEEL NOTES TYPICAL CONNECTION DESIGNS INCLUDING BUT NOT LIMITED TO PARTIALLY RESTRAINED/FLEXIBLE MOMENT CONNECTION DETAIL TO THE ONE SHOWN OR ANY OF THE PRE-QUALIFIED FLANGE PLAYED CONNECTION FOUND IN FINCHIES 11-5 AND 11-6 OF PART 11 IN THE AISC "MANUAL OF STEEL CONSTRUCTION LOAD RESISTANCE FACTORED DESIGN" (PAGES 11-6 AND 11-7 OF THE THIRD EDITION).

TYPICAL PARTIALLY RESTRAINED (PR) BEAM MOMENT CONNECTION - BEAM TO COLUMN FLANGE SCALE: 3/4" = 1'-0"

Fig. 3

Structural Option Dr. Richard Behr




Fig. 4 – Partially-restrained Frame Locations




Fig. 5 – P.R. Moment Frame Elevations (G and 2)






Fig. 6 – P.R. Moment Frame Elevations (A, B, and C)




Fig. 7 – P.R. Moment Frame Elevations (D, E, and F)

Code and Design Requirements

Design Codes and References:

Codes used by Project Team:

International Building Code (IBC)/2003 with Borough Amendments
International Mechanical Code (IMC)/2003 with Borough Amendments
International Plumbing Code (IPC)/2003 with Borough Amendments
International Energy Conservation Code (IECC)/2003 with Borough Amendments
International Code Council Electrical Code (ICCEC)/2003
International Fire Code (IFC)/2003
ACI 318-05
AISC "Steel Construction Manual" (13th Edition)
ACI 530.1/ASCE 6/TMS 602 (2005)

Codes used for Thesis:

International Building Code (IBC)/2006 ACI 318-08 AISC "Steel Construction Manual" (13th Edition) ASCE 7-05

Reference Material:

RS Means Square Foot Cost Data, 2007 RS Means Assemblies Cost Data, 2008 ACI 318-08 Building Code and Commentary Nitterhouse Concrete Products - Precast Design Aids

Deflection Criteria:

Maximum Floor Deflections:

L/360 Live load L/240 Total load L/240 Roof

Material Properties

Material	A.S.T.M.	Minimum Strength						
Concrete								
Foundation Walls, Pile Caps,	-	3000 PSI						
Slab on Grade, Retaining								
Walls, Footings								
Exterior Slabs, Curbs	-	4000 PSI						
Reinforcement	A615 (Grade 60)	60 KSI						
WWF	A185, A497	70 KSI						
Structural Tubing, Round	A500 (Grade B)	42 KSI						
Structural Tubing, Shaped	A500 (Grade B)	46 KSI						
Steel Pipe	A53 (Type E, Grade B)	35 KSI						
Rolled Shapes	A992	50 KSI						
Other Rolled Plates	A36	36 KSI						
Connection Bolts	A325	92 KSI						
Anchor Bolts	A307	-						
Threaded Rods	A36	36 KSI						
Non-shrink Grout	C1107	8000 PSI						
CMU	C90 (lightweight)	2800 PSI						

Loads

Gravity Loads:

Dead Load:

Dead Loads were obtained using typical design values, material specifications, or educated assumptions. My values were very similar to values stated by the Engineer of Record.

Component	Obtained Values
2" Steel Deck (on floors 1-5)	2 PSF
3-1/4" Concrete on Deck (on floors 1-5)	43 PSF
3" Steel Deck (on main roof level)	2 PSF
5-1/4" Concrete on Deck (on main roof level)	82 PSF
Green Roof	25 PSF
Ceiling with Mechanical/Electrical	15 PSF
Floor Finish	3 PSF

Live Load:

Live Loads were taken from ASCE 7-05 along with an assumption for the mechanical rooms. My obtained values were once again very similar to the values on the drawings.

Building Location	Drawing Values	Obtained Values
Corridors (first floor)	100 PSF	100 PSF
Corridors (above first floor)	80 PSF	80 PSF
Procedure/Exam Rooms	50 PSF + 20 PSF partition	40 PSF + 15 PSF partition
Lobbies	100 PSF	100 PSF
Stairs	125 PSF	100 PSF
Mechanical Rooms	75 PSF	150 PSF
Offices	50 PSF + 20 PSF partition	50 PSF + 15 PSF partition
Light Storage	125 PSF	125 PSF
Heavy Storage	250 PSF	250 PSF

Snow Load:

Snow loads were determined using IBC 2006 and Centre Region Code.

$$p_f = 0.7 \times C_e \times C_t \times I \times p_g = 30.8 \text{ psf}$$
 $p_g = 40 \text{ psf}$
 $C_e = 1.0$
 $C = 1.0$
 $I = 1.1$

<u>Alternate Floor Systems</u>

As mentioned in the introduction, three systems were examined to determine the best option to replace the system already in place. These alternative systems are being looked at to see if there legitimate asset to changing the current one such as a smaller floor thickness or decrease in construction cost. The three proposed options are a two-way flat slab, a two-way post tensioned slab, and a hollow core concrete plank on steel W-shapes. Analysis on the current composite steel system was completed in Technical Report 1 and will be attached to this report for reference. A typical interior bay, 23'x29', (shown in Appendix A) was chosen to do calculations on the new systems. The existing column layout was utilized and for the concrete systems, a 20"x20" column was assumed in place of the steel columns.

Composite Steel System (existing)

A composite steel floor system is currently in place at the SHC. There is a 3 1/4" lightweight concrete fill on 2"-20 gage galvanized composite floor deck LOK floor for a total slab thickness of 5 1/4". W-shapes ranging W-12s to W-24s are used in conjunction with this slab. Also included are $3/4\phi \times 4$ " long shear studs equally spaced along the entire lengths of all interior beams and girders that are not part of the partially-restrained moment frame. This floor system was examined in Technical Report 1, and the calculations are shown in Appendix B of this report.

Advantages:

There are several advantages to using this system. The self-weight of the entire system is low which has a low impact on the foundation. Also, the steel goes up fairly quickly once it arrives on site. One reason for this is that there is no forming to put in place like the other concrete systems. The light, airy nature of the architecture is also accented by the slender shapes of a steel frame. If a concrete frame were used, the curtain wall areas wouldn't seem as open and inviting.

Disadvantages:

This system does have its faults though. The overall floor thickness (slab + steel frame) is very thick compared to all-concrete systems. This affects the number of floors you can get per building height. Fireproofing is required for all the steel in the system. Also, the lead time to get the steel designed and to the site is longer than other systems.

Two-Way Flat Slab

The two-way flat slab system was the first alternative studied for this report. This system is popular due to its minimal slab thickness and low cost in certain locations. Another lateral force resisting system would have to be implemented to replace the steel moment frame, if this system was used though.

After analysis, it was determined that a 10" flat slab with 3" drop panel would suffice to carry the loads. The reinforcing used is stated in Appendix C. F'c and Fy were assumed to be 5000 psi and 60,000 psi respectively for analysis and a column size of 20"x20" was also assumed.

Advantages:

Advantages of using a flat slab include a shorter floor thickness than steel. Also, the cost is the smallest out of all of the systems studied. One reduction in cost is the lack of fireproofing needed for the concrete floor. The short lead time to get the material to the site is also highly desirable.

Disadvantages:

One major disadvantage to this proposed system is the self-weight of it. This increased weight will add load to the foundation and this may lead to higher foundation costs. The coordination of trades during constructing may also suffer due to this system because of large slab pours that need time to cure. As mentioned earlier, the larger concrete columns also may not be desirable for the areas behind curtain walls because of their bulkiness in comparison to the steel columns.

Two-Way Post Tensioned Slab

A two-way post tensioned slab was researched and analyzed as another minimal floor thickness alternative. Like the flat plate, the post tensioned system would need to implement a new lateral-force resisting system such as shear walls.

Through doing the calculations, it was determined that an 11" flat slab will work in conjunction with the post tensioning and other reinforcement. Further information about the tendons and rebar quantity and placement can be found in Appendix D.

Advantages:

One reason post tensioned slabs are used frequently are their ability to cover large spans while maintaining a relatively small thickness. The spans between columns are not extensive enough in this building to warrant using a post tensioned slab to its full potential. The current column grid could be change though and maybe it would open up the rooms a bit. The thickness of 11" was the thinnest out of all of the systems looked at. The lead time on materials is short. It is also 2-hour rated and needs no additional fireproofing.

Disadvantages:

Disadvantages may include constructability. There has to be a contractor nearby that has experience with post tensioning to build it correctly and efficiently. Much like the flat plate, it has a lot of weight to it and creates a bigger push down onto the foundation.

Prestressed Hollow Core Plank on Steel

Lastly, a prestressed hollow core plank system set on steel W-shapes was examined. Since this floor system is composed of steel and precast concrete, no labor intensive formwork or concrete pours will be happening. The whole system can be lifted up into place by a crane.

It was found, using Nitterhouse hollow core design aids, that an 8"x4'-0" hollow core plank with 4-1/2" Diam. Strand pattern will work the best to resist the building loads. This plank will sit atop W24x62 beams. Calculations and design aids are in Appendix E.

Advantages:

One major advantage, mentioned earlier, is the lack of formwork and wet concrete, which can be pretty labor intensive. In addition, the lateral-force resisting system in the original design can be kept in place. The floor is also relatively light, reducing detrimental effects on the foundation.

Disadvantages:

This system has many faults. The excessive depth of the plank and steel is a major cost and/or comfort issue, either increasing the building's height or lowering ceiling heights. The lead time to get the steel designed, fabricated, and on the site is lengthy. Fireproofing is needed for all the steel W-shapes and the cost of the overall system is significantly higher than the other proposals.

Comparison

	Floor Systems								
	Composite Steel	Two-way Flat Slab	Two-way Post	Hollow Core					
			Tensioned Slab	Plank on Steel					
System Weight (psf)	51	131	138	68					
Total Depth (in)	29	13	11	32					
Lead Time	Medium	Short	Short	Medium					
Constructability	Medium	Medium	Hard	Medium					
Formwork	No	Yes	Yes	No					
Impact on	-	Yes	Yes	Little					
Foundation									
Impact on Lateral	-	Yes	Yes	No					
System									
Fireproofing Needed	Yes	No	No	Yes					
Cost per SF	\$19.95	\$17.45	\$21.86	\$32.10					
Viable Alternative	-	Yes	Yes	No					
Additional Study	-	Yes	Yes	No					

Conclusion

Technical Report 2 has examined several alternative floors systems to see which ones, if any, are plausible for use in the Student Health Center. Two concrete-dominate systems were looked at, as well as, another steel-dominate system. In the end, the two-way flat slab and the two-way post tensioned slab are the best options to replace the current system, as determined by this report.


Both the flat slab and post tensioned slab reduced the thickness of the floor significantly, with the post tensioned slab being slightly thinner. They both have a short lead time and no need for fireproofing. The flat slab is slightly better in the cost and constructability categories.

The prestressed hollow core plank on steel system did not seem to be an efficient way to go in this project with cons outnumbering the pros on the majority.

Therefore, additional study will be performed on two-way flat slabs and two-way post tensioned slabs.


Appendix


Appendix A: Existing Building Layout



Typical Bay for Calculations (29'x23') (in green)

Appendix B: Existing Composite Steel System





```
ASSUMING E Q = 145
 beet = | 29 (12) = 348"
             15(12)/4: 45. CONTROLS
  a = 200 = 145
0 85ficher = 0.85(3)(45) = 1.26
   Y2 = 5.25"-124/2 = 4.62" => 4.5"
  FROM TABLE 3-19: @ PNA =6
   AM = 269 ftk > 192.2 ft.k : OK
    FROM TABLE 3-21
   DECK PARALLEL
 W/n=3.0 | 17.1=Qn
  LT. WT. CONC.
 EQn (x2) = 145 (x2) = 16.96 -> 17 STUDS REQUIRED


17 > 12 PROVIDED . NO 600D
TEY EQ = 96 @ PNA 7
9 = 96
0.85(3)(45) = 0.837"
   72=5.25-0.83% = 4.83 - 4.5"
   FROM TABLE 3-19 @ PNA = 7
   OM == 241 ft.k > 192.2 ft.k :. STILL OK
  EQn (x2) = 96 (x1) = 11.2 → 12 STUDE REGIO
CHECK DEFLECTION: ILE = 5851/4"

\[ \Delta = \frac{100}{180} = \frac{(0.1 \times 7.5 \times 29)(16)\frac{3}{12}}{100} \]

\[ \Delta = \frac{100}{180} = \frac{(0.1 \times 7.5 \times 29)(16)\frac{3}{12}}{100} \]

\[ \Delta = \frac{100}{180} = \frac{100}{180} = \frac{3}{100} = \frac{3}{10
   DALLOW = 15(12)/300 = 0.5" >0.17" .. OK
```

Appendix C: Two-Way Flat Slab



10

M.W


MOMENIS Mo= & wulzln2 FRAME A: = (300)(23)(29-1.67)3/1000 = 644 ftk FRAME B: \$ (300)(29)(23-161) 3/1000 = 495 fl.k 0.35160 0.35 Mo 0.65 Mo 0.65 Mo 0.65Mo -419 =419 = 322 =37Z (f1.k) FRAME A FRAME B SUMMARY OF MOMENTS FRAME A IM- (11-K) M+1 FRAME B IM- (41+) M" TOTAL MOM. 419 225 TOTAL MOM 322 173 75% 90 to CS To to CS 75% 60% 60% Man INCS 314 MOM IN C.S. 242 135 104 MOM. IN M.S. 105 90 MOM, IN M.S. 80 69 -da = 10-1,5(0625)-0 >5 = 8.5" dB=10-0.5(0.625)-075=8.93" ASSUME #15 Gars DESIGN SLAB REINFORCEMENT IN COL STRIP FRAME A FRAME B M+ M-Item Description Mt Mu (Cirk) 135 242 l 314 104 a 138 174 6 (m) 138 174 3 d (in) 8.3 8,3 893 8.93 R. (ff.k) 314/0.9.349 4567 150 269 116 441 189 233 100 0.0074 Great d 0.0032 0.0029 0,0017 8.48 As regid (in) 3.67 6.06 2.64 As min (ha) 84,C = +08100.0 0,48 3,13 3.13 177 27.4 (58) 6.9 (7) 118 119.500 10,1 (ID

6.9 (7) 8.7 (9)

3.7 (9)

PESIGN SIME REINFORCEMENT IN MID. STRIP Hem Description M- TRAME A M+ M- TRAME B M+ Mu (fit) 105 90 80 69 L b (m) 138 138 174 174 L d (m) 8.3 8.5 8.93 8.93 Hm (fit) 117 100 89 77 R (16/m²) 148 126 77 67 R (16/m²) 148 126 77 67 R (16/m²) 148 126 77 67 R (16/m²) 2.86 2.41 2.02 1.71 R As regid (m²) 2.86 2.41 2.02 1.71 R As min (1²) 2.48 2.48 3.13 3.13 N N 9.2 (10) 8 (8) 10.1 (11) 10.1 (11) Nomin D (9)
PUNCHING SHEAR CHECK @ Drop Fenel (3"DROP) davg = 11.3+11.93 = 11.62" 20" Vo = Wo × A = 0.3 [(23)(29) - (31.62)2] = 198 k 20+11.62=31.62" Vc = 41-17'c · b · d CONTROLLING Vc -> Vc = 41-5000 · (4 × 31.62)(11.62)/1000 = 476k
QSLAB davg = 8.318.95 = 8.62" V= 0.3[(23)(29) - (10.72)2] = 166k Vc = (\(\frac{\pi_{10}}{5.} + 2\)\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
WIDE BEAM CHECK VI = 21500 (23×12) -8.62/1000 = 336 K DROPHINELY OVN = 0.75 (336) = 252 K >894 - V OK 14.51-10-8.62=12.95'

Appendix D: Two-Way Post Tensioned Slab



```
AT = (15+23) x (29) = 551 ft (SMALLEST BAY)
 A= 4(551) = 2204 ft=
 LLred = LL VO. 25+(15/1504) = 0.755(80)
 LLred = 60.4 PSF
DESIGN OF EAST-WEST INTERIOR FRAME
 EQUIVALENT FRAME METHOD

BAY WIDTH BETWEEN &'S = (27.67/2)+(15/2)=21.33'

IGNORE COL STIPFNESS POR SIMPLICITY
 LL/DL 23/4 " NO PATTERN LOADING REQ'D
 CALCULATE SECTION PROPERTIES:
 TWO WAY SLAB MUST BE DESIGNED AS CLASS U
 A = b.k = (21.33 x 12)(8) = 2048 in2
 S. b.h2/6 = (21.33×12)(8)2/6 = 2731 in3
 SET DESIGN PARAMETERS:
CLASS U: ALLOWABLE STRESSES
AT TIME OF JACKING:
    f'zi = 3,000 PSI
     COMPRESSION = 0.60 f2; = 0.6 (3000)=1800 psi
    TENSION = 3172: =313000 = 164 PSI
AT SERVICE LOADS:
    fi= 5000 PSI
     COMPRESSION= 0.45 ( = 0.45 (5000) = 2, 250 PSI
    TENSION= 6/11 = 6(5000 = 424 PSI
AVERAGE PRECOMPRESSION LIMITS:
 P/A = 125 PSI MIN
= 300 PSI MAX
```

TARGET LOAD BALANCES:

60%-80% OF SW FOR SLABS (GOOD APPROXIMATION)

USE 0.60 (SW) = 0.60 (100) = 60 PSF


COVER REQUIREMENTS!

FOR 2-HR RATING FROM THE IEC

RESTRANED SLABS = 3/4" @ Loftom

TENDON PROFILE: PARABOLIC SHAPE

. PT tendor



TENDON ORDINATE

TENDON (CG) LOCATION

EXTERIOR SUPPORT - ANCHOR INTERIOR SUPPORT - TOP INTERIOR SPAN - BOTTOM END SPAN - BOTTOM 4.0" from bottom

Q in+ = 7.0" - 1.0" = 6.0" Qeid = (4.0"+7.0") - 1.75" = 3.75"

e varies along span

PRESTRESS FORCE REQ'D TO BALLANCE 60% OF SW

Wb = 0.60 (Nov) = 0.60 (100) (21.33) = 1280 19/4 = 1,28 4/4

FORCE INTENDONS TO COUNTERACT THE LOAD IN END BAY

P= WoL3/8gend

=(1.28)(29)2/8(3.75/12) = 43/ K

CHECK PRECOMPRESSION ALLOWANCE


OF TENDONS TO ACHIEVE 43/ K

OF TENDONS = (43/3/26.6(/tendon) = 16.19.

USE 16 TENDONS

ACTUAL FORCE FOR BONDED TENDONS: PACTURE = (16 tendons) (26.6 h) = 425.6 k Nb= (425.6/430.6)(1.28)= 1.27 4/44 PROTURE /A = (425.6×1000)/2048 = 208 PSI > MIN = 125 PSI = OR PINTERIOR < PENTERIOR : LESS FORCE REQ'D Wb = 95% < 100% : OK Wb = 426(8)(6.0/12)/292 = 2.02 k/f+ WbL = 95% < 100% : OK EFF. PRESTRESS FORCE, PER= 426 & FOR E-W FRAME CHECK SLAB STRESSES DEAD LOAD MOMENTS: Was = (11875F)(21,33')/1000 = 2.517 K/ff 2.9 291 29' (212 212 53 169 (ft-K) 169 LIVE LOAD MOMENTS: WLL= 60.4 PSF (2133')/1000= 1.289 K/f4 (41.K) BALANCED LOAD AVERAGE: 2×1.27)+2.02 = 1.52 K/ff

TOTAL BALANCING MOMENTS, Mbai:



STAGE 1: STRESSES IMMEDIATELY AFTER JACKING (DL+PT)

MIDSPAN STRESSES INT. SPAN

END SPAN

SUPPORT STRESSES

STAGE 2: STRESSES AT SERVICE LOAD (DL+LL+PT)


MIDSPAN STRESSES FNT SPAN

```
END SPAN
   f+op=[(-169-87+102)(10)(1000)]/(2751)-208
=-677-208=-885 PS/40:45 fic=2250 PS/ :OK
   ful = [(169+87-102)(12)(1000)]/(2731)-208
=677-208 = 469 PS(7676 =424 PS1 :NO GOOD
   SUPPORT STRESSES
   ftop=[(212-129+108)(12)(1000)]/(2721)-208
= 839-208=631 PSI > 67F1=424
  fbat = [(-212+129-108)(12)(1000)]/(2731)-208
=-839-208-1047 PSI 20. 436 = 2250PSI
* INCREASE SLAB THICKNESS
f+op regid + P/A = 424 + 208 = 632 PSI
   [(212-129+108)(12)(1000)] = 632
   S= 3627 in
     3627 = (21.33×12) h2/6 => h=9,2->TRT 11"
  H= (21.33 x12)(11) = 2816 12
  S= (21.33×12)(11)2/6= 5/63 in3
  WDL = (11/12)(150) = 137,5 PSF
  Wb= 0.60(1375)(21.33) = 176016/f+=1.76 k/f+
  P= (1.76)(29)2/8(6.0/12) = 370 K
  # OF TENDONS = 370 /26.6 = 13.9 -> TRY 14 Tendons
  PACTUAL = 14 (266) = 372,46
  Wb= (372.4) (1.76) = 1.77 K/F+
  P/A = (372.4 ×1000) / 2816 = 132 PSI > MIN : OF
  Wbinterior = 372(8)(9/12)/292 = 2.66 k/ct
  WOL = 2.66 = 90.8 % 4 (00% : OK PEFF = 372 K
```

RECHECK SLAB STRESSES

DEAD LOAD MOMENTS:


WOL= (155.5PSF)(21.33')/1000 = 3,317 //+



LIVE LOAD MOMENTS:

(SAME AS BEFORE)

Mbal: Wb = - 2.067 K/ff (AVERAGE)



STAGE 1: (DL+PT)

MIDSPAN STRESSES

frop = [(-70+44)(12)(1000)]/5163 -132 = -192 PSI < 1800 PSI : OK fbot = [(70-44)(12)(1000)]/5163 -132 = -70 PSI < 1800 PSI : OK

END SPAN

frop: [(-223+139)(12)(1000)]/5163-132=-327PS121800PS1:06 fort=[(223-139)(12)(1000)]/5163-132=63PS12164PS1:06 SUPPORT STRESSES

fig=[(279-173)(12)(1000)]/5163-132=114PSI<164PSI:06 fbd:[(-279+173)(12)(1000)]/5163-132=-378PSI<1800PSI:0k STAGE 2: (DL+LL+PT)

MIDSPAN STRESSES INT SPAN

ftop=[(-70-27+44)(12)(1000)]/5163-132=-255 PSIC 2250 PSI: DE fbot=[(70+27-44)(12)(1000)]/5163-132=-9 PSIC 2250 PSI: DE END SPAN

ftop = [(-2)3-87+139)(12×1000)]/5163-132=-529PS1 <-250 PS1 :.OK fbot = [(223+87-139×100)]/5163-132=265PS1<424PS1 :.OE SUPPORT STRESSES

ftop=[(279+108-173)(12)(1000)]/5163-132=365PS1 < 424PS1 ...OK fbot=[(-279-108+173)(12)(1000)]/5163-132=-629PS1 < 2250PS1 ...OK

ULTIMATE STRENGTH

DEFERMINE FACTORED MOMENTS:

e = 0" @ EXT. SUPPORT ; e = 4.5" @ INT. SUPPORTS

M. = P. e = (372.4) (4.5/12) = 140 fl.k

Msec = Meal - M. = 173 - 140 = 33 fl. K @ INT. SUPPORTS

Mu= 1.2 Moc + 1.6 Mac + 1.0 Msec

ATMIDSPAN: Mu=1.2 (223)+1.6(87)+1.0(16.5)=423-F1-K

AT SUPPORT: Mu=1.2 (279)+1.6 (108)+1.0 (33)=-475 f+.k

DETERMINE MIN. BONDED REINE

POSITIVE MOMENT REGION: INTERLOR SPAN: NO POS. REINF. REQ'D

EXTERIOR SPAN: f+=265 PS1>21F2-215000=141 PS1

4= f+/(f++fe)h =[26E/(265+529)](11) = 3.67"

```
No = [Moune /5] (0.5)(4)( Pa)
   = ((223+87)(12)/51637(0,5)(3,67)(21,33)(12)=338K
Asmin = No 10.5+4 = 338/(0.5 × 60) = 11.3 in2
As, min = 11.3/21.33 = 0.530 119/ft
USE #6@9"O.C. BOTTOM = 0.59 in =/ff
MIN. LENGTH SHALL BE 1/3 CLEAR SPAN AND CENTERED
NEGATIVE MOMENT REGION
FUTERIOR SUPPORTS.
Acf = 11" (29×12) = 3828in2
Ac, min= 0.00075 Acf = 0.00075 (3828) = 2.871 in=
      = (15) # 4's TOP (3.0 12)
EXTERIOR SUPPORTS:
Act = 3828 112
As min = 2.871 m2 = (15) #4's top (3.0 m2)
CHECK MIN, REINFORCE MENT
d=11"-3/4"-1/4"=10"
Aps=0.153in3(16)=2,45ih2
for= 174,000+10,000+ =000(01.23)(12)(10) = 201,415 FSI
a = [Asfy+Aps-(ps]/(0.85126)
  =[(3.0)(60)+(2,45)(201)]/(0.85)(5)(29)(12) = 0.455
OMn= 0.9 [Asf, + Aps fps] (d-9/2)
     = 0.9[3.0(60)+2.45(201)](10-0.455/2) = 549fik
                                         I'MIN PEINT OF
USE (15) 44'S TOP AT INT. 4EXT, SUPPORTS
```

```
AT MIDSPAN (END SPAN)

d = (1-1.6-0.25 = 9.25"

fps=200, 109 ps 1


q=[(11,3)(60) + 2.45(200)] /0.85(6)(29)(12) = 0.79"

4M=0.9[(11.3)(60) + (2.45)(200)][9.25-0.72]]/12=776ft.k
>423ft.k

USE $6@9"0.C. BOTTOM

"MIN REINF OF
```

Appendix E: Prestressed Hollow Core Plank on Steel



ΔLL = 5 (80(23)) (29)4(1728) = 0.65" < 1000 = 0.97"

: WILL WORK

USE 8"x4'-0" HOLLOW CORE PLANKS W/4-1/2" \$
STRAND PATTERN ON W24 x62 BEAMS

Prestressed Concrete 8"x4'-0" Hollow Core Plank

2 Hour Fire Resistance Rating With 2" Topping

PHYSICAL PROPERTIES Composite Section $A_c = 301 \text{ in.}^2$ Precast b_w = 13.13 in. Ic = 3134 in.4 Precast Shop = 616 in.3 $Y_{bop} = 5.09 \text{ in.}$ Topping $S_{tot} = 902 \text{ in.}^3$ $Y_{co} = 2.91 \text{ in.}$ Precast Step = 1076 in.3 Precast Wt. = 245 PLF $Y_{tot} = 4.91 \text{ in.}$ Precast Wt. = 61.25 PSF

DESIGN DATA

- 1. Precast Strength @ 28 days = 6000 PSI
- 2. Precast Strength @ release = 3500 PSI
- 3. Precast Density = 150 PCF
- 4. Strand = 1/2"Ø 270K Lo-Relaxation.
- Strand Height = 1.75 in.
- Ultimate moment capacity (when fully developed)... 4-1/2"Ø, 270K = 92.3 k-ft at 60% jacking force 6-1/2"Ø, 270K = 130.6 k-ft at 60% jacking force 7-1/2"Ø, 270K = 147.8 k-ft at 60% jacking force
- 7. Maximum bottom tensile stress is 10 √fc = 775 PSI
- 8. All superimposed load is treated as live load in the strength analysis of flexure and shear.
- 9. Flexural strength capacity is based on stress/strain strand relationships.
- 10. Deflection limits were not considered when determining allowable loads in this table.
- Topping Strength @ 28 days = 3000 PSI. Topping Weight = 25 PSF.
- These tables are based upon the topping having a uniform 2" thickness over the entire span. A lesser thickness might occur if camber is not taken into account during design, thus reducing the load capacity,
- 13. Load values to the left of the solid line are controlled by ultimate shear strength.
- Load values to the right are controlled by ultimate flexural strength or fire endurance limits.
 Load values may be different for IBC 2000 & ACI 318-99. Load tables are available upon request.
- 16. Camber is inherent in all prestressed hollow core slabs and is a function of the amount of eccentric prestressing force needed to carry the superimposed design loads along with a number of other variables. Because prediction of camber is based on empirical formulas it is at best an estimate, with the actual camber usually higher than calculated values.

SAFE SUPERIMPOSED SERVICE LOADS									IBC 2006 & ACI 318-05 (1.2 D + 1.6 L)											
Strand SPAN (FEET)																				
Pa	attern	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35
4 - 1/2"ø	LOAD (PSF)	280	248	214	185	159	138	118	102	87	74	62	52	42	\sim					
6 - 1/2"ø	LOAD (PSF)	366	341	318	299	271	239	211	187	165	146	129	114	101	88	77	67	58	50	42
7 - 1/2"ø	LOAD (PSF)	367	342	320	300	282	265	243	221	202	181	161	144	128	114	101	90	79	70	61

NITTERHOUSE

PRODUCTS

2655 Molly Pitcher Hwy. South, Box N Chambersburg, PA 17202-9203 717-267-4505 Fax 717-267-4518

This table is for simple spans and uniform loads. Design data for any of these span-load conditions is available on request. Individual designs may be furnished to satisfy unusual conditions of heavy loads, concentrated loads, cantilevers, flange or stem openings and narrow widths. The allowable loads shown in this table reflect a 2 Hour & 0 Minute fire resistance rating.

3'-10%

4'-0" +0", =

1읍

7å*

 $5\frac{1}{2}$

5½"

8SF2.0T

11/03/08