

Moon Area High School and District Administration Offices  
Moon Township, PA  
4.13.2010



**KRISTOPHER BRICE**  
Construction Management  
AE Senior Thesis Presentation  
The Pennsylvania State University

Project Overview

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

**Kristopher Brice | Construction Management | 4.13.2010**



Image provided by Eckles Architecture & Engineering, Inc

**Project Overview**

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

**Kristopher Brice | Construction Management | 4.13.2010**

**PROJECT OVERVIEW**

- **Owner**  
Moon Area School District
- **Occupancy Type**  
Educational
- **Size**  
291,387 SF
- **Cost**  
\$ 70,802,784 (Design+Construction)
- **Construction Duration**  
January 2009 – November 2010
- **Delivery Method**  
Design-Bid-Build w/CM Agent

**New Moon Area High School &  
District Administration Offices**



**Project Overview**

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

**Kristopher Brice | Construction Management | 4.13.2010**

**PROJECT OVERVIEW**

- **Owner**  
Moon Area School District
- **Occupancy Type**  
Educational
- **Size**  
291,387 SF
- **Cost**  
\$ 70,802,784 (Design+Construction)
- **Construction Duration**  
January 2009 – November 2010
- **Delivery Method**  
Design-Bid-Build w/CM Agent

**New Moon Area High School &  
District Administration Offices**





**Project Overview**

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

**Kristopher Brice | Construction Management | 4.13.2010**

**PROJECT TEAM**

- **Architect & MEP Designer**  
Eckles Architecture & Engineering, Inc.
- **Construction Manager**  
N. John Cunzolo Associates, Inc.
- **General Contractor**  
Nello Construction Company
- **HVAC Contractor**  
A. J. Demor & Sons, Inc.
- **Plumbing Contractor**  
Vrabel Plumbing Co.
- **Electrical Contractor**  
Clista Electric, Inc.

**New Moon Area High School & District Administration Offices**



Project Overview

**Analysis One: BIM with Multiple Prime Contracts**

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

**Kristopher Brice | Construction Management | 4.13.2010**

## ANALYSIS ONE

- **Opportunity**

In the case of the New Moon Area High School, the building and some of its systems were modeled using 3-dimensional software, but the models were not made available to the construction team. There is a great potential for this project and others like it to benefit from BIM in the future.

- **Objective**

Develop a strategy for making BIM available for contractors in a multiple prime delivery by providing the tools needed to smoothly integrate several specific BIM uses into this widely used delivery method.

## New Moon Area High School & District Administration Offices



Image provided by Fickler Architecture & Engineering, Inc.

Project Overview

**Analysis One: BIM with Multiple Prime Contracts**

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

**Kristopher Brice | Construction Management | 4.13.2010**

## CONCLUSIONS

○ **Challenges**

- Concern over liability among designers
- Unpredictable contractor pool
- Model transfer and level of detail (LOD)
- Owner support

○ **Keys to Success**

- Utilize AIA E202-2008 BIM Protocol Exhibit
- Redevelop specifications for coordination
- Consider HVAC contractor for leading coordination
- Start with 3-4 simple BIM uses

## New Moon Area High School & District Administration Offices



Image provided by Eckles Architecture & Engineering, Inc

Project Overview  
 Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

Kristopher Brice | Construction Management | 4.13.2010

## ANALYSIS TWO


- **Opportunity**

The original design of the foundation wall resulted in a disjointed construction sequence along with the need for the temporary enclosures for parts of construction.

- **Objective**

Determine if a bracing design will allow the first floor of Areas C&E to be completed in sequence with the rest of the structure and further reduce the overall construction schedule.

## New Moon Area High School & District Administration Offices



- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design**
  - **Structural Breadth**
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study
- Conclusions
- Questions

## FOUNDATION WALL DESIGN

- **Size**
  - 15 feet tall
  - 18" thick
  - 436 feet long
- **Support**
  - 28" x 40" grade beam
  - 48" concreted caissons

## New Moon Area High School & District Administration Offices




Image provided by Eckles Construction Services, Inc

- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design**
  - **Structural Breadth**
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study
- Conclusions
- Questions

## FOUNDATION WALL DESIGN

- **Size**
  - 15 feet tall
  - 18" thick
  - 436 feet long
- **Support**
  - 28" x 40" grade beam
  - 48" concreted caissons
- **Backfill Requirements**
  - First floor steel and slab must be in place
  - Slab required to be at 28-day strength




- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design**
  - **Structural Breadth**
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study
- Conclusions
- Questions

## FOUNDATION WALL DESIGN

- **Size**
  - 15 feet tall
  - 18" thick
  - 436 feet long
- **Support**
  - 28" x 40" grade beam
  - 48" concreted caissons
- **Backfill Requirements**
  - First floor steel and slab must be in place
  - Slab required to be at 28-day strength

## New Moon Area High School & District Administration Offices



Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

• **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

• Building Envelope Breadth / M.A.E Study

Conclusions


Questions

Kristopher Brice | Construction Management | 4.13.2010

## FOUNDATION WALL DESIGN

- **Size**
  - 15 feet tall
  - 18" thick
  - 436 feet long
- **Support**
  - 28" x 40" grade beam
  - 48" concreted caissons
- **Backfill Requirements**
  - First floor steel and slab must be in place
  - Slab required to be at 28-day strength

New Moon Area High School &  
District Administration Offices





Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

## BRACING DESIGN AND LAYOUT

- **Mabey Bridge & Shore, Inc – System 160 Bracing**
  - Distribution within 20 miles of site
  - Relatively lightweight
  - Small enough not to interfere with construction
  - Favorable compressive strength

## New Moon Area High School & District Administration Offices



Image provided by Mabey Bridge & Shore, Inc

Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study


Conclusions

Questions

## BRACING DESIGN AND LAYOUT

- **Mabey Bridge & Shore, Inc – System 160 Bracing**
  - Distribution within 20 miles of site
  - Relatively lightweight
  - Small enough not to interfere with construction
  - Favorable compressive strength
- **Bracing Layout**
  - Braces to be spaced at 10' O. C.
  - 44 total braces required (Area C: 21, Area E: 23)

## New Moon Area High School & District Administration Offices




- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design**
  - **Structural Breadth**
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study
- Conclusions
- Questions

## BRACING DESIGN AND LAYOUT

- **Mabey Bridge & Shore, Inc – System 160 Bracing**
  - Distribution within 20 miles of site
  - Relatively lightweight
  - Small enough not to interfere with construction
  - Favorable compressive strength
- **Bracing Layout**
  - Braces to be spaced at 10' O. C.
  - 44 total braces required (Area C: 21, Area E: 23)
- **Additional Requirements**
  - 3' section of 12" thickened slab centered on the anchoring point of braces to prevent slab failure

## New Moon Area High School & District Administration Offices



Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

**Kristopher Brice | Construction Management | 4.13.2010**

## SCHEDULE IMPACT

- **Brace Installation**
  - Must wait for slab on grade to be placed
  - Requires two man crew for installation
  - Three days required for each area
- **Schedule Change**
  - 37 day reduction in the time to complete structure
  - Potential \$60,000 savings in general conditions
  - Structure lies on the critical path

## New Moon Area High School & District Administration Offices



Image provided by Mabey Bridge & Shore, Inc

Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

Kristopher Brice | Construction Management | 4.13.2010

## SCHEDULE IMPACT

- **Brace Installation**
  - Must wait for slab on grade to be placed
  - Requires two man crew for installation
  - Three days required for each area
- **Schedule Change**
  - 37 day reduction in the time to complete structure
  - Potential \$60,000 savings in general conditions
  - Structure lies on the critical path
- **Construction Sequence**
  - Wall can be backfilled shortly after forms are removed
  - Grade beams in Areas C and E installed much earlier

New Moon Area High School &  
District Administration Offices



Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

Kristopher Brice | Construction Management | 4.13.2010

## SCHEDULE IMPACT

- **Brace Installation**
  - Must wait for slab on grade to be placed
  - Requires two man crew for installation
  - Three days required for each area
- **Schedule Change**
  - 37 day reduction in the time to complete structure
  - Potential \$60,000 savings in general conditions
  - Structure lies on the critical path
- **Construction Sequence**
  - Wall can be backfilled shortly after forms are removed
  - Grade beams in Areas C and E installed much earlier

New Moon Area High School &  
District Administration Offices



Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

Kristopher Brice | Construction Management | 4.13.2010

## SCHEDULE IMPACT

- **Brace Installation**
  - Must wait for slab on grade to be placed
  - Requires two man crew for installation
  - Three days required for each area
- **Schedule Change**
  - 37 day reduction in the time to complete structure
  - Potential \$60,000 savings in general conditions
  - Structure lies on the critical path
- **Construction Sequence**
  - Wall can be backfilled shortly after forms are removed
  - Grade beams in Areas C and E installed much earlier

New Moon Area High School &  
District Administration Offices



Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

Kristopher Brice | Construction Management | 4.13.2010

## SCHEDULE IMPACT

- **Brace Installation**
  - Must wait for slab on grade to be placed
  - Requires two man crew for installation
  - Three days required for each area
- **Schedule Change**
  - 37 day reduction in the time to complete structure
  - Potential \$60,000 savings in general conditions
  - Structure lies on the critical path
- **Construction Sequence**
  - Wall can be backfilled shortly after forms are removed
  - Grade beams in Areas C and E installed much earlier

New Moon Area High School &  
District Administration Offices





Project Overview

Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions


Questions

Kristopher Brice | Construction Management | 4.13.2010

## SCHEDULE IMPACT

- **Brace Installation**
  - Must wait for slab on grade to be placed
  - Requires two man crew for installation
  - Three days required for each area
- **Schedule Change**
  - 37 day reduction in the time to complete structure
  - Potential \$60,000 savings in general conditions
  - Structure lies on the critical path
- **Construction Sequence**
  - Wall can be backfilled shortly after forms are removed
  - Grade beams in Areas C and E installed much earlier

New Moon Area High School &  
District Administration Offices



Project Overview  
 Analysis One: BIM with Multiple Prime Contracts

**Analysis Two: Foundation Wall Bracing Design**

- **Structural Breadth**

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

Conclusions

Questions

## COST IMPACT

- **Brace Rental and Installation**
  - Area C (10 weeks): \$11,728
  - Area E (9 weeks): \$11,578
  - Installation: \$1,918
- **Additional Concrete**
  - Thickened slab: \$2,132
- **Total additional Cost to General Contractor**
  - **\$27,356**

## New Moon Area High School & District Administration Offices

Original Wall Design WITH Bracing															
Caissons (3,000 psi)	286	CY	\$	97.16	\$	10.39	\$	0.41	\$	194.32	\$	123.16	\$	35,223.76	
Caisson Reinforcing	11	Tons	\$	1,417.48	\$	712.64	\$	-	\$	2,130.12	\$	2,714.43	\$	29,858.73	
Grade Beams (4,000 psi)	119	CY	\$	101.97	\$	11.03	\$	4.90	\$	117.90	\$	133.85	\$	15,928.15	
Grade Beam Reinforcing	13	Tons	\$	1,345.40	\$	413.96	\$	-	\$	1,759.36	\$	2,146.73	\$	27,907.49	
Concrete Walls (4,000 psi)	371	CY	\$	101.97	\$	18.07	\$	8.04	\$	128.08	\$	147.86	\$	54,856.06	
Wall Reinforcing	16	Tons	\$	1,417.48	\$	497.80	\$	-	\$	1,915.28	\$	2,373.83	\$	37,981.28	
12" Thickened Slab Concrete	16	CY	\$	101.97	\$	10.75	\$	4.77	\$	117.49	\$	133.25	\$	2,132.00	
Bracing System Labor	44	Each	\$		\$	39.63	\$		\$	39.63	\$	43.59	\$	1,918.09	
Area C - Mabey System 160 Wall Brace Rental (23 Braces @ 10)	10	Week							\$	1,040.00	\$	1,112.80	\$	11,728.00	
Area E - Mabey System 160 Wall Brace Rental (23 Braces @ 9)	9	Week							\$	1,140.00	\$	1,219.80	\$	11,578.20	
													<b>TOTAL:</b>	<b>\$</b>	<b>229,111.76</b>

Project Overview

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**

- **Building Envelope Breadth / M.A.E Study**

Conclusions

Questions

**Kristopher Brice | Construction Management | 4.13.2010**

## ANALYSIS THREE

- **Problem**

Delays in the installation of the brick veneer resulted in additional delays in the placement of windows and curtain walls, further pushing back the building dry date.

- **Objective**

Select a precast wall system that will ensure the building enclosure remains on schedule while also adhering to the original design standards.

New Moon Area High School &  
District Administration Offices



Image provided by Eckles Construction Services, Inc

Project Overview

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**

- **Building Envelope Breadth / M.A.E Study**

Conclusions

Questions

## SLENDERWALL PRECAST

○ **SlenderWall Benefits**

- Lightweight design – 30 lbs/ft<sup>2</sup>
- Includes 16 gauge exterior metal framing
- Can be designed as load bearing
- Reduced installation times with Lift-and-Release system
- Increased floor space
- Large variety of colors, textures and finishes available

## New Moon Area High School & District Administration Offices




Image courtesy of SlenderWall

- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design
  - Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**


- **Building Envelope Breadth / M.A.E Study**

- Conclusions
- Questions

## PANEL LAYOUT

- **Panel Sizes**
  - Building not ideally designed for precast application
  - 26 different sizes consisting of 7 different widths
  - Layout requires slight architectural changes
  - Efficiency can be increased with changes to façade details around the gymnasium and auditorium

## New Moon Area High School & District Administration Offices



- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design
  - Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**

- **Building Envelope Breadth / M.A.E Study**

- Conclusions
- Questions

## STRUCTURAL REQUIREMENTS

- **Cavity Wall**
  - Design load 50 lbs/ft<sup>2</sup>
  - Majority of load carried by foundation
- **SlenderWall**
  - Design load 30 lbs/ft<sup>2</sup>
  - Can be load bearing
  - Designed to withstand differential movement
- **Conclusion**
  - Structural design will not be affected
  - Could result in overall savings if designed as load bearing

## New Moon Area High School & District Administration Offices




Image courtesy of SlenderWall

Project Overview  
 Analysis One: BIM with Multiple Prime Contracts  
 Analysis Two: Foundation Wall Bracing Design  
 • Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**


- **Building Envelope Breadth / M.A.E Study**

Conclusions  
 Questions

## THERMAL PERFORMANCE

- **R-Value Comparison**
  - Cavity Wall: 22.086
  - SlenderWall: 22.091
- **Heat Transfer**
  - Summer
    - Cavity Wall: 28,395 Btu/hr
    - SlenderWall: 28,389 Btu/hr
  - Winter
    - Cavity Wall: -89,554 Btu/hr
    - SlenderWall: -89,534 Btu/hr
- **Conclusion**
  - The thermal performance of the SlenderWall system will not affect the design of the mechanical system.

## New Moon Area High School & District Administration Offices



Project Overview  
 Analysis One: BIM with Multiple Prime Contracts  
 Analysis Two: Foundation Wall Bracing Design  
 • Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**


- Building Envelope Breadth / M.A.E Study

Conclusions  
 Questions

## MOISTURE PERFORMANCE

- Condensation Analysis (H.A.M. Toolbox)
  - Cavity Wall
    - Summer: No Condensation
    - Winter: No Condensation
  - SlenderWall
    - Summer: No Condensation
    - Winter: Chance of 5 grains/(ft<sup>2</sup>-day) in air cavity
- Preventative Treatments
  - Apply vapor barrier to back of studs
  - Use foil backed insulation

## New Moon Area High School & District Administration Offices





Project Overview  
Analysis One: BIM with Multiple Prime Contracts  
Analysis Two: Foundation Wall Bracing Design  
• Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**


- **Building Envelope Breadth / M.A.E Study**

Conclusions  
Questions

## SCHEDULE IMPACTS

- **Installation Sequence**
  - Begin during final week of steel construction
  - Overlaps steel construction by three days
  - Start at North façade and continue clockwise
  - Lift-and-Release systems requires 20 minutes per panel

## New Moon Area High School & District Administration Offices



Project Overview  
 Analysis One: BIM with Multiple Prime Contracts  
 Analysis Two: Foundation Wall Bracing Design  
 • Structural Breadth

**Analysis Three: SlenderWall Architectural Precast**  
 • **Building Envelope Breadth / M.A.E Study**

Conclusions  
 Questions

## SCHEDULE IMPACTS

- **Installation Sequence**
  - Begin during final week of steel construction
  - Overlaps steel construction by three days
  - Start at North façade and continue clockwise
  - Lift-and-Release systems requires 20 minutes per panel
- **Schedule Change**
  - Original Duration: 164 days
  - SlenderWall Duration: 39 Days
  - **Difference in completion dates: -32 days**

### Slenderwall Precast vs. Brick Veneer Schedule Comparison

Original Construction Schedule			
Type	Start Date	Finish Date	Total Duration
SlenderWall	3/10/2010	5/3/2010	39
Brick Veneer	10/29/2009	6/15/2010	164
<b>Total Savings:</b>		<b>32 Days</b>	

Project Overview  
 Analysis One: BIM with Multiple Prime Contracts  
 Analysis Two: Foundation Wall Bracing Design  
 • Structural Breadth  
**Analysis Three: SlenderWall Architectural Precast**  
 • **Building Envelope Breadth / M.A.E Study**  
 Conclusions  
 Questions

Kristopher Brice | Construction Management | 4.13.2010

## COST IMPACT

- **Cavity Wall Cost**
  - Includes all building components not required by SlenderWall
  - Total: \$2,289,946
- **SlenderWall Cost**
  - Based on average cost of \$40/SF
  - Includes delivery, erection and insulation
  - Total: \$2,012,912
- **Total Savings to the Owner**
  - **\$277,034**

## New Moon Area High School & District Administration Offices

SlenderWall Precast vs. Brick Veneer Cost Comparison	
Added Material	
Material	Cost
SlenderWall	\$ 1,929,694
Foil Backed Blanket Insulation	\$ 83,218
<b>Total:</b>	<b>\$ 2,012,912</b>
Deleted Material	
Material	Cost
Brick Veneer	\$ 1,765,620.80
Extruded Polystyrene Insul.	\$ 123,553.60
Exterior Sheathing	\$ 82,368.44
Air Barrier	\$ 73,884.00
Exterior Metal Studs	\$ 244,519.74
<b>Total:</b>	<b>\$ 2,289,946.58</b>
<b>Cost Savings:</b>	<b>\$ 277,034.09</b>

- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design
  - Structural Breadth
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study

**Conclusions**

Questions

**CONCLUSIONS**

- **Analysis One: BIM with Multiple Prime Contracts**
  - Change in contracts and specifications
  - Need owner support
  - Not ready for the change

**New Moon Area High School &  
District Administration Offices**



*Image provided by Eckles Architecture & Engineering, Inc*

- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design
  - Structural Breadth
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study

**Conclusions**

Questions

## CONCLUSIONS

- **Analysis One: BIM with Multiple Prime Contracts**
  - Change in contracts and specifications
  - Need owner support
  - Not ready for the change
- **Analysis Two: Foundation Wall Bracing Design**
  - 37 day reduction in construction schedule
  - \$27,356 cost to general contractor
  - More efficient construction sequence

## New Moon Area High School & District Administration Offices



Image provided by Mabey Bridge & Shore, Inc

- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design
  - Structural Breadth
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study

**Conclusions**

Questions

## CONCLUSIONS

- **Analysis One: BIM with Multiple Prime Contracts**
  - Change in contracts and specifications
  - Need owner support
  - Not ready for the change
- **Analysis Two: Foundation Wall Bracing Design**
  - 37 day reduction in construction schedule
  - \$27,356 cost to general contractor
  - More efficient construction sequence
- **Analysis Three: SlenderWall Architectural Precast**
  - 32 day reduction in façade installation
  - \$277,034 saving to the owner
  - Decision must be made in the beginning

## New Moon Area High School & District Administration Offices



Image courtesy of SlenderWall

Project Overview

Analysis One: BIM with Multiple Prime Contracts

Analysis Two: Foundation Wall Bracing Design

- Structural Breadth

Analysis Three: SlenderWall Architectural Precast

- Building Envelope Breadth / M.A.E Study

**Conclusions**

Questions

**ACKNOWLEDGMENTS**

**Eckles Construction Services, Inc.**

Kenneth Holsopple  
 John Pappas  
 Brian Fulkerson

**Eckles Architecture & Engineering, Inc.**

Cassandra Renninger  
 Susan Cooper

**Nello Construction**

Jerry Falso

**The Pennsylvania State University**

Dr. Christopher Magent  
 Professor Holland  
 Professor Parfitt  
 Dr. Richard Behr  
 Craig Dubler

**New Moon Area High School &  
 District Administration Offices**

**Barber & Hoffman Consulting Engineers**

James Pospisil

**Mabey Bridge & Shore, Inc.**

James Porreca

**Hranec Corporation**

Mike Reese

**W.G. Tomko, Inc.**

Rich Miller

**SlenderWall**

Frederic Beck

*... And most of all, I would like to THANK my family and friends!*

- Project Overview
- Analysis One: BIM with Multiple Prime Contracts
- Analysis Two: Foundation Wall Bracing Design
  - Structural Breadth
- Analysis Three: SlenderWall Architectural Precast
  - Building Envelope Breadth / M.A.E Study

Conclusions

**Questions**

**Kristopher Brice | Construction Management | 4.13.2010**

**QUESTIONS?**

**New Moon Area High School &  
District Administration Offices**



Image provided by Eckles Architecture & Engineering, Inc