

Pearland Recreation Center and Natatorium Pearland, Texas



Technical Report #2

**Prepared By: Matt Smiddy
Faculty Consultant: Dr. Magent**

Submitted: October 28, 2009

Table of Contents:

Section 1 – Executive Summary	Pg. 3
Section 2 – Detailed Project Schedule	Pg. 4
Section 3 – Site Layout Planning	Pg. 8
Section 4 – Detailed Structural Systems Estimate	Pg. 12
Section 5 – General Conditions Estimate	Pg. 14
Section 6 – Critical Industry Issues	Pg. 15
Appendix 1 – Detailed Project Schedule	Pg. 18
Appendix 2 – Detailed Structural System Estimate	Pg. 22
Appendix 3 – Detailed Structural System Cost Estimate Hand Take-Offs	Pg. 24
Appendix 4 – RS Means 2009 Building Construction Cost Data Sheets	Pg. 29
Appendix 5 – General Conditions Estimate	Pg. 46

Section 1: Executive Summary

This technical report contains a detailed project schedule and structural system cost estimate, general conditions estimate, and site layout plans for four key phases of construction for the Pearland Recreation Center and Natatorium. The report concludes with an overview of the PACE Roundtable Conference.

Pearland's 11 month project schedule begins with the Notice to Proceed on April 20, 2009 and concludes with Substantial Completion on May 12, 2010. The schedule breaks the building into two portions; the recreation center and the natatorium. These halves of the building have significantly different designs, making it reasonable to separate the construction of the building. The natatorium has a glulam structural system and houses a swimming pool while the recreation center uses a steel structural system and features a competitive gym among other athletic courts and rooms.

Structural system construction cost estimate for the building is \$4,427,368.67. This cost estimate was created by taking a typical bay in the recreation center and extrapolating this cost to obtain a cost for the entire building's structural system. Pricing for this estimate was obtained from RS Means 2009 Building Construction Cost Data and contractor quotes. A general conditions cost estimate of \$560,314.50 was also calculated. Project Management expenses were the majority (>60%) of the general conditions cost.

Site layout plans were created for the excavation, foundations, structural framing erection, and enclosures phases of construction. Construction generally progresses from the northwest corner to the southeast corner of the building. No critical logistical issues were apparent. The site is very open with ample space for material staging and storage. Temporary utilities are easily accessible off of Bailey Road on the south side of the site.

An overview of the PACE Roundtable Conference October 14-15, 2009 and some ongoing issues in the construction industry wrap up the report. PACE Roundtable provided an excellent opportunity to interact with industry members. The conference supplied some good potential thesis research topics, such as considering why the selected project delivery method was chosen by the owner and why no sustainable design was implemented into the project.

Section 2: Detailed Project Schedule

Construction of the Pearland Recreation Center and Natatorium will begin with the Notice to Proceed on April 20, 2009 and conclude with Substantial Completion on May 12, 2010. The complete detailed schedule is available in Appendix 1. To create the construction schedule for the project the building was split into two portions: recreation center and natatorium. This was done because these two portions of the building are very different and will be constructed in a different manner due to the swimming pool and glulam structural system in the natatorium. Table 2.1 – Milestone Date Comparison compares some key construction milestone dates in the recreation center versus the natatorium.

Table 2.1 – Milestone Date Comparison

Milestone	Recreation Center	Natatorium
Notice to Proceed	4/20/2009	4/20/2009
Top Out	8/7/2009	8/30/2009
Dry-In	10/23/2009	12/9/2009
Substantial Completion	5/12/2010	4/28/2010

Structure and Enclosure:

Construction of the building’s structural system and enclosure is sequenced as shown in Figure 2.2 - Structural and Enclosure Trade Construction Sequence




Figure 2.2 – Structural and Enclosure Trade Construction Sequence

Interiors:

Following ‘Dry-In,’ a ‘parade of trades’ construction sequence is applied; that is only one trade works in each space at a time and each trade follows the previous. Figure 2.3 - Interior Trades Construction Sequence shows the order of the interior ‘parade of trades’.




Figure 2.3 - Interior Trades Construction Sequence

Following the interior ‘parade of trades’ a number of specialty items are installed, such as casework, gym flooring, and gym equipment. See the detailed schedule in Appendix 1 for all activities.

Recreation Center:

Construction of the recreation center progresses counterclockwise through the building in three phases. Figure 2.4 – Recreation Center Construction Phase Locations shows the locations of these three phases.




Figure 2.4 – Recreation Center Construction Phase Locations

Second floor activities only have two phases since the gym is double height and the small portion of phase three that has a second level is combined with phase 2 for the second floor.

Natatorium:

There is no phasing of construction in the natatorium as there was in the recreation center. Construction sequencing in the natatorium will revolve around the swimming pool construction. See Figure 2.5 – Swimming Pool Construction Sequence for the sequence of swimming pool construction activities.




Figure 2.5 – Swimming Pool Construction Sequence

Construction of other portions of the natatorium will be occurring throughout the pool construction; however it is critical that the finishing and tiles in the swimming pool are the last activity to occur in the swimming pool area in order to protect the work. Immediately after this is completed, the pool will be filled with water and testing and chemical balancing will begin.

Section 3: Site Layout Planning

Site layout for the Pearland Recreation Center and Natatorium is greatly simplified due to a large site. Consistent across all phases of the project are the dumpsters in the northeast corner of the site with a dedicated entrance off of Bailey road for access to empty them, porta-potties in the northeast corner of the parking lot, the construction offices on the east side of the site, the temporary transformer in the southeast corner of the building, temporary utilities running to the southeast corner of the building from Bailey Rd, contractor parking on the south side of the site, and the site entrance off of Bailey road on the south side of the site.

Site layout for the excavation phase of construction is shown in Figure 3.1 – Excavation Phase Site Plan. Excavation will begin from the northwest corner of the building and proceed towards the southeast corner of the building as shown. Dump trucks will arrive and circulate through the site to remove soil as shown.




Figure 3.1 – Excavation Phase Site Plan

Figure 3.2 – Foundations Phase Site Plan shows the site layout for the foundations phase of construction. Foundations work will again progress from the northwest corner to the southeast corner of the building. A rebar yard, with access provided for flatbed rebar truck deliveries, is provided in the southwest corner of the site. The pump truck and concrete trucks will circulate as shown. They will only be present on site during concrete pours. The location of the pump truck will move eastward on the site as work progresses. A contractor material storage area is also provided in the southeast corner of the site.




Figure 3.2 – Foundations Phase Site Plan

The project site begins to become more congested as the structural framing erection phase of construction begins. Site layout for this phase is shown in Figure 3.3 – Structural Framing Erection Phase Site Plan. Erection of the steel and glulam will proceed from the west end of the building to the east end. Steel and glulam members will be delivered and unloaded in the shake-out area in the southwest corner of the site. Two cranes will be erecting the steel and glulam on site, one on the north side and one on the south side of the building as shown. Steel joists will be delivered to this shake-out area as well, but will then be moved to the joist shake-out area on the north side of the site to be prepared for final erection. There will be an access point for stocking material to the building located at the southwest corner of the building. This will be done using front loaders.




Figure 3.3 – Structural Framing Erection Phase Site Plan

Enclosures is the final phase of construction. Work in this phase will progress in a clockwise direction, first around the recreation center than proceeding to go around the natatorium. There will be a contractor material staging area in the southwest corner of the site. This area will be used by contractors to unload materials from trucks as shown. There are also material storage areas on the north side and in the southeast corner of the site. Materials will again be stocked to the building through the access point at the southwest corner of the building using front loaders. Figure 3.4 – Enclosure Phase Site Plan shows the site layout for this phase of construction.




Figure 3.4 – Enclosure Phase Site Plan

Section 4: Detailed Structural Systems Estimate

A detailed structural system construction cost estimate for the Pearland Recreation Center and Natatorium project yielded just over \$4,425,000, or about \$42/SF. This cost includes all labor, equipment, and material required for construction of the caissons, concrete, structural steel, steel decking, joists, trusses, wood decking, and glulam structural framing. A break-down of the cost estimate is shown in Table 4.1 – Detailed Structural System Estimate Summary. The complete estimate is available in Appendix 2.

Table 4.1 – Detailed Structural System Estimate Summary

Cost Breakdown Summary		
Dev.	Item	Total Cost
02465	Caissons	\$526,841.25
03220	Rebar	\$60,681.51
03221	WWF	\$18,041.18
03310	3000 psi concrete	\$145,747.62
03311	3500 psi concrete	\$36,687.77
03312	Concrete Finishing	\$15,161.58
03313	Concrete Forming	\$471,115.84
03314	Vapor Barrier	\$123,562.53
03315	5" Concrete Edge Form	\$2,729.14
03316	3" Pour Stop	\$821.42
03500	Roof Deck	\$626,272.50
05100	Structural Steel	\$702,167.12
05200	Steel Floor Joists	\$390,755.16
05300	Metal Deck	\$66,784.03
06100	Wood Trusses	\$170,000.00
06110	Glulam (Decking, Purlins, and Columns)	\$1,070,000.00
	Total Cost	\$4,427,368.67

Pricing for the estimate was obtained using RS Means 2009 Building Construction Cost Data and contractor information. RM Rodgers provided the glulam pricing and Tectum Inc. provided pricing for the Tectum E roof decking system over the recreation center. All other pricing information came from RS Means.

The estimate was created by doing a detailed take-off of a typical bay of the building and extrapolating. Figure 4.2 – Location of Typical Bay Used for Estimate shows the 2520 SF (both levels) area, between gridlines G-J and 1-2, which was used.




Figure 4.2 – Location of Typical Bay Used for Estimate

Recreation Center:

Using the total cost estimate obtained from this bay, a cost/SF value was calculated and multiplied by the square footage of the recreation center. This cost/SF did not include the Tectum 'E' roof decking or roof trusses. The cost of these two items were estimated for the entire recreation center then added to the extrapolated cost estimate. See Appendix 2 for the complete detailed cost estimate and Appendix 3 for the hand take-off quantities used to develop this detailed estimate.

Natatorium:

Modifications had to be made to the cost/SF value to estimate the natatorium's structural system cost since the structural system is glulam instead of steel, like the recreation center. Additionally, there are no elevated slabs in the natatorium. To account for these differences the structural steel and elevated deck costs were subtracted from the recreation center's cost/SF. This new cost/SF was then multiplied by the total square footage of the natatorium. This extrapolated value was added to the glulam columns, purlins, and decking value provided by RM Rodgers for the total natatorium structural system construction cost. See Appendix 2 for the complete detailed cost estimate and Appendix 3 for the hand take-off quantities used to develop this detailed estimate.

Pricing sheets for all RS Means values are available in Appendix 4. These costs include all waste factors.

Section 5: General Conditions Estimate

A general conditions cost of just over under \$2 million was estimated for the Pearland Recreation Center and Natatorium project. This estimate was obtained using pricing from RS Means and EMJ Corporation. See Appendix 5 for the complete estimate.

The general conditions estimate contains 5 portions: project management, temporary facilities, temporary utilities, cleaning, and miscellaneous. Project management and insurance, bond, and O&P are the primary costs in the general conditions, totaling almost \$1.9 million. Temporary facilities includes items such as job office trailers, temporary sanitary facilities, and barricades. All material hoisting (lifts, cranes etc.) and heavy equipment are to be provided by the contractors so it was not necessary to include these items. Temporary utilities consists of costs for temporary electric, water, and telephone during construction. The cleaning section will pay for weekly site clean-up and final building clean-up. A miscellaneous section with items such as hand tools, safety, and blue prints is also included. A 2% bond, 3% insurance, and 10% overhead and profit are also included in the estimate. These percentages are of the total project cost (\$16,786,542 as per Tech #1 estimate).

Appendix 4 contains RS Means cost data that was used for the estimate.

Section 6: Critical Industry Issues

PACE Roundtable 2010 was a great opportunity to hear what is happening in the construction industry. Some of the key topics that were discussed during the conference were energy efficiency in buildings, building information modeling (BIM), and business and networking. There were also panel discussions with industry members regarding some interesting developments in the construction market and with students about communication opportunities in emerging technology. I was unfortunately only able to attend the morning session of the conference on Thursday due to another commitment.

PACE Roundtable 2010 kicked off with a networking reception and dinner on Wednesday, October 14, 2009. The reception was a great opportunity to catch up with the industry members. I was able to have a lengthy conversation with Keith Mondock from Turner Construction, who I will be having a second interview with in a few weeks. We discussed my thesis project and how it was progressing. It was a great conversation to lead into my interview.

At dinner I sat beside John Bechtel, of Pennsylvania State University Office of the Physical Plant. Our dinner conversation included a discussion about the construction of the Millennium Science Complex and some upcoming projects at Penn State. Following dinner, Dr. Riley wrapped up the evening with a brief preview of Thursday's schedule.

Thursday morning began with an industry panel discussion of current construction industry issues. Some interesting topics that were discussed during this session included active market sectors, BIM developments, and strategies contractors were using to cope with the economic conditions. The entire industry is seeing far less work than a year ago and backlog is shrinking. The few projects that are being put out for bid are seeing many more bidders. This large influx of bidders on projects has driven down bid amounts. It was pointed out that these low bidders are frequently small firms getting in over their heads and there will likely be a significant increase in failure among construction companies. Some of the active industry sectors include healthcare, senior living, and energy retrofits. Residential projects were cited as being the most inactive due to the tightened credit markets.

During this panel discussion there was also an interesting discussion about how companies are coping with the downturn in available work. The larger companies stated that the reduction in work has allowed them to spend more resources on research, particularly in BIM. On the contrary, the small firms said they have reduced their progressions in BIM implementation due to shrinking resources and an increased need to focus on marketing and obtaining work. Employee training has also been more active. Firms are seizing the opportunity to educate their employees during the lull. Most importantly, companies have ramped up their marketing efforts. They have not only been marketing to past

and current clients, but also have started seeking out potential clients that they have never worked with before.

Following the industry panel there were three break-out groups with different focus topics: energy and the construction industry, business and networking, and BIM executive planning. I attended the business and networking session facilitated by Chris Magent because I have already been exposed to BIM and energy in buildings in academic classes, however business and networking is a topic I have not had much exposure to.

In the business and networking session the need for diversity in market sectors was emphasized. I found it interesting that one of the methods being used to achieve this was joint-ventures. Joint-ventures have allowed companies that haven't worked in a certain sector to team up with a firm that is established in that sector and obtain experience in the new type of project. At the same time, these joint-ventures have been created to increase bonding capacity and other project requirements such as minority company involvement in project teams. A question was posed regarding the difficulty in obtaining cooperation from both firms in a joint-venture; however from experience it has been noted that as long as both companies have similar values there are no problems because both project teams can focus on the same goal: providing the owner with a quality project.

Another topic that was brought up in the business and networking session was trends in project delivery methods. The industry members all reported that they were seeing a rise in the number of lump sum bids coming in. It was acknowledged that this increase can be primarily attributed to repeat clients no longer having projects, resulting in a shift of the types of clients. It was also mentioned, primarily by Balfour Beatty, that there has been an increase in Design-Build projects due to the increased government work that has been created by the stimulus act. Integrated Project Delivery (IPD) was also discussed during this time. Rob Leicht from DPR Construction joined our discussion at this time to act as an 'expert' in this area since he has done significant research on the topic and DPR is a leader in this delivery method. There was confusion surrounding the definition of IPD. Rob defined this as an 'integrated design-bid-build' contract that is signed by the owner, designer, construction manager, and subcontractor and allocated risk between all parties. The best definition was from Southland Industries: 'A Design-Build project done right.'

Attending the PACE Roundtable gave me some ideas of potential thesis topics. The first idea I may want to pursue would be regarding LEED/Sustainability. My project is completely state funded; however there are no sustainable aspects in the building. I may want to speak with the owner and first determine if there was a reason for this and if not, possibly analyze the implementation of some sustainable aspects into the design as well as the construction. I want to also try

to apply some BIM applications, such as 3-D coordination, into my research; however this may be very difficult since I still have not been able to obtain the 2-D CAD drawings for the project.

Two other issues I may want to investigate involve the project delivery method. It is currently being delivered via a Design-Bid-Build method. I may want to look at what an adjustment in the delivery method may do to the project. The project is also being funded by 3 different sources, however only one of the parties are overseeing the construction of the project. There may be some interesting issues to look at with this 'joint-venture' as well.

The PACE Roundtable was a great opportunity for me to not only interact on an interpersonal level with key industry members, but also learn first hand about important developing issues in the construction industry. Without this conference, coming up with ideas for my thesis research would have been much more difficult.

Key Contacts:



Robert Leicht – DPR Construction – Integrated Project Delivery

John Bechtel – Penn State OPP – Integrated Project Delivery/Owner's
Perspective of Delivery Method

Appendix 1

Detailed Project Schedule

Detailed Project Schedule



Pearland Recreation Center and Natatorium – Tech Report #2

ID	Task Name	Duration	Start	Finish	Predecessor	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter		
						Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May
50	Recreation Center - 1st Floor MEP Overhead Rough-In Phase B	10 days	Mon 11/18/09	Fr 11/27/09 49																
52	Recreation Center - 1st Floor Interior Framing Phase A	10 days	Mon 11/18/09	Fr 11/27/09 49																
51	Recreation Center - 1st Floor MEP Overhead Rough-In Phase C	10 days	Mon 11/20/09	Fr 12/11/09 50																
53	Recreation Center - 1st Floor Interior Framing Phase B	10 days	Mon 11/20/09	Fr 12/11/09 50,52																
55	Recreation Center - 1st Floor MEP Rough-In Phase A	10 days	Mon 11/20/09	Fr 12/11/09 52																
135	Natatorium - Dry-In	0 days	Wed 12/30/09	Wed 12/30/09 134																
138	Natatorium - Overhead Rough-In	10 days	Thu 12/10/09	Wed 12/23/09 135																
54	Recreation Center - 1st Floor Interior Framing Phase C	10 days	Mon 12/14/09	Fr 12/25/09 51,53																
56	Recreation Center - 1st Floor MEP Rough-In Phase B	10 days	Mon 12/14/09	Fr 12/25/09 53,55																
58	Recreation Center - 1st Floor Drywall and Insulation Phase A	10 days	Mon 12/14/09	Fr 12/25/09 55																
70	Recreation Center - 2nd Floor MEP Overhead Rough-In Phase A	5 days	Mon 12/21/09	Fr 12/25/09 51																
139	Natatorium - Interior Framing	10 days	Thu 12/24/09	Wed 1/6/10 138																
57	Recreation Center - 1st Floor MEP Rough-In Phase C	10 days	Mon 12/28/09	Fr 1/6/10 54,56																
59	Recreation Center - 1st Floor Drywall and Insulation Phase B	10 days	Mon 12/28/09	Fr 1/6/10 56,58																
61	Recreation Center - 1st Floor Finishing Phase A	10 days	Mon 12/28/09	Fr 1/6/10 58																
71	Recreation Center - 2nd Floor MEP Overhead Rough-In Phase B	5 days	Mon 12/28/09	Fr 1/6/10 70																
72	Recreation Center - 2nd Floor Interior Framing Phase A	5 days	Mon 12/28/09	Fr 1/6/10 70																
73	Recreation Center - 2nd Floor Interior Framing Phase B	5 days	Mon 1/6/10	Fr 1/6/10 71,72																
74	Recreation Center - 2nd Floor MEP Rough-In Phase A	5 days	Mon 1/6/10	Fr 1/6/10 72																
140	Natatorium - Drywall & Insulation	10 days	Thu 1/7/10	Wed 1/20/10 139																
60	Recreation Center - 1st Floor Drywall and Insulation Phase C	10 days	Mon 1/11/10	Fr 1/22/10 57,59																
62	Recreation Center - 1st Floor Finishing Phase B	10 days	Mon 1/11/10	Fr 1/22/10 59,61																
64	Recreation Center - 1st Floor Painting Phase A	10 days	Mon 1/11/10	Fr 1/22/10 61																
75	Recreation Center - 2nd Floor MEP Rough-In Phase B	5 days	Mon 1/11/10	Fr 1/15/10 73,74																
76	Recreation Center - 2nd Floor Drywall & Insulation Phase A	5 days	Mon 1/11/10	Fr 1/15/10 74																
77	Recreation Center - 2nd Floor Drywall & Insulation Phase B	5 days	Mon 1/18/10	Fr 1/22/10 75,76																
78	Recreation Center - 2nd Floor Finishing Phase A	5 days	Mon 1/18/10	Fr 1/22/10 76																
141	Natatorium - Finishing	10 days	Thu 1/21/10	Wed 2/2/10 140																
63	Recreation Center - 1st Floor Finishing Phase C	10 days	Mon 1/25/10	Fr 2/5/10 60,62																
65	Recreation Center - 1st Floor Painting Phase B	10 days	Mon 1/25/10	Fr 2/5/10 62,64																
67	Recreation Center - 1st Floor MEP Fitout Phase A	10 days	Mon 1/25/10	Fr 2/5/10 64																
79	Recreation Center - 2nd Floor Finishing Phase B	5 days	Mon 1/25/10	Fr 1/29/10 77,78																
80	Recreation Center - 2nd Floor Painting Phase A	5 days	Mon 1/25/10	Fr 1/29/10 78																
81	Recreation Center - 2nd Floor Painting Phase B	5 days	Mon 2/1/10	Fr 2/5/10 79,80																
82	Recreation Center - 2nd Floor MEP Fitout Phase A	5 days	Mon 2/1/10	Fr 2/5/10 80																
142	Natatorium - Painting	10 days	Thu 2/4/10	Wed 2/17/10 141																
68	Recreation Center - 1st Floor Painting Phase C	10 days	Mon 2/8/10	Fr 2/19/10 83,85																

Project: Pearland Rec Center and Natatorium
 Date: Sat 10/24/09

Task Split: [Progress Bar] Progress Milestone: [Milestone Icon]

Summary: [Summary Icon] External Tasks: [External Tasks Icon] Deadline: [Deadline Icon]

Project Summary: [Project Summary Icon] External Milestone: [External Milestone Icon]

Page 3

ID	Task Name	Duration	Start	Finish	Predecessor	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter		
						Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May
69	Recreation Center - 1st Floor MEP Fitout Phase B	10 days	Mon 2/8/10	Fr 2/19/10 85,87																
83	Recreation Center - 2nd Floor MEP Fitout Phase B	5 days	Mon 2/8/10	Fr 2/19/10 81,82																
84	Recreation Center - 1st Floor Ceiling Phase A	5 days	Mon 2/8/10	Fr 2/19/10 87																
90	Recreation Center - 2nd Floor Ceiling Phase A	5 days	Mon 2/8/10	Fr 2/19/10 82																
87	Recreation Center - 1st Floor Flooring Phase A	5 days	Mon 2/15/10	Fr 2/19/10 84																
91	Recreation Center - 2nd Floor Ceiling Phase B	5 days	Mon 2/15/10	Fr 2/19/10 83																
82	Recreation Center - 2nd Floor Flooring Phase A	5 days	Mon 2/15/10	Fr 2/19/10 90																
100	Recreation Center - Gym Flooring	15 days	Mon 2/15/10	Fr 3/5/10 83																
143	Natatorium - Ceiling	7 days	Thu 2/18/10	Fr 2/25/10 142																
146	Natatorium - Pool Tile and Finishing	10 days	Thu 2/18/10	Wed 3/3/10 142																
89	Recreation Center - 1st Floor MEP Fitout Phase C	10 days	Mon 2/22/10	Fr 3/5/10 86,88																
85	Recreation Center - 1st Floor Ceiling Phase B	5 days	Mon 2/22/10	Fr 2/29/10 86																
33	Recreation Center - 2nd Floor Flooring Phase B	5 days	Mon 2/22/10	Fr 2/29/10 91																
34	Recreation Center - 1st Floor Doors and Hardware Phase A	5 days	Mon 2/22/10	Fr 2/29/10 87																
37	Recreation Center - 2nd Floor Doors and Hardware Phase A	5 days	Mon 2/22/10	Fr 2/29/10 92																
106	Recreation Center - Racketball Court Systems	25 days	Mon 2/22/10	Fr 3/26/10 86																
86	Recreation Center - 1st Floor Flooring Phase B	5 days	Mon 3/1/10	Fr 3/5/10 85																
36	Recreation Center - 2nd Floor Doors and Hardware Phase B	5 days	Mon 3/1/10	Fr 3/5/10 93																
104	Recreation Center - Casework	1 day	Mon 3/1/10	Mon 3/1/10 93																
145	Natatorium - Flooring	10 days	Mon 3/1/10	Fr 3/12/10 143																
130	Natatorium - Bleachers	5 days	Thu 3/4/10	Wed 3/10/10 149																
152	Natatorium - Pool Testing	10 days	Thu 3/4/10	Wed 3/17/10 149																
88	Recreation Center - 1st Floor Ceiling Phase C	5 days	Mon 3/8/10	Fr 3/12/10 89																
95	Recreation Center - 1st Floor Doors and Hardware Phase B	5 days	Mon 3/8/10	Fr 3/12/10 88																
105	Recreation Center - Specialties	1 day	Mon 3/8/10	Mon 3/8/10 98																
108	Recreation Center - MEP Systems Testing	10 days	Tue 3/9/10	Mon 3/22/10 83																
89	Recreation Center - 1st Floor Flooring Phase C (Gym)	5 days	Mon 3/15/10	Fr 3/19/10 86																
146	Natatorium - MEP Trim-Out	7 days	Mon 3/15/10	Tue 3/23/10 145																
147	Natatorium - Casework	7 days	Mon 3/15/10	Tue 3/23/10 145																
148	Natatorium - Doors and Hardware	7 days	Mon 3/15/10	Tue 3/23/10 145																
153	Natatorium - MEP Testing	10 days	Thu 3/18/10	Wed 3/31/10 152																
96	Recreation Center - 1st Floor Doors and Hardware Phase C	5 days	Mon 3/22/10	Fr 3/26/10 89																
99	Recreation Center - Gym Equipment	15 days	Mon 3/22/10	Fr 4/6/10 89																
101	Recreation Center - Gym Seating/Bleachers	8 days	Mon 3/22/10	Wed 3/31/10 89																
103	Recreation Center - Lockers and Benches	8 days	Mon 3/22/10	Wed 3/31/10 89																
107	Recreation Center - Folding Partitions	8 days	Mon 3/22/10	Wed 3/31/10 89																
102	Recreation Center - Track Flooring	8 days	Tue 3/23/10	Thu 4/1/10 93																

Project: Pearland Rec Center and Natatorium
 Date: Sat 10/24/09

Task Split: [Progress Bar] Progress Milestone: [Milestone Icon]

Summary: [Summary Icon] External Tasks: [External Tasks Icon] Deadline: [Deadline Icon]

Project Summary: [Project Summary Icon] External Milestone: [External Milestone Icon]

Page 4

Pearland Recreation Center and Natatorium – Tech Report #2

ID	Task Name	Duration	Start	Finish	Predecessor	2nd Quarter			3rd Quarter			4th Quarter			1st Quarter			2nd Quarter		
						Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May
151	Natatorium - Specialties	5 days	Wed 3/24/10	Tue 3/30/10 148																
109	Recreation Center - Punchlist	10 days	Thu 4/1/10	Wed 4/14/10 108, 107, 101																All
154	Natatorium - Punchlist	5 days	Thu 4/1/10	Wed 4/7/10 153																All
155	Natatorium - Punchlist Completion	10 days	Thu 4/8/10	Wed 4/21/10 154																All
110	Recreation Center - Punchlist Correction	15 days	Thu 4/15/10	Wed 5/5/10 109																All
156	Natatorium - Final Inspections	5 days	Thu 4/22/10	Wed 4/28/10 155																All
157	Natatorium - Substantial Completion	0 days	Wed 4/28/10	Wed 4/28/10 156																4/28
111	Recreation Center - Final Inspections	5 days	Thu 5/6/10	Wed 5/12/10 110																All
112	Recreation Center - Substantial Completion	0 days	Wed 5/12/10	Wed 5/12/10 111																5/12
158	Building Substantial Completion	0 days	Wed 5/12/10	Wed 5/12/10 157, 112																5/12

Project: Pearland Rec Center and Nat	Task	Progress	Summary	External Tasks	Deadline
Date: Sat 10/24/09	Split	Milestone	Project Summary	External Milestone	

Page 5

Appendix 2

Detailed Structural System Estimate

Detailed Structural System Estimate

Recreation Center: Gridlines G-J and 1/2 (2520 SF)											
Item	Units	Quantity	Labor (\$/unit)	Material (\$/unit)	Equipment (\$/unit)	Total (\$/unit)	Labor	Material	Equipment	Total	RS Means
Caissons											
7" Bell diameter, 48" shaft	EA	5.00	\$975.00	\$450.00	\$1,100.00	\$1,430.00	\$4,875.00	\$2,250.00	\$5,500.00	\$12,625.00	Page 592
Footings											
Concrete - 3000 psi	CYD	1.48	\$33.50	\$101.00	\$123.15	\$257.65	\$49.58	\$149.48	\$182.26	\$381.32	Page 64, 65
Concrete Forming	SFCA	80.00	\$2.93	\$0.70	\$124.15	\$127.78	\$234.40	\$56.00	\$9,932.00	\$10,222.40	Page 46
Reinforcing Steel	TON	0.04	\$680.00	\$1,475.00	\$125.15	\$2,280.15	\$27.20	\$59.00	\$5.01	\$91.21	Page 59
Grade Beams											
Concrete - 3000 psi	CYD	6.00	\$12.05	\$101.00	\$4.39	\$117.44	\$72.30	\$606.00	\$26.34	\$704.64	Page 64, 65
Concrete Forming	SFCA	294.00	\$2.93	\$0.70	\$0.00	\$3.63	\$861.42	\$205.80	\$0.00	\$1,067.22	Page 46
Reinforcing Steel	TON	0.40	\$890.00	\$2,440.00	\$0.00	\$3,330.00	\$358.67	\$983.32	\$0.00	\$1,341.99	Page 58
Sub-On-Grade											
Concrete - 3000 psi	CYD	19.44	\$16.70	\$101.00	\$6.10	\$123.80	\$324.65	\$1,963.44	\$118.58	\$2,406.67	Page 64, 65
Concrete Finishing	SF	1260.00	\$0.18	\$0.00	\$0.00	\$0.18	\$226.80	\$0.00	\$0.00	\$226.80	Page 66
5" Concrete Edge Form	LF	27.25	\$2.02	\$0.38	\$0.00	\$2.40	\$55.00	\$10.36	\$0.00	\$65.40	Page 47
Vapor Barrier	SF	1260.00	\$1.15	\$1.20	\$0.00	\$2.35	\$1,449.00	\$1,512.00	\$0.00	\$2,961.00	Page 152
Reinforcing Steel	TON	0.01	\$620.00	\$1,475.00	\$0.00	\$2,095.00	\$6.20	\$14.75	\$0.00	\$20.95	Page 59
Elevated Slab											
Concrete - 3500 psi	CYD	11.67	\$15.50	\$104.00	\$5.65	\$125.15	\$180.89	\$1,213.68	\$65.94	\$1,460.50	Page 64
Concrete Finishing	CYD	1260.00	\$0.18	\$0.00	\$0.00	\$0.18	\$226.80	\$0.00	\$0.00	\$226.80	Page 66
3" Pour Stop	SF	6.81	\$3.33	\$1.47	\$0.00	\$4.80	\$22.69	\$10.01	\$0.00	\$32.70	Page 44
6 X 6 WWP Reinforcing	CSF	12.60	\$24.50	\$32.50	\$0.00	\$57.00	\$308.70	\$409.50	\$0.00	\$718.20	Page 60
9/16" Metal Decking	SF	1260.00	\$0.36	\$1.72	\$0.03	\$2.11	\$453.60	\$2,167.20	\$37.80	\$2,658.60	Page 124
Steel Columns											
TS 10x10x3/8x16'	LF	6.75	\$51.00	\$1,625.00	\$36.50	\$1,712.50	\$344.25	\$10,968.75	\$246.38	\$11,559.38	Page 110
TS 8x8x3/8x14'	LF	1.93	\$49.00	\$890.00	\$35.00	\$964.00	\$94.50	\$1,697.14	\$67.50	\$1,859.14	Page 110
Steel Beams											
W 27x84	LF	64.50	\$2.96	\$139.00	\$1.58	\$143.54	\$161.32	\$7,575.50	\$96.11	\$7,822.93	Page 114
W 16x26	LF	45.50	\$2.44	\$43.00	\$1.74	\$47.18	\$111.02	\$1,956.50	\$79.17	\$2,146.69	Page 114
W 30x90	LF	27.25	\$2.94	\$163.00	\$1.56	\$167.50	\$80.12	\$4,441.75	\$42.51	\$4,564.38	Page 114
Floor Joists											
2x8LH12	LF	500.50	\$1.96	\$29.00	\$1.12	\$31.08	\$980.90	\$4,014.00	\$60.56	\$15,555.04	Page 121
Total Structural System Cost:										\$86,719.45	
Total Cost/SF:										\$32.83	

Recreation Center Structural System (Except Roof Deck and Trusses)											
Structural System	SF	63300		\$32.83							\$2,027,499.00 NA
Roof Deck											
7 1/4" Tectum E Roof Deck	SF	59645.00	\$3.50	\$7.00	\$0.00	\$10.50	\$208,757.50	\$417,515.00	\$0.00	\$626,272.50	NA
Wood Trusses											
130' LHSP Wood Joist Trusses	EA	68	\$500.00	\$1,500.00	\$500.00	\$2,500.00	\$34,000.00	\$102,000.00	\$34,000.00	\$170,000.00	NA
Total Recreation Center Structural System Cost:										\$2,823,771.94	

*Note: This cost does not include the Roof Deck and Wood Trusses

Natatorium (2520 SF)											
Item	Units	Quantity	Labor (\$/unit)	Material (\$/unit)	Equipment (\$/unit)	Total (\$/unit)	Labor	Material	Equipment	Total	RS Means
Caissons											
7" Bell diameter, 48" shaft	EA	5.00	\$975.00	\$450.00	\$1,100.00	\$1,430.00	\$4,875.00	\$2,250.00	\$5,500.00	\$12,625.00	Page 592
Footings											
Concrete - 3000 psi	CYD	1.48	\$33.50	\$101.00	\$123.15	\$257.65	\$49.58	\$149.48	\$182.26	\$381.32	Page 64, 65
Concrete Forming	SFCA	80.00	\$2.93	\$0.70	\$124.15	\$127.78	\$234.40	\$56.00	\$9,932.00	\$10,222.40	Page 46
Reinforcing Steel	TON	0.04	\$680.00	\$1,475.00	\$125.15	\$2,280.15	\$27.20	\$59.00	\$5.01	\$91.21	Page 59
Grade Beams											
Concrete - 3000 psi	CYD	6.00	\$12.05	\$101.00	\$4.39	\$117.44	\$72.30	\$606.00	\$26.34	\$704.64	Page 64, 65
Concrete Forming	SFCA	294.00	\$2.93	\$0.70	\$0.00	\$3.63	\$861.42	\$205.80	\$0.00	\$1,067.22	Page 46
Reinforcing Steel	TON	0.40	\$890.00	\$2,440.00	\$0.00	\$3,330.00	\$358.67	\$983.32	\$0.00	\$1,341.99	Page 58
Sub-On-Grade											
Concrete - 3000 psi	CYD	19.44	\$16.70	\$101.00	\$6.10	\$123.80	\$324.65	\$1,963.44	\$118.58	\$2,406.67	Page 64, 65
Concrete Finishing	SF	1260.00	\$0.18	\$0.00	\$0.00	\$0.18	\$226.80	\$0.00	\$0.00	\$226.80	Page 66
5" Concrete Edge Form	LF	27.25	\$2.02	\$0.38	\$0.00	\$2.40	\$55.00	\$10.36	\$0.00	\$65.40	Page 47
Vapor Barrier	SF	1260.00	\$1.15	\$1.20	\$0.00	\$2.35	\$1,449.00	\$1,512.00	\$0.00	\$2,961.00	Page 152
Reinforcing Steel	TON	0.01	\$620.00	\$1,475.00	\$0.00	\$2,095.00	\$6.20	\$14.75	\$0.00	\$20.95	Page 59
Total Structural System Cost:										\$32,114.60	
Total Cost/SF:										\$12.74	

Natatorium Structural Costs (Except Glulam Materials)											
Structural System	SF	41811		\$12.74							\$532,911.20 NA
Glulam											
Glulam Framing	SF	41230.00	\$7.34	\$15.90	\$0.00	\$23.24	\$26.95	\$302,485.00	\$655,725.00	\$0.00	\$1,070,000.00 NA
Wood Deck	SF	41230.00		\$2.71	\$0.00	\$2.71	\$0.00	\$111,790.00	\$0.00	\$0.00	NA
Total Natatorium Structural System Cost:										\$1,602,911.20	

*Note: This cost does not include Glulam Products

Total Structural Costs	
Natatorium Structural Cost	\$1,602,911.20
Recreation Center Structural Cost	\$2,823,771.50
Total Structural Cost	\$4,427,366.67
Total Structural Cost/SF	\$42.12

Appendix 3

Detailed Structural System Cost Estimate Hand Take-Offs

Detailed Structural System Cost Estimate Hand Take-Offs

Recreation Center 1 of 4

Structural System Hand Take-Off
From Gridlines G-5/1-4

1) Caissons: (2) @ 48" dia, (2) @ 42" dia
and (2) @ 30" dia. All 12' length

Concrete:

$$2 \times 5.58 \text{ CYD}$$

$$2 \times 4.27 \text{ CYD}$$

$$2 \times 2.18 \text{ CYD}$$

Total Concrete: 24.06 CYD - 3000psi

Reinf. Steel:

Vertical All 6: 8-#10

$$6 \times 8 \times 12' = 576 \text{ lft of \#10}$$

Ties: 2-#3 @ 18" \Rightarrow 8 ties ($\frac{12'}{1.5'}$)

$$(2) - 12.56' \Rightarrow (2)(8)(12.56') = 201'$$

$$(2) - 10.99' \Rightarrow (2)(8)(10.99') = 176'$$

$$(2) - 7.85' \Rightarrow (2)(8)(7.85') = 126'$$

So: #3: $0.376 \frac{\text{lb}}{\text{ft}}$ #10: $4.303 \frac{\text{lb}}{\text{ft}}$ 503' of #3

$$\frac{503' \times 0.376 \frac{\text{lb}}{\text{ft}}}{2000 \frac{\text{lb}}{\text{ton}}} = 0.1 \text{ Ton}$$

$$\frac{576' \times 4.303 \frac{\text{lb}}{\text{ft}}}{2000 \frac{\text{lb}}{\text{ton}}} = 1.24 \text{ Ton}$$

\Rightarrow 1.34 Ton of Rebar

2 of 4

2) Footings: (5) 2'x2'x2' FTGs

$$\text{Concrete: } \frac{40}{27} = \underline{1.48 \text{ CYDs}} - 3000 \text{ psi}$$

$$\text{Forming: } 16 \text{ SFCA} \times 5 = \underline{80 \text{ SFCA}}$$

Steel: 2- #7 T+B

$$5 \times (4)(2') = 40 \text{ ft of } \#7$$

$$\#7: 2.044 \text{ lb/ft}$$

$$\frac{40 \times 2.044}{2000} = \underline{0.04 \text{ Ton}}$$

3) Grade Beam:

$$\text{Total Length: } 73.5'$$

$$\text{Concrete: } 2' \times 1.1' \times 73.5' = 161.7 \text{ CF}$$

$$\underline{6 \text{ CYDs}} - 3000 \text{ psi}$$

$$\text{Forming: } 4' \times 73.5' = \underline{294 \text{ SFCA}}$$

Steel: 2- #7 T+B

$$4 \times 73.5' = 294 \text{ ft of } \#7$$

$$\#3 \text{ Stirrups @ } 10' \text{ o.c.} = 88 \text{ Stirrups}$$

$$6.2' \times 88 = 546' \text{ of } \#3$$

$$\frac{0.376 \times 546 + 294 \times 2.044}{2000} = \underline{0.403 \text{ Tons}}$$

3 of 4

4) Slab-on Grade: Area = 27.25' x 46.25' = 1260 SF

Concrete: 1260 SF x $\frac{5}{12}$ = $\frac{525}{27}$ = 19.44 CYD
- 3000psi

Vapor Barrier: 1260 SF

5" Edge Form: 27.25'

Steel: #3 @ 14" o.c. EW
↳ 1.17'

$$\frac{27.25}{1.17} + \frac{46.25}{1.17} = 24 + 40 = 64 \text{ lft of } \#3$$

$$\frac{0.376 \times 64}{2000} = \underline{0.01 \text{ Ton}}$$

Finishing: 1260 SF

5) Elevated Slab: 1260 SF

Concrete: 1260 x $\frac{3}{12}$ = 11.67 CYD - 3500psi

9/16" Deck: 1260 SF

3" Pour Stop: 27.25 SF

Finishing: 1260 SF

Reinforcing: 1260 SF of 6x6 WWF

*Note: These are for entire bldg. (Rec Center) ⁴⁰⁵⁴

*6) Roof Deck: $319' \times 181' = 57,739 \text{ SF} \times 1.033 = 59,645 \text{ SF}$ ¹²
7/4" Tectum E Roof Deck: 59,645 SF

*7) Wood Trusses: 68 LHSP @ 5' o.c

8) Steel:

Columns: (4) TS 10x10x3/8" - 27'
(1) TS 8x8x3/8" - 27'

Beams: (2) W 27x84 - 27.25'
(1) W 16x26 - 45.5'
(1) W 30x90 - 27.25'

Floor Joists: (11) 28LH12 - 45.5'

Appendix 4

RS Means 2009 Building Construction Cost Data Sheets

RS Means 2009 Building Construction Cost Data Sheets

01 21 Allowances

01 21 61 – Cost Indexes

01 21 61.50 Material Index

	Crew	Daily Output	Labor-Hours	Unit	Material	2009 Labor	Bare Costs Equipment	Total	Total Incl O&P
0010	MATERIAL INDEX (Reference) For over 730 zip code locations in the U.S. and Canada, minimum (Elizabethtown, KY)								
0020				%	90.10%				
0040					100%				
0060				↓	139.60%				

01 21 63 – Taxes

01 21 63.10 Taxes

0010	TAXES	R012909-80							
0020	Sales tax, State, average			%	4.91%				
0050	Maximum	R012909-85			7.25%				
0200	Social Security, on first \$102,000 of wages					7.65%			
0300	Unemployment, combined Federal and State, minimum					.80%			
0350	Average					6.20%			
0400	Maximum					11.76%			

01 31 Project Management and Coordination

01 31 13 – Project Coordination

01 31 13.20 Field Personnel

0010	FIELD PERSONNEL								
0020	Clerk, average			Week	380			380	590
0100	Field engineer, minimum				895			895	1,375
0120	Average				1,165			1,165	1,800
0140	Maximum				1,350			1,350	2,100
0160	General purpose laborer, average				1,250			1,250	1,925
0180	Project manager, minimum				1,650			1,650	2,550
0200	Average				1,925			1,925	2,975
0220	Maximum				2,175			2,175	3,375
0240	Superintendent, minimum				1,600			1,600	2,475
0260	Average				1,775			1,775	2,750
0280	Maximum				2,025			2,025	3,125
0300	Timekeeper, average				1,040			1,040	1,600

Pg. 10

01 31 13.30 Insurance

0010	INSURANCE	R013113-40							
0020	Builders risk, standard, minimum			Job					.24
0050	Maximum	R013113-50							.64
0200	All-risk type, minimum								.25
0250	Maximum	R013113-60							.62
0400	Contractor's equipment floater, minimum			Value					.50
0450	Maximum			"					1.50
0600	Public liability, average			Job					2.02
0800	Workers' compensation & employer's liability, average								
0850	by trade, carpentry, general			Payroll		17.80%			
0900	Clerical					.58%			
0950	Concrete					14.56%			
1000	Electrical					6.46%			
1050	Excavation					10.01%			
1100	Glazing					13.69%			
1150	Insulation					14.44%			
1200	Ironing					10.63%			
1250	Masonry					14.37%			
1300	Painting & decorating					12.49%			

03 11 Concrete Forming

03 11 13 – Structural Cast-In-Place Concrete Forming

03 11 13.25 Forms In Place, Columns		Crew	Daily Output	Labor Hours	Unit	Material	2009 Base Costs		Total	Total incl O&P
							Labor	Equipment		
3300	48" diameter	G	C-1	50	.640	L.F.	68	24	92	113
3350	60" diameter	G		45	.711		42	27	69	88
4500	For second and succeeding months, deduct									
5000	Job-built plywood, 8" x 8" columns, 1 use		C-1	165	.194	SFCA	2.41	7.35	9.76	14.05
5050	2 use			195	.164		1.37	6.20	7.57	11.15
5100	3 use			210	.152		.96	5.75	6.71	10
5150	4 use			215	.149		.79	5.65	6.44	9.60
5500	12" x 12" columns, 1 use			180	.178		2.27	6.75	9.02	12.95
5550	2 use			210	.152		1.25	5.75	7	10.30
5600	3 use			220	.145		.91	5.50	6.41	9.55
5650	4 use			225	.142		.74	5.40	6.14	9.15
6000	16" x 16" columns, 1 use			185	.173		2.24	6.55	8.79	12.60
6050	2 use			215	.149		1.19	5.65	6.84	10.05
6100	3 use			230	.139		.90	5.25	6.15	9.15
6150	4 use			235	.136		.73	5.15	5.88	8.80
6500	24" x 24" columns, 1 use			190	.168		2.49	6.40	8.89	12.65
6550	2 use			216	.148		1.37	5.60	6.97	10.20
6600	3 use			230	.139		.99	5.25	6.24	9.25
6650	4 use			238	.134		.81	5.10	5.91	8.80
7000	36" x 36" columns, 1 use			200	.160		1.81	6.05	7.86	11.40
7050	2 use			230	.139		1.03	5.25	6.28	9.30
7100	3 use			245	.131		.73	4.94	5.67	8.45
7150	4 use			250	.128		.59	4.85	5.44	8.15
7400	Steel frame plywood, based on 50 uses of purchased									
7420	forms, and 4 uses of bracing lumber									
7500	8" x 8" column		C-1	340	.094	SFCA	4.53	3.56	8.09	10.55
7550	10" x 10"			350	.091		3.99	3.46	7.45	9.75
7600	12" x 12"			370	.086		3.38	3.27	6.65	8.80
7650	16" x 16"			400	.080		2.63	3.03	5.66	7.60
7700	20" x 20"			420	.076		2.35	2.88	5.23	7.05
7750	24" x 24"			440	.073		1.67	2.75	4.42	6.10
7755	30" x 30"			440	.073		2.14	2.75	4.89	6.60
7760	36" x 36"			460	.070		1.90	2.63	4.53	6.15

Pg. 44

03 11 13.30 Forms In Place, Culvert

0010	FORMS IN PLACE, CULVERT	R031113-40								
0015	5' to 8' square or rectangular, 1 use		C-1	170	.188	SFCA	6.10	7.15	13.25	17.75
0050	2 use	R031113-60		180	.178		3.90	6.75	10.65	14.75
0100	3 use			190	.168		3.16	6.40	9.56	13.40
0150	4 use			200	.160		2.79	6.05	8.84	12.45

03 11 13.35 Forms In Place, Elevated Slabs

0010	FORMS IN PLACE, ELEVATED SLABS	R031113-40								
1000	Flat plate, job-built plywood, to 15' high, 1 use	R031113-60	C-2	470	.102	S.F.	4.53	3.97	8.50	11.15
1050	2 use			520	.092		2.49	3.59	6.08	8.30
1100	3 use			545	.088		1.81	3.40	5.21	7.20
1150	4 use			560	.086		1.47	3.33	4.80	6.75
1500	15' to 20' high ceilings, 4 use			495	.097		1.67	3.77	5.44	7.70
1600	21' to 35' high ceilings, 4 use			450	.107		2.55	4.15	6.70	9.25
2000	Flat slab, drop panels, job-built plywood, to 15' high, 1 use			449	.107		4.77	4.16	8.93	11.70
2050	2 use			509	.094		2.62	3.67	6.29	8.60
2100	3 use			532	.090		1.91	3.51	5.42	7.55
2150	4 use			544	.088		1.55	3.43	4.98	7
2250	15' to 20' high ceilings, 4 use			480	.100		5.10	3.89	8.99	11.65

03 11 Concrete Forming

03 11 13 – Structural Cast-in-Place Concrete Forming

03 11 13.45	Forms In Place, Footings	Crew	Daily Output	Labor Hours	Unit	Material	2009 Bare Costs			Total incl O&P
							Labor	Equipment	Total	
1500	Keyway, 4 use, tapered wood, 2" x 4"	1 Corp	530	.015	L.F.	.16	.60		.76	1.10
1550	2" x 6"		500	.016		.26	.64		.90	1.28
2000	Tapered plastic		530	.015		.58	.60		1.13	1.51
2250	For keyway hang from supports, odd		150	.053		.65	2.13		2.78	4.02
3000	Pile cap, square or rectangular, job-built plywood, 1 use	C-1	290	.110	SFCA	2.46	4.18		6.64	9.20
3050	2 use		346	.092		1.35	3.50		4.85	6.95
3100	3 use		371	.086		.99	3.27		4.26	6.15
3150	4 use		383	.084		.80	3.16		3.96	5.80
4000	Triangular or hexagonal, 1 use		225	.142		2.86	5.40		8.26	11.50
4050	2 use		280	.114		1.58	4.33		5.91	8.45
4100	3 use		305	.105		1.15	3.97		5.12	7.40
4150	4 use		315	.102		.93	3.85		4.78	6.95
5000	Spread footings, job-built lumber, 1 use		305	.105		2.16	3.97		6.13	8.55
5050	2 use		371	.086		1.20	3.27		4.47	6.35
5100	3 use		407	.080		.84	3.00		3.84	5.65
5150	4 use		418	.077		.70	2.93		3.63	5.30
6000	Support for column, plinth or temporary, 2" x 4" footing		22	1.200	L.F.	3.70	10.50		14.20	19.50
6050	4' x 4' footing		22	1.455		10.80	55		65.80	97.50
6100	8' x 8' footing		20	1.600		21.50	60.50		82	118
6150	12' x 12' footing		17	1.882		26	71.50		97.50	140
7000	Plinths, job-built plywood, 1 use		250	.128	SFCA	2.73	4.85		7.58	10.50
7100	4 use		270	.119		.90	4.49		5.39	7.95

03 11 13.47 Forms In Place, Gas Station Forms

FORMS IN PLACE, GAS STATION FORMS											
0050	Curb fascia, with template, 12 ga. steel, left in place, 9" high	G	1 Corp	50	.160	L.F.	15.70	6.40		22.10	27
1000	Sign or light bases, 18" diameter, 9" high	G		9	.889	Eq.	99	35.50		134.50	164
1050	30" diameter, 13" high	G		8	1		157	40		197	235
2000	Island forms, 10' long, 9" high, 3'-6" wide	G	C-1	10	3.200		440	121		561	675
2050	4' wide	G		9	3.556		455	135		590	710
2500	20' long, 9" high, 4' wide	G		6	5.333		730	202		932	1,125
2550	5' wide	G		5	6.400		760	242		1,002	1,200

Pg. 46

03 11 13.50 Forms In Place, Grade Beam

FORMS IN PLACE, GRADE BEAM												
0020	Job-built plywood, 1 use		R031113-40	C-2	530	.091	SFCA	3.25	3.52		6.77	9.05
0050	2 use		R031113-60		580	.083		1.79	3.22		5.01	6.95
0100	3 use				700	.077		1.88	3.13		5.01	7.25
0150	4 use				605	.079		1.06	3.09		4.15	5.95

03 11 13.55 Forms In Place, Mat Foundation

FORMS IN PLACE, MAT FOUNDATION												
0020	Job-built plywood, 1 use		R031113-40	C-2	290	.166	SFCA	2.94	6.45		9.39	18.25
0050	2 use		R031113-60		310	.155		1.19	6		7.19	10.65
0100	3 use				330	.145		.75	5.65		6.40	9.60
0120	4 use				350	.137		.70	5.35		6.05	9

03 11 13.65 Forms In Place, Slab On Grade

FORMS IN PLACE, SLAB ON GRADE												
1000	Bulkhead forms w/keyway, wood, 6" high, 1 use		R031113-40	C-1	510	.063	L.F.	.84	2.38		3.22	4.60
1050	2 uses		R031113-60		400	.080		.46	3.03		3.49	5.20
1100	4 uses				350	.091		.27	3.46		3.73	5.65
1400	Bulkhead form for slab, 4-1/2" high, exp metal, incl keyway & stakes	G			1200	.027		2.78	1.01		3.79	4.63
1410	5-1/2" high	G			1100	.029		3.23	1.10		4.33	5.25
1420	7-1/2" high	G			960	.033		4.26	1.26		5.52	6.65
1430	9-1/2" high	G			840	.036		4.84	1.44		6.28	7.55

Pg. 47

03 11 Concrete Forming

03 11 13 – Structural Cast-In-Place Concrete Forming

03 11 13.65 Forms In Place, Slab On Grade		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Labor	Bare Costs Equipment	Total	Total Incl O&P
2000	Curb forms, wood, 6" to 12" high, on grade, 1 use	G1	215	.149	SFCA	2.83	5.65		8.48	11.85
2050	2 use		250	.128		1.57	4.85		6.42	9.25
2100	3 use		265	.121		1.13	4.57		5.70	8.35
2150	4 use		275	.116		.92	4.41		5.33	7.95
3000	Edge forms, wood, 4 use, on grade, to 6" high		600	.053	L.F.	.38	2.02		2.40	3.55
3050	7" to 12" high									
3500	For depressed slabs, 4 use, to 12" high		300	.107	L.F.	.56	4.04		4.60	6.85
3550	To 24" high		175	.183		.76	6.90		7.66	11.60
4000	For slab blockouts, to 12" high, 1 use		200	.160		.63	6.05		6.68	10.10
4050	To 24" high, 1 use		120	.267		.80	10.10		10.90	16.55
4100	Plastic (extruded), to 6" high, multiple use, on grade		3000	.040		5.50	1.51		7.01	8.40
5000	Screed, 24 ga. metal key joint, see Div. 03 15 05.25									
5020	Wood, incl. wood stakes, 1" x 3"	G1	900	.036	L.F.	.68	1.35		2.03	2.84
5050	2" x 4"		900	.036	"	.63	1.35		1.98	2.78
6000	Trench forms in floor, wood, 1 use		160	.200	SFCA	1.48	7.55		9.03	13.35
6050	2 use		175	.183		.81	6.90		7.71	11.65
6100	3 use		180	.178		.59	6.75		7.34	11.10
6150	4 use		185	.173		.48	6.55		7.03	10.70
8760	Void form, corrugated fiberboard, 6" x 12", 10" long	G	240	.133	S.F.	.84	5.05		5.89	8.75

Pg. 47

03 11 13.85 Forms In Place, Walls

FORMS IN PLACE, WALLS		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Labor	Bare Costs Equipment	Total	Total Incl O&P
0010	Box out for wall openings, to 16" thick, to 10 S.F.	R031113-10								
0100	Over 10 S.F. (use perimeter)	C-2	24	2	Eq.	21.50	78		99.50	145
0150	Brick sheaf, 4" w/ add to wall forms, use wall area abv sheaf	R031113-40	"	280	.171	L.F.	1.78	6.65	8.43	12.30
0250	1 use	R031113-60	C-2	240	.200	SFCA	1.87	7.80	9.67	14.10
0300	2 use			275	.175		1.03	6.80	7.83	11.70
0350	4 use			300	.160		.75	6.20	6.95	10.45
0500	Bulkhead, wood with keyway, 1 use, 2 piece			265	.181	L.F.	1.68	7.05	8.73	12.75
0600	Bulkhead forms with keyway, 1 piece expanded metal, 8" wall	G	C-1	1000	.032		4.26	1.21	5.47	6.55
0610	10" wall	G		800	.040		4.84	1.51	6.35	7.65
0620	12" wall	G		525	.061		5.80	2.31	8.11	10
0700	Buttress, to 8' high, 1 use	C-2	350	.137	SFCA	7.05	5.35		12.40	16
0750	2 use			430	.112		3.89	4.34	8.23	11.05
0800	3 use			460	.104		2.83	4.06	6.89	9.40
0850	4 use			480	.100		2.33	3.89	6.22	8.60
1000	Corbel or haunch, to 12" wide, add to wall forms, 1 use			150	.320	L.F.	1.95	12.45	14.40	21.50
1050	2 use			170	.282		1.07	11	12.07	18.25
1100	3 use			175	.274		.78	10.65	11.43	17.40
1150	4 use			180	.267		.63	10.35	10.98	16.80
2000	Wall, job-built plywood, to 8' high, 1 use			370	.130	SFCA	2.62	5.05	7.67	10.70
2050	2 use			435	.110		1.61	4.29	5.90	8.40
2100	3 use			495	.097		1.17	3.77	4.94	7.15
2150	4 use			505	.095		.95	3.70	4.65	6.80
2400	Over 8' to 16' high, 1 use			280	.171		9.40	6.65	16.05	28.50
2450	2 use			345	.139		1.34	5.40	6.74	9.85
2500	3 use			375	.128		.96	4.98	5.94	8.75
2550	4 use			395	.122		.78	4.73	5.51	8.20
2700	Over 16' high, 1 use			235	.204		2.71	7.95	10.66	15.30
2750	2 use			290	.166		1.49	6.45	7.94	11.65
2800	3 use			315	.152		1.08	5.95	7.03	10.40
2850	4 use			330	.145		.88	5.65	6.53	9.70
3000	For architectural finish, add			1820	.076		2.72	1.03	3.75	4.58

03 21 Reinforcing Steel

03 21 05 – Reinforcing Steel Accessories

03 21 05.75 Splicing Reinforcing Bars		Crew	Daily Output	Labor Hours	Unit	Material	2009 Base Costs			Total	Total Incl O&P
							Labor	Equipment			
0550	#10-9	G	C-5	95	589	Eq.	22	25.50	8.30	55.80	74
0560	#9-8	G	C-25	105	305		21	10.65		31.65	40.50
0580	#8-7	G		115	278		19.55	9.75		29.30	37.50
0590	#7-6	G		130	246		19.05	8.60		27.65	35
0600	Position coupler for curved bars, taper threaded, #4 bars	G		160	200		22	7		29	35.50
0610	#5 bars	G		145	221		23	7.70		30.70	36
0620	#6 bars	G		130	246		26	8.60		34.60	43
0630	#7 bars	G		110	291		38.50	10.15		48.65	59.50
0640	#8 bars	G		100	320		40	11.20		51.20	62.50
0650	#9 bars	G	C-5	90	622		43.50	27	8.75	79.25	101
0660	#10 bars	G		80	700		47	30.50	9.85	87.35	111
0670	#11 bars	G		70	800		49	35	11.30	95.30	122
0680	#14 bars	G		55	1,018		61	44	14.35	119.35	154
0690	#18 bars	G		40	1,400		88	61	19.75	168.75	216
0700	Transition position coupler for curved bars, taper threaded, #18-14	G		40	1,400		111	61	19.75	191.75	241
0710	#18-11	G		40	1,400		112	61	19.75	192.75	242
0720	#14-11	G		55	1,018		95	44	14.35	153.35	191
0730	#11-10	G		70	800		54.50	35	11.30	100.80	128
0740	#10-9	G		80	700		52	30.50	9.85	92.35	116
0750	#9-8	G	C-25	90	356		48	12.45		60.45	73.50
0760	#8-7	G		100	320		44	11.20		55.20	67
0770	#7-6	G		110	291		42.50	10.15		52.65	64
0800	Sleeve type w/ great filler, for precast concrete, #6 bars	G		72	444		23.50	15.55		39.05	51.50
0802	#7 bars	G		64	500		25.50	17.50		43	57
0805	#8 bars	G		56	571		29	19.95		48.95	65
0807	#9 bars	G		48	667		31.50	23.50		55	73.50
0810	#10 bars	G	C-5	40	1,400		41	61	19.75	121.75	165
0900	#11 bars	G		32	1,750		49	76	24.50	149.50	203
0920	#14 bars	G		24	2,333		79.50	101	33	213.50	286
1000	Sleeve type w/ various filler, for critical structures, #6 bars	G	C-25	72	444		41	15.55		56.55	71
1210	#7 bars	G		64	500		42	17.50		59.50	75
1220	#8 bars	G		56	571		44	19.95		63.95	81.50
1230	#9 bars	G	C-5	48	1,167		45	50.50	16.45	111.95	149
1240	#10 bars	G		40	1,400		48	61	19.75	128.75	172
1250	#11 bars	G		32	1,750		58	76	24.50	158.50	213
1260	#14 bars	G		24	2,333		73	101	33	207	278
1270	#18 bars	G		16	3,500		106	152	49.50	307.50	415
2000	Weldable half coupler, taper threaded, #4 bars	G	E-16	120	133		7.10	6.10	1.12	14.32	19.95
2100	#5 bars	G		112	143		8.40	6.55	1.20	16.15	22
2200	#6 bars	G		104	154		13.35	7.05	1.29	21.69	28.50
2300	#7 bars	G		96	167		15.50	7.60	1.40	24.50	32
2400	#8 bars	G		88	182		16.15	8.30	1.53	25.98	34.50
2500	#9 bars	G		80	200		17.80	9.15	1.68	28.63	37.50
2600	#10 bars	G		72	222		18.20	10.15	1.86	30.21	40
2700	#11 bars	G		64	250		19.45	11.45	2.10	33	44.50
2800	#14 bars	G		56	286		22.50	13.05	2.40	37.95	50.50
2900	#18 bars	G		48	333		36.50	15.25	2.80	54.55	70

Pg. 58

03 21 10 – Uncoated Reinforcing Steel

03 21 10.60 Reinforcing In Place

0015	REINFORCING IN PLACE A615 Grade 60, incl. access. labor	R032110-10									
0100	Beams & Girders, #3 to #7	CN	G	4 Rodm	1.60	20	Ton	1,550	890	2,440	3,150

03 21 Reinforcing Steel

03 21 10 – Uncoated Reinforcing Steel

03 21 10.60 Reinforcing In Place			Crew	Daily Output	Labor-Hours	Unit	Material	2009 Bare Costs		Total	Total Incl O&P
							Labor	Equipment			
0150	#8 to #18	R032110-20	G 4 Rodm	2.70	11.852	Ton	1,550	530		2,080	2,575
0200	Columns, #3 to #7		G	1.50	21.333		1,550	950		2,500	3,250
0250	#8 to #18		G	2.30	13.913		1,550	620		2,170	2,725
0300	Spirals, hot rolled, 8" to 15" diameter		G	2.20	14.545		2,000	650		2,650	3,250
0320	15" to 24" diameter	R032110-40	G	2.20	14.545		1,925	650		2,575	3,150
0330	24" to 36" diameter		G	2.30	13.913		1,825	620		2,445	3,025
0340	36" to 48" diameter	R032110-50	G	2.40	13.333		1,725	595		2,320	2,875
0360	48" to 64" diameter		G	2.50	12.800		1,925	570		2,495	3,025
0380	64" to 84" diameter	R032110-70	G	2.60	12.308		2,000	550		2,550	3,100
0390	84" to 96" diameter		G	2.70	11.852		2,100	530		2,630	3,175
0400	96" to 108" diameter		G	2.80	11.034		1,650	490		2,140	2,600
0500	Footings, #4 to #7		G	2.10	15.238		1,475	680		2,155	2,725
0600	Slab on grade, #3 to #7		G	2.30	13.913		1,475	620		2,095	2,650
0700	Walls, #3 to #7		G	1.50	21.333		1,550	950		2,500	3,250
0750	#8 to #18		G	4	8		1,475	355		1,830	2,200
0900	Use the following for a rough estimate guide:										
1000	Typical in place, average, under 10 ton job, #3 to #7		G 4 Rodm	1.80	17.778	Ton	1,600	790		2,390	3,075
1010	#8 to #18		G	2.70	11.852		1,625	530		2,155	2,675
1050	10 – 50 ton job, #3 to #7		G	2.10	15.238		1,575	680		2,255	2,825
1060	#8 to #18		G	3	10.667		1,600	475		2,075	2,550
1100	50 – 100 ton job, #3 - #7		G	2.20	14.545		1,525	650		2,175	2,750
1110	#8 to #18		G	3.10	10.323		1,575	460		2,035	2,475
1150	Over 100 ton job, #3 - #7		G	2.30	13.913		1,525	620		2,145	2,700
1160	#8 - #18		G	3.20	10		1,550	445		1,995	2,425
1200	High strength steel, Grade 75, #14 bars only, add		G				153			153	168
2000	Unloading & sorting, add to above		C-5	100	.560			24.50	7.90	32.40	47.50
2200	Crane cast for handling, add to above, minimum			135	.415			18	5.85	23.85	35.50
2210	Average			92	.609			26.50	8.60	35.10	52
2220	Maximum			35	1.600			69.50	22.50	92	136
2400	Dowels, 2 feet long, deformed, #3		G 2 Rodm	520	.031	Ea.	.64	1.37		2.01	2.95
2410	#4		G	480	.033		1.14	1.48		2.62	3.68
2420	#5		G	435	.037		1.78	1.64		3.42	4.64
2430	#6		G	360	.044		2.56	1.98		4.54	6.05
2450	Longer and heavier dowels, add		G	725	.022	lb.	.85	.98		1.83	2.55
2500	Smooth dowels, 12" long, 1/4" or 3/8" diameter		G	140	.114	Ea.	1.21	5.10		6.31	9.70
2520	5/8" diameter		G	125	.128		2.11	5.70		7.81	11.60
2530	3/4" diameter		G	110	.145		2.62	6.50		9.12	13.50
2600	Dowel sleeves for CIP concrete, 2-part system										
2610	Sleeve base, plastic, for 5/8" smooth dowel sleeve, fasten to edge form		1 Rodm	200	.040	Ea.	.52	1.78		2.30	3.48
2615	Sleeve, plastic, 12" long, for 5/8" smooth dowel, snap onto base			400	.020		1.03	.89		1.92	2.59
2620	Sleeve base, for 3/4" smooth dowel sleeve			175	.046		.49	2.04		2.53	3.87
2625	Sleeve, 12" long, for 3/4" smooth dowel			350	.023		1.08	1.02		2.10	2.86
2630	Sleeve base, for 1" smooth dowel sleeve			150	.053		.64	2.38		3.02	4.59
2635	Sleeve, 12" long, for 1" smooth dowel			300	.027		1.84	1.19		3.03	3.96
2700	Dowel caps, visual warning only, plastic, #3 to #8		2 Rodm	800	.020		.51	.89		1.40	2.02
2720	#8 to #18			750	.021		1.08	.95		2.03	2.74
2750	Impalement protective, plastic, #4 to #9			800	.020		1.95	.89		2.84	3.61
03 21 10.70 Glass Fiber Reinforced Polymer Bars											
GLASS FIBER REINFORCED POLYMER BARS											
0010	#2 bar, .043 lbs/ ft.					Lf.	35			35	.39
0100	#3 bar, .092 lbs/ ft.						48			48	.53

Pg. 59

03 21 Reinforcing Steel

03 21 10 – Uncoated Reinforcing Steel

03 21 10.70 Glass Fiber Reinforced Polymer Bars	Daily Crew	Output	Labor Hours	Unit	Material	2009 Labor	Bore Costs Equipment	Total	Total Incl O&P
0150 #4 bar, 160 lbs./ft.				Lf.	.70			.70	.77
0200 #5 bar, 253 lbs./ft.					.98			.98	1.06
0250 #6 bar, 372 lbs./ft.					1.35			1.35	1.49
0300 #7 bar, 497 lbs./ft.					1.70			1.70	1.87
0350 #8 bar, 620 lbs./ft.					2.25			2.25	2.48
0400 #9 bar, 800 lbs./ft.					2.90			2.90	3.19
0450 #10 bar, 1,08 lbs./ft.					3.45			3.45	3.80
0500 For Bands, add per band				ea.	1			1	1.10

03 21 13 – Galvanized Reinforcing Steel

03 21 13.10 Galvanized Reinforcing

0010 GALVANIZED REINFORCING									
0150 Add to uncoated reinforcing price for galvanizing				Ton	1,150			1,150	1,250

03 21 16 – Epoxy-Coated Reinforcing Steel

03 21 16.10 Epoxy-Coated Reinforcing

0010 EPOXY-COATED REINFORCING									
0100 Add to uncoated reinforcing price for coating with epoxy				Ton	865			865	950

03 22 Welded Wire Fabric Reinforcing

03 22 05 – Uncoated Welded Wire Fabric

03 22 05.50 Welded Wire Fabric

03 22 05.50 WELDED WIRE FABRIC ASTM A185	R032205-30									
0030 Made from recycled materials										
0050 Sheets										
0100 6 x 6 - W1.4 x W1.4 (10 x 10) 21 lb. per C.S.F.	CN	G	2 Radm	35	.457	C.S.F.	18.05	20.50	38.55	53.50
0200 6 x 6 - W2.1 x W2.1 (8 x 8) 28 lb. per C.S.F.		G		31	.516		26.50	23	49.50	67
0300 6 x 6 - W2.9 x W2.9 (6 x 6) 42 lb. per C.S.F.		G		29	.552		32.50	24.50	57	76
0400 6 x 6 - W4 x W4 (4 x 4) 85 lb. per C.S.F.		G		27	.593		48.50	28.50	77	98.50
0500 4 x 4 - W1.4 x W1.4 (10 x 10) 31 lb. per C.S.F.		G		31	.516		26.50	23	49.50	67
0600 4 x 4 - W2.1 x W2.1 (8 x 8) 44 lb. per C.S.F.		G		29	.552		38	24.50	62.50	81.50
0650 4 x 4 - W2.9 x W2.9 (6 x 6) 61 lb. per C.S.F.		G		27	.593		50.50	26.50	77	98.50
0700 4 x 4 - W4 x W4 (4 x 4) 85 lb. per C.S.F.		G		25	.640		65.50	28.50	94	119
0750 Rolls										
0800 2 x 2 - #14 galv., 21 lb./C.S.F., beam & column wrap		G	2 Radm	6.50	2.462	C.S.F.	66	110	176	252
0900 2 x 2 - #12 galv. for gunite reinforcing		G	"	6.50	2.462	"	65.50	110	175.50	252

03 23 Stressing Tendons

03 23 05 – Prestressing Tendons

03 23 05.50 Prestressing Steel

03 23 05.50 PRESTRESSING STEEL	R034136-90										
0100 Grouted strand, post-tensioned in field, 50' span, 100 kip		G	C-3	1200	.053	Lb.	2.33	2.18	.09	4.60	6.15
0150 300 kip		G		2700	.024		1.05	.97	.04	2.06	2.75
0300 100' span, 100 kip		G		1700	.038		2.33	1.54	.06	3.93	5.10
0350 300 kip		G		3200	.020		2.02	.82	.03	2.87	3.57
0500 200' span, 100 kip		G		2700	.024		2.32	.97	.04	3.33	4.15
0550 300 kip		G		3500	.018		2.01	.75	.03	2.79	3.44
0800 Grouted bars, 50' span, 42 kip		G		2600	.025		1.25	1.01	.04	2.30	3.03
0850 143 kip		G		3200	.020		1.21	.82	.03	2.06	2.68
1000 75' span, 42 kip		G		3200	.020		1.24	.82	.03	2.11	2.74

03 31 Structural Concrete

03 31 05 – Normal Weight Structural Concrete

03 31 05.30 Concrete, Field Mix		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Cost:		Total	Total Incl O&P
							Labor	Equipment		
0010	CONCRETE, FIELD MIX	R033105-65								
0015	FOB forms 2250 psi				C.Y.	90			90	99
0020	3000 psi				"	94			94	103
03 31 05.35 Normal Weight Concrete, Ready Mix										
0010	NORMAL WEIGHT CONCRETE, READY MIX, delivered	R033105-10								
0012	Includes local aggregate, sand, portland cement, and water									
0015	Excludes all additives and treatments	R033105-20								
0020	2000 psi				C.Y.	97			97	107
0100	2500 psi	R033105-30				98.50			98.50	108
0150	3000 psi	CN				101			101	111
0200	3500 psi	R033105-40				104			104	114
0300	4000 psi					107			107	117
0350	4500 psi	R033105-50				109			109	120
0400	5000 psi	CN				111			111	122
0411	6000 psi					127			127	139
0412	8000 psi					206			206	227
0413	10,000 psi					293			293	320
0414	12,000 psi					355			355	390
1000	For high early strength cement, add					10%				
1010	For structural lightweight with regular sand, add					25%				
1300	For winter concrete (hot water), add					5.25			5.25	5.80
1400	For hot weather concrete (ice), add					7.20			7.20	7.90
1410	For mid-range water reducer, add					3.95			3.95	4.35
1420	For high-range water reducer/superplasticizer, add					5.85			5.85	6.40
1430	For retarder, add					2			2	2.20
1440	For non-Chloride accelerator, add					4.75			4.75	5.25
1450	For Chloride accelerator, per 1%, add					2.75			2.75	3.03
1460	For fiber reinforcing, synthetic (1 lb./C.Y.), add					6			6	6.60
1500	For Saturday delivery, add					5.50			5.50	6.05
1510	For truck holding/waiting time past 1st hour per load, add				Hr.	92			92	101
1520	For short load (less than 4 C.Y.), add per load				Ea.	100			100	110
2000	For all lightweight aggregate, add				C.Y.	45%				
03 31 05.70 Placing Concrete										
0010	PLACING CONCRETE	R033105-70								
0020	Includes labor and equipment to place and vibrate									
0050	Beams, elevated, small beams, pumped		C-20	60	1.067	C.Y.	36	13.15	49.15	70
0100	With crane and bucket		C-7	45	1.600		55	26.50	81.50	113
0200	Large beams, pumped		C-20	90	.711		24	8.80	32.80	46.50
0250	With crane and bucket		C-7	65	1.108		38	18.40	56.40	78.50
0400	Columns, square or round, 12" thick, pumped		C-20	60	1.067		36	13.15	49.15	70
0450	With crane and bucket		C-7	40	1.800		61.50	30	91.50	127
0600	18" thick, pumped		C-20	90	.711		24	8.80	32.80	46.50
0650	With crane and bucket		C-7	55	1.309		45	22	67	92.50
0800	24" thick, pumped		C-20	92	.696		23.50	8.60	32.10	45.50
0850	With crane and bucket		C-7	70	1.029		35	17.10	52.10	73
1000	36" thick, pumped		C-20	140	.457		15.50	5.65	21.15	29.50
1050	With crane and bucket		C-7	95	.736		31	12.94	43.94	60.50
1400	Elevated slabs, less than 6" thick, pumped		C-20	140	.457		15.50	5.65	21.15	29.50
1450	With crane and bucket		C-7	95	.736		31	12.94	43.94	60.50
1500	6" to 10" thick, pumped		C-20	160	.400		13.55	4.94	18.49	26.50
1550	With crane and bucket		C-7	110	.655		22.50	10.90	33.40	46
1600	Slabs over 10" thick, pumped		C-20	180	.356		12.05	4.39	16.44	23.50

Pg. 64

14.05

03 31 Structural Concrete

03 31 05 – Normal Weight Structural Concrete

03 31 05.70 Placing Concrete		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Bare Costs			Total Incl O&P
							Labor	Equipment	Total	
1650	With crane and bucket	C-7	130	554	C.Y.		18.95	9.20	28.15	39
1900	Footings, continuous, shallow, direct chute	C-6	120	400			13.20	.43	13.63	21
1950	Pumped	C-20	150	427			14.45	5.25	19.70	28
2000	With crane and bucket	C-7	90	800			27.50	13.30	40.80	56.50
2100	Footings, continuous, deep, direct chute	C-6	140	343			11.35	.37	11.72	17.80
2150	Pumped	C-20	160	400			13.55	4.94	18.49	26.50
2200	With crane and bucket	C-7	110	655			22.50	10.90	33.40	46
2400	Footings, spread, under 1 C.Y., direct chute	C-6	150	330			28.00	1.01	29.01	45
2450	Pumped	C-20	65	985			33.50	12.15	45.65	64.50
2500	With crane and bucket	C-7	90	720			28.00	1.01	29.01	45
2600	Over 5 C.Y., direct chute	C-6	120	400			13.20	.43	13.63	21
2650	Pumped	C-20	150	427			14.45	5.25	19.70	28
2700	With crane and bucket	C-7	100	720			24.50	11.95	36.45	50.50
2900	Foundation mats, over 20 C.Y., direct chute	C-6	350	137			4.53	.15	4.68	7.10
2950	Pumped	C-20	400	160			5.45	1.97	7.42	10.45
3000	With crane and bucket	C-7	300	240			8.20	3.99	12.19	16.95
3100	Grade beams, direct chute	C-6	150	320			18.00	.35	18.35	28.00
3250	Pumped	C-20	180	356			12.05	4.39	16.44	23.50
3300	With crane and bucket	C-7	100	720			24.50	11.95	36.45	50.50
3500	High rise, for more than 5 stories, pumped, add per story	C-20	2100	.030			1.03	.38	1.41	1.99
3510	With crane and bucket, add per story	C-7	2100	.034			1.17	.57	1.74	2.42
3700	Pile caps, under 5 C.Y., direct chute	C-6	90	533			17.65	.58	18.23	27.50
3750	Pumped	C-20	110	582			19.75	7.20	26.95	38
3800	With crane and bucket	C-7	80	900			31	14.95	45.95	63.50
3850	Pile cap, 5 C.Y. to 10 C.Y., direct chute	C-6	175	274			9.05	.30	9.35	14.25
3900	Pumped	C-20	200	320			10.85	3.95	14.80	21
3950	With crane and bucket	C-7	150	480			16.45	8	24.45	34
4000	Over 10 C.Y., direct chute	C-6	215	223			7.40	.24	7.64	11.55
4050	Pumped	C-20	240	267			9.05	3.29	12.34	17.45
4100	With crane and bucket	C-7	185	389			13.30	6.45	19.75	27.50
4200	Slab on grade, up to 6" thick, direct chute	C-6	110	434			14.00	.47	14.47	22.50
4350	Pumped	C-20	130	492			16.70	6.10	22.80	32
4400	With crane and bucket	C-7	100	720			24.50	11.95	36.45	50.50
4600	Over 6" thick, direct chute	C-6	165	291			9.60	.31	9.91	15.10
4650	Pumped	C-20	185	346			11.75	4.27	16.02	22.50
4700	With crane and bucket	C-7	145	497			17	8.25	25.25	35
4900	Walls, 8" thick, direct chute	C-6	90	533			17.65	.58	18.23	27.50
4950	Pumped	C-20	100	640			21.50	7.90	29.40	41.50
5000	With crane and bucket	C-7	80	900			31	14.95	45.95	63.50
5050	12" thick, direct chute	C-6	100	480			15.85	.52	16.37	25
5100	Pumped	C-20	110	582			19.75	7.20	26.95	38
5200	With crane and bucket	C-7	90	800			27.50	13.30	40.80	56.50
5300	15" thick, direct chute	C-6	105	457			15.10	.49	15.59	23.50
5350	Pumped	C-20	120	533			18.10	6.60	24.70	35
5400	With crane and bucket	C-7	95	758			26	12.60	38.60	53.50
5600	Wheeled concrete dumping, add to placing costs above									
5610	Walking cart, 50' haul, add	C-18	32	281	C.Y.		8.95	1.72	10.67	15.80
5670	150' haul, add		24	375			11.95	2.30	14.25	21
5700	250' haul, add		18	500			15.90	3.07	18.97	28
5800	Riding cart, 50' haul, add	C-19	80	113			3.58	1.08	4.66	6.75
5810	150' haul, add		60	150			4.77	1.44	6.21	9
5900	250' haul, add		45	200			6.35	1.92	8.27	11.95

Pg. 65

03 35 Concrete Finishing

03 35 29 – Tooled Concrete Finishing

03 35 29.30 Finishing Floors		Crew	Daily Output	Labor Hours	Unit	Material	2009 Labor	Bare Costs Equipment	Total	Total Incl O&P
0010	FINISHING FLOORS									
0020	Manual screed finish	C-10	4800	.005	S.F.		.18		.18	.27
0100	Manual screed, bull float						.43		.43	.64
0125	Manual screed, bull float, manual float		2000	.012			.47		.47	.70
0150	Manual screed, bull float, manual float & broom finish		1850	.013			.66		.66	1.02
0200	Manual screed, bull float, manual float, manual steel trowel		1265	.019			.50	.02	.52	.78
0250	Manual screed, bull float, machine float & trowel (walk-behind)	C-10C	1715	.014			.36	.05	.41	.59
0300	Power screed, bull float, machine float & trowel (walk-behind)	C-10D	2400	.010			.22	.06	.28	.39
0350	Power screed, bull float, machine float & trowel (ride-on)	C-10E	4000	.006			1.37	.24	1.71	2.44
0400	Integral topping and finish, using 1:1:2 mix, 3/16" thick	C-10B	1000	.040		.10	1.44	.25	1.95	2.74
0450	1/2" thick		950	.042		.26	1.61	.28	2.28	3.18
0500	3/4" thick		850	.047		.39	1.93	.32	2.67	3.68
0600	1" thick		750	.053		.52	2.32	.41	3.02	4.28
0800	Granolithic topping, laid after, 1:1:1-1/2 mix, 1/2" thick		590	.068		.29	2.36	.41	3.20	4.50
0820	3/4" thick		580	.069		.43	2.38	.42	3.37	4.70
0850	1" thick		575	.070		.57	2.74	.48	4.37	5.95
0950	2" thick		500	.080		1.15	4.29	.75	5.77	8.15
1200	Heavy duty, 1:1:2, 3/4" thick, prestripped, gray, 20 MSF		320	.125		.73	3.61	.63	4.63	6.55
1300	100 MSF		380	.105		.39				.97
1600	Exposed local aggregate finish, minimum	1 Calf	625	.013		.22	.66		1.32	1.69
1650	Maximum		465	.017		.66			.80	1.01
1800	Floor abrasives, .25 psf, aluminum oxide		850	.009		.44			.97	1.20
1850	Silicon carbide		850	.009		.61			.87	1.09
2000	Floor hardeners, metallic, light service, .50 psf, add		850	.009		.51			.76	.96
2050	Medium service, .75 psf		750	.011		.76			1.48	1.80
2100	Heavy service, 1.0 psf		650	.012		1.01			2.05	2.45
2150	Extra heavy, 1.5 psf		575	.014		1.52			.59	.78
2300	Non-metallic, light service, .50 psf		850	.009		.23			.34	.41
2350	Medium service, .75 psf		750	.011		.34			.45	.53
2400	Heavy service, 1.00 psf		650	.012		.45			.68	.85
2450	Extra heavy, 1.50 psf		575	.014		.68			1.21	1.53
2800	Trap rack wearing surface for monolithic floors									
2810	2.0 psf	C-10B	1250	.032	S.F.	.03	1.10	.19	1.32	1.90
3000	Floor coloring, dusted on, minimum (0.6 psf), add to above	1 Calf	1300	.006		.43			.67	.81
3050	Maximum (1.0 psf), add to above	"	625	.018		.71			1.20	1.50
3100	Colored powder only				Lb.	.71			.71	.78
3600	1/2" topping using 0.6 psf powdered color	C-10B	590	.068	S.F.	4.86	2.32	.41	7.59	9.30
3650	1/2" topping using 1.0 psf powdered color	"	590	.068		5.15	2.32	.41	7.88	9.60
3800	Dustproofing, solvent-based, 1 coat	1 Calf	1900	.004		.17			.33	.43
3850	2 coats		1300	.006		.61			.85	1.02
4000	Epoxy-based, 1 coat		1500	.005		.15			.20	.26
4050	2 coats		1500	.005		.29			.49	.62
4400	Stair finish, float		275	.029					1.11	1.43
4500	Steel trowel finish		200	.040					1.53	2.24
4600	Silicon carbide finish, .25 psf		150	.053		.44			2.48	3.47

Pg. 66

03 35 29.35 Control Joints, Saw Cut

0010 CONTROL JOINTS, SAW CUT		Crew	Daily Output	Labor Hours	Unit	Material	2009 Labor	Bare Costs Equipment	Total	Total Incl O&P
0100	Sawcut in green concrete									
0120	1" depth	C-27	2000	.008	L.F.	.07	.31	.07	.45	.60
0140	1-1/2" depth		1800	.009		.10	.34	.08	.52	.70
0160	2" depth		1600	.010		.13	.38	.09	.60	.81
0200	Clean out control joint of debris	C-28	6000	.001			.05		.05	.07

Pearland Recreation Center and Natatorium – Tech Report #2

05 12 Structural Steel Framing

05 12 23 – Structural Steel for Buildings

		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Labor	2009 Base Equip	Total	Total Ind O&P
--	--	------	--------------	-------------	------	----------	-----------------	-----------------	-------	---------------

05 12 23.05 Canopy Framing

0010	CANOPY FRAMING										
0020	6" and 8" members, shop fabricated	G	E-4	3000	.011	Lb.	1.80	.46	.04	2.32	2.89

05 12 23.10 Ceiling Supports

		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Labor	2009 Base Equip	Total	Total Ind O&P	
0010	CEILING SUPPORTS										
1000	Entrance door/folding partition supports, shop fabricated	G	E-4	60	.533	L.F.	30	24	2.23	56.23	76.50
1100	Linear accelerator door supports	G		14	2.286		137	103	9.60	249.60	345
1200	Lintels or shelf angles, hung, exterior hot dipped galv.	G		267	.120		20.50	5.40	.50	26.40	32.50
1250	two coats primer paint instead of galv.	G		267	.120		17.75	5.40	.50	23.65	29.50
1400	Monitor support, ceiling hung, expansion bolted	G		4	8	Eq.	475	360	33.50	868.50	1,200
1450	Hung from pre-set inserts	G		6	5.333		510	241	22.50	773.50	1,025
1600	Water supports for overhead doors	G		4	8		242	360	33.50	635.50	950
1700	Partition support for heavy folding partitions, without pocket	G		24	1.333	L.F.	68.50	60.50	5.60	134.60	188
1750	Supports at pocket only	G		12	2.667		137	121	11.15	269.15	375
2000	Rolling grilles & fire door supports	G		34	.941		58.50	42.50	3.94	104.94	145
2100	Spider-leg light supports, expansion bolted to ceiling slab	G		8	4	Eq.	195	181	16.75	392.75	555
2150	Hung from pre-set inserts	G		12	2.667		210	121	11.15	342.15	460
2400	Toilet partition support	G		36	.889	L.F.	68.50	40	3.72	112.22	151
2500	X-ray trolley gantry support	G		12	2.667		234	121	11.15	366.15	485

05 12 23.15 Columns, Lightweight

		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Labor	2009 Base Equip	Total	Total Ind O&P	
0010	COLUMNS, LIGHTWEIGHT										
1000	Lightweight units (lally), 3-1/2" diameter		E-2	780	.072	L.F.	6.70	3.13	2.23	11.46	14.50
1050	4" diameter			900	.062		8.95	2.71	1.93	13.59	16.55
5800	Adjustable jack post, 8' maximum height, 2-3/4" diameter	G				Eq.	33			33	36.50
5850	4" diameter	G					53			53	58

05 12 23.17 Columns, Structural

		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Labor	2009 Base Equip	Total	Total Ind O&P	
0010	COLUMNS, STRUCTURAL										
0015	Made from recycled materials										
0020	Shop fab'd for 100-ton, 1-2 story project, bolted connections										
0800	Steel, concrete filled, extra strong pipe, 3-1/2" diameter		E-2	660	.085	L.F.	49.50	3.70	2.64	55.84	63.50
0830	4" diameter			780	.072		55	3.13	2.23	60.36	68.50
0890	5" diameter			1020	.055		65.50	2.39	1.71	69.60	78.50
0930	6" diameter			1200	.047		87	2.03	1.45	90.48	101
0940	8" diameter			1100	.051		87	2.22	1.58	90.80	102
1100	For galvanizing, add					Lb.	.40			.40	.44
1300	For web ties, angles, etc., add per added lb.			1 Spwk	945	.008	1.50	.38		1.88	2.32
1500	Steel pipe, extra strong, no concrete, 3" to 5" diameter	G	E-2	16000	.004		1.50	.15	.11	1.76	2.03
1600	6" to 12" diameter	G		14000	.004		1.50	.17	.12	1.79	2.09
1700	Steel pipe, extra strong, no concrete, 3" diameter x 12'-0"	G		60	.933	Eq.	185	40.50	29	254.50	305
1750	4" diameter x 12'-0"	G		58	.966		270	42	30	342	400
1800	6" diameter x 12'-0"	G		54	1.037		515	45	32	592	680
1850	8" diameter x 14'-0"	G		50	1.120		910	49	35	994	1,125
1900	10" diameter x 16'-0"	G		48	1.167		1,325	51	36.50	1,412.50	1,575
1950	12" diameter x 18'-0"	G		45	1.244		1,775	54	38.50	1,867.50	2,075
3300	Structural tubing, square, A500GrB, 4" to 6" square, light section	G		11270	.005	Lb.	1.50	.22	.15	1.87	2.19
3600	Heavy section	G		32000	.002		1.50	.08	.05	1.63	1.84
4000	Concrete filled, add					L.F.	4.04			4.04	4.45
4500	Structural tubing, sq, 4" x 4" x 1/4" x 12'-0"	G	E-2	58	.966	Eq.	248	42	30	320	375
4550	6" x 6" x 3/8" x 12'-0"	G		54	1.037		495	45	32	572	655
4600	8" x 8" x 3/8" x 14'-0"	G		50	1.120		880	49	35	964	1,075
4650	10" x 10" x 1/2" x 16'-0"	G		48	1.167		1,625	51	36.50	1,712.50	1,925
5100	Structural tubing, sq, 4" to 6" square, light section	G		11270	.005	Lb.	1.50	.22	.15	1.87	2.19
5200	Heavy section	G		12000	.005		1.50	.20	.15	1.85	2.16

Pg. 110

05 12 Structural Steel Framing

05 12 23 – Structural Steel for Buildings

05 12 23.75 Structural Steel Members		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Costs			Total Ind O&P	
							Labor	Equipment	Total		
1500	x 26	G	E-2	880	.064	L.F.	43	2.77	1.98	47.75	54
1520	x 35	G		810	.069		58	3.01	2.15	63.16	71
1560	x 50	G		750	.075		82.50	3.25	2.32	88.07	99
1580	x 58	G		750	.075		95.50	3.25	2.32	101.07	113
1700	x 72	G		640	.088		119	3.81	2.72	125.53	140
1740	x 87	G		640	.088		144	3.81	2.72	150.53	167
1900	W 14 x 26	G		990	.057		45	2.46	1.76	47.22	53
2100	x 30	G		900	.062		49.50	2.71	1.95	54.14	61.50
2300	x 34	G		810	.069		56	3.01	2.15	61.14	69
2320	x 43	G		810	.069		71	3.01	2.15	76.14	85.50
2340	x 53	G		800	.070		87.50	3.05	2.18	92.73	104
2360	x 74	G		760	.074		122	3.21	2.29	127.50	142
2380	x 90	G		740	.076		149	3.30	2.35	154.65	171
2700	W 16 x 26	G		1000	.056		43	2.44	1.74	47.18	53
2900	x 31	G		800	.070		66	3.05	2.18	71.23	80
3100	x 40	G		800	.070		82.50	3.05	2.18	87.73	98.50
3120	x 50	G		800	.070		111	3.21	2.29	116.50	130
3140	x 67	G	E-5	760	.074		58	3.67	1.95	63.62	72
3300	W 18 x 35	G		960	.083		66	3.67	1.95	71.62	81
3500	x 40	G		960	.083		76	3.67	1.95	81.62	92
3520	x 46	G		912	.088		82.50	3.87	2.06	88.43	100
3700	x 50	G		912	.088		91	3.87	2.06	96.93	109
3900	x 55	G		900	.089		107	3.92	2.08	113	127
3920	x 65	G		900	.089		125	3.92	2.08	131	147
3940	x 76	G		900	.089		142	3.92	2.08	148	165
3960	x 86	G		900	.089		175	3.92	2.08	181	201
3980	x 106	G		1064	.075		72.50	3.32	1.76	77.58	87.50
4100	W 21 x 44	G		1064	.075		82.50	3.32	1.74	87.58	98.50
4300	x 50	G		1036	.077		102	3.41	1.81	107.22	121
4500	x 62	G		1036	.077		112	3.41	1.81	117.22	131
4700	x 68	G		1000	.080		137	3.53	1.88	142.41	159
4720	x 83	G		1000	.080		153	3.53	1.88	158.41	177
4740	x 93	G		1000	.080		167	3.53	1.88	172.41	191
4760	x 101	G		1000	.080		201	3.53	1.88	206.41	229
4780	x 122	G		1110	.072		91	3.18	1.69	95.87	107
4900	W 24 x 55	G		1110	.072		102	3.18	1.69	106.87	120
5100	x 62	G		1110	.072		112	3.18	1.69	116.87	130
5300	x 68	G		1110	.072		125	3.18	1.69	129.87	145
5500	x 76	G		1080	.074		139	3.27	1.74	144.01	160
5700	x 84	G		1080	.074		155	3.27	1.74	160.01	179
5720	x 94	G		1050	.076		172	3.36	1.79	177.15	197
5740	x 104	G		1050	.076		193	3.36	1.79	198.15	220
5760	x 117	G		1050	.076		241	3.36	1.79	246.15	273
5780	x 144	G		1190	.067		139	2.96	1.58	143.54	159
5800	W 27 x 84	G		1190	.067		157	2.96	1.58	159.54	178
5900	x 114	G		1150	.070		188	3.07	1.63	192.70	214
5920	x 146	G		1150	.070		241	3.07	1.63	245.70	272
5940	x 177	G		1150	.070		266	3.07	1.63	270.70	299
6100	W 30 x 99	G		1200	.067		163	2.94	1.56	167.50	187
6300	x 108	G		1160	.069		191	3.04	1.62	195.66	218
6500	x 116	G									

Pg. 114

05 21 Steel Joist Framing

05 21 16 – Longspan Steel Joist Framing

05 21 16.50 Longspan Joists		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Costs		Total	Total Incl O&P
							Labor	Equipment		
2340	28LH11, 25 Lb/LF	G	1800	.044		28	1.96	1.12	31.08	35.50
2360	32LH08, 17 Lb/LF	G	1800	.044		34	1.96	1.12	37.08	42
2380	32LH13, 30 Lb/LF	G	1800	.044		34	1.96	1.12	26.58	30.50
2400	36LH09, 21 Lb/LF	G	1800	.044		23.50	1.96	1.12	43.58	49
2420	36LH14, 36 Lb/LF	G	1800	.044		40.50	1.96	1.12	26.01	30
2440	40LH10, 21 Lb/LF	G	2200	.036		23.50	1.60	.91	43.01	48.50
2460	40LH15, 36 Lb/LF	G	2200	.036		40.50	1.60	.91	27.51	31.50
2480	44LH11, 22 Lb/LF	G	2200	.036		25	1.60	.91	50.01	56
2500	44LH16, 42 Lb/LF	G	2200	.036		47.50	1.60	.91	27.51	31.50
2520	48LH11, 22 Lb/LF	G	2200	.036		25	1.60	.91	50.01	56
2540	48LH16, 42 Lb/LF	G	2200	.036		47.50	1.60	.91	50.01	56
2600	For less than 40-ton job lots									
2602	For 30 to 39 tons, add					10%				
2604	20 to 29 tons, add					20%				
2606	10 to 19 tons, add					30%				
2607	5 to 9 tons, add					50%	25%			
2608	1 to 4 tons, add					75%	50%			
2609	Less than 1 ton, add					100%	100%			
6000	For welded cross bridging, add							30%		

Page 121

05 21 19 – Open Web Steel Joist Framing

05 21 19.10 Open Web Joists

05 21 19.10 OPEN WEB JOISTS		Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Costs		Total	Total Incl O&P	
							Labor	Equipment			
0010	OPEN WEB JOISTS										
0015	Made from recycled materials										
0020	K series, 40-ton joist, horiz. bridging, spans to 30', shop primer, minimum	G	E-7	15	5.333	Ton	1,825	235	134	2,194	2,550
0050	Average	G		12	6.667		2,050	294	167	2,511	2,950
0080	Maximum	G		9	8.889		2,450	390	223	3,063	3,625
0130	8K1, 5.1 Lb/LF	G		1200	.067	LF	5.20	2.94	1.67	9.81	12.65
0140	10K1, 5.0 Lb/LF	G		1200	.067		5.10	2.94	1.67	9.71	12.55
0160	12K3, 5.7 Lb/LF	G		1500	.053		5.80	2.35	1.34	9.49	11.95
0180	14K3, 6.0 Lb/LF	G		1500	.053		6.10	2.35	1.34	9.79	12.30
0200	16K3, 6.3 Lb/LF	G		1800	.044		6.40	1.96	1.12	9.48	11.65
0220	16K6, 8.1 Lb/LF	G		1800	.044		8.25	1.96	1.12	11.33	13.70
0240	18K5, 7.7 Lb/LF	G		2000	.040		7.85	1.76	1	10.61	12.80
0260	18K9, 10.2 Lb/LF	G		2000	.040		10.40	1.76	1	13.16	15.60
0410	Span 30' to 50', minimum	G		17	4.706	Ton	1,775	208	118	2,101	2,450
0440	Average	G		17	4.706		2,000	208	118	2,326	2,700
0460	Maximum	G		10	9		2,125	355	201	2,681	3,150
0500	20K5, 8.2 Lb/LF	G		2000	.040	LF	8.20	1.76	1	10.96	13.15
0520	20K9, 10.8 Lb/LF	G		2000	.040		10.80	1.76	1	13.56	16.05
0540	22K5, 8.8 Lb/LF	G		2000	.040		8.80	1.76	1	11.56	13.85
0560	22K9, 11.3 Lb/LF	G		2000	.040		11.30	1.76	1	14.06	16.60
0580	24K6, 9.7 Lb/LF	G		2200	.036		9.70	1.60	.91	12.21	14.45
0600	24K10, 13.1 Lb/LF	G		2200	.036		13.10	1.60	.91	15.61	18.20
0620	26K6, 10.6 Lb/LF	G		2200	.036		10.60	1.60	.91	13.11	15.45
0640	26K10, 13.8 Lb/LF	G		2200	.036		13.80	1.60	.91	16.31	19
0660	28K8, 12.7 Lb/LF	G		2400	.033		12.70	1.47	.84	15.01	17.40
0680	28K12, 17.1 Lb/LF	G		2400	.033		17.10	1.47	.84	19.41	22.50
0700	30K8, 13.2 Lb/LF	G		2400	.033		13.20	1.47	.84	15.51	17.95
0720	30K12, 17.6 Lb/LF	G		2400	.033		17.60	1.47	.84	19.91	23
0800	For less than 40-ton job lots										
0802	For 30 to 39 tons, add					10%					

05 31 Steel Decking

05 31 23 – Steel Roof Decking

05 31 23.50 Roof Decking

	CN	G	Crew	Daily Output	Labor Hours	Unit	Material	2009 Base Costs			Total	Total Ind O&P
								Labor	Equipment			
2200	50-500 squares		E-4	4900	.007	S.F.	2	.30	.03		2.33	2.76
2400	Over 500 squares			5100	.006		1.85	.28	.03		2.16	2.58
2600	20 gauge, under 50 squares			3865	.008		3.03	.37	.03		3.43	4.04
2650	50-500 squares			4170	.008		2.42	.35	.03		2.80	3.32
2700	Over 500 squares			4300	.007		2.18	.34	.03		2.55	3.02
2900	18 gauge, under 50 squares			3800	.008		3.91	.38	.04		4.33	5.05
2950	50-500 squares			4100	.008		3.13	.35	.03		3.51	4.11
3000	Over 500 squares			4300	.007		2.82	.34	.03		3.19	3.78
3050	16 gauge, under 50 squares			3700	.009		5.25	.39	.04		5.68	6.55
3060	50-500 squares			4000	.008		4.21	.36	.03		4.60	5.30
3100	Over 500 squares			4200	.008		3.79	.34	.03		4.16	4.82
3150	For intermediate rib instead of wide rib, deduct						.04				.04	.05
3160	For narrow rib instead of wide rib, add						.79				.79	.87

05 31 33 – Steel Form Decking

05 31 33.50 Form Decking

FORM DECKING												
Made from recycled materials												
6100	Slab form, steel, 28 gauge, 9/16" deep, uncoated		G	E-4	4000	.008	S.F.	1.72	.36	.03	2.11	2.57
	Galvanized		G		4000	.008		1.32	.36	.03	1.71	2.17
6220	24 gauge, 1" deep, uncoated		G		3900	.008		1.87	.37	.03	2.27	2.76
6240	Galvanized		G		3900	.008		2.20	.37	.03	2.60	3.12
6300	24 gauge, 1-5/16" deep, uncoated		G		3800	.008		1.99	.35	.04	2.41	2.91
6400	Galvanized		G		3800	.008		2.34	.38	.04	2.76	3.29
6500	22 gauge, 1-5/16" deep, uncoated		G		3700	.009		2.50	.39	.04	2.93	3.49
6600	Galvanized		G		3700	.009		2.55	.39	.04	2.98	3.55
6700	22 gauge, 2" deep uncoated		G		3600	.009		3.28	.40	.04	3.72	4.37
6800	Galvanized		G		3600	.009		3.22	.40	.04	3.66	4.30
7000	Sheet metal edge closure form, 12" wide with 2 bends, galv											
7100	18 gauge		G	E-14	360	.022	L.F.	5.30	1.04	.37	6.71	8.10
7200	16 gauge		G	"	360	.022	"	7.20	1.04	.37	8.61	10.15

Pg. 124

05 35 Raceway Decking Assemblies

05 35 13 – Steel Cellular Decking

05 35 13.50 Cellular Decking

CELLULAR DECKING												
Made from recycled materials												
0200	Cellular units, galv, 2" deep, 20-20 gauge, over 15 squares		G	E-4	1460	.022	S.F.	10.20	.99	.09	11.28	13.10
0250	18-20 gauge		G		1420	.023		11.60	1.02	.09	12.71	14.70
0300	18-18 gauge		G		1390	.023		11.95	1.04	.10	13.09	15.10
0320	16-18 gauge		G		1360	.024		14.20	1.06	.10	15.36	17.60
0340	16-16 gauge		G		1330	.024		15.85	1.09	.10	17.04	19.45
0400	3" deep, galvanized, 20-20 gauge		G		1375	.023		11.25	1.05	.10	12.40	14.35
0500	18-20 gauge		G		1350	.024		13.60	1.07	.10	14.77	16.95
0600	18-18 gauge		G		1290	.025		13.55	1.12	.10	14.77	17.05
0700	16-18 gauge		G		1230	.026		15.25	1.18	.11	16.54	19
0800	16-16 gauge		G		1150	.028		16.65	1.26	.12	18.03	20.50
1000	4-1/2" deep, galvanized, 20-18 gauge		G		1100	.029		15.70	1.31	.12	17.13	19.70
1100	18-18 gauge		G		1040	.031		15.60	1.39	.13	17.12	19.75
1200	16-18 gauge		G		980	.033		17.55	1.48	.14	19.17	22
1300	16-16 gauge		G		935	.034		19.15	1.55	.14	20.84	24

07 12 Built-up Bituminous Waterproofing

07 12 13 – Built-Up Asphalt Waterproofing

07 12 13.20 Membrane Waterproofing	Crew	Daily Output	Labor-Hours	Unit	Material	2009 Base Costs			Total Incl O&P
						Labor	Equipment	Total	
0010 MEMBRANE WATERPROOFING									
0012 On slabs, 1 ply, felt, mopped	G-1	3000	.019	S.F.	.34	.60	.15	1.09	1.55
0100 On slabs, 1 ply, glass fiber fabric, mopped		2100	.027		.36	.85	.21	1.42	2.06
0300 On slabs, 2 ply, felt, mopped		2500	.022		.69	.72	.18	1.59	2.16
0400 On slabs, 2 ply, glass fiber fabric, mopped		1850	.034		.79	1.09	.27	2.15	2.95
0600 On slabs, 3 ply, felt, mopped		2100	.027		1.03	.85	.21	2.09	2.81
0700 On slabs, 3 ply, glass fiber fabric, mopped		1550	.036		1.07	1.16	.28	2.51	3.44
0710 Asphalt hardboard protection board, 1/8" thick	2 Rofc	500	.032		.40	1.10		1.50	2.28
1000 1/4" EPS membrane protection board		3500	.005		.21	.16		.37	.49
1050 3/8" thick		3500	.005		.23	.16		.39	.51
1060 1/2" thick		3500	.005		.26	.16		.42	.55
1070 Fiberglass fabric, black, 20/10 mesh		116	.138	Sq.	18	4.72		22.72	28
1080 White, 20/10 mesh		116	.138	"	18	4.72		22.72	28

07 13 Sheet Waterproofing

07 13 53 – Elastomeric Sheet Waterproofing

07 13 53.10 Elastomeric Sheet Waterproofing and Access.

0010 ELASTOMERIC SHEET WATERPROOFING AND ACCESS.	Crew	Daily Output	Labor-Hours	Unit	Material	Labor	Equipment	Total	Total Incl O&P
0090 EPDM, plain, 45 mils thick	2 Rofc	580	.028	S.F.	1.19	.95		2.14	2.98
0100 60 mils thick		570	.028		1.25	.96		2.21	2.99
0300 Nylon reinforced sheets, 45 mils thick		580	.028		1.16	.95		2.11	2.86
0400 60 mils thick		570	.028		1.47	.96		2.43	3.23
0600 Waterproofing splicing tape for above, 2" wide				C.L.F.	43.50			43.50	47.50
0700 4" wide				"	99.50			99.50	109
0900 Adhesive, bonding, 60 SF per gal				Gal.	16.50			16.50	18.15
1000 Splicing, 75 SF per gal				"	32			32	35
1200 Neoprene sheets, plain, 45 mils thick	2 Rofc	580	.028	S.F.	1.68	.95		2.63	3.44
1300 60 mils thick		570	.028		2.86	.96		3.82	4.77
1500 Nylon reinforced, 45 mils thick		580	.028		1.75	.95		2.70	3.52
1600 60 mils thick		570	.028		2.46	.96		3.42	4.33
1800 120 mils thick		500	.032		4	1.10		5.10	6.25
1900 Adhesive, splicing, 150 S.F. per gal, per coat				Gal.	17.50			17.50	19.25
2100 Fiberglass reinforced, fluid applied, 1/8" thick	2 Rofc	500	.032	S.F.	1.88	1.10		2.98	3.93
2200 Polyethylene and rubberized asphalt sheets, 1/8" thick		550	.029		.79	1		1.73	2.48
2210 Asphalt hardboard protection board, 1/8" thick		500	.032		.40	1.10		1.50	2.09
2220 1/4" thick		450	.036		.68	1.22		1.90	2.60
2400 Polyvinyl chloride sheets, plain, 10 mils thick		580	.028		.17	.95		1.12	1.79
2500 20 mils thick		570	.028		.28	.96		1.24	1.92
2700 30 mils thick		560	.029		.39	.98		1.37	2.06
3000 Adhesives, trowel grade, 40-100 SF per gal				Gal.	27			27	29.58
3100 Brush grade, 100-250 SF per gal				"	27			27	29.58
3200 Polyurethane fluid applied, 55 mils thick	2 Rofc	665	.024	S.F.	1.8	1.08		2.88	3.81
3600 Vinyl plastic, sprayed on, 25 to 40 mils thick		475	.034	"	1.20	1.15		2.35	3.24

Pg. 192

31 63 Bored Piles

31 63 26 – Drilled Caissons

31 63 26.13 Fixed End Cassion Piles		Crew	Daily Output	Labor Hours	Unit	Material	2009 Bare Costs		Total	Total Incl O&P
							Labor	Equipment		
0010	FIXED END CASSION PILES									
										8316326-60
0015	Including excavation, concrete, 50 lbs reinforcing									
0020	per C.Y., not incl. mobilization, boulder removal, disposal									
0100	Open style, machine drilled, to 50' deep, in stable ground, no									
0110	casing or ground water, 18" diam., 0.065 C.Y./L.F.	B-43	200	240	V.L.F.	9.05	8.30	12.65	30	35.50
0200	24" diameter, 0.116 C.Y./L.F.		190	253		16.20	6.75	13.35	38.30	46
0300	30" diameter, 0.182 C.Y./L.F.		150	320		25.50	11.10	16.90	53.50	63.50
0400	36" diameter, 0.262 C.Y./L.F.		125	384		36.50	13.30	20.50	70.30	83
0500	48" diameter, 0.465 C.Y./L.F.		100	480		65	16.60	25.50	107.10	125
0600	60" diameter, 0.727 C.Y./L.F.		90	533		102	18.45	28	148.45	172
0700	72" diameter, 1.05 C.Y./L.F.		80	600		147	21	31.50	199.50	229
0800	84" diameter, 1.43 C.Y./L.F.		75	640		200	22	34	256	291
1000	For bell excavation and concrete, add									
1020	4' bell diameter, 24" shaft, 0.444 C.Y.	B-43	20	2,400	Ex.	45	83	127	255	315
1040	6' bell diameter, 30" shaft, 1.57 C.Y.		5.70	8,421		159	292	445	896	1,100
1060	8' bell diameter, 36" shaft, 3.72 C.Y.		2.40	20		375	695	1,050	2,120	2,625
1080	9' bell diameter, 48" shaft, 4.48 C.Y.		2	24		450	830	1,275	2,555	3,175
1100	10' bell diameter, 60" shaft, 5.24 C.Y.		1.70	28,235		530	980	1,500	3,010	3,725
1120	12' bell diameter, 72" shaft, 8.74 C.Y.		1	48		885	1,650	2,525	5,060	6,300
1140	14' bell diameter, 84" shaft, 13.6 C.Y.		.70	68,571		1,375	2,375	3,625	7,375	9,125
1200	Open style, machine drilled, to 50' deep, in wet ground, cased									
1300	casing and pumping, 18" diameter, 0.065 C.Y./L.F.	B-48	160	350	V.L.F.	9.05	19.35	17.90	39.30	48.50
1400	24" diameter, 0.116 C.Y./L.F.		150	445		16.20	10.00	23	55	67
1500	30" diameter, 0.182 C.Y./L.F.		120	559		25.50	23	34.50	82	100
1600	36" diameter, 0.262 C.Y./L.F.		100	820		36.50	25	47.50	117	145
1700	48" diameter, 0.465 C.Y./L.F.	B-49	55	1,600		65	58.50	66.50	170	235
1800	60" diameter, 0.727 C.Y./L.F.		50	2,514		102	72	104	278	350
1900	72" diameter, 1.05 C.Y./L.F.		30	2,933		147	108	122	377	460
2000	84" diameter, 1.43 C.Y./L.F.		25	3,520		200	129	146	475	580
2100	For bell excavation and concrete, add									
2120	4' bell diameter, 24" shaft, 0.444 C.Y.	B-48	19.80	2,880	Ex.	45	99.50	144	248.50	308
2140	6' bell diameter, 30" shaft, 1.57 C.Y.		5.70	1,823		159	315	465	939	1,160
2160	8' bell diameter, 36" shaft, 3.72 C.Y.		2.40	23,333		375	325	1,200	2,400	2,975
2180	9' bell diameter, 48" shaft, 4.48 C.Y.	B-49	3.30	26,867		450	975	1,100	2,525	3,175
2200	10' bell diameter, 60" shaft, 5.24 C.Y.		1.70	81,768		530	1,150	1,500	2,980	3,725
2220	12' bell diameter, 72" shaft, 8.74 C.Y.		1.60	55		885	2,025	2,275	5,185	6,575
2240	14' bell diameter, 84" shaft, 13.6 C.Y.		1	88		1,375	3,225	3,650	8,250	10,500
2300	Open style, machine drilled, to 50' deep, in soft rocks and									
2400	medium hard shales, 18" diameter, 0.065 C.Y./L.F.	B-49	50	1,760	V.L.F.	9.05	64.50	73	146.55	190
2500	24" diameter, 0.116 C.Y./L.F.		30	2,933		16.20	108	122	246.20	320
2600	30" diameter, 0.182 C.Y./L.F.		20	4,400		25.50	161	183	369.50	480
2700	36" diameter, 0.262 C.Y./L.F.		15	5,867		36.50	215	243	494.50	640
2800	48" diameter, 0.465 C.Y./L.F.		10	8,800		65	325	365	755	965
2900	60" diameter, 0.727 C.Y./L.F.		7	12,571		102	460	520	1,082	1,400
3000	72" diameter, 1.05 C.Y./L.F.		4	14,667		147	540	610	1,297	1,650
3100	84" diameter, 1.43 C.Y./L.F.		5	17,600		200	645	730	1,575	2,025
3200	For bell excavation and concrete, add									
3220	4' bell diameter, 24" shaft, 0.444 C.Y.	B-49	10.90	8,073	Ex.	45	296	335	676	875
3240	6' bell diameter, 30" shaft, 1.57 C.Y.		3.10	28,387		159	1,050	1,175	2,384	3,075
3260	8' bell diameter, 36" shaft, 3.72 C.Y.		1.30	67,692		375	2,475	2,800	5,650	7,350
3280	9' bell diameter, 48" shaft, 4.48 C.Y.		1.10	80		450	2,925	3,325	6,700	8,675
3300	10' bell diameter, 60" shaft, 5.24 C.Y.		.90	97,778		530	3,575	4,050	8,155	10,600
3320	12' bell diameter, 72" shaft, 8.74 C.Y.		.60	146		885	5,375	6,075	12,335	15,900

19-592

Appendix 5

General Conditions Estimate

General Conditions Estimate

General Conditions Estimate				
Item	Unit	Unit Cost	Quantity	Total Cost
General Contractor Personnel (RS Means Page 10)				
Admin/Secretary	MTH	\$3,200.00	5	\$2,555.00
Assistant Superintendant	MTH	\$7,600.00	13	\$98,800.00
Superintendant	MTH	\$8,227.00	13	\$106,951.00
Project Engineer	MTH	\$7,145.00	13	\$92,885.00
Project Manager	MTH	\$8,346.00	6.5	\$54,249.00
Senior Project Manager	MTH	\$8,660.00	1.5	\$12,990.00
Temporary Facilities (EMJ Corporation)				
Jobsite Office	MTH	\$486.67	15	\$7,300.00
Temporary Toilets	MTH	\$513.33	15	\$7,700.00
Barricades	MTH	\$66.67	15	\$1,000.00
Construction Signs	MTH	\$60.00	15	\$900.00
Dumpsters	MTH	\$133.33	15	\$2,000.00
Temporary Utilities (EMJ Corporation)				
Temporary Electric	MTH	\$1,000.00	15	\$15,000.00
Temporary Water	MTH	\$46.67	15	\$700.00
Temporary Telephone	MTH	\$646.67	15	\$9,700.00
Cleaning (EMJ Corporation)				
Misc. Clean-up	MTH	\$233.33	15	\$3,500.00
Site Clean-up	LS	\$2,500.00	1	\$2,500.00
Final Building Clean-up	LS	\$37,000.00	1	\$37,000.00
Miscellaneous (EMJ Corporation)				
Trash Removal	MTH	\$966.67	15	\$14,500.00
Blueprints	LS	\$3,500.00	1	\$3,500.00
Safety (Drug Testing, Equipment, etc.)	LS	\$1,500.00	1	\$1,500.00
Hand Tools	LS	\$6,000.00	1	\$6,000.00
Engineering and Layout	LS	\$2,000.00	1	\$2,000.00
Incidentals	LS	\$4,000.00	1	\$4,000.00
Insurance	% of Contract	\$16,786,542.00	3%	\$503,596.26
Bonds	% of Contract	\$16,786,542.00	2%	\$335,730.84
O&P	% of Contract	\$16,786,542.00	4%	\$671,461.68
Total				\$1,998,018.78