

Thesis Proposal

Voorhees Replacement Facility | Voorhees, NJ

Steven Farrah | Construction Option

12/15/2009

Chris Magent



Table of Contents

Executive Summary.....	3
Analysis 1: Sustainability.....	4
Analysis 2: Patient Room Lighting.....	5
Analysis 3: Exterior Open Joint Wall Systems.....	6
Analysis 4: Curtain Wall System.....	7
Breadth Analysis's.....	8
Weight Matrix.....	8



Executive Summary

The following proposal is an outline that will guide my research for the spring of 2010. It identifies my 4 major areas of construction management analysis and provides research steps that will be taken to complete each analysis.

The first analysis is sustainability in healthcare projects and will determine if the design of LEED healthcare buildings is worth pursuing and what LEED areas within LEED are most applicable to healthcare projects. This analysis will also apply what is learned from the research to the Voorhees Replacement Hospital and attempt to add sustainable ideas into the building without compromising the architect's design.

The second analysis is the redesign of patient room lighting. Currently the patient rooms are design using fluorescent lighting but with owners continuously looking for energy saving ideas I will determine if using LED lighting is more efficient and cost effective then the fluorescent lighting in place. Also I will research the effect of lighting on patient's recovery and overall health and determine if the switch from LED to fluorescent lighting will have a positive or negative effect on patients.

The third analysis involves the exterior open joint wall systems including the stone and phenolic panels. The current systems required a grid system fastened to the metal stud backup wall, which created issues with watertightness. This analysis will investigate into different systems and or options to replace the current system and reduce the cost and time it took to install the system in place.

The last analysis includes determining if it will save the project time and money by switching the current stick built curtain wall system to a prefabricated.

My two breadth analysis's come from analysis 2: patient room lighting. The first breadth analysis will determine if switching from LED lighting to fluorescent lighting in the patient rooms will reduce the HVAC load and my second breadth analysis is the lighting design of the room.



Analysis 1: Sustainability

Problem

Because of the complexity of healthcare projects, one does not often see a LEED rated hospital because of the extra expense. Although the Voorhees Replacement Hospital does incorporate some green design it is not attempting to achieve a sustainable rating of any kind. In a continuously growing green market is there a way to push the hospitals design to incorporate more sustainable ideas and possibly achieve a LEED rating?

Goal

To determine if the design of a LEED healthcare building is worth pursuing and what the best LEED areas are to pursue without inflating the budget.

Research Steps

Step 1: Research LEED certification and the points needed to achieve LEED certification.

Step 2: Analyze the feasibility of each point based upon healthcare construction requirements.

Step 3: Talk with industry professionals who have worked on healthcare projects to determine the feasibility of attempting to achieve a LEED rating.

Step 4: Analyze the Voorhees Replacement Hospital for current LEED design and determine where there is room for improvement and new LEED ideas.

Step 5: Analyze present costs and lifecycle costs of implementing new LEED ideas into the building.

Expected Outcome

I expect that LEED certification on healthcare projects will be obtainable with careful preconstruction planning and good construction management. I also expect that it will be expensive to incorporate new LEED ideas into the building and this is the main deterrent for healthcare owners.



Analysis 2: Patient Room Lighting

Problem

The patient rooms are currently designed around the use of fluorescent lighting. As energy issues grow and owners continuously look for energy savings in their buildings I will investigate the use of LED lighting in the patient rooms. I will also ask if a patient feels more comfortable under the use of LED lighting than fluorescent.

Goal

To redesign the current patient rooms to include more efficient and cost effective lighting and determine if the use of LED lighting will increase the patient's happiness and make them feel more comfortable in the hospital.

Research Steps

Step 1: Determine the requirements for lighting in hospital patient rooms.

Step 2: Redesign the patient room lighting plan using LED lighting to meet lighting requirements.

Step 3: Conduct an initial cost analysis of the LED lighting verse the fluorescent lighting followed by a life cycle cost analysis.

Step 4: Research by articles and talking to healthcare professionals the effect of lighting on patients.

Step 5: Conduct surveys regarding the difference in room comfortableness by each lighting type.

Step 6: Determine if patients would be affected positively with the use of LED's verse fluorescent lighting.

Expected Outcome

I expect that the LED lighting will provide a better cost model then the fluorescent lighting and will ultimately provide more cost savings although the initial investment may be more expensive. I also expect that LED lighting will provide a more comfortable experience for hospital patients.



Analysis 3: Exterior Open Joint Wall Systems

Problem

On the Voorhees Replacement Hospital the stone and phenolic panel exterior wall systems require a grid system fastened to the metal stud backup wall in order to support the façade. This created a watertight issue due to the number of screws that were going through the waterproofing to attach the grid system to the backup wall and in turn required extra materials and manpower to complete the system as well as schedule delays.

Goal

To investigate the current systems put in place and determine if there is a better way to attach the stone and phenolic panels to the building without requiring the extra materials and manpower.

Research Steps

Step 1: Study the drawings and pictures of the current system put in place to understand fully the problem that occurred.

Step 2: Research different less intrusive ways to attach the façade materials to the building.

Step 3: Conduct a constructability analysis to make sure the proposed attachment method can be done.

Step 4: Conduct a cost analysis on the proposed method vs. the method put in place.

Step 5: Conduct a schedule analysis to determine if any schedule reduction is possible.

Expected Outcome

I expect that I will be able to find a different way of attaching the materials to the building without requiring the extra waterproofing or superintendents to make sure the building stays watertight. I also expect that this proposed method will save the project both money and time.



Analysis 4: Curtain Wall

Problem

The large curtain wall system at the bed tower was stick built and along the critical path of the project. Since water tightness controls when the rough-in and finish stages of the project can begin I believe that prefabricating the curtain wall can save the project time and money.

Goal

To determine if switching the curtain wall system from stick built to prefabricated will save time and money to the project.

Research Steps

Step 1: Determine the cost and schedule for the stick built curtain wall system.

Step 2: Research prefabricated systems by speaking with industry experts.

Step 3: Perform takeoffs and determine the cost to install a prefabricated system.

Step 4: Conduct a schedule analysis to determine the time required to install a prefabricated system.

Step 5: Conduct a site utilization plan for the installation of the prefabricated system.

Expected Outcome

I expect that by switching from a stick built curtain wall system to a prefabricated curtain wall system the project will be able to save money and reduce the installation schedule allowing for rough-in and finishes to start earlier. I also expect that due to the wide open area of construction there will not be an issue with using a crane to install the system.



Breadth Analysis's

Mechanical Breadth – Analysis 2: Patient Room Lighting

This analysis will include a mechanical breadth analysis. The breadth analysis will be determining the current HVAC loads in the patient room before and after the lighting change to see if there could be a reduction in equipment or duct size resulting in a cost reduction.

Lighting/Electrical Breadth – Analysis 2: Patient Room Lighting

This analysis will include a lighting breadth analysis. The breadth analysis will be the redesign of a patient room from fluorescent lighting to LED lighting.

Weight Matrix

Description	Research	Value Engineering	Const. Rev.	Sched. Red.	Total
Sustainability	15%	5%	5%		25%
Patient Room Lighting	10%	10%			20%
Exterior Open Joint Wall Systems		10%	10%	10%	30%
Curtain Wall		10%	5%	10%	25%
Total	25%	35%	20%	20%	100%