Technical Assignment 1

Voorhees Replacement Facility | Voorhees, NJ

Steven Farrah | Construction Option

10/5/2009

Steven Farrah Tech 1

Voorhees Replacement Facility Voorhees, NJ



Table of Contents

Executive Summary	3
Schedule Summary	4
Building Systems Summary	6
Project Cost Evaluation	10
Site Plan of Existing Conditions	14
Local Conditions	15
Client Information	16
Project Delivery System	17
Staffing Plan	19
Primavera Schedule Summary	Appendix A
Breakdown of Actual Costs by Bid Package	Appendix B
D4 Statement of Probable Cost	Appendix C
RS Means Data Sheets	Appendix D
Site Plan of Existing Conditions	Appendix E
Boring Sample Report	Appendix F
Turner Staffing Plan	Appendix G



Executive Summary

Virtua Health is a non-profit healthcare organization that has decided to construct a replacement hospital for their current Voorhees facility. The decision to construct the new hospital was made to accommodate both the increasing demand of the community and the ever-changing technology in hospitals.

This technical assignment provides insight into the existing conditions of the Voorhees Replacement Facility, systems being put in place, construction management techniques, project delivery techniques including project staffing and a cost and schedule analysis.

Through completing a general schedule analysis of about thirty items it was found that Turner commenced the buyout of certain subcontractors before the completion of design development to allow for a fast tracked schedule. It was also found that the fit-out of the bed tower building becomes the critical path once steel erection has been completed. The fit-out of the bed tower is something that may be worth looking at in the future to see if it would be possible to shorten the schedule.

From carrying out a cost comparison it was found that using the rough estimate tools, RS Means Square Foot Cost Data and D4 Cost estimating software provides a estimate construction cost much less then the actual construction. It was found that the D4 Cost estimating software was more accurate to actual construction costs due to the fact that the envelope systems more closely matched that of the Voorhees Replacement Facility then what was offered in RS Means Square Foot Cost Data.

Lastly the project is being delivered via the traditional design-bid-build approach in which Turner acts as the CM@ Risk to the owner Virtua Health. Turner holds a GMP contract with the owner and also with all of its subcontractors. The owner on this project holds an OCIP that allows them to be sure every subcontractor has the proper insurance covered. It was also found from examining the Turner staffing plan that the building was split up between the bed tower building and ancillary spaces to ensure that the superintendents were not overwhelmed with responsibility.



Schedule Summary

Please see Appendix A for project schedule summary.

As seen from the project schedule summary the total duration from schematic design to building turnover of the project spans from November 2006 to March 2011. It is important to note however that the owner Virtua Health had owned the site before bringing in the Architect to conceptualize a design. During this time Virtua did site evaluations including bringing in the geo-technical engineer to assess the site conditions.

The schematic design process unlike most design-bid-build projects was used to create bid documents for the construction manager bidding process because of such a fast tracked schedule. Turner Construction was awarded the project and then authorized to commence their duties on March 26, 2007. Again due to the fast tracked schedule, design packages were scheduled to release in different phases starting with the structural package so that Turner could buyout a subcontractor and start the long procurement time of structural steel. Throughout a good portion more of the design development stage the remainder of the design packages were released from the architecturals all the way to electrical and telecommunications. The end date of the design development phase shown on the schedule summary is when the last major design change was released.

As shown on the schedule summary contractor buyouts and engineering/procurement are very long duration tasks. This is because contractors that do not commence work until the final stages of construction are not bought out immediately.

The key element of the foundation and site work are the geo-piles. As described in a later section almost 4,000 stone piles were installed around the site. This was the critical path at this point in construction because without the geo-piles installed in the ground foundation work could not start. It was important to get the site cleared and start installing the geo-piles as early as possible.

During the structural steel erection the key element is simply to keep on schedule. There were no space limitations due to such a large sites so keeping on schedule and to the erection plan was key to completing the steel erection on time.

During the finishing stages the fit-out of the bed tower become the critical path. The fit-out of the bed tower does not complete until nearly the end of the project, any

Steven Farrah Tech 1 Voorhees Replacement Facility Voorhees, NJ

delays in the schedule will push back the completion date. As the construction manager it is important to manage our resources during this fit-out. With the numerous trades coming and going from the space it is extremely important to make sure that trades do not overlap and get in the way of each other. By making sure each trade has enough space to complete their work as well as making sure each trade knows the project schedule the fit-out can go smoothly and to schedule.



Building Systems Summary

Demo

Since any buildings did not previously occupy the location of the Replacement Hospital, the only demolition that was required to allow for construction to start was the clearing of trees and prepping the site for breaking ground.

Structural Steel Frame

The main structural system of the Replacement Hospital is composite steel framing for the floors and non-composite steel framing for the roofs. Typical bay sizes are approximately 30'x32' in the bed tower and 31'-4"x29'-4" in the ancillary portion of the building. Elevated floors use a 3" thick by 18 gauge galvanized composite steel deck while the roofs consist of a 3" thick by 20 gauge galvanized roof deck. Beam to beam and beam to column connections are typical bolt shear connections except in areas where lateral forces are being resisted. At these locations where lateral forces are being resisted welded connections were used.

Lateral loads on the building are resisted by steel braced frames and steel moment frames. It was a particular design challenge to design the lateral systems of the building without compromising the buildings appearance. Some basement walls also act as shear walls to transfer lateral loads to the building foundation.

To erect the steel, 3 300-ton crawler cranes were used.

Cast in Place Concrete

All cast in place concrete used on the job was placed using a pump truck and plywood formwork. Typical elevated floors have 3 ½" of 3500 psi lightweight concrete on top of the metal decking. Elevated slabs are reinforced with fiber reinforcing. Typical slab on grade concrete is 5" and has a strength of 4000 psi reinforced with welded wire fabric.

Precast Concrete

No precast concrete on this project.

Mechanical System

The main mechanical equipment is located in 2 different locations throughout the building. The main chiller equipment is located in the central utility plant with the

Steven Farrah Tech 1 Voorhees Replacement Facility Voorhees, NJ

main electrical and emergency electrical equipment. The remainder of the mechanical equipment is located in the spine portion of the building between floors 5 and 8.

Building heating, HVAC humidification, domestic water heating, and auxiliary steam is being provided primarily from the 5th floor utility plant in the spine. The system consists of saturated steam boilers, condensing hot water boilers, a chiller heat recovery system, and space for future domestic hot water heaters.

Facility cooling will be provided by a centralized chilled water system. The chilled water generation will take place in the Central Utility Plant area. The chilled water will be generated by electric drive, water-cooled, centrifugal water chillers. Cooling heat will be rejected through 4 induced cooling tower cells.

There are a total of 3 sets of AHUs that service all of the hospital and are located on the 7th floor of the spine. AHU-1 consists of 2 50,000 CFM VAV units stacked on each other. This AHU will serve non-patient care areas such as dietary, environmental services, receiving, and lab and maintenance. AHU-2 consists of 2 50,000 CFM VAV units stacked on each other. This AHU will service the emergency department, pediatric emergency, surgery, c-section operating rooms, the pharmacy and the NICU. AHU-3 consists of 6 75,000 CFM VAV units stacked on each other. AHU-3 will service all of the patient care areas in the ancillary and bed tower.

Electrical

The electrical service to the building is being provided at 12,470 volts where it is distributed to 6 main substations of the building located in the main electrical room in the central utility plant. Already put in place is an extra set of concrete encased PVC conduit for a second service to the building when the hospital expands in the future.

At the substations a transformer brings down the power to 480/277 3 phase 4 wire. The substations are broken down into 3 sets of 2 to create redundancy in the system. If one of the substations fails, the paired substation is sized large enough to take on the full load of both substations until the substation is repaired.

From the substations, power is carried to each floor via cables and either kept at the 480/277 voltage or dropped down even further to 120/208 for certain building functions. Most lighting will be 277V because this allows for more lights per circuit and lower voltage drops across long lengths of wire.



For emergency standby power, there are 3 1,500 KW diesel generators that will service all life safety and building functions that cannot afford to lose power. There is space to provide a 4th generator when the hospital expands in the future. The fuel tank for the generators is sized to provide 96 hours of backup.

To provide uninterrupted backup power before the generators kick in if power failure occurs there is a 900 KW rotary UPS installed. The rotary UPS is sized to provide about 36 seconds of run time, long enough to provide power to the building during the 10-second lag time until the generators kick in.

Masonry

A majority of the masonry on the project is veneer masonry. The only load bearing masonry is located at the loading dock and has a concrete masonry unit veneer. Veneer masonry is located mainly on the bed tower and is made up of both calcium silicate building stone and limestone. Typical veneer masonry connection can be seen in figure 1. The masonry is being installed by using both hex scaffolding and swing stages.




Figure 1

Curtain Wall

Along the bed tower portion of the replacement hospital is a curtain wall system. The system is made up of exposed aluminum finishes and concealed steel reinforcement. The glass in the curtain wall system includes vision and spandrel glass, fritted in some locations to provide natural sunshade to the patient rooms.



The curtain wall is stick built and is put in place using hex scaffolding. A typical curtain wall connection detail can be seen in figure 2.




Figure 2

Support of Excavation

There was no major excavation on this project so no major temporary or permanent support systems were necessary. However the geotechnical engineer determined that the site consisted of mostly loose sands, which do not perform well under seismic conditions. In order to stabilize the ground to allow for typical spread footings to be installed a process of installing stone columns was recommended. Almost 4,000 stone columns, each about 45 feet deep were installed under the building footprint to get the soil to an allowable pressure of 6000 psf. Over 100 million pounds of stone was used in this soil stabilization.

Since the water table in the location of the building was determined to be 8 feet below the surface dewatering was necessary to allow for the stone column installation. Since the footprint of the building is so large dewatering was done in multiple phases, this allowed for the stone columns to be installed more quickly and reduce the cost of providing a dewatering system over the entire footprint.

Project Cost Evaluation

Actual Project Costs

Cost Type	Total Cost	Cost / SF
Construction Cost	\$294,561,141.00	\$436.39/SF
Total Project Cost	\$450,000,000.00	\$666.66/SF
Structural Steel	\$25,466,126.00	\$37.73/SF
Rough Carpentry & Drywall	\$21,677,690.00	\$32.11/SF
Construction Cost Total Project Cost Structural Steel Rough Carpentry & Drywall Windows, Storefronts and Curtain Wall Systems Plumbing, HVAC Piping/Sheet Metal/Equipment and Medical Gas Electrical Core/Shell and	\$10,376,859.00	\$15.37/SF
Construction Cost Total Project Cost Structural Steel Rough Carpentry & Drywall Windows, Storefronts and Curtain Wall Systems Plumbing, HVAC Piping/Sheet Metal/Equipment and Medical Gas Electrical Core/Shell and	\$64,952,583.00	\$96.22/SF
Electrical Core/Shell and Fit-Out	\$35,765,769.00	\$52.98/SF

Table 1

Please see the above table 1 for all actual costs regarding the Voorhees Replacement Facility. For a full breakdown of actual costs by bid package please see Appendix B.

Construction cost as shown in table 1 is defined as all of the direct costs to the project. This does not include any general conditions, insurance, contingency or construction management or architect fees. Sitework was left in the construction cost price due to the large majority of the sitework bid package including the geopiles to create a more stable ground.

Total project cost as shown in table 1 is defined as the total of every cost incurred by both construction and indirect fees.

Parametric Estimate Using D4Cost Software

Project	Size (SF)	Total Cost	Dates of Construction
Baylor Regional Medical	242 000	\$62,016,920,00	Mar 2002 Nov 2004
Center	I Medical 342,000 \$63,916,839.00 Mar 2003-Nov 2004 onal 347,000 \$44,308,500.00 Aug 1992-Jul 1995 ildren's 332,979 \$53,764,000.00 Dec 1993-Feb 1996 y Vs. Ys.		
Alamance Regional	347 000	\$44.308.500.00	Aug 1002-Jul 1005
Medical Center	347,000	\$ 44 ,300,300.00	Aug 1992-jul 1993
Connecticut Children's	222 070	\$52.764.000.00	Dog 1002 Feb 1006
Hospital	334,777	\$33,704,000.00	Dec 1993-reb 1990
Average Today Vs.			
Voorhees Replacement	675,000	\$223,356,057.00	Mar 2008-Mar 2011
Facility			

Table 2

Please see table 2 above for a quick comparison of the D4 project used to reach the estimate for the Voorhees Replacement Hospital. For a full statement of probable cost generated by the D4 software please see Appendix C.

In order to create a comparison based estimate using D4 software three similar projects were chosen from the program and averaged together using adjustments for time and differing square footage of the building. The three projects used to generate the estimate can be seen in table 2. Some similarities between the three buildings chosen that resemble the Voorhees Replacement Facility are listed below.

- Steel Frame
- Bed Towers
 /Inpatient Care
 and Offices
- High Cost

- Glass Curtain Wall
- Similar types of medicine practiced (equipment)
- Larger Square Footage
- Similar Finishes
- Contained outdoor courtyards
- # of Stories

Reviewing the D4 estimate for the Voorhees Replacement Facility one can see that the D4 estimate is significantly lower then the actual construction cost of the building. This 70 million dollar difference might be explained by a few different factors. First the projects chosen from D4 did not mention any soil strengthening techniques used. There was a large cost to install the geo-piles before footing construction started that is included in the construction costs.

Next, even though each of the three projects chosen had a glass curtain wall incorporated into the building, the enormous curtain wall of the Replacement

Steven Farrah Tech 1 Voorhees Replacement Facility Voorhees, NJ

Facility belittles them. This immense curtain wall along the bed tower with a plethora of metal panels and louvers on the exterior of the spine could cause a spike in construction cost.

Subsequently the actual mechanical cost of the building compared to the D4 estimate is about 20 million higher when one adds fire protection to the cost given in the actual cost section. This could be explained by the large amount of rooms located in the bed tower. The hospitals chosen for the estimate in D4 did not include an amount of beds close to the 270 in the Replacement Hospital. This statistic coupled with the fact that every overnight patient gets his or her own room could not only increase the amount of sheet metal needed but also the size of the air handling units needed to provide clean air to patients.

Lastly one can see that the actual cost of the electrical work is greater then the D4 cost estimate. The changing medical technology and single patient rooms could explain this difference in price along with the addition of large generators and a UPS system. The hospitals chosen for the D4 estimate may not have been attempting to make their building highly based around technology. The Voorhees Replacement Facility is attempting to become virtually paperless and this requires extensive and expensive telecommunication work.

R.S. Means Cost Data

RS Means Square Foot Costs 2009 was used to create a rough estimate of the Voorhees Replacement Facility based upon its square footage. After completing the appropriate square foot cost adjustments, adding in lump sum additions and applying the location modifier the total cost came out to be \$199,817,102.

It is important to note that the square footage of the Voorhees Replacement Facility is much greater then the largest square foot given in RS Means. Because of this the largest square footage data was used when calculating the estimate. The perimeter adjustment was an addition of \$11.8 per square foot. Since RS Means assumes that each floor has the same perimeter, the perimeter of each floor was averaged together to obtain a perimeter to use for the adjustment. The height adjustment was an addiction of \$3.37 per square foot. Again about half of the hospital has floor heights of 15 feet while the other half has 14 foot floor heights. Using the average floor height of 14.5 feet, the height adjustment was found. Please see Appendix D for a copy of the RS Means pages used in the calculation.

Steven Farrah Tech 1 Voorhees Replacement Facility Voorhees, NJ

One can see that the RS Means estimate is almost 100 million dollars less then the actual construction costs of the building. I believe that there is three main factors that account for this giant gap in cost.

The first factor is the building envelope. RS Means defines a more traditional approach to hospital construction with the only options being face brick and precast panels. This typical construction does not have a high cost and can be installed fairly easily. The building envelope of the Voorhees Replacement Facility is made up of a giant glass curtain wall system at the bed tower, stone veneer, metal panels and solid phenolic panels. All of these systems are considerably more expensive then the typical face brick as defined in the RS Means estimate.

The second factor is the mechanical systems of the building. Like the D4 Cost estimate, it is probable that the RS Means estimate does not take into account each overnight patient having his or her own room. This alone could greatly increase the amount of sheet metal needed as well as increase the mechanical load on the building causing an increase in mechanical equipment size.

The last factor is the electrical system of the building. RS Means does include an emergency generator and UPS system in the estimate but the actual emergency generator in the building is twice the size and there are three of them. Secondly there are extra substations being provided in the building to create redundancy that are probably not accounted for in the RS Means estimate. Lastly the low voltage systems of the building are much more in depth then the RS Means data makes them out to be. Virtua will be running nearly everything on their network and there is a large, expensive telecommunication system to go with it.

D4 vs. RS Means

In this particular case the D4 estimate was more accurate when attempting to do a rough estimate of the new hospital. The D4 estimate was more accurate because with such a specialized hospital both MEP wise and building enclosure wise the D4 estimate allowed for the averaging of hospitals with similar characteristics where RS Means's only commonality between buildings is the buildings function and Superstructure. Because of this D4 was the more accurate estimating method in this case.



Site Plan of Existing Conditions

Please see Appendix E for the site plan of existing conditions.

The site for the Voorhees Replacement Facility is located in Voorhees, New Jersey located between Dutchtown Road and Route 73. There are no buildings immediately surrounding the site that would constrain any construction operations. In Figure 3 one can see the location of the new hospital. The dotted red line indicates the property boundary.



Figure 3 (Courtesy of Google Maps)



LOCAL CONDITIONS

Since this is a private project, the preferred method of construction is really defined by an owner's needs and wants. In the case of Virtua Health (owner) they knew that they didn't want just low bid. They wanted to select each company involved with the management and design of the project that would provide the best value, a combination of both cost and healthcare experience.

Since the site as explained earlier is very large and does not have any restrictions due to proximity to other buildings, site parking was able to be provided for all trades. After the site was prepared the base build of the main hospital parking lot was put down so that subcontractors could set up their trailers and have space to park.

Currently the project is not seeking LEED certification but Turner has made an effort to ensure that all trash leaving the project is sorted and materials that are able to be recycled are done so properly.

Over the course of June 2006, Virtua hired a geo-technical engineer to run tests to determine the soil conditions of the site. A sample copy of one test location can be viewed in Appendix F. From the geo-technical report it was found that in depths up to 35 feet the soil was only made up of sand and silts. Due to this discovery it was the recommendation of the geo-technical engineer to provide ground improvements under the entire building pad to mitigate potential for excessive settlements during a seismic event. The ground solution that was recommended was the installation of stone columns described earlier in tech 1.

From the geo-technical report it was also reported that groundwater showed up an average of about 8 feet below the surface. This discovery required dewatering during the stone column installation as described earlier in tech 1.

Steven Farrah Tech 1 Voorhees Replacement Facility Voorhees, NJ

CLIENT INFORMATION

Virtua Health is a non-profit organization employing about 7,900 clinical and administrative personnel and over 1,800 physicians as medical staff members. Virtua consists of four hospitals: Virtua Memorial, Berlin, Marlton and Voorhees. Virtua delivers nearly 7,600 babies a year, more then any other healthcare organization in its region. Virtua's hospitals also provide the latest technology and treatments for all types of cancer.

Currently Virtua owns a hospital located in the same town, Voorhees, NJ that has reached its capacity and does not have space to accommodate the growing needs of the community. The current hospital was also designed on outdated technology and is not able to implement future technology along with Virtua's new and improved workflow plan.


Virtua's vision for the new Voorhees Replacement Facility is to create a warm and comfortable environment that promotes positive human interaction through personalized service and enhances healing through the use of light, space and the application of the advanced technology being showcased in the new hospital.

Since this is a new hospital there is no phased occupancy requirements that Virtua has. However with the opening of the replacement facility all patients of the existing hospital will be transported to the new hospital. This creates an emphasis on completing construction on time. Virtua wanted a fast-tracked schedule and in order to get the 3-year construction schedule started as soon as possible steel and foundation packages were issued long before the rest of the design was complete.

The key to completing the Voorhees Replacement Facility on time is to manage the subcontractors efficiently. With such a large volume project it is easy to have setbacks due to subcontractors getting in the way of one another due to the excessive number of workers on site at any time. This with a combination of proper engineering and project management will ensure that Turner can deliver the hospital on time to Virtua.



PROJECT DELIVERY SYSTEM



The Voorhees Replacement Facility is being delivered using the traditional design-bid-build approach. Virtua Health hired each company using the "best value" approaching meaning they took into account both price and experience when selecting each company they hold contracts with. As seen above in the organizational chart Virtua holds contracts with the A/E, Program Manager, Construction Manager, and their Safety Rep. Virtua also holds other contracts such as their medical equipment planner and food service consultant however the 4 companies shown in the chart are the main players during construction. The contract that Virtua holds with Turner Construction is a GMP contract which means that Turner has guaranteed that per the drawings given to them they can do the work for no more then their bid price.

Since Turner Construction is acting as a CM@ Risk, they hold all the subcontractor contracts. Turner, like Virtua did not just select their subcontractors by low price but used their prequalification system to select the right subcontractor for each bid package. The contract type between Turner and all of the subcontractors is a GMP contract. Since the project is utilizing BIM to do MEP coordination one of important contract terms to note is that all the subcontractors that are used in the coordination process are required to submit and update a 3D model so that Turner can utilize 3D coordination.

Steven Farrah Tech 1 Voorhees Replacement Facility Voorhees, NJ

Lastly it is important to note that Virtua holds an OCIP on this particular project. An OCIP is an Owner Controlled Insurance Program and provides insurance to all participants on the project have insurance coverage. An advantage to having an OCIP is it allows for both the owner and the construction manager to hire the best subcontractors for the project without having to worry about the availability of insurance coverage for any subcontractor. Having an OCIP also reduces the cost of the project for the owner as well as reduces the number of claims.



STAFFING PLAN

Please see Appendix G for a copy of the staffing plan.


The Staffing plan of Turner Construction for the Voorhees Replacement Facility is set up like any large construction project. One can see from the staffing plan in Appendix F, Senior Project Manager Bill Swanson is the highest up full time employee on site. Under Bill comes the Project Engineers and the Superintendents.

To make the workload on the Superintendents manageable the building was split into 2 different areas, the bed tower building and ancillary building. A Superintendent was placed in charge of each of these areas and given Assistant Superintendents and Field Engineers to work under them. Separately there is a Superintendent in charge of MEP over the entire hospital who also has Assistant Superintendents working under him.

The site office is an existing house that was purchased with the property. This allowed Turner to have all utilities already provided and made their mobilization easier.

Appendix A

Primavera Schedule Summary



Appendix B

Breakdown of Actual Costs by Bid Package

Decision Structural States 25,065,126 Ches States Concary		681,395	
BP02 State Concreted	Bid Package	Total	Subcontractor Name
BPOS Sile Concrete BPOS Sel Improvements File Sile Concrete File Sile Concrete File Sile Sel Improvements File Sile Sel Improvements File Sel Improvements Fil	BP01 Structural Steel	25,466,126	
PROS Sile Flectric	BP02 Sitework	13,054,422	
BP05 Soil Improvements	BP04 Site Concrete	W/ BP09	
Section Sect	BP05 Site Electric	762,648	
BP08 Superintuctural Comorates 5,760,715 B. Plettini & Sons	BP06 Soil Improvements	6,393,024	
BP19 Manarom Patri Manarom	BP07 Concrete Foundations and Slab-on-Grade	5,550,159	
BP11 Metal Fabrications	BP08 Superstructure Concrete	5,760,715	
### 12 Expansion Joint Covers and Slab Edge Firestopping	BP09 Masonry	7,313,191	
BP15 Exterior Backup Wall	BP11 Metal Fabrications	2,983,654	
BP14 Carpentry and Drywall Ancillary Building 10,169,955 Daile Construction Company	BP12 Expansion Joint Covers and Slab Edge Firestopping	973,719	
BP15 Carpentry and Drywall: Bad Tower 11.507.735 Thomas Building Group	BP13 Exterior Backup Wall	6,463,399	
### ### ### ### ### ### ### ### ### ##	BP14 Carpentry and Drywall: Ancillary Building	10,169,955	
BP18 Lab, Mail and Pharmacy Casework 628,142 Dancker, Sellew & Douglas	BP15 Carpentry and Drywall: Bed Tower	11,507,735	
Philadelphia Fireproofing	BP17 Millwork and Finish Carpentry	7,404,340	Legere Group, Ltd.
Page 20 Phenoting Pamels Page 20 Phenoting Phenoting	BP18 Lab, Metal and Pharmacy Casework	628,142	Dancker, Sellew & Douglas
Page 12 Waterproofing Wy BP22 Hamada, Inc. A C Deliovade BP24 Caulking 628,652 Struc-tile Restoration, Inc. Tru-fit Frame & Door Company Mational Class & Metal Company Mational Class & Mational Class & Metal Company Mational Class & Metal Company Mational Class & Metal Company Mational Class & Mational Class & Mational Class & Metal Company Mational Class & Mational Class & Metal Company Mational Class & Meta	BP19 Spray Fireproofing	2,073,575	Philadelphia Fireproofing, Inc.
BP22 Rooting and Waterproofing 5,089,076 Hamada, Inc. BP23 Louvers and Insulated Metal Panels 5,735,013 AC Delitovade BP24 Cauking 628,652 Struc-tite Restoration, Inc. BP25 Doors, Frames and Hardware 2,577,646 Thiff Frame & Door Company BP26 Interior Glass and Glazing 2,884,416 National Glass & Metal Compnay BP28 Palsitic Screen Wall 265,000 Sign Spec, Inc. BP29 Ceramic Tile 3210,754 Ommenical Flooring BP30 Carpet and Resilient Flooring 3,210,754 Commenical Flooring BP31 Specialty Flooring 11,228 Speciality Flooring BP32 Apocialty Flooring 11,228 Speciality Flooring BP33 Acoustic Wall Panels W/ BP4 Hispanic Ventures BP33 Wall Protection 1,068,210 Dale Construction Company BP38 Wall Protection 1,068,210 Dale Construction Company BP38 Raised Access Floors 49,814 ARI Products BP38 Raised Access Floors 48,814 Modernfold/Styles, Inc. BP40 Food Service Equipment 2,000,473 Singer Equipment Company <td< td=""><td>BP20 Phenolic Panels</td><td>2,142,256</td><td>Philadelphia D&M, Inc.</td></td<>	BP20 Phenolic Panels	2,142,256	Philadelphia D&M, Inc.
### BP23 Lowers and Insulated Metal Panels	BP21 Waterproofing	W/ BP22	Hamada, Inc.
BP24 Caulking 628,652 Struc-tite Restoration, Inc. BP25 Doors, Frames and Hardware 2,577,646 Tru-fit Frame & Door Company BP26 Doors, Frames and Hardware 2,577,646 Tru-fit Frame & Door Company BP26 Plastic Screen Wall 2,894,416 National Glass & Metal Company BP27 Windows, Storefronts and Curtainwall Systems 10,376,859 National Glass & Metal Company BP28 Ceramic Tile 1,862,172 Roman Mosaic & Tile BP30 Carpet and Resilient Flooring 3,210,754 Commercial Flooring BP31 Spocialty Flooring 11,228 Speciality Flooring BP32 Painting and Special Coatings 1,417,667 Blancian Glass & Metal Company BP33 Acoustic Wall Panels W/BP14 Commercial Flooring BP34 Specialities 1,779,890 Material Distributors BP38 Wall Protection 1,068,210 Dale Construction Company BP38 Raised Access Floors 49,814 ARI Products BP39 Operable Folding Partitions 38,814 Modernfold/Styles. Inc. BP40 Food Service Equipment 2,000,473 Modernfold/Styles. Inc. BP42 RF Shielding 129,118	BP22 Roofing and Waterproofing	5,089,076	Hamada, Inc.
### P25 Doors, Frames and Hardware 2,577,846 Tru-fit Frame & Door Company ### B25 Doors, Frames and Glazing 2,884,416 ### B26 Interior Glass and Glazing 2,884,416 ### B26 Plastic Screen Wall 265,000 ### B27 Windows, Storefronts and Curtainwall Systems 1,862,172 ### B29 Ceramic Tile 3,210,754 ### B293 Capret and Resilient Flooring 3,210,754 ### B293 Capret and Resilient Flooring 11,225 ### B293 Epart and Resilient Flooring 1,417,567 ### B294 Speciality Flooring 1,417,567 ### B294 Speciality Flooring 1,417,567 ### B294 Speciality Protection 1,068,210 ### B293 Epart Apart Apar	BP23 Louvers and Insulated Metal Panels	5,735,013	AC Dellovade
BP26 Interior Glass and Glazing 2,884,416 National Glass & Metal Compnay BP26A Plastic Screen Wall 265,000 Sign Spec, Inc. BP27 Windows, Storefronts and Curtainwall Systems 10,376,859 National Glass & Metal Company BP28 Carpet and Resilient Flooring 1,862,172 Roman Mosaic & Tile BP30 Carpet and Resilient Flooring 3,210,754 Commerical Flooring BP31 Specialty Flooring 11,228 Specialty Flooring BP32 Painting and Special Coatings 1,417,567 Hispanic Ventures BP33 Acoustic Wall Panels W/ BP14 Date Construction Company BP34 Specialties 1,779,890 Material Distributors BP36 Lockers 386,393 Material Distributors BP37 Window Treatment 245,384 ARI Products BP38 Raised Access Floors 49,814 Modermold/Styles, Inc. BP39 Operable Folding Partitions 39,814 Modermold/Styles, Inc. BP40 Food Service Equipment 2,000,473 Singer Equipment Company BP42 RF Shielding 129,118 Swisslog Translogic BP43 Pneumatic Tube Systems 730,809 Moderm Handling Equipm	BP24 Caulking	628,652	Struc-tite Restoration, Inc.
BP26A Plastic Screen Wall 265,000 BP27 Windows, Storefronts and Curtainwall Systems 10,376,859 BP29 Ceramic Tile 1,862,172 BP30 Carpet and Resilient Flooring 3,210,754 BP31 Specialty Flooring 11,228 BP32 Painting and Special Coatings 1,417,567 BP33 Acoustic Wall Panels W/ BP14 BP34 Specialties 1,779,890 BP35 Wall Protection 1,068,210 BP36 Lockers 386,333 BP37 Window Treatment 245,384 BP38 Raised Access Floors 49,814 BP39 Operable Folding Partitions 39,814 BP40 Food Service Equipment 2,000,473 BP41 Loading Dock Equipment and Overhead Doors 155,560 BP42 F Shietding 129,118 BP43 Pneumatic Tube Systems 730,805 BP44 Chutes 139,385 BP45 Special Construction and Allowances 5,479,162 BP46 Elevators 5,479,162 BP49 Underground Plumbing W/ BP48 BP49 Underground Plumbing W/ BP48 BP50 HvAC Piping W// BP48	BP25 Doors, Frames and Hardware	2,577,646	Tru-fit Frame & Door Company
BP27 Windows, Storefronts and Curtainwall Systems 10,376,859 National Glass & Metal Company BP29 Ceramic Tile 1,862,172 Roman Mosaic & Tile BP30 Carpet and Resilient Flooring 3,210,754 Commerical Flooring BP31 Specialty Flooring 11,228 Speciality Flooring Hispanic Ventures BP32 Palliting and Special Coatings 1,417,567 Dale Construction Company BP33 Acoustic Wall Panels W/ BP14 Material Distributors BP34 Specialties 1,779,890 Material Distributors BP35 Wall Protection 1,688,210 Dale Construction Company BP36 Lockers 386,393 Material Distributors BP37 Window Treatment 245,384 Rall Products BP39 Raised Access Floors 49,814 ARI Products BP39 Operable Folding Partitions 39,814 Modern Handling Equipment Company BP40 Food Service Equipment and Overhead Doors 155,560 Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) BP42 RF Sheiding 129,118 TBD Swisslog Translogic BP44 Chutes 139,385 March, Inc. BP45 Special Co	BP26 Interior Glass and Glazing	2,884,416	National Glass & Metal Compnay
BP29 Carpet and Resilient Flooring 3,210,754 Commerical Flooring 3,210,754 Commerical Flooring 3,210,754 Commerical Flooring BP31 Specialty Flooring 11,228 Speciality Flooring Hispanic Ventures Speciality Flooring Hispanic Ventures Dale Construction Company Material Distributors BP35 Wall Protection 386,393 Material Distributors M	BP26A Plastic Screen Wall	265,000	Sign Spec, Inc.
BP30 Carpet and Resilient Flooring BP31 Specialty Flooring BP32 Painting and Special Coatings BP33 Acoustic Wall Panels BP34 Specialties BP35 Wall Protection BP36 Lockers BP37 Window Treatment BP38 Raised Access Floors BP38 Raised Access Floors BP39 Operable Folding Partitions BP41 Loading Dock Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP46 Elevators BP46 Elevators BP48 Plimbing, HVAC Piping and Medical Gas BP50 HVAC Sheetmetal: Bed Tower BP50 HVAC Sheetmetal: Bed Tower BP50 HVAC Sheetmetal: Bed Tower BP50 Medical Gas BP50 Commerical Flooring Speciality Flooring Hispanic Ventures Dale Construction Company Material Distributors Material Distributors Material Distributors Kay & Sons ARI Products Modern Houter Material Distributors Modern Houter Modern Houter Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) BP45 Precisions Door Co (OH doors) BP45 Precisions Door Co (OH doors) BP46 Elevator Majek Fire Protection BP46 Elevator Majek Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas W/ BP48 BP48 Plasca Mechanical BP50 Medical Gas W/ BP48 BP50 Medical Gas BP51 HVAC Sheetmetal: Ancillary Building BP52 HVAC Sheetmetal: Bed Tower BP50 Medical Government BP50 Medical Gas GA, JVS BP53 HVAC Sheetmetal: Bed Tower BP50 Medical Gas GA, JVS	BP27 Windows, Storefronts and Curtainwall Systems	10,376,859	National Glass & Metal Company
BP31 Specially Flooring BP32 Painting and Special Coatings BP33 Acoustic Wall Panels BP33 Acoustic Wall Panels BP34 Specialties BP35 Wall Protection BP36 Lockers BP37 Window Treatment BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP45 Special Construction and Allowances BP45 Special Construction and Allowances BP46 Elevators BP46 Elevators BP49 Underground Plumbing BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP51 HVAC Sheetmetal: Bed Tower BP53 HVAC Sheetmetal: Bed Tower BP53 HVAC Sheetmetal: Bed Tower BP53 HVAC Sheetmetal: Bed Tower BP45 Special Construction and Allowance, Interest and Elevator BP50 Medical Gas BP50 Medical: Bed Tower BP61 Loading Bed Construction Company Material Distributors Material Distributors ARI Products ARI Products ARI Products Moderni Handling Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) BP64 Products BP65 Medical Gas BP66 Elevator BP67 Froduction Company BP67 Froduction BP67 Froducts BP68 Products	BP29 Ceramic Tile	1,862,172	Roman Mosaic & Tile
BP32 Painting and Special Coatings BP33 Acoustic Wall Panels BP34 Specialties BP35 Will Protection BP36 Lockers BP37 Window Treatment BP37 Window Treatment BP39 Operable Folding Partitions BP30 Painting and Overhead Doors BP41 Loading Dock Equipment and Overhead Doors BP42 R F Shielding BP43 Protection and Allowances BP44 Chutes BP45 Pecial Construction and Allowances BP46 Elevators BP46 Elevators BP48 Plumbing, HVAC Piping and Medical Gas BP50 HVAC Sheetmetal: Ancillary Building BP50 HVAC Sheetmetal: Ancillary Building BP50 HVAC Sheetmetal: Ancillary Building BP50 Medical Gas BP50 Medical Gas BP50 Medical Gas BP50 Medical Company BP50 Medical Gas H13.759 BP50 Medical Construction and Allowances BP50 HVAC Sheetmetal: Ancillary Building BP50 HVAC Sheetmetal: Ancillary Building BP50 Medical Gas Equipment BP50 Medical Gas H13.759 BP50 Medical Construction Service Equipment BP50 Medical Gas BP50 HVAC Sheetmetal: Ancillary Building BP50 HVAC Sheetmetal: Bed Tower BP50 Medical Company, Material Distributors Material Distribu	BP30 Carpet and Resilient Flooring	3,210,754	Commerical Flooring
BP33 Acoustic Wall Panels BP34 Specialties BP35 Wall Protection BP36 Lockers BP37 Window Treatment BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP55 HVAC Sheetmetal: Ancillary Building BP55 HVAC Sheetmetal: Ancillary Building BP55 Window Treatment 1,779,890 1,779,890 Material Distributors	BP31 Specialty Flooring	11,228	Speciality Flooring
BP34 Specialties BP35 Wall Protection BP36 Lockers BP37 Window Treatment BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower Material Distributors Dale Construction Company Material Distributors ARI Products Material Distributors Dale Construction Company Material Distributors ARI Products Material Distributors ARI Products Material Distributors ARI Products Material Distributors Material Distributors ARI Products Modernfold/Styles, Inc. Singer Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD TBD TBD Swisslog Translogic March, Inc. Guality Elevator Majek Fire Protection Falasca Mechanical Falasca Company, Inc.	BP32 Painting and Special Coatings	1,417,567	Hispanic Ventures
BP35 Wall Protection BP36 Lockers BP37 Window Treatment BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP50 Medical Gas BP50 Medical Gas BP51 HVAC Piping BP53 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower BP53 RVAC Sheetmetal: Bed Tower BP46 Elevators 1,068,210 Advantage/ADS, JV Bed Construction Company Material Distributors Kay & Sons Adaerial Distributors Adaeria Distributors Adaerial Distributors Adaerial Distributors Adaeria Distribu	BP33 Acoustic Wall Panels	W/ BP14	Dale Construction Company
BP36 Lockers BP37 Window Treatment BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Indiana Medical Gas BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower 386,393 Material Distributors Kay & Sons ARI Products Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD Singer Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD TBD Swisslog Translogic March, Inc. Quality Elevator Majek Fire Protection Falasca Mechanical Falasca Company, Inc.	BP34 Specialties	1,779,890	Material Distributors
BP37 Window Treatment BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 HvAC Piping BP50 HvAC Piping BP50 HvAC Sheetmetal: Ancillary Building BP50 HvAC Sheetmetal: Bed Tower ARI Products Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Hunding Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) Brab Brain Hunding Hunding Hand	BP35 Wall Protection	1,068,210	Dale Construction Company
BP38 Raised Access Floors BP39 Operable Folding Partitions BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower Assignment Sayses BP49 Underground Plumbing BP53 HVAC Sheetmetal: Bed Tower Assignment Company Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modernfold/Styles, Inc. Modern Handling Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Doc (OH doors) Breading Tequipment (Loading Dock) & Precisions Modern Handling Equipment (Loading Dock	BP36 Lockers	386,393	Material Distributors
BP39 Operable Folding Partitions BP40 Food Service Equipment BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Sheetmetal: Ancillary Building BP52 HVAC Sheetmetal: Bed Tower 39,814 Modernfold/Styles, Inc. Singer Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD Swisslog Translogic March, Inc. Quality Elevator 43,094, 153 BP48 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Sheetmetal: Ancillary Building BP52 HVAC Sheetmetal: Bed Tower Associated Another Company Modern Handling Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD Swisslog Translogic March, Inc. Quality Elevator 4,479,162 Quality Elevator 5,479,162 Quality Elevator 5,479,162 Aguality Elevator Falasca Mechanical	BP37 Window Treatment	245,384	Kay & Sons
BP40 Food Service Equipment BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower Singer Equipment Company Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD Swisslog Translogic March, Inc. Quality Elevator Majek Fire Protection Falasca Mechanical Falasca Company, Inc.	BP38 Raised Access Floors	49,814	ARI Products
BP41 Loading Dock Equipment and Overhead Doors BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower BP41 Loading Dock & Precisions Door Co (OH doors) TBD Swisslog Translogic March, Inc. Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors) TBD Swisslog Translogic March, Inc. Quality Elevator Majek Fire Protection Falasca Mechanical Falasca Mechanical Falasca Mechanical Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP39 Operable Folding Partitions	39,814	Modernfold/Styles, Inc.
BP42 RF Shielding BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower BP48 Plumbing, IVAC Sheetmetal: Ancillary Building BP50 Medical Gas BP50 Medical Gas BP50 Medical Gas BP51 HVAC Sheetmetal: Bed Tower BP50 Medical Gas BP51 HVAC Sheetmetal: Bed Tower BP52 BP53 HVAC Sheetmetal: Bed Tower BP53 BP53 HVAC Sheetmetal: Ancillary Building BP54 BP55 BP56 BP56 BP56 BP56 BP56 BP56 BP56	BP40 Food Service Equipment	2,000,473	Singer Equipment Company
BP43 Pneumatic Tube Systems BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower Swisslog Translogic March, Inc.	BP41 Loading Dock Equipment and Overhead Doors	155,560	Modern Handling Equipment (Loading Dock) & Precisions Door Co (OH doors)
BP44 Chutes BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower March, Inc.	BP42 RF Shielding	129,118	TBD
BP45 Special Construction and Allowances BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower S,479,162 Quality Elevator Majek Fire Protection Falasca Mechanical Falasca Mechanical Falasca Mechanical Falasca Mechanical BP48 Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP43 Pneumatic Tube Systems	730,809	Swisslog Translogic
BP46 Elevators BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower 5,479,162 Quality Elevator Majek Fire Protection Falasca Mechanical Falasca Mechanical W/ BP48 Falasca Mechanical W/ BP48 Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP44 Chutes	139,385	March, Inc.
BP47 Fire Protection BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower Majek Fire Protection Falasca Mechanical Falasca Mechanical W/ BP48 Falasca Mechanical W/ BP48 Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP45 Special Construction and Allowances		
BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower BP48 Plumbing, HVAC Piping and Medical Gas W/ BP48 Falasca Mechanical Falasca Mechanical Falasca Mechanical Falasca Mechanical Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP46 Elevators	5,479,162	Quality Elevator
BP48 Plumbing, HVAC Piping and Medical Gas BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower BP48 Falasca Mechanical Falasca Mechanical Falasca Mechanical Falasca Mechanical Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP47 Fire Protection		Majek Fire Protection
BP49 Underground Plumbing BP50 Medical Gas BP51 HVAC Piping BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower W/ BP48 Falasca Mechanical Falasca Mechanical Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.	BP48 Plumbing, HVAC Piping and Medical Gas		Falasca Mechanical
BP50 Medical Gas W/BP48 Falasca Mechanical W/BP48 Falasca Mechanical Falasca Mechanical Falasca Mechanical Advantage/ADS, JV BP53 HVAC Sheetmetal: Bed Tower 6,413,759 Falasca Mechanical Advantage/ADS, JV E.J. Deseta Company, Inc.			Falasca Mechanical
BP52 HVAC Sheetmetal: Ancillary Building BP53 HVAC Sheetmetal: Bed Tower 9,607,657 Advantage/ADS, JV E.J. Deseta Company, Inc.		W/ BP48	Falasca Mechanical
BP52 HVAC Sheetmetal: Ancillary Building 9,607,657 Advantage/ADS, JV E.J. Deseta Company, Inc.	BP51 HVAC Piping	W/ BP48	Falasca Mechanical
BP53 HVAC Sheetmetal: Bed Tower 6,413,759 E.J. Deseta Company, Inc.			Advantage/ADS, JV
			E.J. Deseta Company, Inc.
			Turner

	681,395	
Bid Package	Total	Subcontractor Name
BP54 Testing and Balancing	551,268	Fisher Balancing
BP55.1 Equipment Vendor: Cooling Towers	436,747	Turner Logistics
BP55.2 Equipment Vendor: Chillers	761,500	Turner Logistics
BP55.3 Equipment Vendor: Air Handlers	2,662,145	Turner Logistics
BP55.4 Equipment Vendor: Boilers	1,653,234	Turner Logistics
BP55.5 Equipment Vendor: VFD's	323,388	Turner Logistics
BP55.6 Equipment Vendor: Plumbing Fixtures	W/ BP48	Turner Logistics
BP56 ATC System	2,822,186	Johnson Controls
BP57 Electrical Core and Shell	11,271,176	Scalfo Electric, Inc.
BP58 Electrical Fitout: Bed Tower	11,906,034	R. Palmieri & Sons
BP59 Electrical Fitout: Ancillary Building	12,588,559	Petrocelli Electric Co., Inc.
BP60 Security, CCTV, Nurse Call, Paging	5,816,125	Johnson Controls
BP61 Tele/Data	4,005,540	Johnson Controls
BP62 Fire Alarm	3,183,960	Johnson Controls
BP63 Generator and ATS Supplier	2,766,238	Turner Logistics
BP64 Electrical Gear Supplier	1,918,066	Turner Logistics
BP65 UPS Equipment Supplier	W/ BP63	Turner Logistics
BP66 Lighting Fixture Vendor	3,663,350	Turner Logistics
BP67 Landscaping and Irrigation	2,918,683	Bustleton
BP68 Fences and Pergola	342,899	Delaware Valley Designers
BP69 Traffic Signals	NIC	
BP70 Roadway Improvements	NIC	
BP73 Garden Roof	W/ BP22	
BP98 General Requirements	7,617,616	
BP99 Miscellaneous Insurance	87,603	
TOTAL DIRECT COSTS	294,561,141	
GC'S/INSURANCE/CONTINGENCY/FEE	28,512,794	
TOTAL CONSTRUCTION COST	323,073,935	



Appendix C


D4 Statement of Probable Cost

Statement of Probable Cost

	Voorhees Replace	ment Hospital - Se	p 2009 - NJ - Camden		
, n	Prepared By:		Prepared For:		
	Building Sq. Size: Bid Date: No. of floors: No. of buildings: Project Height: 1st Floor Height: 1st Floor Size:		Site Sq. Size: 14	ax: 94108 edical	
Division		Percent	Sq.	Cost	Amount
00	Bidding Requirements Bidding Requirements	0.96 0.96		3.18 3.18	2,148,032 2,148,032
	bluding requirements	0.50		0.10	2,140,002
01	General Requirements General Requirements	6.87 6.87		2.73 2.73	15,340,790 15,340,790
02	Site Work	6.61	2	1.88	14,772,339
02	Site Work Site Work	6.61		1.88	14,772,339
03	Concrete	10.26	3	3.95	22,915,926
	Concrete	10.26	3	3.95	22,915,926
04	Masonry	2.88		9.53	6,434,851
	Masonry	2.88		9.53	6,434,851
05	Metals	6.76	2	2.37	15,097,100
	Metals	6.76	2	2.37	15,097,100
06	Wood & Plastics	2.38		7.88	5,321,922
	Wood & Plastics	2.38		7.88	5,321,922
07	Thermal & Moisture Protection	3.53	1	1.69	7,893,641
	Thermal & Moisture Protection	3.53	1	1.69	7,893,641
08	Doors & Windows	5.78	1	9.12	12,906,624
	Doors & Windows	5.78	1	9.12	12,906,624
09	Finishes	10.83	3	5.84	24,190,808
	Finishes	10.83	3	5.84	24,190,808
10	Specialties	1.09		3.62	2,444,160
	Specialties	1.09		3.62	2,444,160
11	Equipment	1.20		3.98	2,687,665
	Equipment	1.20		3.98	2,687,665
12	Furnishings	1.20		3.96	2,674,340
	Furnishings	1.20		3.96	2,674,340
13	Special Construction	0.55		1.80	1,217,958
	Special Construction	0.55		1.80	1,217,958
14	Conveying Systems	1.80		5.95	4,018,570
	Conveying Systems	1.80		5.95	4,018,570
15	Mechanical	24.33	8	0.52	54,351,458
	Mechanical	24.33	. 8	0.52	54,351,458
16	Electrical	12.96	4	2.87	28,939,874
	Electrical	12.96		2.87	28,939,874
	· · · · · · · · · · · · · · · · · · ·				
Total Bui	Iding Costs	100.00	33	0.90	223,356,057

Appendix D

RS Means Data Sheets



Costs per square foot of floor area

F	S.F. Area	100000	125000	150000	175000	200000	225000	250000	275000	300000
Exterior Wall	L.F. Perimeter	594	705	816	783	866	950	1033	1116	1200
Face Brick with	Steel Frame	280.75	277.00	274.45	268.85	267.35	266.20	265.20	264.40	263.85
Face Brick with Steel Frame 275.25 271.65 269.25 264.45 263.05 262.00 261.10 260.30	264.70	264.10								
Face Brick with	Steel Frame	275 25	271.65	269.25	264.45	263.05	262.00	261.10	260.30	259.75
hace Brick with Concrete Block Back-up	R/Conc. Frame	276.00	272.40	269.95	265.15	263.75	262.70	261.80	261.05	260,50
Precast Concrete Panels	Steel Frame	276.05	272.40	269.95	265.00	263.65	262.55	261.60	260,85	260,30
With Exposed Aggregate	R/Conc, Frame	276.80	273.15	270.70	265.75	264,35	263.25	262.30	261.60	261.00
Perimeter Adj., Add or Deduct	Per 100 L.F.	4.65	3.70	3.10	2.60	2.30	2.00	1,85	1.75	1,50
Story Hgt. Adj., Add or Deduct	Per 1 Ft.	2.10	1.90	1,90	1,55	1.45	1.40	1,45	1.45	1.35

The above costs were calculated using the basic specifications shown on the facing page. These costs should be adjusted where necessary for design alternatives and owner's requirements. Reported completed project costs, for this type of structure, range from \$164.90 to \$402.10 per S.F.

Common additives

Description	Unit	\$ Cost	Description	Unit	S Cost
Cabinets, Base, door units, metal	L.F.	256	Nurses Call Station		
Drawer units	L.E.	505	Single bedside call station	Each	310
Tall storage cabinets, 7' high, open	L.F.	480	Ceiling speaker station	Each	143
With doors	LE	565	Emergency call station	Each	192
Wall, metal 12-1/2" deep, open	LE	192	Pillow speaker	Each	296
With doors	L.F.	345	Double bedside call station	Each	385
Closed Circuit TV (Patient monitoring)			Duty station	Eoch	325
One station camera & monitor	Each	1850	Standard call button	Eoch	169
For additional camera add	Each	1000	Master control station for 20 stations	Each	6025
For automatic iris for low light add	Each	2600	Sound System		
Hubbard Tank, with accessories			Amplifier, 250 warts	Each	2350
Stainless steel, 125 GPM 45 psi	Each	27,600	Speaker, ceiling or wall	Each	191
For electric hoist, add	Each	3000	Trumpet	Each	365
Mortuary Refrigerator, End operated			Station, Dietary with ice	Each	16,800
2 capacity	Each	13,600	Sterilizers		
6 capacity	Each	24,500	Single door, steam	Eoch	166,000
322 0			Double door, steam	Each	213,500
			Portable, counter top, steam	Each	3975 - 6225
			Gas	Each	41,200
			Automatic washer/sterilizer	Each	57,000

Model costs calculated for a 6 story building with 12' story height and 200,000 square feet

0

)

Ü

ctors

Hospital, 4-8 Story

OT TI	oor area		Unit	Unit Cost	Cost Per S.F.	Sub-
Α. :	SUBSTRUCTURE					TI-E
1010	Standard Foundations	Poured concrete; strip and spread footings	S.F. Ground	14,46	2.41	
1020	Special Foundations	N/A	-		-	
1030	Slab on Grade	4" reinforced concrete with vapor barrier and granular base	S.F. Slab	7,29	1.22	2.0
2010	Basement Excavation Basement Walls	Site preparation for slab and trench for foundation wall and footing 4' foundation wall	S.F. Ground LF. Wall	.17 78	.03	
-		4 foundation was	Lr. yyali	7.0	.34	SQUARTE
В. 3	SHELL			000		
1010	B10 Superstructure Floor Construction	Concrete slob with metal deck and beams, steel columns	S.F. Floor	23.48	19.57	
1020	Roof Construction	Metal deck, open web steel joists, beams, interior columns	S.F. Roof	10.44	1.74	10.
Jall	820 Exterior Enclosure				3030	10.00
2010	Exterior Walls	Face brick and structural facing tile 70% of wall	S.F. Wall	43.99	9.60	532
2020	Exterior Windows	Aluminum sliding 30% of wall	Each .	552	3.45	7.
2030	Exterior Doors	Double aluminum and glass and sliding doors	Each	5115	.72	
0010	B30 Roofing	I note that the second of the	S.F. Roof	714	1.10	
3010 3020	Roof Coverings Roof Openings	Built-up tar and gravel with flashing; perlite/EPS composite insulation Roof hatches	S.F. Roof	7.14	1,19	0.
	NTERIORS				OSH WIR	95015
1010	Partitions	Gypsum board on metal studs with sound deadening board 9 S.F. Floor/L.F. Partition	S.F. Partition	7.71	8.57	251012
020	Interior Doors	Single leaf hollow metal 90 S.F. Floor/Door	Each Each	904	10.03	
1030	Fillings	Hospital curtains	S.F. Floor	.95	95	
2010	Stair Construction	Concrete filled metal pan	Flight	12,650	1.64	23.
3010	Wall Finishes	40% vinyl wall covering, 35% ceramic tile, 25% epoxy coating	S.F. Surface	3.36	7.47	
020	Floor Finishes	60% vinyl tile, 20% ceramic, 20% terrazzo	S.F. Floor	10.20	10.20	
030	Ceiling Finishes	Plaster on suspended metal lath	S.F. Ceiling	7.44	7.44	Shirts
D. S	ERVICES					
010	D10 Conveying Elevators & Lifts	Six geared hospital elevators	Each	215,333	6.46	100
020	Escalators & Moving Walks	N/A	-	- 10,000	-	3.
	D20 Plumbing					
2010	Plumbing Fixtures	Kitchen, tailet and service fixtures, supply and drainage 1. Fixture/416S.F. Floor	Each	4489	10.79	555
020	Domestic Water Distribution Rain Water Drainage	Electric water heater Roof drains	S.F. Floor	6.81	6.81	9.3
040	THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.	Roof drains	S,F, Floor	3.06	.51	HIGH
010	D30 HVAC Energy Supply	Oil fired hat water, wall fin radiation	S.F. Floor	4.01	4.01	VALED
020	Heat Generating Systems	Hot water boilers, steam boiler for services	Each	30,475	.38	
030	Cooling Generating Systems	Chilled water units	S.F. Floor	2.70	2.70	17.8
050	Terminal & Package Units	N/A	-		2	
090	Other HVAC Sys. & Equipment	Conditioned air with reheat, operating room air curtains	S.F. Floor	27.78	27.78	
Contract of the	D40 Fire Protection			2.00	0.00	
010	Sprinklers Standpipes	Wer pipe sprinkler system Standpipe	S.F. Floor S.F. Floor	2.29	2.29	1.4
7710112	D50 Electrical		VI. 11001		BIALLIS	WE
010	Electrical Service/Distribution	4000 ampere service, panel board and feeders	S.F. Floor	4.17	4.17	
020	Lighting & Branch Wiring	High efficiency hospital grade light fixtures, receptacles, switches, A.C. and misc. power	S.F. Floor	18.32	18.32	1,44
030	Communications & Security	Addressable alarm systems, internet wiring, communications system, emergency lighting	S.F. Floor	2.20	2.20	14.7
290	Other Electrical Systems	Emergency generator, 800 kW with fuel tank, uninterruptible power supply	S.F. Floor	4.17	4.17	
. EG	QUIPMENT & FURNISHIN	IGS				TI-SS
010	Commercial Equipment	N/A	-	-	-	
020	Institutional Equipment	Medical gases, curtain partitions	S.F. Floor	14,75	14.75	9.4
030	Vehicular Equipment Other Equipment	N/A Patient wali systems	S.F. Floor	3.78	3.78	
-	ECIAL CONSTRUCTION	Company and ayarenta	un riodi	EN DESCRI	3.70	0.00
020	CANADA TANDA CANADA CAN	N/A	THE MAN THE	et ey turbility	- United	
040	Integrated Construction Special Facilities	N/A N/A	-	_	_	0.0
;. BI	UILDING SITEWORK	N/A				100
SINGER			Sub	-Total	196.21	100
-	CONTRACTOR PERSON	5 table of 1 table of the sales	300			100
	CONTRACTOR FEES (General ARCHITECT FEES	Requirements: 10%, Overhead: 5%, Profit: 10%)		25% 9%	49.07 22.07	

Location Factors

	MINNESOTA (CONT d)	Commercial	
MINNESOTA (1 559 560 561 562 563 564 565 566 567	Rochester Mankato Windom Willmar St. Cloud Brainerd Detroit Lakes Bernioli	1.01 .82 .83 1.06 .96 .95	1.01 .99 .88 .90 1.05 .97 .96 .97
MISSISSIPPI 386 387 388 389 390,392 393 394 395 396 397	Greenville Tupelo Greenwood Jackson Meridian Laurel Bilton Mocomb	.84 .79 .80 .85 .83 .80 .82	.81 .88 .83 .82 .87 .86 .84 .83 .81
MISSOURI 630-631 633 634 635 636 637 638 639 640-641 644-645 646 647 648 650-651 653 654-655 656-658	Bowling Green Hannibal Kirksville Flat River Cape Girardeau Sikeston Poplar Bluff Kansas City St. Joseph Chilicothe Harrisonville Joplin Jefferson City Columbia Sedala Rolla	.95 .86 .80 .94 .88 .82 .83 1.03 .93 .87 .96 .83 .87 .87	.94 .89 .88 .95 .94 .88 .88 1.02 .95 .84 .96 .85 .92 .93
MONTANA 590-591 592 593 594 596 596 597 598 599	Wolf Point Miles City Great Falls Havre Helena Butte Missoula	.84 .86 .89 .82 .88 .87	.90 .89 .88 .91 .89 .90 .90
NEBRASKA 180-681 183-685 186 187 188 188 189 190 191 192 193	Lincoln	.87	.91 .89
EVADA 89-891 93 94-895 97	Las Vegas Ely Reno Carson City Elko	1.03 .85 .93 .94 .91	1.06 .88 .97 .97
EW HAMPSHIRE 30 31 32-033 44 5 6 7 8	Nashua Manchester Concord Keene Littleton Charleston Claremont Portsmouth	.94 .94 .92 .75 .81 .74 .75 .93	.94 .94 .92 .78 .81 .76 .76

STATE/ZII	P CITY	Resident	
NEW JERSEY 070-071	Serset Newark Elizabeth 1.12 1.10 1.03 1.05 1.04 1.10 1.08 1.06 1.08 1.06 1.08 1.00 1.08 1.01 1.08 1.00 1.08 1.00		
072 073 074-075 076 077 078 079 080,083 081 082,084 085-086 087 088-089	Elizabeth Jersey City Paterson Hackensack Long Branch Dover Summit Vineland Camden Atlantic City Trenton Point Pleasant	1.14 1.10 1.11 1.10 1.11 1.11 1.11 1.08 1.09 1.11 1.10 1.09	1.10 1.08 1.09 1.08 1.07 1.08 1.07 1.08 1.05 1.05 1.05
NEW MEXICO 870-872 873 874 875 877 878 879 880 881 882 883 884	Gallup Farmington Santa-Fe Las Vegas Socorro Truth/Consequence Las Cruces Clovis Roswell Carrizozo	,85 ,86 ,86 ,85 ,85 ,85 ,84 ,83 ,85 ,85	.90 .90 .90 .91 .89 .89 .87 .85 .88
NEW YORK 100-102 103 104 105 106 107 108 109 110 111 112 113 114 115,117,118 116 119 120-122 123 124 125-126 127 128 129 130-132 133-135 136 137-139 140-142 143 144-146 147 148-149	Staten Island Bronx Mount Vernon White Plains Yonkers New Rochelle Suffern Queens Long Island City Brooklyn Flushing Jamaica Hicksville Far Rockaway Riverhead Albany Schenectady Kingston Poughikeepsie Monticello Gens Falls Plattsburgh Syracuse Utica Watertown Binghamton Buffalo Niagara Falls Rochester Jamestown	1.31 1.33 1.14 1.17 1.18 1.18 1.18 1.13 1.31 1.34 1.35 1.33 1.33 1.33 1.20 1.32 1.21 94 .95 1.02 1.19 1.04 .88 .92 .96 .94 .93 .93 .93 1.04 1.00 .96 .87	1.31 1.27 1.26 1.14 1.17 1.14 1.09 1.27 1.28 1.28 1.28 1.28 1.28 1.21 96 97 1.06 1.12 1.06 1.12 1.06 1.12 1.06 1.12 1.06 1.12 1.06 1.12 1.09 9.92 9.92 9.94 9.93 1.02 9.97 9.90
NORTH CAROLINA 270,272-274 271 275-276 277 278 279 280 281-282 283 284 285 286 287-288 289	Greensboro Winston-Salem Raleigh Durharm Rocky Mount Elizabeth City Gastoma Charlotte Fayetteville Wilmington Kinston Hickory Asheville	.83 .84 .83 .73 .75 .84 .85 .82 .81 .74 .78	.79 .79 .80 .80 .74 .75 .78 .80 .81 .77 .73
NORTH DAKOTA 580-581 582 583 584 585	Grand Forks Devils Lake	-75 -78	.82 82

Appendix E

Site Plan of Existing Conditions



Appendix F
Boring Sample Report

Project	Final	Inve	stigation - F	L Replace	One Pavilion Avenue, Riverside, NJ 0807 ement Facility Client Virtua Health					1 of v	
					- Voorhees, NJ					er Data	. ,,
Drill Me	thod:	Holl	ow Stem Ai	uger II	O4.25" Casing ID	Depth				si Data	
Grouted		ate	06-0	5-06		Date	06-05-	-06			
						Time	End of B	oring			
	Sam	ple	Blow			· · · · · · · · · · · · · · · · · · ·			•	%	
) (#		je.	Count	ogy	Classification of Materials (Based upon samples recovered and o	hservatio	n n		٤	ure nt, %	
Depth (ft.)	Type	Number	(Blows per 6 inches)	Lithology	of materials returned between samples	3)			Stratum	Moisture Content,	
0	7	i-1	2-2-2-2		Brown medium-fine SAND, little Silt	······································			vis	20	_
<u></u>			Z=Z=Z=Z				··· ··· ··				
-	s	-2	3-2-4-4		Orange brown coarse-fine SAND, little Silt			_			
_								-			
5	S	3-3	4-4-5-7								
_	/ s	-4	6-7-7-7		Orange brown coarse-fine SAND, little medium-f	ine Grave	el, little Silt				
¥			***************************************		Orange brown medium-fine SAND, some Silt, tra	ce fine G	 Travel				
	S	-5	5-5-5-6				70101				
10											
_					Orange brown coarse-fine SAND, some Sitt		-				
_	7				Orange brown coarse-line SAND, Some Silt			-			
	S	-6	9-13-9-8								
'`											
					Orange brown medium-fine SAND, some Silt	***************************************					
-	7				or and, some on			\exists			
20		-7	2-2-3-2								
								-			
		-8	3-2-4-4					\dashv			
25		-0	3-2-4-4								
					Gray fine SAND, little Silt				İ		
M-1			504044		•			\exists			
30		-9	5-9-13-14								
					Dark gray fine SAND and SILT			_	M		
-	1				0.7,			+	.,,		
35	7 S-	10	4-4-4-4					-			

Appendix G

Turner Staffing Plan





Proposed Team Organization

