



TECHNICAL ASSIGNMENT TWO

LancasterHistory.Org
Lancaster, PA

Eric R. Buckwalter
Chimay J. Anumba, Ph.D., D.Sc., P.E.
Comprehensive Architectural Engineering Senior Project I
Construction Management
16 November 2012

EXECUTIVE SUMMARY

The following technical assignment analyzes key information regarding the LancasterHistory.org project that impacts project execution. The \$13.5 million project is located just outside of Lancaster City, PA on Presidents Ave. It is a renovation/addition, totaling in a 32,068 square feet of area. Benchmark Construction is the general contractor on the project, and Centerbrook is the architect. Its construction began in October 2011, and final completion was slotted for the first of this month (11/1), however delays postponed the milestone and the building is still being commissioned.

The project schedule was one of the key aspects of the project, as the owner required it to be completed by the first. Unfortunately, this was delayed due to unforeseen soil conditions early into the project. The schedule in this report details the original plan, and more information regarding the delay may be found in the constructability challenges portion of this report. BIM was only utilized in the design phase of the projects life, but it is recommended that BIM extend throughout the entire duration, should the owner be convinced. A detailed structural system estimate is presented in this report as an extrapolated model. In addition to the structural estimate, a general conditions estimate is provided. All aspects described above have an impact on the delivery of the project, regarding cost and time, two quintessential aspects for any service provided, but particularly the construction industry. Enjoy!

TABLE OF CONTENTS

| | |
|--|----|
| Detailed Structural Systems Estimate..... | 3 |
| Detailed Project Schedule..... | 5 |
| General Conditions Estimate..... | 7 |
| Building Information Modeling Use Evaluation..... | 9 |
| Constructability Challenges..... | 13 |
| Works Cited..... | 16 |
| Appendix A: Detailed Structural Estimate Data..... | 17 |
| Appendix B: Detailed Structural Estimate Calculations..... | 20 |
| Appendix C: Detailed Project Schedule..... | 23 |
| Appendix D: BIM Goals..... | 26 |
| Appendix E: BIM Use Analysis..... | 27 |
| Appendix F: BIM Level-1 Process Map..... | 28 |

DETAILED STRUCTURAL SYSTEMS ESTIMATE

In providing a detailed structural systems estimate for the LancasterHistory.org project, I selected the middle roof arc area as a module. On the structural drawings, the area spans from location C to location E. I have chosen to use this as a modulus because it is proportionately larger and smaller than the neighboring roof arcs in length and height. All modules are the same width. Please see Appendix A for detailed estimate and calculations.

On the lower level foundation plan, there are spread footings on the East and West sides of the building, spanning 50 feet each. In addition, there are two F7 type footers each at locations C and E. There are two F8 footers at location D. Last, there are three F6 footers and a F4 footer in this module. The concrete slab on grade of the lower level encompasses a 50'X59' area. Formwork is done by a three man crew, consisting of a carpenter, a foreman and a laborer. Rebar is placed with a rodman and a foreman, and WWF is placed with a rodman and a common laborer. The concrete is poured via a three men crew of a foreman, a common laborer and a vibrator operator. The lower level slab and ground level topping are finished, protected and cured with a two person crew of a laborer and finisher.

At ground level, there are five W24X55 beams. Three of the W24X55 beams span 17'6", one spans 15' and the last spans 11'6". There are two WT-1 beams, a W10X30 and three HSS members also. Structural steel for this level and for all other levels is set and welded in moment connections. It is set with a crane operator, foreman and steelworker, and it is welded with a field welder, equipment operator and gas welding machine.

The roof framing consists of three bays along FRAME B and FRAME C, spanning locations C and E. The outer walls have GB-4 girders and the two inner girders are GB-3. Bridging occurs at 1/3 points between these girders. 1 3/4 "X16" LVL rafters located 2'4" on center from FRAME B to FRAME C. There are two LVLs at the elevator shaft for lateral stability. The shaft also contains a W8X31 member. A HSS12X8X1/2 serves as a lintel over the stairwell window on the west side. Lumber is placed with a foreman, laborer, carpenter and a crane operator for the girder beams.

The structural FRAME B has all HSS 12X8X1/2 members. The two middle columns extend from the BOF elevation to the EAVE, and the two exterior columns extend from the ground level to the eave. Six HSS beams connect the columns, three at ground level and three at eave level. All are moment connections.

The structural FRAME C has all HSS 12X8X1/2 columns. The two middle columns extend from the BOF elevation to the top of the arc at 23'3", and the two exterior columns extend from the ground level to the top of the arc. Six HSS beams connect the columns, three HSS 16X8X1/2 at approx. 12' above grade and three at approx. 22' above grade. All are moment connections.

From the ground level up, there is 878 sqft of masonry on the first shear wall and 788 sqft of masonry on the second shear wall. This is placed with a five person crew, consisting of a foreman, a layer, a mortar mixer, a laborer and a hod carrier.

The total cost of the structural system of the building for the selected module is just over one hundred thousand dollars (\$107,290.49). Materials will cost \$79,454, labor will cost \$21,224 and equipment will cost \$1,218. These values will be extrapolated to estimate the costs of the entire addition. The SQFT area of the addition is 19,755, and the SQFT area of the selected module is 6,133, so the extrapolated ratio is 3.2211. By multiplying this with the module's cost, it is estimated that the total cost of the building addition will be three hundred forty-five thousand, five hundred and ninety-three dollars (\$345,593).

| | MATERIAL | LABOR | EQUIPMENT | TOTAL |
|-----------------|-----------|----------|-----------|-----------|
| Module | \$79,454 | \$21,224 | \$1,218 | \$107,290 |
| Addition | \$255,929 | \$68,365 | \$3,923 | \$345,593 |

Detailed structural estimate breakdown for module

DETAILED PROJECT SCHEDULE

Overview

The construction schedule for LancasterHistory.org is critical to the project's success, because the owner requires it to be delivered by a certain date. Notice to proceed was received by Benchmark construction on October 3, 2011, and the project was expected to be complete thirteen months later, by November 1, 2012. This target complete date was not reached due to soil complications (see Constructability Challenges on page 13). Also, several change orders were requested by the owner. The detailed construction schedule in this report does not include delays, and it represents the schedule that was originally planned by Benchmark. The schedule can be found in Appendix C of this report (page 23). It details the duration of the construction, and it includes renovation work as well as construction completed for the addition. Many construction sequences overlap in order to expedite the construction process, and a summary of the construction sequencing can be found on the following page.

Sequencing

To meet the construction completion deadline, many construction sequences overlap, and there is very little float. Essentially, sequencing is completed from north to south for all categories of construction. In this way, the addition extends out from the existing building. Several enclosure activities are conducted at the same time the building structure is sequenced. As such, building Dry-in is scheduled for April 26, 2012. Lower level construction activities are completed at the same time as ground level activities to further expedite the schedule. It can be noted that building commissioning is scheduled to take an unusually large portion of time relative to project duration. It is scheduled to take 97 days, which can be attributed to the complex nature of MEPF elements of the building and the projects goal to reach LEED Gold certification.

| LancasterHistory.org Construction Sequences Breakdown | | | |
|---|----------|------------------|-------------------|
| | Duration | Start | Finish |
| Preconstruction | 15 days | 3 October 2011 | 21 October 2011 |
| Foundation | 46 days | 18 October 2011 | 21 December 2011 |
| MEPF | 191 days | 12 December 2011 | 10 September 2011 |
| Structure | 88 days | 12 December 2011 | 13 April 2012 |
| Enclosure | 59 days | 6 February 2011 | 26 April 2012 |
| Exterior | 69 days | 4 April 2012 | 11 July 2012 |
| Ground Level | 120 days | 26 April 2012 | 15 October 2012 |
| Lower Level | 61 days | 30 April 2012 | 25 July 2012 |
| Commissioning | 97 days | 18 June 2012 | 1 November 2012 |

GENERAL CONDITIONS ESTIMATE

The General Conditions Estimate for the LancasterHistory.org project encompasses project personnel, site expenses and miscellaneous costs for the project. The personnel involved in the project include a project manager, assistant project manager, administrative assistant, superintendent and a foreman. Project site expenses are incurred primarily from utilities but also from maintenance, company trucks and dumpsters amongst others. These line items are chosen by looking at the project's site plan from Tech Report 1 and from looking at the project schedule (see Appendix C on page 23). Last, miscellaneous costs are incurred from insurance, bond and permits.

The estimate comes out to over half a million dollars (\$576,641). This number was reached using RS Means, combined with information provided by Benchmark Construction. The cost of utilities, bond, permits and the general conditions total cost are known. Means was used to estimate all other costs. These costs were occasionally manipulated within reason to reach the actual general conditions total cost given by Benchmark. By comparing the general conditions cost with the total project cost for the LancasterHistory.org project, it is determined that general conditions account for only six percent (7.5%) of the original schedule.

| LINE ITEM | AMNT. | UNIT | RATE | TOTAL COST |
|---------------------------|--------|--------|--------------|-------------------|
| PERSONELL | | | | |
| Project Manager | 10 | WEEKS | \$ 3,200 | \$ 48,000 |
| Assistant Project Manager | 30 | WEEKS | \$ 2,800 | \$ 84,000 |
| Administrative Assistant | 20 | WEEKS | \$1,550 | \$ 31,000 |
| Superintendent | 10 | WEEKS | \$ 3,560 | \$ 35,600 |
| Foreman | 20 | WEEKS | \$ 2,560 | \$ 51,200 |
| SITE EXPENSES | | | | |
| Utilities | 1 | N/A | N/A | \$116,445 |
| Site Maintenance | 54 | WEEKS | \$ 230 | \$12,420 |
| Dumpsters | 30 | EACH | \$ 400 | \$12,000 |
| Fencing | 30 | WEEKS | \$ 100 | \$ 3,000 |
| Company Trucks | 54 | WEEKS | \$ 240 | \$ 12,960 |
| Drawings & Specifications | 1 | N/A | N/A | \$ 2,500 |
| CPM Schedule | 1 | N/A | N/A | \$ 4,000 |
| Signage | 1 | N/A | N/A | \$ 1,500 |
| Cell Phones | 13 (5) | MONTHS | \$ 40 | \$ 2,600 |
| Postage & Shipping | 30 | WKS | \$ 75 | \$ 2,250 |
| Porta-Johns | 8 | MONTHS | \$ 550 | \$ 4,400 |
| MISCELLANEOUS | | | | |
| Insurance | 1 | % | \$ 7,697,206 | \$ 76,972 |
| Bond | 1 | N/A | N/A | \$ 56,550 |
| Building Permits | 1 | N/A | N/A | \$ 19,241 |
| TOTAL COST | | | | \$ 576,641 |

BUILDING INFORMATION MODELING USE EVALUATION

Before developing a BIM use list it is important to list the goals of the project as they relate to BIM. The projects goals listed in this report are specific to the LancasterHistory.org project (see Appendix C for BIM Goal List). They encompass all stages of the building's creation from planning to design to operation. As a note, the owner does not require BIM for building operation, and Benchmark opted to not use any BIM in the construction process. The goals are then be used to determine how BIM is applied to the project (see Appendix D for Level-1 Process Map).

After listing the projects goals, a chart is created in the form of a BIM Goal List. Each goal is paired with potential BIM applications that are or would be used to facilitate reaching them. Further, the goals are ranked in priority from low to high. This is used to allocate resources later in the BIM planning process. From the chart on page 27, it can be seen that the most important BIM uses for this particular project include (In descending order): Phase Planning (4D Modeling), 3D Coordination, Sustainability (LEED) Evaluation, Building System Analysis, Construction System Design (Virtual Mockup), Site Utilization Planning, and Space Management/Tracking. BIM use analysis is later conducted in this section to determine BIM use implementation.

Phase Planning is the combination of a 3D model with the added element of time. It is used to demonstrate the construction sequence and space requirements of the project, allowing for better communication between involved parties. This is important to reduce project cost and schedule duration. It is to be used in the design and construction phases of the project. Required resources include scheduling software, a 3D model and 4D modeling software.

Three-Dimensional Coordination is important because it is used to determine major system conflicts before they happen. It is used in the design and construction phases of the project. Its applications are crucial to this project in particular, because there are so many separate entities involved in the design process. It would have greatly facilitated the communication between

parties, saving time and money.

Sustainability (LEED) Evaluation helps the goals of the LancasterHistory.org project by bringing sustainable criteria to it in all phases of facility life. It is used in tandem with Building Systems Analysis via 3D coordination to save time and money by quickly analyzing design changes and bringing about a quality design. It is also used to reduce operational costs for the owner. Perhaps most importantly, the model supplements the LEED evaluation, to actually make the building green.

Building System Analysis is what it sounds like. MEPF and solar aspects of the LancasterHistory.org building are analyzed. These components of the building are analyzed to ensure they meet the owner's criteria in the design phase and the design criteria in the construction/commissioning phase of the project. Further, it could be used to make sure systems continue to operate properly in the maintenance phase, had the owner requested this service. This BIM application requires systems analysis software.

Virtual Mockup is used on the project in its design phase to analyze construction and increase planning, to increase construction productivity and to decrease language barriers between parties. Because of the unusual shape of the roof arcs in the LancasterHistory.org project, this BIM application is used to communicate enclosure of the building. This is very important to ensure the building's longevity (i.e. so that water damage does not occur). It only requires 3D modeling software, but it would be used with many other BIM applications.

Site Utilization Planning is facilitated with BIM because space and sequencing can be more realistically represented than with just two dimensional drawings. Labor, materials and equipment can all be accounted for. The BIM application of Site Utilization Planning saves time and more effectively evaluates construction safety concerns. It is used with Phase Planning, and it is particularly important for the LancasterHistory.org project, given its ambitious schedule and the fact that nearby facilities remain operational.

Space Management is used on this project to effectively allocate, manage and monitor space

usage for the LancasterHistory.org Project. This is important for the project at hand because it is an addition that requires much more space than the existing building. This BIM application helps the owner and architect determine how much space is needed for various historical artifacts and exhibits in the design phase. It can also be used in the maintenance phase to monitor artifacts and other resources during the facilities operation. It requires space mapping and bi-directional model manipulation software.

Next, a BIM use analysis chart is created (see Appendix D on page 27). This chart determines parties involved in the BIM Process, and it rates each party capability per BIM use. After considering additional resources or competencies required, a decision is made to proceed or not to proceed with the considered BIM applications and relevant parties. It is determined in this report that Phase Planning, 3D Coordination, Building System Analysis, Virtual Mockup, Site Utilization Planning and Space Management are all to be implemented on the LancasterHistory.org project, (It can be noted that LEED Evaluation is not practical for this project because the project size is too small to achieve profit.). Active parties in the BIM process are determined to be the owner, architect, contractor, MEPF engineer, structural engineer and occasional subcontractors (excavation, structural-steel, mechanical & electrical subs.). Given the resources and experience of the LEED certified Architect on the project, LEED Gold Certification can still be achieved.

To better understand the implementation of the BIM Uses, BIM project execution process is designed. In doing so, a process map is established, which defines various processes performed by parties. It also communicates information exchanges between parties. This map is later used to determine member selection criteria, contract structure, BIM deliverable requirements and IT infrastructure. A BIM Overview Map for the LancasterHistory.org project can be found in Appendix E.

Critical Evaluation:

Given both the goals and personnel involved in the LancasterHistory.org project, the BIM uses selected are appropriate. Each party creates their own models and brings them to coordination

meetings, which are held every Thursday morning. Significant design changes are submitted to relevant personnel as soon as possible, and models are shared online to keep information current. Benchmark personnel should communicate with subcontractors on-site when applicable and keep up-to-date models (from all parties) for documentation purposes.

BIM was used on this project only by the owner, architect and structural engineer to each of their benefits. It was not used by Benchmark or the MEPF engineer given the size of the project and experience of the parties. However, the complicated nature of the building's various elements suggests time and money could have been saved in the long run had the contractor and MEPF engineer implemented BIM. It is particularly surprising that 3D and 4D models were not utilized by the contractor, since various 3D models were already developed in the design phase of the project. Benchmark should utilize BIM in the construction phase of the project and could keep a record model in case the owner has difficulty with maintenance and later changes its mind. Thus, BIM should have been utilized in all phases of LancasterHistory.org's construction to maximize its potential value for everyone.

| PLAN | DESIGN | CONSTRUCT | OPERATE |
|--------------------------|---------------------------|---------------------------|--------------------------|
| 4D Model | 4D Model | 4D Model | 4D Model |
| 3D Coordination | 3D Coordination | 3D Coordination | |
| Building System Analysis | Building System Analysis | Building System Analysis | Building System Analysis |
| | Virtual Mockup | Virtual Mockup | Virtual Mockup |
| | Site Utilization Planning | Site Utilization Planning | |
| Space Management | Space Management | Space Management | Space Management |


BIM Uses

CONSTRUCTABILITY CHALLENGES

Differing Soil Conditions

Plan bottom for contract documents is specified to be at an elevation of three hundred ninety-nine feet (399'). However, the specified Stratham Type II soil was not encountered within rock bin #2 until 2' below plan bottom at an elevation of three hundred ninety seven feet (397'), as determined by Benchmark and D.H. Funk (site subcontractor) and validated by ECS Testing Agency. In addition to the unsuitable soil condition, a change order request had to be filed by Benchmark for the additional excavation below the plan bottom.

As can be expected, the change order request cost extra time and money. First, there was lag time for the change order to be processed and approved. Further, extra excavation had to be done, extra waterproofing had to be installed, and extra backfill had to be done. Consequently, the construction of the CMU exterior walls (see Appendix C on page 23) was delayed, and the Dry-in Building Milestone could not be reached.



Minimizing Disruption to the Buchanan Estate

The construction site for LancasterHistory.org hosts the Wheatland residence, a historical landmark, and it remained open for the duration of the project. Safety was a top priority in this regard, as the Wheatland residence remained in operation for the duration of construction.

Museum goers need to be protected, which means a lot of fencing and signage. Many children that attend the site with their families and it is important that none get onto the construction site unmonitored. As an added precaution, there is a double gate with a lock. Construction noise was minimized on site, with work synchronized to accommodate museum tours. This required very detailed scheduling and planning.


In addition to the Wheatland Residence, the site happens to host the Louise Arnold Tanger Arboretum. As such, the owner, required that several rare species of trees go unharmed and that most of the 104 varieties of trees go unharmed. Some protected trees were situated right in the middle of construction, so tree fences and nets were used to supplement meticulous logistical planning. Benchmark wished to uproot several trees, but the owner would not allow it (see *Technical Report 1* for site fencing and logistics plans).

A Leak-proof Enclosure



One of the biggest concerns in the construction industry is that water damage will inhibit the longevity of the final product. This type of damage is extremely prevalent in buildings, and it is

typically not covered under insurance. Given the unusual architectural design and shape of the LancasterHistory.org project (see above drawing), the building is especially at risk. During the enclosure phase of construction, inspection around windows is quintessential (see clerestory window below). The flat roof above the soffit requires proper drainage installation as well. The brick façade of the building should have well placed weep holes to allow breathability, should moisture get behind it.



WORKS CITED

RS Means, Square Foot Costs 2013

BIM Execution Planning Guide V2.1

APPENDIX A: DETAILED STRUCTURAL ESTIMATE DATA

Cost Estimate - Standard Construction Project

Detail - With Taxes and Insurance

Estimator :

Project Size : sqft

| Description | TotalCost | \$/sqft | \$/0000 | % of Est |
|--------------------------|-------------------|---------|---------|----------------|
| CONTINUOUS FOOTING FORMS | 2,719.06 | | | 2.534 |
| COLUMN FTG FORMS | 2,688.48 | | | 2.506 |
| FNDN WALL FORMS | 691.25 | | | 0.644 |
| SLAB ON GRADE EDGE FORMS | 345.68 | | | 0.322 |
| SLAB EDGE FORMS | 689.50 | | | 0.643 |
| WALL REBAR | 433.69 | | | 0.404 |
| FOUNDATION WALL REBAR | 1,495.83 | | | 1.394 |
| CONTINUOUS FOOTING REBAR | 1,455.20 | | | 1.356 |
| COLUMN FOOTING REBAR | 805.45 | | | 0.751 |
| MAT FOUNDATION REBAR | 239.41 | | | 0.223 |
| 6x6 W1.4/W1.4 MESH | 2,354.57 | | | 2.195 |
| 6x6 W2.1/W2.1 MESH | 2,939.22 | | | 2.740 |
| 3000 PSI DIRECT | 1,295.76 | | | 1.208 |
| 3000 PSI DIRECT | 1,645.60 | | | 1.534 |
| 3500 PSI DIRECT | 2,881.09 | | | 2.685 |
| 3000 PSI DIRECT | 12,688.07 | | | 11.826 |
| CONCRETE TOPPING | 1,195.08 | | | 1.114 |
| FLOAT FINISH | 1,514.70 | | | 1.412 |
| PROTECT & CURE | 711.70 | | | 0.663 |
| PC HOLLOW CORE PLANK | 12,473.02 | | | 11.626 |
| 8" CONC BLOCK | 7,280.90 | | | 6.786 |
| W10 x 30 | 1,095.20 | | | 1.021 |
| W24 x 55 | 5,348.48 | | | 4.985 |
| HSS 6X6X3/8" | 429.00 | | | 0.400 |
| HSS 6X4X1/2" | 404.00 | | | 0.377 |
| HSS 6X6X5/16 COLUMNS | 2,145.00 | | | 1.999 |
| HSS 10X4X1/4" | 845.50 | | | 0.788 |
| HSS 12X8X1/2 COLUMNS | 11,912.00 | | | 11.103 |
| HSS 12X8X1/2" | 1,489.00 | | | 1.388 |
| HSS 14X6X1/2" BEAMS | 10,140.00 | | | 9.451 |
| HSS 16X8X1/2" BEAMS | 12,552.00 | | | 11.699 |
| 2X12X19 1/2 RAFTERS | 203.05 | | | 0.189 |
| 6 3/4X30 GIRDER BEAMS | 2,184.00 | | | 2.036 |
| Total Gross Cost | 107,290.49 | | | 100.000 |

EDF Report - Standard Construction Project

Estimator : erb5074
 Project Size : sqft
 Date : 11/12/2012
 Time : 10:52 AM

Group 1: Divisions
 Group 2: Major ItemCode Groups
 Group 3: Minor ItemCode Groups
 Group 4: Alternates

| ItemCode | Description | Quantity | UM | Labor\$ | MH/Unit | Units/MH |
|-----------------------------|--------------------------------|----------|------|---------|-------------|----------|
| Concrete | | | | | | |
| <i>Structural CIP forms</i> | | | | | | |
| <i>Structural CIP forms</i> | | | | | | |
| <i>Alternates Blank</i> | | | | | | |
| 03110.100 | CONTINUOUS FOOTING FORMS | 530.00 | SQFT | 3.6583 | 0.139683 | 7.15909 |
| 03110.105 | COLUMN FTG FORMS | 506.00 | SQFT | 3.8412 | 0.146667 | 6.81818 |
| 03110.120 | FNDN WALL FORMS | 130.00 | SQFT | 3.7173 | 0.141935 | 7.04545 |
| 03110.200 | SLAB ON GRADE EDGE FORMS | 100.00 | LNFT | 2.3048 | 0.088 | 11.36364 |
| 03110.316 | SLAB EDGE FORMS | 176.00 | LNFT | 2.5608 | 0.097778 | 10.22727 |
| | **** Total Alternates Blank | | | | \$7,133.96 | |
| | *** Total Structural CIP forms | | | | \$7,133.96 | |
| | ** Total Structural CIP forms | | | | \$7,133.96 | |
| Reinforcing steel | | | | | | |
| <i>Reinforcing steel</i> | | | | | | |
| <i>Alternates Blank</i> | | | | | | |
| 03210.160 | WALL REBAR | 7.26 | CWT | 32.9629 | 1.037037 | 0.96429 |
| 03210.165 | FOUNDATION WALL REBAR | 25.80 | CWT | 31.2281 | 0.982456 | 1.01786 |
| 03210.200 | CONTINUOUS FOOTING REBAR | 24.86 | CWT | 31.7857 | 1.00 | 1.00 |
| 03210.210 | COLUMN FOOTING REBAR | 13.76 | CWT | 31.7857 | 1.00 | 1.00 |
| 03210.230 | MAT FOUNDATION REBAR | 4.09 | CWT | 31.7857 | 1.00 | 1.00 |
| | **** Total Alternates Blank | | | | \$4,429.59 | |
| | *** Total Reinforcing steel | | | | \$4,429.59 | |
| | ** Total Reinforcing steel | | | | \$4,429.59 | |
| Welded wire fabric | | | | | | |
| <i>Welded wire fabric</i> | | | | | | |
| <i>Alternates Blank</i> | | | | | | |
| 03220.010 | 6x6 W1.4/W1.4 MESH | 87.00 | SQS | 18.8640 | 0.80 | 1.25 |
| 03220.011 | 6x6 W2.1/W2.1 MESH | 90.00 | SQS | 22.0080 | 0.933333 | 1.07143 |
| | **** Total Alternates Blank | | | | \$5,293.79 | |
| | *** Total Welded wire fabric | | | | \$5,293.79 | |
| | ** Total Welded wire fabric | | | | \$5,293.79 | |
| Structural concrete | | | | | | |
| <i>Structural concrete</i> | | | | | | |
| <i>Alternates Blank</i> | | | | | | |
| 03310.151 | 3000 PSI DIRECT | 19.63 | CUYD | 11.0090 | 0.45 | 2.22222 |
| 03310.201 | 3000 PSI DIRECT | 24.93 | CUYD | 11.0090 | 0.45 | 2.22222 |
| 03310.363 | 3500 PSI DIRECT | 43.98 | CUYD | 11.0090 | 0.45 | 2.22222 |
| 03310.551 | 3000 PSI DIRECT | 182.09 | CUYD | 14.6787 | 0.60 | 1.66667 |
| 03313.280 | CONCRETE TOPPING | 16.36 | CUYD | 12.0489 | 0.533333 | 1.875 |
| | **** Total Alternates Blank | | | | \$19,705.60 | |
| | *** Total Structural concrete | | | | \$19,705.60 | |
| | ** Total Structural concrete | | | | \$19,705.60 | |
| Finishing | | | | | | |
| <i>Finishing</i> | | | | | | |
| <i>Alternates Blank</i> | | | | | | |
| 03350.132 | FLOAT FINISH | 5,500.00 | SQFT | 0.2754 | 0.010667 | 93.75 |
| | **** Total Alternates Blank | | | | \$1,514.70 | |
| | *** Total Finishing | | | | \$1,514.70 | |
| | ** Total Finishing | | | | \$1,514.70 | |
| Curing | | | | | | |
| <i>Curing</i> | | | | | | |
| <i>Alternates Blank</i> | | | | | | |

| ItemCode | Description | Quantity | UM | Labor\$ | MH/Unit | Units/MH |
|--------------------------|---|----------|------|---------|-------------|----------|
| 03390.010 | PROTECT & CURE | 5,500.00 | SQFT | 0.1102 | 0.004267 | 234.375 |
| | **** Total Alternates Blank | | | | \$711.70 | |
| | *** Total Curing | | | | \$711.70 | |
| | ** Total Curing | | | | \$711.70 | |
| | Plant precast structural concrete | | | | | |
| | Plant precast structural concrete | | | | | |
| | Alternates Blank | | | | | |
| 03410.105 | PC HOLLOW CORE PLANK | 2,650.00 | SQFT | 1.1228 | 0.035556 | 28.125 |
| | **** Total Alternates Blank | | | | \$12,473.02 | |
| | *** Total Plant precast structural concrete | | | | \$12,473.02 | |
| | ** Total Plant precast structural concrete | | | | \$12,473.02 | |
| | * Total Concrete | | | | \$51,262.36 | |
| Masonry | | | | | | |
| | Concrete masonry units | | | | | |
| | Concrete masonry units | | | | | |
| | Alternates Blank | | | | | |
| 04220.303 | 8" CONC BLOCK | 1,435.00 | SQFT | 2.8594 | 0.111304 | 8.98438 |
| | **** Total Alternates Blank | | | | \$7,280.90 | |
| | *** Total Concrete masonry units | | | | \$7,280.90 | |
| | ** Total Concrete masonry units | | | | \$7,280.90 | |
| | * Total Masonry | | | | \$7,280.90 | |
| Metals | | | | | | |
| | Structural steel | | | | | |
| | Structural steel | | | | | |
| | Alternates Blank | | | | | |
| 05122.729 | W10 x 30 | 20.00 | LF | 4.9900 | | |
| 05122.863 | W24 x 55 | 64.00 | LF | 3.5700 | | |
| 05126.038 | HSS 6X6X3/8" | 1.00 | EACH | 51.0000 | | |
| 05126.144 | HSS 6X4X1/2" | 1.00 | EACH | 51.0000 | | |
| 05126.147 | HSS 6X6X5/16 COLUMNS | 5.00 | EACH | 51.0000 | | |
| 05126.218 | HSS 10X4X1/4" | 1.00 | EACH | 55.0000 | | |
| 05126.264 | HSS 12X8X1/2 COLUMNS | 8.00 | EACH | 57.0000 | | |
| 05126.264 | HSS 12X8X1/2" | 1.00 | EACH | 57.0000 | | |
| 05126.274 | HSS 14X8X1/2" BEAMS | 6.00 | EACH | 57.0000 | | |
| 05126.284 | HSS 18X8X1/2" BEAMS | 6.00 | EACH | 57.0000 | | |
| | **** Total Alternates Blank | | | | \$46,360.18 | |
| | *** Total Structural steel | | | | \$46,360.18 | |
| | ** Total Structural steel | | | | \$46,360.18 | |
| | * Total Metals | | | | \$46,360.18 | |
| Wood and plastics | | | | | | |
| | Wood framing | | | | | |
| | Wood framing | | | | | |
| | Alternates Blank | | | | | |
| 06110.756 | 2X12X19 1/2 RAFTERS | 429.00 | BDFT | 0.2133 | 0.007882 | 126.8646 |
| | **** Total Alternates Blank | | | | \$203.05 | |
| | *** Total Wood framing | | | | \$203.05 | |
| | ** Total Wood framing | | | | \$203.05 | |
| | Prefabricated structural wood | | | | | |
| | Prefabricated structural wood | | | | | |
| | Alternates Blank | | | | | |
| 06171.358 | 6 3/4X30 GIRDER BEAMS | 208.00 | LNFT | 2.5000 | 0.092372 | 10.82582 |
| | **** Total Alternates Blank | | | | \$2,184.00 | |
| | *** Total Prefabricated structural wood | | | | \$2,184.00 | |
| | ** Total Prefabricated structural wood | | | | \$2,184.00 | |
| | * Total Wood and plastics | | | | \$2,387.05 | |

APPENDIX B: DETAILED STRUCTURAL ESTIMATE CALCULATIONS

MC² Estimate

Steel Frame (Columns & Beams)
 Items 1-7 are from structural plans
 8-10 are from Grid C
 11-13 Grid E

Foundation

14 exterior: $2(4' \times 50') = 400 \text{ SF}$ } g30
 #5 #14: $(14.5' + 13' + 8.5' + 15' + 14')(2') = 130 \text{ SF}$ }
 (16 #7: 4(49 SF) + 2(64 SF) + 3(36 SF) + 74 SF = 506 SF }
 #7 #8 #9 #6 # Elev.

Rebar

17 continuous fly exterior: #5 $(3.83')(2)(100')(\frac{12''}{9 \text{ oc}})$
 $+ 5(100') = 1521.5' \quad (1.043 \text{ lb/ft}) = 1587 \text{ lb}$

#4 $\left[\frac{40(.16 \text{ diam})}{2.083'} + (1.28') \right] (2)(100')(\frac{12''}{18'' \text{ oc}})(2)$
 $= 969' \quad (.668 \text{ lb/ft}) = 647 \text{ lb}$

$1587 \text{ lb} \#5 + 647 \text{ lb} \#4 = 2,234 \text{ lb}$
 $2,234 \text{ lb} \left\{ \frac{1 \text{ cwt}}{100 \text{ lbs}} \right\} = 22.34$

18 interior: #5 $(3)(65') = 195' \quad (1.043 \text{ lb/ft}) = 203 \text{ lb}$
 #4 $(4.5')(1)(\frac{12''}{18 \text{ oc}})(65') = 79' \quad (.668 \text{ lb/ft}) = 49 \text{ lb}$

19 Fly: #6 16 bars (7')(4 factors) fly #7 = 448 ft = 252 lb
 18 bars (8')(2 factors) fly #8 = 288 ft = 2.51 cwt
 10 bars (6')(3 factors) fly #6 (916 ft) (1.502 lb/ft) = 1376 lb = 13.76 cwt

20 #7 20 bars (10')(1) elev = 200 ft (2.04 lb/ft) = 409 lb = 4.09 cwt

Foundation (cont.)

Concrete

- 21 cont. footer ext $100' (4') (1') = 400 \text{ ft}^3 = 14.815 \text{ cu. yd}$
- 22 cont footer int $65' (2') (1') = 130 \text{ ft}^3 = 4.815 \text{ cu. yd}$
- 23 footers $4(495\text{SF}) \left(\frac{1.25'}{2} \right) + 2(645\text{SF}) (1.5')$
 $+ 3(365\text{SF}) (1.5')$
 elev $745\text{SF} (1') = 673 \text{ ft}^3 = 24.93 \text{ cu. yd}$

SOG

- 24 conc. $\frac{(2930\text{SF} - 805\text{SF}) \left(\frac{5'}{12} \right)}{260} = 1186 \text{ ft}^3 = 43.98 \text{ cu. yd}$
- 26 WWP $\frac{50'}{6} = 8.3 \Rightarrow 9 \quad 9 \times 10 = 90 \text{ sheets}$
 $\frac{59}{6} = 9.8 \Rightarrow 10$

Foundation wall

- 29 form $(13' \text{ wall}) / (100' \text{ long}) = 130 \text{ SFT}$
- 30 rebar $\left. \begin{aligned} \#4 & \quad 13(2)(100' \text{ long}) \cdot 2600 \\ & \quad \cdot \left(\frac{13}{18} \right) (13') (100' \text{ long}) \end{aligned} \right\} = 3067 \text{ ft} \left(1.668 \text{ lb/ft} \right) = 2,131.6 \text{ lb}$
 $\left. \begin{aligned} \#5 & \quad \left(\frac{13}{18} \right) (13') (100') \cdot 867 \\ & \quad 2(2)(100') \end{aligned} \right\} = 1267 (1.04316 \text{ lb/ft}) = 1,321 \text{ lb}$
 $2,131.6 \text{ lb} + 1,321 \text{ lb} = 2,588 \text{ lb} = 25.88 \text{ cwt}$
- 31 conc. $(130 \text{ SF}) \left(\frac{16''}{12} \right) = 173 \text{ cu. yd}$

Elevated Deck (ground level)

- 31 Plank $2890 \text{ SF} - 20 @ 5\text{F} = 2,690 \text{ SF}$
- 33 WWF $90 - 3 = 87 \text{ sheets}$
- 35 topping $2,690 \left(\frac{2}{12}\right) = 442 \text{ Ft}^3 = 16.3\text{F cwyd}$


Masonry Shear Wall

- 3-8 CMUS 778 SF on west
- 657 SF on east
- $1,435 \text{ SF}$
- assume all the same type of 6" CMUS
- 39 rebar #4 $100' \left(\frac{1}{2}\right) (15')$ $750 \text{ ft} \cdot (.66\text{F}) = 5011\text{b}$ *Assume 15' w/length*
- #6 $10 (15')$ $150 \text{ ft} (1.50\text{F}) = 2251\text{b}$
- #4 conc. $7261\text{b} = 7.6\text{ cwt}$
- Assume .26 cufF per BLK
- $1,435 / \left(\frac{8 \times 16}{12}\right) = 134.5 \Rightarrow 135 \text{ Blocks}$
- $135 (.26 \text{ cufF}) = 9.09\text{F cwyd}$

Roof

- Assume are is 30 feet long flat
- 41 rafters $52' \times 59' = 3,068 \text{ SF}$
- 42 CB Assume $2011 \times 52'$ LVL joist instead of $6.75" \times 30"$

APPENDIX C: DETAILED PROJECT SCHEDULE



| Activity ID | Activity Name | Activity Duration | Start | Finish | 2012 | | | | | | | | | | | | 2013 | | | | | | |
|----------------------|--|-------------------|------------------|------------------|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|--|--|
| | | | | | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | | |
| A1730 | Gyp Board Systems Ground Level | 20 | 04-Jun-12 | 29-Jun-12 | | | | | | | | | | | | | | | | | | | |
| A1820 | Interior Wood Window Systems | 15 | 05-Jul-12 | 25-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1840 | Paint - Prime and 1st Coat Ground Lev | 10 | 09-Jul-12 | 20-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1870 | Catering Kitchen Casework | 10 | 27-Jul-12 | 09-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1880 | Folding Glass Door | 3 | 30-Jul-12 | 01-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1890 | Wood Plank Accoustical Ceiling | 10 | 30-Jul-12 | 10-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1900 | 2" Toppin Slab & Saw Cut | 3 | 30-Jul-12 | 01-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1910 | Interior Wall Layout - Ground Level | 2 | 02-Aug-12 | 03-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1930 | Metal Stud Framing - Ground Level | 10 | 03-Aug-12 | 16-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1940 | ACT Tile | 15 | 03-Aug-12 | 23-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1950 | Bookstore Casework | 15 | 06-Aug-12 | 24-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A1980 | Workroom - Casework | 8 | 23-Aug-12 | 04-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A1990 | Sound Absorbing Wall Panel | 5 | 28-Aug-12 | 04-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A2000 | Resilient Flooring | 15 | 28-Aug-12 | 18-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A2010 | Library Wood Panels & Trim | 4 | 28-Aug-12 | 31-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A2020 | Circulation Desk & Reading Room Cas | 12 | 28-Aug-12 | 13-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A2050 | Concrete Stained | 5 | 04-Sep-12 | 10-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A2060 | Carpet | 20 | 18-Sep-12 | 15-Oct-12 | | | | | | | | | | | | | | | | | | | |
| A2070 | Paint - Cut and Roll Final Coat | 20 | 18-Sep-12 | 15-Oct-12 | | | | | | | | | | | | | | | | | | | |
| A2080 | Protection Board - Stained Concrete Fl | 3 | 18-Sep-12 | 20-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A2090 | Reception Desk | 5 | 18-Sep-12 | 24-Sep-12 | | | | | | | | | | | | | | | | | | | |
| Lower Level | | 61 | 30-Apr-12 | 25-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1640 | Gypsum Board Systems | 15 | 30-Apr-12 | 18-May-12 | | | | | | | | | | | | | | | | | | | |
| A1670 | Paint - Prime & First Coat | 20 | 18-May-12 | 15-Jun-12 | | | | | | | | | | | | | | | | | | | |
| A1700 | Rigid Insulation | 2 | 18-May-12 | 21-May-12 | | | | | | | | | | | | | | | | | | | |
| A1740 | Wood Doors | 10 | 07-Jun-12 | 20-Jun-12 | | | | | | | | | | | | | | | | | | | |
| A1600 | Elevator Pit Water Proofing | 4 | 11-Jun-12 | 14-Jun-12 | | | | | | | | | | | | | | | | | | | |
| A1750 | Special Collections Room Casework | 20 | 11-Jun-12 | 09-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1760 | Board Paneling Ceiling | 20 | 13-Jun-12 | 11-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1770 | Ceramic Tile | 25 | 13-Jun-12 | 18-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1800 | Door Hardware | 1 | 02-Jul-12 | 02-Jul-12 | | | | | | | | | | | | | | | | | | | |
| A1810 | ACT Grid | 15 | 05-Jul-12 | 25-Jul-12 | | | | | | | | | | | | | | | | | | | |
| Commissioning | | 97 | 18-Jun-12 | 01-Nov-12 | | | | | | | | | | | | | | | | | | | |
| A2140 | Pre-Installation Checks | 45 | 18-Jun-12 | 20-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A2130 | Building System Commissioning | 0 | 18-Jun-12 | | | | | | | | | | | | | | | | | | | | |
| A1850 | Elevator | 15 | 18-Jul-12 | 07-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A2150 | Bumb Systems | 20 | 18-Jul-12 | 14-Aug-12 | | | | | | | | | | | | | | | | | | | |
| A2160 | In Place Commissioning | 50 | 18-Jul-12 | 26-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A1860 | Building Commissioning | 50 | 23-Jul-12 | 01-Oct-12 | | | | | | | | | | | | | | | | | | | |
| A2040 | LEED Commissioning | 20 | 04-Sep-12 | 01-Oct-12 | | | | | | | | | | | | | | | | | | | |
| A2170 | Air System Balancing | 10 | 17-Sep-12 | 28-Sep-12 | | | | | | | | | | | | | | | | | | | |
| A2180 | Building Air Blowdown | 10 | 05-Oct-12 | 18-Oct-12 | | | | | | | | | | | | | | | | | | | |
| A2100 | Punchlist | 10 | 15-Oct-12 | 26-Oct-12 | | | | | | | | | | | | | | | | | | | |
| A2110 | Final Inspections | 5 | 26-Oct-12 | 01-Nov-12 | | | | | | | | | | | | | | | | | | | |
| A2190 | Final Completion | 0 | | 01-Nov-12 | | | | | | | | | | | | | | | | | | | |

APPENDIX D: BIM GOALS

| PRIORITY (HIGH/MED/LOW) | GOAL DESCRIPTION | POTENTIAL BIM USES |
|----------------------------|---|--|
| High | Ensure building is operating to sustainable standards | Building systems Analysis |
| Medium | Ensure building is operating to specified design | Building systems Analysis |
| High | Identify opportunities to modify system operations to improve performance | Building systems Analysis |
| Medium | Increase the efficiency of transition planning and management | Space management & tracking |
| High | Proficiently track the use of current and space and resources | Space management & tracking |
| High | Assist in planning future space needs for the facility | Space management & tracking |
| Medium | Improve the effectiveness of Emergency response | Disaster Planning |
| Medium | Minimize risks to responders | Disaster Planning |
| High | Accurately evaluate site layout for safety concerns | Site Utilization Planning |
| Medium | Effectively communicate construction sequence and layout to all interested parties | Site Utilization Planning |
| High | Minimize the amount of time spent performing site utilization planning | Site Utilization Planning |
| Medium | Increase constructability of a complex building system | Construction System Design (Virtual Mockup), 3D Coordination |
| High | Increase construction productivity, Phase Planning (4D Modeling) | Construction System Design (Virtual Mockup), 3D Coordination |
| Medium | Decrease language barriers | Construction System Design (Virtual Mockup), 3D Control and Planning (Digital Layout) |
| High | Ensure quality of information | Digital Fabrication |
| Low | Reduce lead time | Digital Fabrication |
| Medium | Decrease layout errors by linking model with real world coordinates | 3D Control and Planning (Digital Layout) |
| Low | Reduce rework because control points are received directly from the model | 3D Control and Planning (Digital Layout) |
| High | Reduce and eliminate field conflicts | 3D Coordination |
| High | Reduce construction cost | 3D Coordination, Phase Planning (4D Modeling), Cost Estimation |
| High | Decrease construction time | 3D Coordination, Phase Planning (4D Modeling) |
| High | Better control and quality control of design, cost and schedule | Design Authoring, Sustainability (LEED) Evaluation, Design Reviews |
| High | Achieve optimum, energy-efficient design solution by applying various rigorous analyses | Engineering Analysis, Facility Energy Analysis |
| Low | Automate analysis, saving time and cost | Engineering Analysis, Facility Energy Analysis |
| Medium | Early and reliable evaluation of design alternatives. | Sustainability (LEED) Evaluation, Design Reviews |
| High | Reduce operational costs of the facility due to the energy performance of the project | Sustainability (LEED) Evaluation |
| Low | Reduced turnaround time | Code Validation |
| High | Space and workspace conflicts identified and resolved ahead of the construction process | Phase Planning (4D Modeling) |
| Medium | Monitor procurement status of project materials | Phase Planning (4D Modeling) |
| High | Identification of schedule, sequencing or phasing issues | Phase Planning (4D Modeling) |

APPENDIX E: BIM USE ANALYSIS

| BIM USE | VALUE TO PROJECT | RESPONSIBLE PARTY | VALUE TO RESP PARTY | CAPABILITY RATING | | | ADDITIONAL RESOURCES/COMPETANCIES REQUIRED TO IMPLEMENT | PROCEED WITH USE |
|--|------------------|---------------------|---------------------|-------------------|------------|------------|---|------------------|
| | | | | SCALE 1-3 (1=LOW) | | | | |
| | HIGH/MED/LOW | | HIGH/MED/LOW | Resources | Competency | Experience | | YES/NO/MAYBE |
| Building systems Analysis | High | Architect | Medium | 3 | 3 | 3 | Building Systems Analysis Software, Record Model | Yes |
| | | MEPF Engineer | High | 3 | 2 | 2 | | |
| | | Contractor | High | 2 | 2 | 2 | | |
| Space management & tracking | High | Owner | High | 2 | 3 | 3 | Bi-Directional 3D Model Manipulation | Yes |
| Disaster Planning | Medium | Contractor | Medium | 1 | 3 | 3 | Record Model | Maybe |
| Site Utilization Planning | High | Contractor | High | 3 | 3 | 3 | | Yes |
| Construction System Design (Virtual Mockup) | High | Architect | High | 3 | 2 | 2 | | Yes |
| | | MEPF Engineer | High | 3 | 3 | 2 | | |
| | | Structural Engineer | Medium | 3 | 3 | 2 | | |
| Digital Fabrication | Low | Structural Engineer | Low | 2 | 2 | 1 | | No |
| | | Contractor | Low | 3 | 3 | 2 | | |
| | | Fabricator | Medium | 3 | 3 | 3 | | |
| 3D Control and Planning (Digital Layout) | Low | Architect | Low | 2 | 2 | 1 | | No |
| | | MEPF Engineer | Low | 3 | 3 | 3 | | |
| | | Contractor | Medium | 2 | 3 | 2 | | |
| | | Subcontractors | Low | 1 | 2 | 1 | | |
| 3D Coordination | High | Architect | High | 3 | 3 | 3 | Teach Subcontractors | Yes |
| | | MEPF Engineer | High | 3 | 3 | 3 | | |
| | | Contractor | High | 2 | 3 | 3 | | |
| | | Subcontractors | Medium | 1 | 2 | 1 | | |
| | | Structural Engineer | High | 3 | 2 | 2 | | |
| Code Validation | Low | Contractor | Low | 3 | 2 | 2 | | No |
| Phase Planning (4D Modeling) | High | Contractor | High | 3 | 3 | 3 | Teach Subcontractors | Yes |
| | | Subcontractors | Medium | 1 | 3 | 1 | | |
| Design Reviews | Low | Architect | Medium | 3 | 2 | 2 | | No |
| | | Owner | Low | 2 | 1 | 1 | | |
| Facility Energy Analysis | Medium | Architect | Medium | 3 | 2 | 3 | | No |
| | | MEPF Engineer | High | 3 | 2 | 3 | | |
| | | Contractor | Medium | 2 | 2 | 1 | | |
| Sustainability (LEED) Evaluation | High | Contractor | High | 2 | 2 | 1 | Knowledge of up-to-date LEED information | Maybe |
| | | Owner | High | 2 | 2 | 1 | | |
| | | Architect | High | 3 | 2 | 3 | | |
| Cost Estimation | Low | Architect | Low | 2 | 1 | 2 | | No |
| | | Contractor | Medium | 3 | 3 | 3 | | |
| Design Authoring | Low | Architect | Medium | 2 | 2 | 1 | | No |
| | | Owner | Low | 2 | 1 | 1 | | |
| | | Structural Engineer | Low | 2 | 2 | 2 | | |
| Engineering Analysis | Medium | Architect | Medium | 2 | 2 | 1 | Engineering analysis software | Maybe |
| | | MEPF Engineer | High | 3 | 3 | 3 | | |
| | | Structural Engineer | Medium | 3 | 3 | 3 | | |
| | Medium | Contractor | Medium | 2 | 2 | 1 | | Maybe |
| | | Facility Manager | Low | 2 | 1 | 1 | | |
| | | Architect | Low | 2 | 1 | 1 | | |

APPENDIX G: BIM LEVEL-1 PROCESS MAP

