

Reston Station Phase 1 Garage

Reston, Virginia



Penn State Architectural Engineering Senior Thesis

Jon Fisher

Construction Option

Advisor: Dr. Robert Leicht

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements



Project Overview

Location

- Reston, Virginia

Size

- 1.3 Million Square Feet
- 7 Underground Levels
- 5 Additional Buildings in Future Phases

Function

- 2300 Public Parking Spaces
- Silver Line Metrorail

Schedule

- April 2011 – July 2013
- 27 Months

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements



Project Overview

Cost



- \$92 Million

Delivery Method

- Guaranteed Maximum Price
- CM at Risk – Davis Construction

Owner


- Fairfax County and Comstock Partners



Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management



Public-Private Partnerships

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Goal of Analysis #1

- To understand the public-private partnership used on the project and determine the implications partnerships have on construction as a whole



Public-Private Partnerships

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Public-Private Partnership: “A government service or private business venture funded and operated through a partnership of government and one or more private sector companies.”

- When government and the private sector work together



PPP's In Construction

Simple Example: Toll Roads

- Sharing risk and reward



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Public-Private Partnerships

PPP At Reston Station

- County given development funds from VDOT
- Fairfax approached by Comstock for future building rights
- Virginia Public-Private Partnership Act
- 99-year lease
- Proffer agreement contains terms
- Price tag divided by parking ratio

Advantages of Public Private Partnerships

<i>Public Owner</i>	<i>Private Owner</i>
<ul style="list-style-type: none">• Reduced Cost• Delivery Method Freedom• Possible Increase in Revenue• Increased Efficiency	<ul style="list-style-type: none">• Operation in New Markets• New Revenue Opportunity• Government Relationship


OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Public-Private Partnerships

Challenges

Usage of Garage Area



Decision Making


- Limited conflicts in separated areas
- Decision making paralysis on shared spaces
- Decision making flow chart

Reston Station Phase 1 Garage


Reston, Virginia

Jon Fisher | Construction Management

Reston Station Decision Making



Generalized Decision Making



OUTLINE

- I. Project Overview
- II. **Analysis #1: Public-Private Partnerships**
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Public-Private Partnerships

Conclusion

- PPP's are great in theory but still untested with general building construction
- Best to proceed in a PPP with critical awareness
- Large variance between different levels and states

Long Beach Courthouse

- Not a transportation example
- Long Beach Judicial Partners LLC
 - Clack Design-Build
 - AECOM
 - Johnson Controls
- \$490 Million Design-Build-Operate-Maintain
- Performance based service fee
- Funding source complications



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Equipment Staging and Bonded Warehouses

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Goal of Analysis #2

- To investigate an alternative option for the storage of construction materials utilizing off-site bonded warehouses



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Equipment Staging and Bonded Warehouses

Current Situation

- Escalator frames, ventilation fans, and stone façade
- Escalators originally to be stored on finished slab
- Design delay caused complications
- 140 fans and 2 escalators stored on slabs for extended period of time



Intended Storage of Escalators



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Equipment Staging and Bonded Warehouses

Current Situation

- Escalator frames, ventilation fans, and stone façade
- Escalators originally to be stored on finished slab
- Design delay caused complications
- 140 fans and 2 escalators stored on slabs for extended period of time



Actual Storage of Escalators



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Equipment Staging and Bonded Warehouses

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management


How Bonded Warehouses Could Help

Typical Method of Equipment Delivery


- Delivered directly to the site
- Stored on site
- Good for projects site freedom

Using Bonded Warehouses for Short Term

- Logistics services company
- Month-to-month storage
- No long term contract
- Sites with some restrictions



The Traditional Method



Limited Bonded Warehouse Use

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Equipment Staging and Bonded Warehouses

Difference from Subcontractor "Yard"

Cash Flow

"§9.3.2 Unless otherwise provided in the contract document, payments shall be made on account of materials and equipment delivered and suitably store at the site for subsequent incorporation in the work. If approved in advance by the owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing."

-General Conditions of the Contract for Construction (AIA A201)



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Equipment Staging and Bonded Warehouses

Costs

- Added stage of transportation
- Month-to-Month storage
- Insurance of materials

Total Cost of Off Site Storage of Limited Items	
Storage Cost	\$ 20,600.00
Transportation Cost	\$ 7,600.00
Bonding (1% Value of Goods)	\$ 8,036.00
TOTAL	\$ 36,236.00

Data from England Logistics & Innerspace



Limited Bonded Warehouse Use

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. **Analysis #2: Bonded Warehouses**
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Equipment Staging and Bonded Warehouses

Using Bonded Warehouses as a HUB


- All deliveries to bonded warehouse
- Could be used for multiple projects
- Long-term lease
- Pentagon Renovation Example



Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management



Bonded Warehouses as HUBs

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Equipment Staging and Bonded Warehouses

Costs

- Added staff and equipment
- 36 month lease
- Bonding on warehouse

Total Cost of Off Long Term Off Site Storage	
Storage Cost	\$ 896,019.48
Transportation Cost	\$ 162,020.00
Staff	\$ 660,000.00
TOTAL	\$ 1,718,039.48

Compared to \$36,000 for short term use



Bonded Warehouses as HUBs

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Equipment Staging and Bonded Warehouses

Reston Station Phase 1 Garage


Reston, Virginia

Jon Fisher | Construction Management


Comparing Costs

Per Month Comparison of Bonded Warehouse Use			
Scenario	Time Span (mo.)	Cost	Cost/Mo
Warehouse Leasing	36	\$ 1,718,039.48	\$ 47,723.32
Short Term Warehouse Space Usage	6	\$ 36,236.00	\$ 6,039.33

- Short term time span from construction schedule
- Warehouse leasing option = 1.5% project budget
- Minimized impact if used by several projects



Limited Bonded Warehouse Use



Extensive Bonded Warehouse Use

Equipment Staging and Bonded Warehouses

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Comparing Costs

Per Month Comparison of Bonded Warehouse Use			
Scenario	Time Span (mo.)	Cost	Cost/Mo
Warehouse Leasing	36	\$ 1,718,039.48	\$ 47,723.32
Short Term Warehouse Space Usage	6	\$ 36,236.00	\$ 6,039.33

- Short term time span from construction schedule
- Warehouse leasing option = 1.5% project budget
- Minimized impact if used by several projects

Advantages

- Reduced Risk
- Consolidated Delivery
- Early Subcontractor cash flow
- Eliminates delays in Production

Value of Goods Being Stored and Transported

Item	Cost	Quantity	Unit	Total
Granite Stone Façade	\$ 18.00	10200	SF	\$ 183,600.00
Garage Supply Air Fans	\$ 3,140.00	50	Ea	\$ 157,000.00
Garage Exhaust Air Fans	\$ 2,700.00	90	Ea	\$ 243,000.00
Escalator Trusses	\$ 110,000.00	2	Ea	\$ 220,000.00
TOTAL				\$ 803,600.00

\$800,000 OF MATERIALS

Equipment Staging and Bonded Warehouses

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Conclusion

Recommendation: Implementation of warehouse as month-to-month storage for escalators, stone, and fans will mitigate risk and help site production at Reston.

- Leasing warehouse as HUB space is cost prohibitive
- Better suited for when required or serving multiple projects

Advantages

- Reduced Risk
- Consolidated Delivery
- Early Subcontractor cash flow
- Eliminates delays in Production

Value of Goods Being Stored and Transported					
Item	Cost	Quantity	Unit		Total
Granite Stone Façade	\$ 18.00	10200	SF		\$ 183,600.00
Garage Supply Air Fans	\$ 3,140.00	50	Ea		\$ 157,000.00
Garage Exhaust Air Fans	\$ 2,700.00	90	Ea		\$ 243,000.00
Escalator Trusses	\$ 110,000.00	2	Ea		\$ 220,000.00
				TOTAL	\$ 803,600.00

\$800,000 OF MATERIALS

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling**
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Short Interval Production Scheduling

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Goal of Analysis #3


- To utilize Short Interval Production Scheduling (SIPS) and matrix scheduling to accelerate and illustrate garage finish sequence

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Short Interval Production Scheduling

Original Finish Sequence




- Each level divided by East and West
- Original zones = 99,000 SF
- Concrete sequence determined finish sequence

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Original Finish Sequence



Reshore restrictions defined finish schedule

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Short Interval Production Scheduling

Reston Station Phase 1 Garage

Reston, Virginia


Jon Fisher | Construction Management

Adjusted Sequence



- Simplified sequence
- Includes co-location of certain trades

Original Finish Sequence



Reshore restrictions defined finish schedule

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Short Interval Production Scheduling

Reston Station Phase 1 Garage

Reston, Virginia



Jon Fisher | Construction Management

Adjusted Sequence



- Simplified sequence
- Includes co-location of certain trades

Redefined Zones



- Takes most advantage of concrete sequence
- Each Subzone = 8,250 Square Feet

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Short Interval Production Scheduling

Productivity Rates and Crew Adjustment

Garage Activity Productivity Rates					
Schedule Indicator	Activity	Baseline Duration (Days)	Productivity (SF/Man/Day)	SIPS Subzone Area	# of Workers (SIPS)
A	Layout	5	9900	8250 SF	2
B	Curbs	20	413		20
C	CMU Walls	20	620		14
D	Doors & Hardware	5	9900		2
	Railings	10	3300		3
E	Mech Rough In	10	2475		4
	Electrical Rough In	10	1650		6
F	Plumbing Rough In	20	495		17
G	Sprinkler Rough In	30	825		10
H	Remove Reshores	3	8250		4
	Paint Walls and Ceilings	15	660		13
I	Traffic Coating	24	1094	8	
J	Light Fixtures	20	825	10	
K	Pavement Markings	5	3300	6	



- Crew sizes adjusted to achieve 1 subzone/day
- Some crew sizes were “irreducible”

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Redefined Zones



- Takes most advantage of concrete sequence
- Each Subzone = 8,250 Square Feet

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Short Interval Production Scheduling

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Productivity Rates and Crew Adjustment

Garage Activity Productivity Rates					
Schedule Indicator	Activity	Baseline Duration (Days)	Productivity (SF/Man/Day)	SIPS Subzone Area	# of Workers (SIPS)
A	Layout	5	9900	8250 SF	2
B	Curbs	20	413		20
C	CMU Walls	20	620		14
D	Doors & Hardware	5	9900		2
	Railings	10	3300		3
E	Mech Rough In	10	2475		4
	Electrical Rough In	10	1650		6
F	Plumbing Rough In	20	495		17
G	Sprinkler Rough In	30	825		10
H	Remove Reshores	3	8250		4
	Paint Walls and Ceilings	15	660		13
I	Traffic Coating	24	1094	8	
J	Light Fixtures	20	825	10	
K	Pavement Markings	5	3300	6	

- Crew sizes adjusted to achieve 1 subzone/day
- Some crew sizes were “irreducible”

“Perfect” Matrix

Level	Subzone	14-Feb	15-Feb	16-Feb	17-Feb	20-Feb	21-Feb	22-Feb	23-Feb	24-Feb	27-Feb	28-Feb	29-Feb	1-Mar	2-Mar	5-Mar	6-Mar	7-Mar	8-Mar	9-Mar	12-Mar	13-Mar	
G7	1A	A	B	C	D	E	F	G	H	I	J	K											
G7	1B		A	B	C	D	E	F	G	H	I	J	K										
G7	1C			A	B	C	D	E	F	G	H	I	J	K									
G7	1D				A	B	C	D	E	F	G	H	I	J	K								
G7	1E					A	B	C	D	E	F	G	H	I	J	K							
G7	1F						A	B	C	D	E	F	G	H	I	J	K						
G7	2A							A	B	C	D	E	F	G	H	I	J	K					
G7	2B								A	B	C	D	E	F	G	H	I	J	K				
G7	2C									A	B	C	D	E	F	G	H	I	J	K			
G7	2D										A	B	C	D	E	F	G	H	I	J	K		
G7	2E											A	B	C	D	E	F	G	H	I	J	K	


168 Zones
Duration: 178 Days

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Short Interval Production Scheduling

Structural Breadth




- Original 2+4 Requirement
- Redesign of slab to achieve 2+2
- ACI 318-11
 - Deflections
 - Punching Shear

Reston Station Phase 1 Garage

Reston, Virginia


Jon Fisher | Construction Management



Combined Capacity > Combined Loading

ASCE 37

Slab Dead Load (10" slab) = 125 PSF
 Formwork = 10 PSF
 Reshores = 5 PSF
 Construction Live Load = 75 PSF



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements


Short Interval Production Scheduling

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Structural Breadth



- Original 2+4 Requirement
- Redesign of slab to achieve 2+2
- ACI 318-11
 - Deflections
 - Punching Shear



10" Slab with 5.5" Drop Panel Meets Requirements

5.5" drop panel allows for dimensional 2x6 form work

- Saves time and labor

Short Interval Production Scheduling

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Conclusion

- SIPS REQUIRES COORDINATION
- Concrete progress had big impact on finishes
- Early completion means lower general conditions
- Crew size adjustments impact cost curve

- Slab redesign with SIPS = \$2,350/saved day
- Liquidated Damages = approx. \$10,000/day after Substantial Completion
- Financially beneficial to owner

SIPS Schedule Results						
Finish Scenario	Start	Finish	Duration	Saved Duration	Days Complete Before BL Finish	Cost Increase
Baseline Schedule	14-Feb-12	5-Feb-13	256	-	-	\$ -
"Perfect" Matrix	14-Feb-12	18-Oct-12	178	78	78 Days	\$ -
SIPS w/ 4+2 Shoring	14-Feb-12	13-Nov-12	196	60	60 Days	\$ -
SIPS w/ 2+2 Shoring	2-Jan-12	10-Oct-12	203	53	85 Days	\$ 200,000.00

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. **Analysis #4: Mechanical Chases**
- VI. Summary and Conclusions
- VII. Acknowledgements

Mechanical Chases and Design Coordination

Reston Station Phase 1 Garage


Reston, Virginia

Jon Fisher | Construction Management

Goal of Analysis #4

- To assess the impacts of adding mechanical pipe chases to the garage on design coordination and project cost.

Design Coordination



Architect - Hickok Cole Structural - Structura MEP - Hoffman Borowski	Architect - Davis, Carter, Scott Structural - Luis Fernandez MEP - Jordan & Skala	Architect - Murphy/Jahn Structural - Thorton Thomasetti MEP - GHT Chartered
-----------------------------------------------------------------------------	-----------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------

- 3 Separate Design Teams
- Penetration Coordination difficult with varying stages of design

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. **Analysis #4: Mechanical Chases**
- VI. Summary and Conclusions
- VII. Acknowledgements

Mechanical Chases and Design Coordination

Mechanical Breadth

Roof Drains

Reston 100 Year Storm = 3"/hour

Flat Roof Slope = 1/4" / Ft.

Assumes Consolidation to 1 Pipe

Building	Total Roof Area (SF)	Largest Roof Drain Pipe Size
Office Building 1	30000	10"
Office Building 2	40000	12"
Office Building 3	35400	10"
Apartment 4	58125	12"
Hotel 5	14400	8"

Size of Pipe in.	Flow at 1/4 in./ft Slope gpm	Maximum Allowable Horizontal Projected Roof Areas Square Feet at Various Rainfall Rates				
		1 in./h	2 in./h	3 in./h	4 in./h	5 in./h
3	48	4640	2320	1546	1160	928
4	110	10,600	5300	3533	2650	2120
5	196	18,880	9440	6293	4720	3776
6	314	30,200	15,100	10,066	7550	6040
8	677	65,200	32,600	21,733	16,300	13,040
10	1214	116,800	58,400	38,950	29,200	23,350
12	1953	188,000	94,000	62,600	47,000	37,600
15	3491	336,000	168,000	112,000	84,000	67,250

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. **Analysis #4: Mechanical Chases**
- VI. Summary and Conclusions
- VII. Acknowledgements

Mechanical Chases and Design Coordination

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Mechanical Breadth

Roof Drains

Reston 100 Year Storm = 3"/hour

Flat Roof Slope = 1/4" / Ft.

Assumes Consolidation to 1 Pipe

Building	Total Roof Area (SF)	Largest Roof Drain Pipe Size
Office Building 1	30000	10"
Office Building 2	40000	12"
Office Building 3	35400	10"
Apartment 4	58125	12"
Hotel 5	14400	8"

Size of Pipe in.	Flow at 1/4 in./ft Slope gpm	Maximum Allowable Horizontal Projected Roof Areas Square Feet at Various Rainfall Rates				
		1 in./h	2 in./h	3 in./h	4 in./h	5 in./h
3	48	4640	2320	1546	1160	928
4	110	10,600	5300	3533	2650	2120
5	196	18,880	9440	6293	4720	3776
6	314	30,200	15,100	10,066	7550	6040
8	677	65,200	32,600	21,733	16,300	13,040
10	1214	116,800	58,400	38,950	29,200	23,350
12	1953	188,000	94,000	62,600	47,000	37,600
15	3491	336,000	168,000	112,000	84,000	67,250

Sanitary Drains

Slope of Drain Pipe = 1/8" / ft

Assumes Consolidation to 1 Pipe

Exception: 2 Pipes in Apartment due to excessive drop

Building	DFU's	Building Sainitary Drain Size
Office Building 1	468.5	6"
Office Building 2	244	5"
Office Building 3	202	5"
Apartment 4 (A)	3116	12"
Apartment 4 (B)	3116	12"
Hotel 5	1478	8"

Table of Drainage Fixture Unit Values

Automatic Clothes Washer	2
Shower	2
Dishwashing Machine	2
Lavatory	1
Kitchen Sink	2
Service Sink	2
No-Flush Urinal	0.5
Water Closet (Private)	3
Water Closet (Public)	4

TABLE 22.5 Building Drains and Sewers

Diameter of Pipe in.	mm ^b	Maximum Number of dfu Connected to Any Portion of the Building Drain or Building Sewer, Including Branches of the Building Drain ^a Fall, in. per ft (% slope)			
		1/4 (0.5%)	1/2 (1.04%)	3/4 (2.1%)	1 (4.2%)
2	51			21	26
2 1/2	64			24	31
3	76		36	42	50
4	102		180	216	250
5	127		390	480	575
6	152		700	840	1000
8	203	1400	1600	1920	2300
10	254	2500	2900	3500	4200
12	305	3900	4600	5600	6700
15	381	7000	8300	10,000	12,000

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases**
- VI. Summary and Conclusions
- VII. Acknowledgements

Mechanical Chases and Design Coordination


Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Chase Design


- 8" CMU Partition Walls
- Outward Swinging Doors
- Steel Grating
- 6' x 8'



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. **Analysis #4: Mechanical Chases**
- VI. Summary and Conclusions
- VII. Acknowledgements

Mechanical Chases and Design Coordination



Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Location For Chases

The Good

- Perimeter locations simplify connection to exterior
- Could coincide with stairwell or elevator shaft location

The Bad

- 10 Public and 12 Private Parking Spaces lost

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. **Analysis #4: Mechanical Chases**
- VI. Summary and Conclusions
- VII. Acknowledgements

Mechanical Chases and Design Coordination

Recommendation

- Cost prohibitive
- Further investigation needed for achieving better design coordination efforts

The Ugly

Cost of Chases								
Item	Unit	Quantity	Labor (Unit Cost)	Material (Unit Cost)	Equipment	Total Labor	Total Material	Total Equipment
Steel Grating	SF	1008	\$ 14.85	\$ 4.50	\$ 2.49	\$ 14,968.80	\$ 4,536.00	\$ 2,509.92
Steel Angles	Ea	56	\$ 56.00	\$ 29.50	\$ -	\$ 3,136.00	\$ 1,652.00	\$ -
HM Doors	Ea	28	\$ 560.00	\$ 39.00	\$ -	\$ 15,680.00	\$ 1,092.00	\$ -
HM Frames	Ea	28	\$ 199.00	\$ 44.00	\$ -	\$ 5,572.00	\$ 1,232.00	\$ -
CMU Block	SF	6688	\$ 2.40	\$ 4.34	\$ -	\$ 16,051.20	\$ 29,025.92	\$ -
Concrete Expansion Anchors	Ea	280	\$ 2.38	\$ 3.07	\$ -	\$ 666.40	\$ 859.60	\$ -
Total						\$ 56,074.40	\$ 38,397.52	\$ 2,509.92
Tax							\$ 2,303.85	
Total						\$ 99,285.69		

Chase Cost = \$99,000

12" Core Drills					
unit	Quantity	Material	Labor	Equipment	Total Cost
Ea	132	\$ 2.75	\$ 71.02	\$ 12.16	\$ 11,001.54

Core Drill Cost = \$11,000

Conclusions

Final Conclusions

Public-Private Partnerships: Good research, caution needed when working with a PPP

Bonded Warehouses: Shows benefit for month-to-month short term needs but leasing is cost prohibitive for Reston

SIPS Scheduling: Biggest impact on schedule comes from design delays. SIPS could have helped in hindsight.

Mechanical Chases: Cost prohibitive

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. **Summary and Conclusions**
- VII. Acknowledgements

OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements

Acknowledgements

Reston Station Phase 1 Garage

Reston, Virginia


Jon Fisher | Construction Management


Penn State Architectural Engineering Faculty

Friends, Family and God







Industry Members







Appendix (Bonded Warehouses)



Cost of Renting Bonded Warehouse Space (Short Term Limited Use)

Storage Costs						
Item	Cost	Quantity	Unit	Duration (mo)	Total	Notes
Oversize Pallets For Fans	\$ 20.00	220	/pallet/m	2	\$ 8,800.00	Transwestern Estimate
Drop Trailer Rental	\$ 150.00	4	/mo	6	\$ 3,600.00	England Logistics Quote
Drop Trailer Drop off/ Pick up	\$ 125.00	8	Ea		\$ 1,000.00	England Logistics Quote
40 foot drop trailer storage	\$ 300.00	4	/drop trai	6	\$ 7,200.00	Transwestern Estimate
TOTAL					\$ 20,600.00	

Transportation Costs

Item	Cost	Quantity	Unit	Total	Notes
"Live Load" delivery of fans and stone	\$ 400.00	14	/Load	\$ 5,600.00	England Logistics Quote
"Live Load" delivery of escalator drop trailers	\$ 500.00	4	/Load	\$ 2,000.00	England Logistics Quote
TOTAL				\$ 7,600.00	

Value of Goods Being Stored and Transported

Item	Cost	Quantity	Unit	Total	Notes
Granite Stone Façade	\$ 18.00	10200	SF	\$ 183,600.00	
Garage Supply Air Fans	\$ 3,140.00	50	Ea	\$ 157,000.00	
Garage Exhaust Air Fans	\$ 2,700.00	90	Ea	\$ 243,000.00	
Escalator Trusses	\$ 110,000.00	2	Ea	\$ 220,000.00	
TOTAL				\$ 803,600.00	

Total Cost of Off Site Storage of Limited Items

Storage Cost	\$ 20,600.00
Transportation Cost	\$ 7,600.00
Bonding (1% Value of Goods)	\$ 8,036.00
TOTAL	\$ 36,236.00

Cost of Renting Bonded Warehouse Space (Long Term Extensive Use)

Storage Costs						
Item	Cost	Quantity	Unit	Duration (Yr)	Total	Notes
Lease on Warehouse Space	\$ 12.00	24,643	/SF/Year	3	\$ 887,148.00	Minimum 3-year Lease, Transwestern
Bonding	\$ 8,871.48				\$ 8,871.48	1% of Lease Value
TOTAL					\$ 896,019.48	

Staffing Costs

Team Member	Cost	Quantity	Unit	Duration	Total	Notes
Warehouse Manager	\$ 80,000.00	1	/Year	3	\$ 240,000.00	Includes Phone + Computer + Benefits
Drivers	\$ 70,000.00	2	/Year	3	\$ 420,000.00	Includes Phone + Benefits
TOTAL					\$ 660,000.00	

Transportation Costs

Item	Cost	Quantity	Unit	Duration	Total	Notes
Truck (Class 8)	\$ 45,000.00	2	Ea		\$ 90,000.00	
Flatbed Trailer	\$ 15,000.00	1	Ea		\$ 15,000.00	
Dry Van Trailer	\$ 5,000.00	1	Ea		\$ 5,000.00	
Diesel Gas	\$ 4.25	16	Gal/Day	765	\$ 52,020.00	Duration = Workdays in 3 Years
TOTAL					\$ 162,020.00	

Total Cost of Off Long Term Off Site Storage

Storage Cost	\$ 896,019.48
Transportation Cost	\$ 162,020.00
Staff	\$ 660,000.00
TOTAL	\$ 1,718,039.48

OUTLINE

RENOVATED SPACE FOR LEASE

Renaissance Park

Flex Space & Warehouse for Lease with Outside Storage
2770-2782 Towerview Road, Herndon, VA




- 12,524 SF Flex
 - 3,000 SF of office
 - 100% conditioned warehouse
 - 1 dock and 1 drive-in
 - \$10.00 PSF, NNN
- 24,443 SF Industrial
 - 4,000 SF of office
 - Secured outside storage
 - 3 docks
 - \$8.50 PSF, NNN
 - 2012 operating expenses (estimated) \$2.15 PSF

AMENITIES

- Building has capacity for 8MVA of power
- Deli on-site
- Minutes from Dulles Airport
- Nearby amenities include hotels, restaurants, health club and more

TRANSWESTERN
8614 Wakefield Center Drive, Suite 800
Vienna, VA 22182
Ph: 703.621.0040 Fax: 703.734.2607
www.transwestern.net

Bob Shaffer
703.749.9433
bshaffer@transwestern.net



Appendix (Bonded Warehouses)

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Commercial Truck Trader
www.commercialtrucktrader.com

HOME FIND SELL AUCTIONS RESEARCH
Search Trucks Browse Trucks Browse Trailers Find A Dealer Truck Locator

CommercialTruckTrader.com > 2007 Freightliner M21126-4S 108385677

2007 FREIGHTLINER M211264S CONVENTIONAL - DAY CAB \$45,250.00

CONTACT SELLER

PENSKE

PENSKE USED TRUCKS
(888) 236-3799
EMAIL SELLER

1295 SEMINOLE TRAIL
CHARLOTTESVILLE, VA 22901 (Map)

See All Inventory | Visit Dealer Web Site
Shop Safely. Protect Your Money.



Commercial Truck Trader
www.commercialtrucktrader.com

HOME FIND SELL AUCTIONS RESEARCH
Search Trucks Browse Trucks Browse Trailers Find A Dealer Truck Locator

CommercialTruckTrader.com > 2006 TRANSCRAFT 48'X102 101317556



2006 TRANSCRAFT 48'X102 FLATBED TRAILER \$14,900.00

CONTACT SELLER

Virginia Equipment Distributors
(888) 847-6308
EMAIL SELLER

288 North Madison
Orange, VA 22960 (Map)

See All Inventory
Shop Safely. Protect Your Money.



OUTLINE

- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements
- VIII. Appendix

Appendix (SIPS)

Garage Activity Productivity Rates							
Schedule Indicator	Activity	Baseline Duration (Days)	Baseline Sequence Zone Area	Productivity (SF/Man/Day)	SIPS Subzone Area (SF)	# of Workers (Baseline)	# of Workers (SIPS)
A	Layout	5	99,000 SF	9900	8250	2	2
B	Curbs	20	99,000 SF	413	8250	12	20
C	CMU Walls	20	99,000 SF	620	8250	8	14
D	Doors & Hardware	5	99,000 SF	9900	8250	2	2
	Railings	10	99,000 SF	3300	8250	3	3
E	Mech Rough In	10	99,000 SF	2475	8250	4	4
	Electrical Rough In	10	99,000 SF	1650	8250	6	6
F	Plumbing Rough In	20	99,000 SF	495	8250	10	17
G	Sprinkler Rough In	30	99,000 SF	825	8250	8	10
H	Remove Reshores	3	99,000 SF	8250	8250	4	4
	Paint Walls and Ceilings	15	99,000 SF	660	8250	10	13
I	Traffic Coating	24	99,000 SF	1094	8250	8	8
J	Light Fixtures	20	99,000 SF	825	8250	6	10
K	Pavement Markings	5	99,000 SF	3300	8250	6	6

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Level	Subzone	14-Feb	15-Feb	16-Feb	17-Feb	20-Feb	21-Feb	22-Feb	23-Feb	24-Feb	27-Feb	28-Feb	29-Feb	1-Mar	2-Mar	5-Mar	6-Mar	7-Mar	8-Mar	9-Mar	12-Mar	13-Mar	14-Mar	15-Mar	16-Mar	19-Mar	20-Mar	21-Mar	22-Mar	23-Mar	26-Mar	27-Mar	28-Mar	29-Mar	30-Mar					
G7	1A	A	B	C	D	E	F	G	H	Crew 1				J	K																									
G7	1B		A	B	C	D	E	F	G	H	Crew 2				J	K																								
G7	1C			A	B	C	D	E	F	G	H	Crew 3				J	K																							
G7	1D				A	B	C	D	E	F	G	H	Crew 4				J	K																						
G7	1E					A	B	C	D	E	F	G	H	Crew 1				J	K																					
G7	1F						A	B	C	D	E	F	G	H	I	I	I	I	J	K																				
G7	2A							A	B	C	D	E	F	G	H	I	I	I	I	J	K																			
G7	2B								A	B	C	D	E	F	G	H	I	I	I	I	J	K																		
G7	2C									A	B	C	D	E	F	G	H	I	I	I	I	J	K																	
G7	2D										A	B	C	D	E	F	G	H	I	I	I	I	J	K																
G7	2E											A	B	C	D	E	F	G	H	I	I	I	I	J	K															
G7	2F												A	B	C	D	E	F	G	H	I	I	I	I	J	K														
G6	1A													A	B	C	D	E	F	G	H	I	I	I	I	J	K													
G6	1B														A	B	C	D	E	F	G	H	I	I	I	I	J	K												
G6	1C															A	B	C	D	E	F	G	H	I	I	I	I	J	K											
G6	1D																A	B	C	D	E	F	G	H	I	I	I	I	J	K										
G6	1E																	A	B	C	D	E	F	G	H	I	I	I	I	J	K									
G6	1F																		A	B	C	D	E	F	G	H	I	I	I	I	J	K								
G6	2A																			A	B	C	D	E	F	G	H	I	I	I	I	J	K							
G6	2B																				A	B	C	D	E	F	G	H	I	I	I	I	J	K						
G6	2C																					A	B	C	D	E	F	G	H	I	I	I	I	J	K					
G6	2D																						A	B	C	D	E	F	G	H	I	I	I	I	J	K				
G6	2E																							A	B	C	D	E	F	G	H	I	I	I	I	J	K			
G6	2F																								A	B	C	D	E	F	G	H	I	I	I	I	J	K		

OUTLINE





- I. Project Overview
- II. Analysis #1: Public-Private Partnerships
- III. Analysis #2: Bonded Warehouses
- IV. Analysis #3: SIPS Scheduling
- V. Analysis #4: Mechanical Chases
- VI. Summary and Conclusions
- VII. Acknowledgements
- VIII. Appendix

Reston Station Phase 1 Garage

Reston, Virginia

Jon Fisher | Construction Management

Appendix (SIPS)



OUTLINE

Appendix (Mechanical Chases)

Apartment 4														
Floor	Area	Classification	Area/Occupant (SF)	Studios	1 BR	2 BR	3BR	Water Closets	Lavatories	Showers	Sinks	Dishwashers	Clotheswashers	Service Sink
P1	2700	Assembly	10					8	6					1
	7600	Residential	200	2	3	2		9	9	9	7	7	7	1
	1600	Bussiness	150					2	2					1
P2	10600	Residential	200	2	3	2		9	9	9	7	7	7	1
P3	18150	Residential	200	5	9	3		20	20	20	17	17	17	1
P4	18100	Residential	200	5	9	3		20	20	20	17	17	17	1
P5	17850	Residential	200	5	9	3		20	20	20	17	17	17	1
P6	17850	Residential	200	5	9	3		20	20	20	17	17	17	1
P7	17800	Residential	200	6	8	3		20	20	20	17	17	17	1
P8	17800	Residential	200	6	8	3		20	20	20	17	17	17	1
R9	17800	Residential	200	8	14	8		38	38	38	30	30	30	1
R10	29000	Residential	200	8	14	7		36	36	36	29	29	29	1
R11	29000	Residential	200	5	14	9		37	37	37	28	28	28	1
R12	29000	Residential	200	7	14	9		39	39	39	30	30	30	1
R13	29000	Residential	200	7	14	9		39	39	39	30	30	30	1
R14	29000	Residential	200	7	14	9		39	39	39	30	30	30	1
R15	29000	Residential	200	7	14	9		39	39	39	30	30	30	1
R16	29000	Residential	200	7	14	9		39	39	39	30	30	30	1
R17	28000	Residential	200	7	14	9		39	39	39	30	30	30	1
R18	28000	Residential	200	7	14	9		39	39	39	30	30	30	1
R19	25000	Residential	200		2	7	5	31	41	26	14	14	14	1
R19	25000	Residential	200		2	7	5	31	41	26	14	14	14	1
Total Fixtures								594	612	574	441	441	441	22
dfu's								1782	612	1148	882	882	882	44
Building dfu's								6232						

Office Building 1								
Floor	Area	Classification	Area/Occupant (SF)	# of Occupants	Public Water Closets	Urinals	Lavatories	Service Sink
L1	7700	Mercantile	66	117	2	2	2	1
L2	12900	Bussiness	150	86	4	3	4	1
L3	16600	Bussiness	150	111	6	4	4	1
L4	17150	Bussiness	150	114	6	4	4	1
L5	17690	Bussiness	150	118	6	4	4	1
L6	23470	Bussiness	150	156	6	4	4	1
L7	24000	Bussiness	150	160	6	4	4	1
L8	24600	Bussiness	150	164	6	4	6	1
L9	25000	Bussiness	150	167	6	4	6	1
L10	25600	Bussiness	150	171	6	4	6	1
L11	26100	Bussiness	150	174	6	4	6	1
L12	26600	Bussiness	150	177	6	4	6	1
L13	27200	Bussiness	150	181	6	4	6	1
L14	27700	Bussiness	150	185	6	4	6	1
L15	28400	Bussiness	150	189	6	4	6	1
Total Fixtures					84	57	74	15
dfu's					336	28.5	74	30
Building dfu's					468.5			

Office Building 2								
Floor	Area	Classification	Area/Occupant (SF)	# of Occupants	Public Water Closets	Urinals	Lavatories	Service Sink
L1	14000	Mercantile	66	212	2	2	2	1
L10	25720	Bussiness	150	171	6	4	6	1
L11	26150	Bussiness	150	174	6	4	6	1
L12	26535	Bussiness	150	177	6	4	6	1
L13	38070	Bussiness	150	254	8	6	6	1
L14	38500	Bussiness	150	257	8	6	6	1
L15	38900	Bussiness	150	259	8	6	6	1
Total Fixtures					44	32	38	7
dfu's					176	16	38	14
Building dfu's					244			

Office Building 3								
Floor	Area	Classification	Area/Occupant (SF)	# of Occupants	# Water Closets	Urinals	# Lavatories	Service Sink
L1	7000	Mercantile	66	106	2	2	2	1
L10	25600	Assembly (A-4)	25	1024	20	12	7	1
L11	26100	Assembly (A-4)	25	1044	20	12	7	1
Total Fixtures					42	26	16	3
dfu's					167	13	16	6
Building dfu's					202			

Hotel 5								
Floor	Area	Classification	Area/Occupant (SF)	Hotel Rooms	Water Closets	Lavatories	Showers	Service Sink
P1	15000	Assembly	25		12	8	0	1
P2	15000	Residential	200	20	20	20	20	1
P3	15000	Residential	200	20	20	20	20	1
P4	15000	Residential	200	20	20	20	20	1
P5	15000	Residential	200	20	20	20	20	1
P6	15000	Residential	200	20	20	20	20	1
P7	15000	Residential	200	20	20	20	20	1
P8	15000	Residential	200	20	20	20	20	1
P9	15000	Residential	200	20	20	20	20	1
P10	15000	Residential	200	20	20	20	20	1
P11	15000	Residential	200	20	20	20	20	1
Total Fixtures					212	208	200	11
dfu's					848	208	400	22
Building dfu's					1478			