

GEISINGER GRAY'S WOODS AMBULATORY CARE CAMPUS - PHASE II



**Rendering of front view supplied by Alexander Building Construction with Owner Permission

PENN STATE AE
SENIOR CAPSTONE
PROJECT

GEORGE M. ANDONIE

CONSTRUCTION OPTION

ADVISOR: ROB LEICHT

APRIL 16TH, 2014

PENNSTATE





PRESENTATION OUTLINE:

I. INTRODUCTION

II. PROJECT OVERVIEW

III. ANALYSIS #1: VIRTUAL MOCKUPS

IV. ANALYSIS #2: FAÇADE PREFABRICATION

V. ANALYSIS #3: REVALUATING COMP. SLAB

VI. FINAL RECOMMENDATIONS

VII. ACKNOWLEDGEMENTS

PROJECT OVERVIEW




ANALYSIS 1 | VIRTUAL MOCKUP IMPLEMENTATION



ANALYSIS 2 | BRICK FAÇADE PREFABRICATION



ANALYSIS 3 | RE-VALUATING COMPOSITE SLAB






PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
 - PROJECT BACKGROUND
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

■ Building Functions:

- Outpatient Surgery Center
- Houses 70 Exam Rooms, 4 Operating Rooms, 4 Endoscopy Suites & 2 Main Therapy Rooms
- Phase 1: 2007-2008
- Phase 2 :2012-2014




General Building Information	
Building Name	Grays Woods Ambulatory Care Campus
Location	Port Matilda, PA
Function	Outpatient Surgery Center
Size	77,560 GSF
Height	2 Stories (48' Total Height)
Cost	\$26.3 Million GMP
Construction	July '12 - February '14
Delivery	Design-Bid-Build
LEED	LEED Certified

■ Project Team:

Legend:

- Guaranteed Maximum Price (GMP)
- Cost + Fee Contract
- Lump Sum
- Communication
- Other Contracts





PRESENTATION OUTLINE:

I. INTRODUCTION

II. PROJECT OVERVIEW

III. ANALYSIS #1: VIRTUAL MOCKUPS

PROBLEM IDENTIFICATION

VIRTUAL MOCKUP DEVELOPMENT

VIRTUAL MOCKUP APPLICATION

IMPLEMENTATION & RECOMMENDATION

IV. ANALYSIS #2: FAÇADE PREFABRICATION

V. ANALYSIS #3: REVALUATING COMP. SLAB

VI. FINAL RECOMMENDATIONS

VII. ACKNOWLEDGEMENTS

Analysis #1
**Implementing Virtual Mockups on
Operating & Endoscopy Rooms**

IN-PLACE MOCKUP PROCESS



PRESENTATION OUTLINE:


- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS**
 - PROBLEM IDENTIFICATION**
 - VIRTUAL MOCKUP DEVELOPMENT
 - VIRTUAL MOCKUP APPLICATION
 - IMPLEMENTATION & RECOMMENDATION
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

■ Problem Identification:

- 8-week Mock-Up Process
- Low Level of Detail (LOD)
- Waste Generation
- Costly & Time Consuming Process
- Obstruction to Schedule
- Risk of Delays

■ Current Schedule:

Task Name	Duration	Start	Finish
1 Interior Work for Operating/Endoscopy Rooms	115 days	Thu 3/28/13	Wed 9/4/13
2 Partition Framing	24 days	Thu 3/28/13	Tue 4/30/13
3 MEP Rough-in	20 days	Tue 4/2/13	Mon 4/29/13
4 O.R. Light/Boom Support Steel	14 days	Tue 4/2/13	Fri 4/19/13
5 Sheetrock Installation, Finish, Paint	5 days	Mon 4/15/13	Fri 4/19/13
6 Drywall Ceiling	5 days	Fri 6/28/13	Thu 7/4/13
7 Install & Hookup Surgical Scrub/Sinks	5 days	Mon 7/15/13	Fri 7/19/13
8 Light Fixtures	5 days	Mon 8/5/13	Fri 8/9/13
9 Install Grills/Registrers/Diffusers	5 days	Mon 8/5/13	Fri 8/9/13
10 Pull Wire/Terminate - Branch Power & Lighting	4 days	Mon 8/26/13	Thu 8/29/13
11 Device Installation - Fire Alarm, Nurse Call, PA, CATV, V&D	4 days	Mon 8/26/13	Thu 8/29/13
12 MEP Trim-Out	3 days	Mon 9/2/13	Wed 9/4/13



■ Proposed Solution:

- Virtual Mockups for Design Reviews

■ Research Goal:

- Develop Virtual Mockup for Operating & Endoscopy Rooms
- Capture Efforts, Criteria & Workflow
- Schedule Analysis Implementation

VIRTUAL MOCKUP DEVELOPMENT




PRESENTATION OUTLINE:


- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
 - PROBLEM IDENTIFICATION
 - VIRTUAL MOCKUP DEVELOPMENT
 - VIRTUAL MOCKUP APPLICATION
 - IMPLEMENTATION & RECOMMENDATION
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REEVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Development Process:


1. Autodesk Revit:
 - Model Building Space
 - Model MEP Systems
 - Model Equipment & Casework
 - Populate & Arrange
2. 3ds Max:
 - Material Placement
 - Scale Adjustment
3. Unity Game Engine:
 - Scripting Model Interaction




EWING COLE



AUTODESK REVIT



unity



VIRTUAL MODEL APPLICATION




PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS**
 - PROBLEM IDENTIFICATION
 - VIRTUAL MOCKUP DEVELOPMENT
 - VIRTUAL MOCKUP APPLICATION**
 - IMPLEMENTATION & RECOMMENDATION
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Model Application:

1. Model Walkthrough:
 - First Person Controller (FPC)
 - Computer/Iconn Lab
2. Design Review:
 - Functionality & Room Layout
 - Check Clearances
 - Equipment/Casework Location
 - Mounting heights
 - General Appearance
3. Provide Feedback:
 - Online Survey Completion


Welcome Menu:



Operating Room Design Review:



Feedback Survey



Endoscopy Room Design Review:





PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS**
 - PROBLEM IDENTIFICATION
 - VIRTUAL MOCKUP DEVELOPMENT
 - VIRTUAL MOCKUP APPLICATION
- IMPLEMENTATION & RECOMMENDATION**
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Time Requirements:


Time Requirement	
Step Description	Duration (Hrs.)
1. Obtained Existing Revit Model	-
2. Combine Architectural & MEP Revit Models	2
3. Strip Out Revit Model	0.5
4. Model all Owner Furnished Equipment	8
5. Export Model to 3Ds Max	1
6. Export Model to Unity	1
7. Develop Scripting and Textures in Unity	8
Total	20.5 Hrs

Cost Implications:

Cost Summary			
Item Description	Mhrs	Hourly Wage	Total Cost
Develop & Modify Model	23	\$35/hr	\$805
Design-Review Meetings (GC)	50	\$65/hr	\$3,250
Total			\$4,055

*Costs taken from RS Means 2013

Schedule Implications:



Source: Maing, M. (2012) Physical or Virtual

- Design Phase: Implement Early
 - Design-Review meetings between project participants & end users
 - Changes can be costly to implement later in the project lifecycle
- Construction Phase: Visual communication of built space

Recommendation:

- Implement Virtual Mockups for Operating & Endoscopy Rooms

Potential Value Added:

- Streamlining the design and construction process
- Subcontractor & end user feedback
- Reduce project waste (time & cost)
- Strong visualization/communication tool
- Ensuring the end product meets owner's needs
- No disturbance to project schedule



PRESENTATION OUTLINE:

I. INTRODUCTION

II. PROJECT OVERVIEW

III. ANALYSIS #1: VIRTUAL MOCKUPS

IV. ANALYSIS #2: FAÇADE PREFABRICATION

CURRENT VS. PREFABRICATED FAÇADE

PANEL DESIGN

MECHANICAL BREADTH ANALYSIS

PANEL IMPLEMENTATION

CONCLUSION & RECOMMENDATIONS

V. ANALYSIS #3: REVALUATING COMP. SLAB

VI. FINAL RECOMMENDATIONS

VII. ACKNOWLEDGEMENTS

Analysis #2

Brick Façade Prefabrication

FAÇADE COMPARISON



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION**
 - CURRENT VS. PREFABRICATED FAÇADE
 - PANEL DESIGN
 - MECHANICAL BREADTH ANALYSIS
 - PANEL IMPLEMENTATION
 - CONCLUSION & RECOMMENDATIONS
- V. ANALYSIS #3: REEVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Opportunity Identification:


- Time & Labor Intensive
- Site Congestion
- Weather Delays
- Critical Path

Research Goals:

- Identify alternative panel
- Reduce schedule & cost
- Reduce site congestion & trade coordination on site

Original Façade:


- 4" Brick on Metal Stud
- \$674,000
- 178 Day Construction Duration



*Image Courtesy of www.veneerbricks.com


Proposed Façade:

- 9" Insulated Precast Panel
- Embedded Thin Brick
- Cost = \$25/SF
- Erection = 16 panels/ day



*Image Courtesy of Nitterhouse Concrete

House of Quality:



Interrelationship matrix

Owner Requirements	Design Requirements	Assembly Location (Miles)	Insulation Properties (R-Value)	Impact Resistant (Relative)	Face Material Aesthetic (Relative)	Cost of Panel (\$)	Installation Time (SE/Hr)	Component Weight (Lbs/SF)	Customer Rating (1-6)	Weighted Importance (%)
Exterior Matches Existing			30	270					1	30%
Low Construction Cost	60	20	20	20	180				2	20%
Short Installation Schedule	48					144	48		3	16%
Good Insulation Performance		126					14		4	14%
Durable Wall Exterior		36	108	12					5	12%
Maintenance Free Wall Assemblies		8	24	8					6	8%
Total (Σ Column)	108	190	182	290	200	144	62		1176	
Total (% Column)	9.2	16.2	15.5	24.7	17.0	12.2	5.3		100%	
Existing Wall Performance (Units)	0	25.1	-	-	40.3	103	54			
HighConcrete Performance (Units)	160	20	-	-	38.4	560	100			
NitterHouse Performance (Units)	100	31.2	-	-	48.2	600	87.5			
PBVS Performance (Units)	20	25	-	-	52	300	54			
HighConcrete Panel Ranking	0.6	0.6	0.6	0.6	1	0.8	0.6			814.4
NitterHouse Panel Ranking	0.8	1	0.8	0.8	0.8	1	0.8			1007.6
PBVS Wall Assembly Ranking	1	0.8	1	1	0.6	0.6	1			1000.4

TOTAL VALUE: Σ(Σ Column * Rank)

*Correlation Matrix:
+ Positive Correlation
- Negative Correlation

*Weighting Factors:
⊙ Strong (9)
○ Moderate (3)
△ Weak (1)

*Customer Rating:
6 High, 1 Low

*Panel Rank Weights:
1.0 = Best
0.8 = Second Best
0.6 = Third Best

*Note: Values for panel costs, duration, and weight are relative and are used for performance comparison purposes only.

PANEL DESIGN



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION**
- CURRENT VS. PREFABRICATED FAÇADE
- PANEL DESIGN**
- MECHANICAL BREADTH ANALYSIS
- PANEL IMPLEMENTATION
- CONCLUSION & RECOMMENDATIONS
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

■ Panel Design:

- Consistency & transportation
- Span Building Height (40')
- Maximum width 12'
- Total 74 precast panels
 - 14 different panel widths


Panel Installation Durations			
Façade Orientation	Panel Qty.	Calculated Duration	Adjusted Duration
East Façade	19	1.27 Days	2 Days
South Façade	25	1.67 Days	2 Days
West Façade	22	1.47 Days	2 Days
North Façade	8	0.53 Days	1 Day
Total	74	4.93 Days	7 Days

* Durations taken from Precast Panel Takeoff, and assume productivity of 16 Panels/Day.


East Elevation:




North Elevation:



South Elevation:



West Elevation:





PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION**
 - CURRENT VS. PREFABRICATED FAÇADE
 - PANEL DESIGN
 - MECHANICAL BREADTH ANALYSIS**
 - PANEL IMPLEMENTATION
 - CONCLUSION & RECOMMENDATIONS
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Mechanical Analysis:

- Evaluate Thermal Performance
 - Thermal Property Comparison
 - Energy Performance

Heat Transfer Rate:

$$Q = (U\text{-Value}) * (\text{Area}) * (\Delta T)$$

Annual Heating Fuel Consumption:


$$AHFC = \frac{24 * Q * HDD}{\Delta T_w * HV * HEE}$$

Annual Cooling Energy Consumption:

$$ACEC = \frac{24 * Q * CDD}{\Delta T_s * CV}$$


Heat Loss & Heat Gain Calculations							
Wall Assembly	R - Value	U-Value	Area (SF)	Heat Loss (Winter)		Heat Gain (Summer)	
				ΔT (°F)	BTU/Hr	ΔT (°F)	BTU/Hr
Existing Brick Assembly	25.05	0.03992	17,551	69	48,344	29	20,318
Precast Wall Assembly	31.22	0.03203	17,551	69	38,790	29	16,303
Difference	6.17	0.00789	-		9,554 BTU/hr		4,015 BTU/hr

*R-Values taken from Nitterhouse Manufacturer



Breadth Conclusions:

- Improved Thermal Performance (By 20%)
 - Heat Gain/Loss Reduction
 - Reduced Heating/Cooling Costs
- No condensation in systems
- Potentially Downsize Mechanical System




PANEL IMPLEMENTATION



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION**
 - CURRENT VS. PREFABRICATED FAÇADE
 - PANEL DESIGN
 - MECHANICAL BREADTH ANALYSIS
 - PANEL IMPLEMENTATION**
 - CONCLUSION & RECOMMENDATIONS
- V. ANALYSIS #3: REEVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS


■ Schedule Implications:



Shorten Brick Installation by 96 Days!

Schedule Savings = 3 weeks

■ Site Layout:



PANEL IMPLEMENTATION



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION**
 - CURRENT VS. PREFABRICATED FAÇADE
 - PANEL DESIGN
 - MECHANICAL BREADTH ANALYSIS
 - PANEL IMPLEMENTATION
 - CONCLUSION & RECOMMENDATIONS**
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Cost Implications:

- Implement = Additional \$10/SF
- Interior Components Same
 - Vapor Barrier, Sheathing & Backup
- Cost Changes
 - 2” vs. 4” Insulation
 - Caulking Panel Joints
- General Conditions Savings
 - 21 Days = \$43,663

Building Enclosure Construction Cost Comparison						
Material Description	Total	Unit	Prefabricated Panels		Traditional Brick	
			Cost/SF	Total Cost	Cost/SF	Total Cost
Exterior Face Wall	17,551	SF	\$25.00	\$438,775	\$16.10	\$282,571
Interior Component	17,551	SF	\$19.63	\$344,485	\$19.63	\$344,485
Insulation (2" or 4")	17,551	SF	\$1.37	\$24,045	\$2.68	\$47,037
Caulking	3,360	LF	\$2.16	\$7,258	-	-
Transportation	-	-	Included	Included	-	-
Erection Equipment (Scaffolding or Crane)	-	-	Included	Included	-	\$47,037
Total			\$48.2	\$814,563	\$38.4	\$721,130

Costs provided by Nitterhouse Concrete, RS Means 2013, and Actual Project Costs

Building Enclosure Cost Comparison Summary		
Item Description	Prefabricated Panels Total Cost	Existing Brick Total Cost
Cost of Assembly	\$814,562.69	\$721,130
General Conditions Cost	\$742,260.05	\$785,922
Total	\$1,556,823	\$1,507,052

**Estimated Assembly costs based on RS Means 2013, Nitterhouse Concrete, and Actual Project Costs

Final Conclusions:

- 74 Architectural Precast Panels
- Improve Thermal Performance by 20%
- Schedule Reduction = 21 Days
- Implementation Cost = \$50,000

Recommendation:

- Not in owner’s best interest to pursue
 - Increased cost and planning for implementation outweigh savings in schedule and building performance



PRESENTATION OUTLINE:

I. INTRODUCTION

II. PROJECT OVERVIEW

III. ANALYSIS #1: VIRTUAL MOCKUPS

IV. ANALYSIS #2: FAÇADE PREFABRICATION

V. ANALYSIS #3: REVALUATING COMP. SLAB

PROBLEM IDENTIFICATION

STRUCTURAL BREADTH ANALYSIS

PROJECT IMPACTS & RECOMMENDATIONS

VI. FINAL RECOMMENDATIONS

VII. ACKNOWLEDGEMENTS

Analysis #3

Re-evaluation of Structural Composite Slab

EXISTING CONDITIONS



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REEVALUATING COMP. SLAB**
- PROBLEM IDENTIFICATION**
- STRUCTURAL BREADTH ANALYSIS
- PROJECT IMPACTS & RECOMMENDATIONS
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

■ **Opportunity Identification:**

- Vale Engineering on Structural System (20% of Building Costs)
 - Reduce Overall Building Costs

■ **Proposed Solution:**


- Change Lightweight Composite Deck to Normal Concrete
 - NW = Lower Material Cost

■ **Research Goal:**


- Reduce building costs
- Improve building performance

■ **Existing Conditions:**

- 38,000 SF of Composite Floor
- 3 ¼” Lightweight Concrete
- 2” Composite Metal Decking (18-Gauge)
- Typical 30’ x 30’ Bays (40)



Current Typical Bay (LW Concrete)



STRUCTURAL BREADTH




PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB**
 - PROBLEM IDENTIFICATION
 - STRUCTURAL BREADTH ANALYSIS**
 - PROJECT IMPACTS & RECOMMENDATIONS
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

Structural Calculations:


- Determine NW Deck Assembly
- Check Beam Sizing
- Check Girder Sizing
- Check Column Sizing
- Check Footing Sizing



Source: Vulcraft Decking Catalog

**CURRENT TYPICAL BAY
(LIGHTWEIGHT CONCRETE)**

Existing LW Design	
Item Description	Size
LW Concrete Material	3.25"
Concrete Placing	<6"
Concrete Reinforcing	6x6 W1.4xW1.4
Floor Decking	2VLI18
Shear Studs	½" Diameter
Steel Beams (4)	W18x35
Steel Girders (2)	W24x62
Steel Columns (2)	W10x49
Additional Fireproofing	-




**PROPOSED TYPICAL BAY DESIGN
(NORMAL CONCRETE)**

Proposed NW Design	
Item Description	Size
NW Concrete Material	4.5"
Concrete Placing	<6"
Concrete Reinforcing	6x6 W2.1xW2.1
Floor Decking	2VLI18
Shear Studs	½" Diameter
Steel Beams (4)	W18x35
Steel Girders (2)	W24x68
Steel Columns (2)	W10x49
Additional Fireproofing	-

Breadth Conclusions:

- 4 ½" NW Composite Deck
 - Increase Reinforcement
- Beam Spacing and Size
- Girder Sizes Increase to W24x68
 - 360lbs of Steel/Bay
- Column and Footing Sizes Acceptable
- Member Quantity Constant
- No Additional Fireproofing



Proposed Typical Bay (NW Concrete)

PROJECT IMPACTS



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB**
- PROBLEM IDENTIFICATION
- STRUCTURAL BREADTH ANALYSIS
- PROJECT IMPACTS & RECOMMENDATIONS**
- VI. FINAL RECOMMENDATIONS
- VII. ACKNOWLEDGEMENTS

■ **Construction Implications:**

1. Floor-to-floor height:
 - Loose 1.25” per floor
 - Absorbed by ceiling plenum
2. Beam Deflections:
 - Impact on building’s serviceability
 - Addressed in Structural Analysis
3. Improved Quality Control:
 - Moisture Content
 - Fireproofing

■ **Cost Implications:**

Overall Cost Comparison			
Item Description	System A: Proposed NW	System B: Existing LW	Cost Ratio (A/B)
Concrete Material & Placing	\$85,068.00	\$80,643.60	1.05
Concrete Reinforcing	\$15,480.00	\$12,960.00	1.19
Composite Metal Decking	\$136,440.00	\$136,440.00	1.00
Headed Shear Stud Connectors	\$22,080.00	\$22,080.00	1.00
Structural Steel Framing	\$713,904.00	\$693,504.00	1.03
Additional Fireproofing	-	-	-
TOTAL	\$972,972	\$945,627	1.03

Costs taken from 30x30' Typical Bay Detailed Estimate (Assuming 40 Bays)

- Implementing change increases system cost by 3%
 - Concrete costs still increased
 - Largest % Increase = Reinforcement
 - Metal Decking & Studs Constant

■ **Final Conclusions:**

- Initial Goal = Reduce Project Costs
 - Escalate Costs by \$27,344
 - Upsize Girders (Additional 7.2 Tons of Steel)
- Revised Goal = Improve Building Performance
 - Vibration, Moisture, & Fireproofing

■ **Recommend Change:**

- Improved Quality Control
- Reduce Risks of Escalating Project Cost & Schedule
 - Could have saved project over \$100,000



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REEVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS**
- VII. ACKNOWLEDGEMENTS

- IMPROVE EFFICIENCY** ✓
- INCREASED COLLABORATION** ✓
- STREAMLINE PROCESS** ✓
- REDUCE RISK** ✓ ✓
- REDUCE COST** ✗
- REDUCE SCHEDULE** ✗
- IMPROVE QUALITY CONTROL** ✓

ANALYSIS 1 | VIRTUAL MOCKUP IMPLEMENTATION:

- Implement Virtual Mockups for the facility's Operating & Endoscopy Rooms
 - Save Cost
 - Save Time
 - Reduce Risk
 - Solve Constructability Issues

ANALYSIS 2 | BRICK FAÇADE PREFABRICATION

- Would not recommend the prefabrication of the building's facade
 - Increased Cost & Planning
 - Reduced Schedule & Building Performance

ANALYSIS 3 | REEVALUATING COMPOSITE SLAB

- Recommend Changing from LW to NW Composite Slab
 - Increased Cost
 - Improved Quality Control (Reduce Risk)

ACKNOWLEDGEMENTS



PRESENTATION OUTLINE:

- I. INTRODUCTION
- II. PROJECT OVERVIEW
- III. ANALYSIS #1: VIRTUAL MOCKUPS
- IV. ANALYSIS #2: FAÇADE PREFABRICATION
- V. ANALYSIS #3: REVALUATING COMP. SLAB
- VI. FINAL RECOMMENDATIONS

VII. ACKNOWLEDGEMENTS

Architectural Engineering Faculty:

Dr. Rob Leicht (Advisor)

Dr. John Messner

Dr. Ali Memari



Special Thanks to:

My Family & Friends

Geisinger Health Systems

Douglas Workman, Josh Progar & Alexander's Project Team

Mathew Hoerner - Alexander Building Construction

Ray Sowers & Ed Gannon - Penn State's OPP

Mark Taylor - Nitterhouse Concrete

Sonali Kumar - Balfour Resource Group

George Burnley - High Concrete Group

PACE Industry Members

Industry Acknowledgements:

ALEXANDER

A BUTZ FAMILY COMPANY



**EWING
COLE**

GEISINGER
REDEFINING BOUNDARIES™

THANK YOU




**Rendering courtesy of Alexander Building Construction with Owner Permission

Questions & Comments



**Rendering courtesy of Alexander Building Construction with Owner Permission

APPENDIX 1A



APPENDIX 2A

GEISINGER GRAYS WOODS AMBULATORY CARE CAMPUS - PHASE II



Interrelationship matrix

Design Requirements	Assembly Location (Miles)	Insulation Properties (R-Value)	Impact Resistant (Relative)	Face Material Aesthetic (Relative)	Cost of Panel (\$)	Installation Time (SF/HR)	Component Weight (Lbs/SF)	Customer Rating (1-6)	Weighted Importance (%)
Exterior Matches Existing		30	270					1	30%
Low Construction Cost	60	20	20	20	180			2	20%
Short Installation Schedule						144	48	3	16%
Good Insulation Performance		126					14	4	14%
Durable Wall Exterior								5	12%
Maintenance Free Wall Assemblies	8	24		8				6	8%
Total (Σ Column)	108	190	182	290	200	144	62		1176
Total (% Column)	9.2	16.2	15.5	24.7	17.0	12.2	5.3		100%
Existing Wall Performance (Units)	0	25.1	-	-	40.3	103	54		
HighConcrete Performance (Units)	160	20	-	38.4	560	100			
NitterHouse Performance (Units)	100	31.2	-	48.2	600	87.5			
PBVS Performance (Units)	20	25	-	52	300	54			
HighConcrete Panel Ranking	0.6	0.6	0.6	1	0.8	0.6			814.4
NitterHouse Panel Ranking	0.8	1	0.8	0.8	0.8	1			1007.6
PBVS Wall Assembly Ranking	1	0.8	1	1	0.6	0.6			1000.4

***Correlation Matrix:**
+ Positive Correlation
- Negative Correlation

***Weighting Factors:**
● Strong (9)
○ Moderate (3)
△ Weak (1)

***Customer Rating:**
6 High, 1 Low

***Panel Rank Weights:**
1.0 = Best
0.8 = Second Best
0.6 = Third Best


TOTAL VALUE:
Σ (Σ Column * Rank)

***Note:** Values for panel costs, duration, and weight are relative and are used for performance comparison purposes only.

Precast Panel Takeoffs

Panel Orientation	Panel Designation	Panel Width (Ft.)	Panel Height (Ft.)	Openings (Qty. & Type)	Total Opening Area (SF)	Joint Sealant (LF)	East Façade	South Façade	West Façade	North Façade	Total Quantity	Total Panel Area (SF)	Average Cost/SF	Total Cost	
VERTICAL	A-1	2.5	10.5	-	0	26	-	-	1	-	1	26.25	\$25.00	\$656.25	
	B-1	5	31.72	-	0	73.44	1	-	-	-	1	158.6	\$25.00	\$3,965.00	
	B-2	5	41.7	-	0	93.4	-	-	-	1	1	208.5	\$25.00	\$5,212.50	
	C-1	7.25	30	-	0	74.5	-	-	3	-	3	652.5	\$25.00	\$16,312.50	
	D-1	7.5	30	1 x W5	33	75	3	-	-	-	3	576	\$25.00	\$14,400.00	
	D-2	7.5	21.85	1 x W5	33	58.7	1	-	-	-	-	130.875	\$25.00	\$3,271.88	
	E-1	8	15	1 x W4	20.5	46	-	1	-	-	-	99.5	\$25.00	\$2,487.50	
	E-2	8	9.77	1 x D1	55.66	35.54	-	1	-	-	-	22.5	\$25.00	\$562.50	
	E-3	8	30	1 x W5	33	76	-	1	-	-	-	1	207	\$25.00	\$5,175.00
	F-1	9	30	1 x W6	26	78	2	-	-	-	-	2	488	\$25.00	\$12,200.00
	F-2	9	30	2 x W1	25.6	78	-	-	1	-	-	1	244.4	\$25.00	\$6,110.00
	F-3	9	30	1 x W7	14	78	-	6	-	-	-	6	1536	\$25.00	\$38,400.00
	G-1	9.25	30	-	0	78.5	-	-	2	-	-	2	555	\$25.00	\$13,875.00
	G-2	9.25	30	2 x W1	25.6	78.5	-	-	2	-	-	2	503.8	\$25.00	\$12,595.00
	G-3	9.25	30	1 x W7	14	78.5	-	1	-	-	-	1	263.5	\$25.00	\$6,587.50
	H-1	10	30	2 x W1	25.6	80	-	-	1	-	-	1	274.4	\$25.00	\$6,860.00
	H-2	10	30	2 x W5	66	80	-	-	3	-	-	3	702	\$25.00	\$17,550.00
	H-3	10	30	1 x W5	33	80	-	1	-	-	-	1	267	\$25.00	\$6,675.00
	H-4	10	30	1 x W6	26	80	3	-	-	-	-	3	822	\$25.00	\$20,550.00
	H-5	10	27	-	0	74	-	1	-	-	-	1	270	\$25.00	\$6,750.00
H-6	10	9.77	-	0	39.54	-	1	-	-	-	1	97.7	\$25.00	\$2,442.50	
I-1	10.5	30	-	0	81	-	-	1	-	-	1	315	\$25.00	\$7,875.00	
I-2	10.5	30	1 x W5	33	81	-	1	-	-	-	1	282	\$25.00	\$7,050.00	
J-1	11	13.6	-	0	49.2	-	-	1	-	-	1	149.6	\$25.00	\$3,740.00	
J-2	11	30	1 x W6	26	82	1	-	-	-	-	1	304	\$25.00	\$7,600.00	
K-1	11.2	30	2 x W1	25.6	82.4	-	-	2	-	-	2	620.8	\$25.00	\$15,520.00	
L-1	11.5	30	-	0	83	-	-	1	-	-	1	345	\$25.00	\$8,625.00	
L-2	11.5	30	2 x W5	66	83	-	-	1	-	-	1	279	\$25.00	\$6,975.00	
M-1	11.7	30	-	0	83.4	-	2	1	-	-	3	1053	\$25.00	\$26,325.00	
M-2	11.7	30	L1, L2	22	83.4	-	1	-	-	-	1	329	\$25.00	\$8,225.00	
M-3	11.7	30	L3, L4	12	83.4	-	1	-	-	-	1	339	\$25.00	\$8,475.00	
M-4	11.7	30	1 x L5	11	83.4	-	2	-	-	-	2	680	\$25.00	\$17,000.00	
M-5	11.7	30	1 x W1	12.8	83.4	-	1	-	-	-	1	338.2	\$25.00	\$8,455.00	
N-1	12	30	-	0	84	1	-	-	-	-	1	360	\$25.00	\$9,000.00	
N-2	12	30	2 x W3	51.2	84	1	-	-	-	-	1	308.8	\$25.00	\$7,720.00	
N-3	12	30	1 x W5	33	84	1	3	-	-	-	4	1308	\$25.00	\$32,700.00	
N-4	12	30	1 x W6	26	84	2	-	-	-	-	2	668	\$25.00	\$16,700.00	
N-5	12	40	-	0	104	-	1	-	-	-	1	480	\$25.00	\$12,000.00	
HORIZONTAL	O-1	13.3	2.5	-	0	31.6	-	-	1	1	1	33.25	\$25.00	\$831.25	
	P-1	30	3.25	-	0	66.5	-	-	2	2	2	195	\$25.00	\$4,875.00	
	Q-1	16	4	-	0	40	1	-	-	-	1	64	\$25.00	\$1,600.00	
	R-1	19	4	-	0	46	-	-	1	1	1	76	\$25.00	\$1,900.00	
	S-1	21.25	4	-	0	50.5	-	-	1	1	1	85	\$25.00	\$2,125.00	
	T-1	30	4	-	0	68	-	-	2	2	2	240	\$25.00	\$6,000.00	
	U-1	23.62	10	-	0	67.24	1	-	-	-	1	236.2	\$25.00	\$5,905.00	
	V-1	10.65	10	-	0	41.3	1	-	-	-	1	106.5	\$25.00	\$2,662.50	
	W-1	5.54	-	-	0	32.9	-	-	1	-	-	1	57.9	\$25.00	\$1,447.50
	X-1	15.56	-	-	0	56.1	-	-	1	-	-	1	192.5	\$25.00	\$4,812.50
TOTAL						3,360 LF	19	25	22	8	74	17,551 SF	\$25.00	\$438,782	
*Anticipated Schedule Durations (Days)							1.19	1.56	1.38	0.50	4.63				
Opening	D1	W1	W3	W4	W5	W6	W7	L1 & L2	L3 & L4	L5					
Area (SF)	55.66	12.8	25.6	20.5	33	26	14	11	6	11					

*Costs and Productivity Rates provided by Nitterhouse Concrete
- Quantity Takeoffs taken from.....
*Assuming Productivity of 15 Panels/Day




APPENDIX 2B



CONDENSATION ANALYSIS

The Heat, Air and Moisture Building Science Toolbox - V.1B-EU (11a)



PROJECT			
Name	Geisinger Grays Woods		
Number	001		
City	Port Matilda, PA		
Date	2/20/2014		
Analysis by:	George Andonie		
Wall Type	<input type="checkbox"/>	Option	<input type="checkbox"/>


CLIMATIC CONDITIONS				
	Winter		Summer	
Temp (°F)	Int. 70	Ext. 1	Int. -	Ext. -
RH (%)	25	67	-	-
DPT (°F)	33	-6	-	-

PENNSYLVANIA STATE UNIVERSITY
104 ENGINEERING, UNIT A
UNIVERSITY PARK, PA, USA, 16802

Material	Manufacturer	Model No.	Rvap (1/M)	Temp (°F)	VapSat (in.Hg)	VapCont (in.Hg)
1	air film (ext), 3/4 in.	No Recor...	0.001	1.4	0.041	0.027
2	brick, facing, 1/2 in.	No Recor...	0.358	1.6	0.041	0.028
3	concrete wall, 4 in.	No Recor...	1.430	2.9	0.044	0.036
4	ureth.(int.) insul., 2 in.	No Recor...	2.861	30.4	0.168	0.051
5	concrete wall, 4 in.	No Recor...	1.430	31.7	0.178	0.058
6	cavity, 2 in.	No Recor...	0.016	33.9	0.195	0.058
7	semi-rigid ins., 2 in.	No Recor...	0.029	49.8	0.360	0.058
8	membrane (#1), .080 in.	No Recor...	21.190	49.9	0.362	0.168
9	plywood shgt., 1/2 in.	No Recor...	1.054	51.3	0.381	0.173
10	framing, 2x6s, 6 in.	No Recor...	2.043	67.6	0.680	0.184
11	gypsum bd., 5/8 in., (#1)	No Recor...	0.229	68.6	0.705	0.185
12	air film (int), 3/4 in.	No Recor...	0.006	70.0	0.740	0.185
TOTAL (or 1 layer 0)			30.774	(1.0)	(0.040)	(0.027)

CONDENSATION ANALYSIS

The Heat, Air and Moisture Building Science Toolbox - V.1B-EU (11a)



PROJECT			
Name	Geisinger Grays Woods		
Number	001		
City	Port Matilda, PA		
Date	2/20/2014		
Analysis by:	George Andonie		
Wall Type	<input type="checkbox"/>	Option	<input type="checkbox"/>

CLIMATIC CONDITIONS				
	Winter		Summer	
Temp (°F)	Int. 70	Ext. 1	Int. -	Ext. -
RH (%)	25	67	-	-
DPT (°F)	33	-6	-	-

PENNSYLVANIA STATE UNIVERSITY
104 ENGINEERING, UNIT A
UNIVERSITY PARK, PA, USA, 16802

Material	Manufacturer	Model No.	Rvap (1/M)	Temp (°F)	VapSat (in.Hg)	VapCont (in.Hg)
1	air film (ext), 3/4 in.	No Recor...	0.001	1.5	0.041	0.027
2	brick (TTW), 4 in.	No Recor...	1.430	3.2	0.045	0.035
3	cavity, 2 in.	No Recor...	0.016	5.9	0.051	0.035
4	semi-rigid ins., 4 in.	No Recor...	0.057	45.0	0.301	0.036
5	membrane (#1), .080 in.	No Recor...	21.190	45.2	0.303	0.165
6	plywood shgt., 1/2 in.	No Recor...	1.054	47.0	0.324	0.171
7	framing, 2x6s, 6 in.	No Recor...	2.043	67.0	0.667	0.184
8	gypsum bd., 5/8 in., (#1)	No Recor...	0.229	68.3	0.697	0.185
9	air film (int), 3/4 in.	No Recor...	0.006	70.0	0.740	0.185
TOTAL (or 1 layer 0)			26.135	(1.0)	(0.040)	(0.027)

Prefabricated Brick Wall R-Value

Material Component	Thick.	R-Value
R ₀ Outside Air Film	-	0.17
R ₁ Exterior Face Thin Brick	5/8"	0.12
R ₂ Exterior Concrete Wythe	3-3/8"	0.58
R ₃ Insulation (Polyisocyanurate)	2"	13
R ₄ Interior Concrete Wythe	3"	0.23
R ₅ Air Cavity	1-1/2"	0.98
R ₆ Semi-Rigid Insulation	2"	7.12
R ₇ Air Vapor Barrier	-	Negligible
R ₈ Sheathing	1/2"	0.64
R ₉ Cold Formed Metal Stud	6"	7.28
R ₁₀ Gypsum Wall Board	5/8"	0.46
R ₁₁ Inside Air Film	-	0.64
Total	1' 7-5/8"	31.22
U-Value		0.032031

*R-Values taken from Nitterhouse Concrete Manufacturer


Existing Brick Wall R-Value

Material Component	Thick.	R-Value
R ₀ Outside Air Film	-	0.17
R ₁ Exterior Face Brick	3-5/8"	0.64
R ₂ Air Cavity	1-1/2"	0.98
R ₃ Semi-Rigid Insulation	4"	14.24
R ₄ Air Vapor Barrier	-	Negligible
R ₅ Sheathing	1/2"	0.64
R ₆ Cold Formed Metal Stud	6"	7.28
R ₇ Gypsum Wall Board	5/8"	0.46
R ₈ Inside Air Film	-	0.64
Total	1' 4-1/4"	25.05
U-Value		0.03992

*R-Values taken from ASHRAE 2009 Fundamentals (Tables 4 & 7)

R VALUE ANALYSIS

The Heat, Air and Moisture Building Science Toolbox - V.1B-EU (11)



PROJECT			
Name	Geisinger Grays Woods		
Number	001		
City	Port Matilda, PA		
Date	2/20/2014		
Analysis by:	George Andonie		
Wall Type	<input type="checkbox"/>	Option	<input type="checkbox"/>


CLIMATIC CONDITIONS				
	Winter		Summer	
Temp (°F)	Int. 70	Ext. 1	Int. 75	Ext. 104
RH (%)	25	67	50	72
DPT (°F)	33	-6	56	94

PENNSYLVANIA STATE UNIVERSITY
104 ENGINEERING, UNIT A
UNIVERSITY PARK, PA, USA, 16802

Generic Material	Manufacturer	Model No.	Thick (in.)	RVal (R)	W.Temp. (°F)	S.Temp. (°F)
1	air film (ext), 3/4 in.	No Recor...	0.75	0.17	1.5	103.8
2	brick (TTW), 4 in.	No Recor...	4.00	0.64	3.2	103.1
3	cavity, 2 in.	No Recor...	2.00	0.98	5.9	101.9
4	semi-rigid ins., 4 in.	No Recor...	4.00	14.24	45.0	85.5
5	membrane (#1), .080 in.	No Recor...	0.08	0.07	45.2	85.4
6	plywood shgt., 1/2 in.	No Recor...	0.50	0.64	47.0	84.7
7	framing, 2x6s, 6 in.	No Recor...	6.02	7.28	67.0	76.3
8	gypsum bd., 5/8 in., (#1)	No Recor...	0.63	0.46	68.3	75.7
9	air film (int), 3/4 in.	No Recor...	0.75	0.64	70.0	75.0
Total (or 1 layer 0)			17.23	25.11	(1.0)	(104.0)

R VALUE ANALYSIS

The Heat, Air and Moisture Building Science Toolbox - V.1B-EU (11)



PROJECT			
Name	Geisinger Grays Woods		
Number	001		
City	Port Matilda, PA		
Date	2/20/2014		
Analysis by:	George Andonie		
Wall Type	<input type="checkbox"/>	Option	<input type="checkbox"/>

CLIMATIC CONDITIONS				
	Winter		Summer	
Temp (°F)	Int. 70	Ext. 1	Int. 75	Ext. 104
RH (%)	25	67	50	72
DPT (°F)	33	-6	56	94

PENNSYLVANIA STATE UNIVERSITY
104 ENGINEERING, UNIT A
UNIVERSITY PARK, PA, USA, 16802

Generic Material	Manufacturer	Model No.	Thick (in.)	RVal (R)	W.Temp. (°F)	S.Temp. (°F)
1	air film (ext), 3/4 in.	No Recor...	0.75	0.17	1.4	103.8
2	brick, facing, 1/2 in.	No Recor...	0.50	0.12	1.6	103.7
3	concrete wall, 4 in.	No Recor...	4.00	0.58	2.9	103.2
4	ureth.(int.) insul., 2 in.	No Recor...	2.00	12.34	30.4	91.6
5	concrete wall, 4 in.	No Recor...	4.00	0.58	31.7	91.1
6	cavity, 2 in.	No Recor...	2.00	0.98	33.9	90.2
7	semi-rigid ins., 2 in.	No Recor...	2.00	7.12	49.8	83.5
8	membrane (#1), .080 in.	No Recor...	0.08	0.07	49.9	83.4
9	plywood shgt., 1/2 in.	No Recor...	0.50	0.64	51.3	82.8
10	framing, 2x6s, 6 in.	No Recor...	6.02	7.28	67.6	76.0
11	gypsum bd., 5/8 in., (#1)	No Recor...	0.63	0.46	68.6	75.6
12	air film (int), 3/4 in.	No Recor...	0.75	0.64	70.0	75.0
Total (or 1 layer 0)			21.73	30.97	(1.0)	(104.0)

APPENDIX 2C



Annual Heating Fuel Consumption (Winter)			
Variable	Unit	Existing Brick Assembly	Precast Panel Assembly
Heat Loss (Q)	BTU/hr	48,344	38,790
Annual Heating Degree Days (HDD)	°F * # Days	6087	6087
Winter Temperature Difference (ΔT)	°F	69	69
Heating Value of Natural Gas (HV)	BTU/ft ³	1027	1027
Heating Efficiency of Equipment (HEE)	%/100	0.8	0.8
Annual Heating Fuel Consumption	Cubic Feet	124,579	99,959
Average Cost of Natural Gas (PA)	\$ / 1000ft ³	11.67	11.67
Annual Heating Cost (\$)		\$1,617	\$1,297


*Pennsylvania's Average Price of Natural Gas Cost taken from U.S. Energy Information Administration

$$\text{Annual Heating Fuel Consumption (AHFC)} = \frac{24 * Q * \text{HDD}}{\Delta T_w * \text{HV} * \text{HEE}}$$

Annual Cooling Energy Consumption (Summer)				
Variable	Unit	Existing Brick Assembly	Precast Panel Assembly	
Heat Gain (Q)	BTU/hr	20,318	16,303	
Annual Cooling Degree Days (HDD)	°F * # Days	622	622	
Winter Temperature Difference (ΔT)	°F	29	29	
Cooling Value (CV)	BTU/KWh	3415	3415	
Annual Cooling Energy Consumption	KWh	3,063	2,457	
Average Electricity Cost (PA)	\$/KWh	0.0921	0.0921	
Annual Cooling Cost (\$)		\$398	\$319	

*Pennsylvania's Average Electricity Costs taken from U.S. Energy Information Administration

$$\text{Annual Cooling Energy Consumption (ACEC)} = \frac{24 * Q * \text{CDD}}{\Delta T_s * \text{CV}}$$



APPENDIX 3A



VULCRAFT

Table with columns: Restraint Assembly Rating, Type of Protection, Concrete Thickness & Type (1), U.L. Design No. (2,3,4), Classified Deck Type, Unrestrained Beam Rating. Includes rows for 2 Hr, 3 Hr, and 4 Hr ratings with various deck types like 2 1/2\"/>

NOTES: 1. Concrete thickness is thickness of slab above deck. In. 2. Refer to the U.L. "Fire Resistance Directory" for the necessary construction details. 3. Fluted deck finish shall be galvanized.

VULCRAFT

Table 2 VLI: Maximum Sheet Length 42'-0\"/>

STEEL SECTION PROPERTIES

Table with columns: Deck Type, Design Thickness, Deck Weight, Section Properties (I_x, S_x, V_x, F_u, F_y). Includes sub-tables for (N=9.35) NORMAL WEIGHT CONCRETE (145 PCF) and (N=14.15) LIGHTWEIGHT CONCRETE (110 PCF).

VULCRAFT

Table SLAB INFORMATION: Total Slab Depth, Thick. Concrete Volume, Recommended Welded Wire Fabric.

(N=14.15) LIGHTWEIGHT CONCRETE (110 PCF)

Table with columns: TOTAL SLAB DEPTH, DECK TYPE, SDI Max. Unrestrained Clear Span, Superimposed Live Load, P_SIF. Includes sub-tables for (N=9.35) NORMAL WEIGHT CONCRETE (145 PCF) and (N=14.15) LIGHTWEIGHT CONCRETE (110 PCF).

DESIGN OF FLEXURAL MEMBERS

Table 3-2 (continued) W-Shapes Selection by Z_x. Columns: Shape, Z_x, M_p/L_p, phi M_p, M_r/L_r, phi M_r, B F/L_b, phi B F, L_p, L_r, I_x, V_x/L_v, phi V_x. Includes sub-tables for (N=9.35) NORMAL WEIGHT CONCRETE (145 PCF) and (N=14.15) LIGHTWEIGHT CONCRETE (110 PCF).

DESIGN OF FLEXURAL MEMBERS

Table 3-2 (continued) W-Shapes Selection by Z_x. Columns: Shape, Z_x, M_p/L_p, phi M_p, M_r/L_r, phi M_r, B F/L_b, phi B F, L_p, L_r, I_x, V_x/L_v, phi V_x. Includes sub-tables for (N=9.35) NORMAL WEIGHT CONCRETE (145 PCF) and (N=14.15) LIGHTWEIGHT CONCRETE (110 PCF).


DESIGN OF COMPRESSION MEMBERS

Table 4-1 (continued) Available Strength in Axial Compression, kips. Columns: Shape, W10, W10x, Design, ASD, LRFD. Includes sub-tables for (N=9.35) NORMAL WEIGHT CONCRETE (145 PCF) and (N=14.15) LIGHTWEIGHT CONCRETE (110 PCF).

APPENDIX 3B



Calculating Beam Size:




Assumptions:
 Tributary Width: $W_T = 10'$
 Influence Area: $K_{LL} A_T = 20' \times 30'$
 $K_{LL} A_T = 600SF$
 $600SF \geq 400SF$ ∴ Reducible LL
 Live Loads: Hospital = 60psf, Wall Partitions = 20psf

Calculations:
 $LL_D = 80psf + (0.25 + \frac{15}{\sqrt{600}})$
 $LL_D = 80psf + 0.86$
 $LL_D = 69psf$
 $DL = (Comp. Deck) + (Super.) + (Beam)$
 $DL = 69psf + 10psf + 5psf$
 $DL = 84psf$
 $W_u = 1.2D + 1.6L$
 $W_u = 1.2(84) + 1.6(51.6)$
 $W_u = 211.18psf$

Check W18x35:
 $\phi M_n = 249^k \geq 237.58^k$ ∴ OK
 $\phi V_n = 159^k \geq 31.67^k$ ∴ OK
 $\Delta = \frac{5wL^4}{384EI} = 631'' \leq \frac{L}{240} = 15''$ ∴ OK

Calculating Girder Size:




Assumptions:
 Girder Tributary Width: $W_T = 30'$
 Influence Area: $K_{LL} A_T = 60' \times 60'$
 $K_{LL} A_T = 3,600SF$
 $3,600SF \geq 400SF$ ∴ Reducible LL
 Live Loads: Hospital = 60psf, Wall Partitions = 20psf

Calculations:
 $P_u = 2 \times 31.67$
 $P_u = P_{u1} = P_{u2} = 63.34^k$
 $w_u = W_u \cdot A_T$
 $w_u = 211.18 \times 30'$
 $w_u = 6339^k$
 $P_{u1} = w_u \cdot W_T$
 $P_{u1} = 6339^k \cdot 30' = 1.9^k$
 $\sum M = 0$
 $0 = 10 \cdot (-P_{u1}) + 15' \cdot (-P_{u2}) + 20' \cdot (-P_{u3}) + 30' \cdot V_1$
 $0 = 10 \cdot (-63.34^k) + 15'(1.8^k) + 20'(63.34^k) + 30' \cdot V_1$
 $V_1 = V_2 = 64.24^k$
 $M_{u,max} = (V_1 \cdot 10') - \frac{1}{2}(1.8 \cdot 15 + 0.5)$
 $M_{u,max} = (64.24^k \cdot 10') - \frac{1}{2}(6)$
 $M_{u,max} = 639.4^k$

Check W24x68:
 $\phi M_n = 664^k \geq 639.4^k$ ∴ OK
 $\phi V_n = 295^k \geq 64.24^k$ ∴ OK
 $\Delta = \frac{5wL^4}{384EI} = 911'' \leq \frac{L}{240} = 15''$ ∴ OK

Calculating Column Size:




Assumptions:
 Tributary Area: $A_T = \frac{(30' + 30') \cdot (30' + 30')}{2}$
 $A_T = 30' \times 30'$
 $A_T = 900SF$
 Influence Area: $K_{LL} A_T = 60' \times 60'$
 $K_{LL} A_T = 3,600SF$
 $3,600SF \geq 400SF$ ∴ Reducible LL
 Live Loads: Hospital = 60psf, Wall Partitions = 20psf

Calculations:
 $DL = (Roof) + (Deck) + (FP) + (Super.) + (Beams)$
 $DL = 30psf + 3psf + 3psf + 10psf + 5psf + 2psf$
 $DL = 53psf$
 Effective Column Length (KL):
 $K = 1$ (Pin-Pin Connection)
 $L = 15'$
 $KL = 15'$
 a) First Floor:
 $P_{u1} = (2 \cdot V_{u,Girder}) + (2 \cdot V_{u,Beams})$
 $P_{u1} = (2 \cdot 64.24^k) + (2 \cdot 31.67^k)$
 $P_{u1} = (128.48^k) + (63.34^k)$
 $P_{u1} = 191.74^k$
 b) Roof:
 $P_{u2} = (1.2D + 1.6L)$
 $P_{u2} = (1.2(53^k) + 1.6(30^k))$
 $P_{u2} = (63.6^k + 48^k)$
 $P_{u2} = 111.6^k$
 $\sum P_u = 191.74^k + 111.6^k = 303.34^k$

Check W10x49: $\phi P_n = 449^k \geq 303.34^k$ ∴ OK

Calculating Footing Size:



Assumptions:
 Column (12-L) Size:
 Width = 9'
 Length = 9'
 Allowable Bearing Capacity:
 $q_u = 4,000psf = 4^ksf$

Calculations:
 $q_u = \frac{P_u}{Area} = \frac{262.34^k}{9' \times 9'} = \frac{262.34^k}{81ft^2} = 3.238^ksf$
 $3.238^ksf < 4^ksf$ ∴ OK

EQUATIONS

LIVE LOAD REDUCTION:
 $L_r = L_o \left[.25 + \frac{15}{\sqrt{K_{LL} A_T}} \right]$

FACTORED DISTRIBUTED LOAD:
 $w_u = (W)(Tributary Area)$

FACTORED BENDING MOMENT:
 $M_u = \frac{(w_u)(l^2)}{8}$

FACTORED SHEAR:
 $V_u = \frac{w_u \times Length}{2}$

Table 3-23 Shears, Moments and Deflections

1. SIMPLE BEAM — UNIFORMLY DISTRIBUTED LOAD

Total Equiv. Uniform Load = wl
 $R = V = \frac{wl}{2}$
 V_s (when $x = \frac{l}{2}$) = $\frac{wl}{2} - wx$
 M_{max} (at center) = $\frac{wl^2}{8}$
 M_s (when $x = \frac{l}{2}$) = $\frac{wx}{2}(l-x)$
 Δ_{max} (at center) = $\frac{5wl^4}{384EI}$
 Δ_s (when $x = \frac{l}{2}$) = $\frac{wx}{24EI}(l^3 - 2lx^2 + x^3)$

2. SIMPLE BEAM — LOAD INCREASING UNIFORMLY TO ONE END

Total Equiv. Uniform Load = $\frac{16W}{9\sqrt{3}} = 1.03W$
 $R = V = \frac{W}{3}$
 $R_L = V_L = V_{max} = \frac{2W}{3}$
 V_s = $\frac{W}{3} - \frac{Wx^2}{l^2}$
 M_{max} (at $x = \frac{l}{\sqrt{3}} = 0.577l$) = $\frac{2Wl}{9\sqrt{3}} = 0.128Wl$
 M_s = $\frac{Wx}{3l^2}(l^3 - x^3)$
 Δ_{max} (at $x = \sqrt{\frac{8}{15}}l = 0.519l$) = $0.0130 \frac{Wl^4}{EI}$
 Δ_s = $\frac{Wx}{180EI} (5x^4 - 10l^2x^2 + 7l^4)$

3. SIMPLE BEAM — LOAD INCREASING UNIFORMLY TO CENTER

Total Equiv. Uniform Load = $\frac{4W}{3}$
 $R = V = \frac{W}{2}$
 V_s (when $x = \frac{l}{2}$) = $\frac{W}{2}(l^2 - 4x^2)$
 M_{max} (at center) = $\frac{Wl^3}{6}$
 M_s (when $x = \frac{l}{2}$) = $\frac{Wx}{2}(\frac{l}{2} - \frac{x}{3})$
 Δ_{max} (at center) = $\frac{Wl^4}{80EI}$
 Δ_s (when $x = \frac{l}{2}$) = $\frac{Wx}{480EI} (6l^2 - 4x^2)^2$

TABLE 4-1 MINIMUM UNIFORMLY DISTRIBUTED LIVE LOADS, L_U, AND MINIMUM CONCENTRATED LIVE LOADS

Occupancy or Use	Uniform psf (kN/m ²)	Conc. lb (kN)
Apartments (see Residential)		
Access floor systems		
Office use	50 (2.4)	2,000 (8.9)
Computer use	100 (4.79)	2,000 (8.9)
Armories and drill rooms	150 (7.18)	
Assembly areas and theaters		
Fixed seats (fastened to floor)	60 (2.87)	100 (4.79)
Lobbies	100 (4.79)	100 (4.79)
Movable seats	100 (4.79)	100 (4.79)
Platforms (assembly)	100 (4.79)	100 (4.79)
Stage floors	150 (7.18)	
Balconies (exterior)	100 (4.79)	
On one- and two-family residences only, and not exceeding 100 ft ² (9.3 m ²)	60 (2.87)	
Bowling alleys, poolrooms, and similar recreational areas	75 (3.59)	
Corridors		
First floor	100 (4.79)	
Other floors, same as occupancy served except as indicated	100 (4.79)	
Dance halls and ballrooms	100 (4.79)	
Decks (patio and roof)		
Same as area served, or for the type of occupancy accommodated		
Dining rooms and restaurants	100 (4.79)	
Dwellings (see Residential)		
Elevator machine room grating (on area of 4 in. ² [2,580 mm ²])		300 (1.33)
Finish light floor plate construction (on area of 1 in. ² [645 mm ²])		200 (0.89)
Fire escapes		
On single-family dwellings only	100 (4.79)	
Garages (passenger vehicles only)	40 (1.92)	
Trucks and buses		See Section 4.4
Grandstands (see Stadiums and arenas, Bleachers)		
Gymnasiums—main floors and balconies	100 (4.79)	
Hospitals, guardrails, and grab bars		See Section 4.4
Hospitals		
Operating rooms, laboratories	60 (2.87)	1,000 (4.45)
Patient rooms	40 (1.92)	1,000 (4.45)
Corridors above first floor	80 (3.83)	1,000 (4.45)
Hotels (see Residential)		
Libraries		
Reading rooms	60 (2.87)	1,000 (4.45)
Stack rooms	150 (7.18)	1,000 (4.45)
Corridors above first floor	80 (3.83)	1,000 (4.45)
Manufacturing		
Light	125 (6.00)	2,000 (8.90)
Heavy	250 (11.97)	3,000 (13.40)
Managers	75 (3.59)	
Office Buildings		
File and computer rooms shall be designed for heavier loads based on anticipated occupancy		
Lobbies and first-floor corridors	100 (4.79)	2,000 (8.90)
Offices	50 (2.40)	2,000 (8.90)
Corridors above first floor	80 (3.83)	2,000 (8.90)
Penal Institutions		
Cell blocks	40 (1.92)	
Corridors	100 (4.79)	
Residential		
Dwellings (one- and two-family)		
Uninhabitable attics without storage	10 (0.48)	
Habitable attics and sleeping areas	20 (0.96)	
Uninhabitable attics with storage	30 (1.44)	
All other areas except stairs and balconies	40 (1.92)	
Hotels and multifamily houses		
Private rooms and corridors serving them	40 (1.92)	
Public rooms and corridors serving them	100 (4.79)	
Reviewing stands, grandstands, and bleachers	100 (4.79)	

REFERENCES



American Society of Civil Engineers, ASCE Standard 7-05 Minimum Design Loads for Buildings and Other Structures. Virginia: ASCE/AEI, 2010

American Institute of Steel Construction, Manual of Steel Construction, 13th Edition. Chicago: AISC, 2005.

“Concrete in Practice”. (2003) NRCMA. Web

<<http://www.nrmca.org/aboutconcrete/cips/36p.pdf>>

Dunston, P.S., Arns, L.L., McGlothlin, J.D (2007). “An immersive virtual reality mock-up for design review of hospital patient rooms”. 7th International Conference on Applications of Virtual Reality. Web

<https://www.engr.psu.edu/convr/proceedings/papers/01_Dunston_submission_45.pdf>

HAM Toolbox, V.B1. *Quirouette Building Science*. Computer Software

Hoerner, Matthew (2013). "Utilizing Head Mounted Displays for Healthcare Design Review." The Pennsylvania State University, University Park, PA

International Code Council, International Building Code, 2009. Illinois: International Code Council Publications, Sixth Printing December 2010

Kesik, T.J. (2013) “Building Enclosure Design Principles and Strategies.” WBDG. Web

<<http://www.wbdg.org/resources/buildingenclosuredesignstrategies.php>>

Kumar, S., Hedrick, M., Wiacek, C., and Messner, John I. (2011). “Developing an Experienced-based Design Review Application for Healthcare Facilities using a 3D Game Engine.” Information Technology in Construction, 16, 84–103

Leicht, R.M., and Messner, J.I. (2009). “Physical or virtual mock-up: A case study.” CIC Technical Report, No. 57, The Pennsylvania State University, University Park, PA

Leicht, Robert M., Sonali Kumar, John I. Messner. (2010). “Gaining End User Involvement through virtual reality mock-ups: A medical facility case study.” Penn State CIC Program. Web

< <http://itc.scix.net/data/works/att/w78-2010-143.pdf>>

LIANG J., MEMARI A.M. (2011) “INTRODUCTION OF A PANELIZED BRICK VENEER WALL SYSTEM AND ITS BUILDING SCIENCE EVALUATION.” ASCE JOURNAL, ARCHITECTURAL ENGINEERING 17(1):1–14

Maing, Minjung (2012). “Physical or Virtual? Effectiveness of virtual mockups of building envelope systems”. Building Enclosure Science & Technology 5th National Conference. Web

<http://www.brikbases.org/sites/default/files/best3_maing.pdf>

Martin, D.P., Zimmer, A.S (2013). “The Advantages and Disadvantages of Lightweight Concrete in Building Construction.” *Structure Magazine*. Web

<<http://www.structuremag.org/article.aspx?articleID=1587>>

“Minimizing Floor Vibration Problems.” (2009) *Steven Schaefer Associates*. Web

<<http://www.ssastructural.com/doc/FloorVibrartionArticle.pdf>>

“Moisture in Lightweight Structural Concrete Decks”. NRCA. Web

<http://staticcontent.nrca.net/pdf/0813_IndustryIssueUpdate.pdf>

NITTERHOUSE CONCRETE PRODUCTS. (2014). WEB

<[HTTP://NITTERHOUSE.COM/HOME](http://NITTERHOUSE.COM/HOME)>

“PENNSYLVANIA SHIPPING PERMIT REGULATIONS” (2013). *WIDELOADSHIPPING*. WEB

<[HTTP://WIDELOADSHIPPING.COM/](http://WIDELOADSHIPPING.COM/)>

RSMeans (2013). *Building Construction Cost Data*. 65th ed. Kingston, MA: Construction publishers & Consultants

SIECK, J., JOHNSON, G.. (2004). “UNDERSTANDING HOUSE OF QUALITY”. ASQC QUALITY PRESS. WEB

<[HTTP://WWW.PUBLIC.IASTATE.EDU/~VARDEMAN/IE361/F01MINI/JOHNSON.PDF](http://WWW.PUBLIC.IASTATE.EDU/~VARDEMAN/IE361/F01MINI/JOHNSON.PDF)>

“Steel Roof and Floor Deck Catalog”. (2008). *Vulcraft*. Online Catalog, Pgs. 52-52, 70-71.

Straube, J., and Burnett, E. (2005). “Building science for building enclosures.” Building Science Press, Westford, MA.

“Structural Lightweight Concrete” (2010). Web

<<http://www.escsi.org/ContentPage.aspx?id=68>>

“The Value of Mock-ups in healthcare Construction.” (2009). *SKANSA*. Web

<<http://www.usa.skanska.com/cdn-1ceb94c9cd1aa84/Global/Healthcare%20COE.pdf>>

TRUCK MILE CALCULATOR. (2013). WEB

<[HTTP://WWW.TRUCKMILES.COM/](http://WWW.TRUCKMILES.COM/)>

Ungar, E.U (2007). “Vibration Criteria for Healthcare Facility Floors.” *Acentech*. Web

<<http://www.sandv.com/downloads/0709unga.pdf>>

Unity Game Engine, Version 4.3. *Unity Technologies, Inc.* Computer Software

Weber, R.A. (2013). “Building Envelope Design Guide – Masonry Wall Systems.” WBDG. Web

<http://www.wbdg.org/design/env_wall_masonry.php>

Wolfe, B. and Craig, P. (2012). “Another Look at the Drying of Lightweight Concrete”. *Concrete International*. Web

<<http://www.us-concrete.com/aridus/DryingofLightweightConcrete.pdf>>