

HEIFER INTERNATIONAL CENTER

LITTLE ROCK, ARKANSAS



TECHNICAL REPORT III

SIKANDAR PORTER-GILL

ADVISOR: DR. THOMAS BOOTHBY



SITE AND LOCATION

DOWNTOWN LITTLE ROCK



HEIFER INTERNATIONAL CENTER

WILLIAM J CLINTON PRESIDENTIAL
LIBRARY & MUSEUM

LITTLE ROCK, ARKANSAS

HEIFER INTERNATIONAL CENTER

Height	65'-0"
Stories	4
Square Footage	98,000 GSF
Construction Dates	February 2004 – January 2006
Approximate Cost	\$18 million
Project Delivery	Construction Management at Risk
USGBC Rating	LEED Platinum




UNIQUE ARCHITECTURE

INVERTED ROOF

RAINWATER STORAGE




TYPICAL FLOOR PLAN



TYPICAL FLOOR PLAN

PUBLIC AREAS



PUBLIC AREAS

OFFICES

MECHANICAL SPACE

EXISTING STRUCTURAL SYSTEM

- FOUNDATION
 - Geopier™ Rammed Aggregate Pier® System
 - Increase soil capacity to 5 to 7 ksf
 - Grade Beams
 - Slab On Grade



EXISTING STRUCTURAL SYSTEM

- **GRAVITY SYSTEM**

- Composite Deck, Beam and Girder System
 - 3VLI Decking with 2 ½" NWC Topping
 - Beams and Girders Cambered
- HSS COLUMNS



- **LATERAL SYSTEM**

- Steel plate shear wall system



GRAVITY SPOT CHECKS | DECK

3VLI 20 Gauge, 2 1/2" NWC

- **CLEAR SPAN CHECK**

- 11'-0" span > 2 and 3 span condition

Pass!

- Failed 1 span condition



No Good!

- **STRENGTH CHECK**

- $w_{LL} + w_{misc,DL} \leq$ Superimposed Live Load


- 92 PSF \leq 106 PSF

Pass!



GRAVITY SPOT CHECKS | BEAM

W14x22 (26) [1"]



- **STRENGTH CHECK**

- $\phi M_n = 265.4'k < M_u = 273'k$

Pass!

- **UNSHORED STRENGTH CHECK**

- $\phi M = 125'k > M_u = 118.3'k$
- No Shoring Required

Pass!

- **WET CONCRETE CHECK**


- $\Delta_{wc,max} = 1.5" < \Delta_{wc} = 1.84"$
- Beam Requires Camber

Camber!

- **LIVE LOAD DEFLECTION CHECK**


- $\Delta_{LL,max} = l/360 = 1" > \Delta_{LL} = 0.850"$

Pass!



GRAVITY SPOT CHECKS | GIRDER

W16x26 (18)



- **STRENGTH CHECK**

- $\phi M_n = 336'k < M_u = 401'k$

Pass!

- **UNSHORED STRENGTH CHECK**

- $\phi M = 166'k > M_u = 466'k$

- Shoring Required

Shoring!

- **WET CONCRETE CHECK**


- $\Delta_{wc,max} = 1.1" > \Delta_{wc} = 0.784"$

Pass!

- **LIVE LOAD DEFLECTION CHECK**

- $\Delta_{LL,max} = l/360 = 0.733" > \Delta_{LL} = 0.330"$

Pass!



GRAVITY SPOT CHECKS | GIRDER

W14x22 (10)

- **STRENGTH CHECK**

- $\phi M_n = 229'k < M_u = 234'k$

Pass!

- **UNSHORED STRENGTH CHECK**

- $\phi M = 125'k < M_u = 233'k$

- Shoring Required

Shoring!

- **WET CONCRETE CHECK**



- $\Delta_{wc,max} = 1.1" > \Delta_{wc} = 0.6"$

Pass!

- **LIVE LOAD DEFLECTION CHECK**

- $\Delta_{LL,max} = l/360 = 0.733" > \Delta_{LL} = 0.614"$

Pass!



GRAVITY SPOT CHECKS | COLUMNS

HSS24x0.5*

- **INTERIOR COLUMN**

- $\phi P_n = 1080^k > P_u = 511^k$

Pass!

- **EXTERIOR COLUMN**

- $\phi P_n = 1080^k > P_u = 262^k$

Pass!



*Axial compression values used for an HSS20x0.5, Steel Construction Manual (14th Edition) does not have HSS24x0.5

ALTERNATIVE SYSTEMS

- Glulam
- Hollow Core Plank
- Post Tension Slab



Image Courtesy:
ArchiEXPO.com
SEPSA Precast Solutions Corp.
Kansas Department of Transportation

ALT. #1 - GLULAM



Heifer International Visitor and Education Center




ALT. #1 - GLULAM

DESIGN

- (5) 8 3/4" x 22 1/2" 24F-V4
 - @ 5'-6" spacing
- (1) 10 3/4" x 33" 24F-V4
- (1) 8 3/4" x 27" 24F-V4

DURABILITY

- Common material for construction, currently in use Heifer International's Visitor Center



ALT. #1 - GLULAM

SYSTEM DEPTH

37" > 21.2"
GLULAM EXISTING

SYSTEM FIRE RATING

1 HR
Char of 1.5" / HR

RS MEANS COST

\$20.43 / SF

SYSTEM WEIGHT

18 psf

LATERAL SYSTEM

- Steel Plate Shear Walls
 - Setup in existing building at mechanical and lobby space at both ends and middle core
- Prefabricated System
 - SIMPSON Strong-Tie®
 - Steel or Wood Shear Walls
 - Moment Frames



ALT. #2 – HOLLOW CORE PLANKS



Image Courtesy:

Spiroll Precast Services, Ltd.
Mabetón España, S.A.


ALT. #2 – HOLLOW CORE PLANKS

DESIGN

- (8) 6" x 4'-0" Planks
 - 7 – ½" Ø Strands @ 2" Concrete Topping
- W24x84 Beam

DURABILITY

- Strong concrete system that allows more open space in a building



ALT. #2 – HOLLOW CORE PLANKS

SYSTEM DEPTH

32.7" > 21.2"
PLANKS EXISTING

SYSTEM FIRE RATING

1 HR

RS MEANS COST

\$11.04 / SF

SYSTEM WEIGHT

57 psf

LATERAL SYSTEM

- Concrete Masonry Walls
 - Could be integrated into existing mechanical, elevator and stair towers
- Steel Plate Shear Walls
 - System not as compatible with existing lateral system



ALT. #3 – POST TENSION SLAB



Image Courtesy:

Metzger Testing & Inspection
Architectoid, Learning Architecture for Life


ALT. #3 – POST TENSION SLAB

DESIGN

- 8" Slab Concrete Slab
 - 270kips @ 90% Jacking
 - 2 Strands @ 10" O.C. (N-S)
- (1) 18" x 27" NWC Beam
 - (7) #5 Longitudinal
 - (16) #3 Stirrup @ 7" (2" from ends)
- (1) 15" x 25" NWC Beam
 - (5) #8 Longitudinal
 - (10) #3 Stirrup @ 11" (2" from ends)

DURABILITY

- Post tension is extremely durable and is an established system for use in offices and garages



ALT. #3 – POST TENSION SLAB

SYSTEM DEPTH

35" > 21.2"

POST TENSION EXISTING

SYSTEM FIRE RATING

2 HR

ACHIEVED

RS MEANS COST

\$18.92 / SF

SYSTEM WEIGHT

132 psf

LATERAL SYSTEM

- Moment Frame
 - Redesign of office layout will be required, may complicate this system
- Concrete Shear Wall
 - Could be integrated into existing mechanical, elevator and stair towers



STRUCTURAL CONSIDERATIONS & FUTURE INVESTIGATION

Considerations		Gravity Systems			
		Composite Deck and Beam	Glulam	Prefabricated Hollow Plank	Post Tension Slab
Alterations	Gravity System	Composite deck and composite beams	Engineered glulam beams and girders, supporting 4" T&G floor decking	Prefabricated 4' hollow core planks supported by steel beams	Post tensioned 8" slab, supported by interior and exterior concrete girders
	Lateral System	Steel plate shear wall (SPSW)	SPSW or Prefabricated Wood Shear Wall	Concrete or masonry shear walls, SPSW not viable	Moment Frame or Concrete Shear Wall
	Impact	-	Minor adjustments	Minor adjustments to bay sizes	Increased weight will impact existing foundation system
Potential Future Investigation					
		-	Yes, Hybrid Steel and Wood System	No, semicircular building not viable in prefabricated rectangular sections	Yes, research viability on semi-circular building



ARCHITECTURAL CONSIDERATIONS

Considerations		Graivty Systems			
		Composite Deck and Beam	Glulam	Prefabricate d Hollow Plank	Post Tension Slab
	Size of Bay	22' x 30'	22' x 30'	22' x 32'	22' x 30'
	Fire Protection	None*	None	None	None
	Fire Rating	1 HR	1 HR @ Char of 1.5" / HR	1 HR	2 HR ACHIEVED
	MEP Coordination	Underfloor Air Distribution (UFAD) System	No concealed spaces allowed, UFAD not possible	No impact	No impact
	Impact	Framing members not protected from fire	Decrease in floor to floor height	Decrease in floor to floor height	Decrease in floor to floor height

SYSTEM STATISTICS

Considerations		Gravity Systems			
		Composite Deck and Beam	Glulam	Prefabricated Hollow Plank	Post Tension Slab
System Weight		57 psf	18 psf	57 psf	132 psf
Slab Depth		5.5"	4"	8"	8"
System Depth		21.2"	37"	32.7"	35"
Constructability		Easy	Easy	Easy	Challenge
Durability		Acceptable	Acceptable	Acceptable	Acceptable
Cost		\$17.93 / SF	\$20.43 / SF	\$11.04 / SF	\$18.92 / SF

THANK YOU

