



AE 481W : SENIOR THESIS



Technical Assignment 2

Cost and methods analysis



Prepared for

Architectural Engineering Department
Construction Management
Penn State University

By

Inyoung Hwang

October 31, 2005

- Benner Pike Shops
- State College, PA
-
-
-
-
-



Executive Summary

This assignment focuses detailed analysis based on the information gathered on Tech 1. Detailed project schedule is created for the cost loading. One of the interesting features that Benner Pike Shops is that the schedules for each shop are different. Careful schedules are needed to be developed among the shops in order to avoid any safety issues or construction delays.

Site plans are then created based on the site plan developed in Tech 1. Different phases are verified in the drawings to show how the construction site is running during a specific phase. Critical phases included are: excavation, superstructure, and finish phase. These plans are useful when dealing with congestion issues, and efficiency. Problems that could not be seen from paper work could be found from the plans, and it is easy to check how efficient each process is going.

Detailed structural systems estimate was performed along with assemblies estimate. By performing estimate using different methods would be helpful to become familiar with the estimate systems and, it would give comparison between the two different methods. Structural system for the Benner Pike Shops is estimated which consists of foundation, slab on grade, columns, beams, and roof deck. Unit costs for entire system are calculated using square foot method to give general idea of material, labor, and equipment costs. For the assemblies estimate, exterior closure of the shops is estimated. The system will include exterior walls, windows, and doors. Items are lump summed in this process to get an estimate based on square foot unit. General conditions estimate is performed to give staffing costs, temporary costs, and equipment rentals through out the entire project. Any schedule savings could be proposed later based on G.C. savings calculation.

- Benner Pike Shops
- State College, PA
-
-
-
-
-



Table of Contents

Executive Summary	2
Table of Contents	3
Detailed Project Schedule	4
Site Layout Planning	5
Assemblies Estimate	6
Detailed Structural System	9
General Conditions Estimate	13
Appendix A	14
Appendix B	15

- Benner Pike Shops
- State College, PA
-
-
-
-



Detailed Project Schedule

Detailed project schedule was developed based on different phases through out the construction. Phases include site work, excavation & foundation, structural system, first floor, roof, enclosure, and finish. During some of the phases, activities were described based on three major units of building; Bed Bath & Beyond, Ross Dress For Less, and the rest of the stores. Bed Bath & Beyond was referred as Unit 1, Ross Dress For Less was referred as Unit 2, and the rest as Unit 3 in the schedule.

ID	Task Name	Duration	Start	Finish	2005												2006			
					Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb
1	Sitework	126 days	Fri 12/17/04	Fri 6/10/05	[Red bar from Nov to Jun]															
2	Mobilization	5 days	Fri 12/17/04	Thu 12/23/04	[Blue bar]															
3	E&S Systems	5 days	Fri 12/24/04	Thu 12/30/04	[Blue bar]															
4	Site Clearing	10 days	Fri 12/31/04	Thu 1/13/05	[Blue bar]															
5	Temporary Fences	3 days	Fri 1/14/05	Tue 1/18/05	[Blue bar]															
6	Construct Haul Road	10 days	Mon 1/3/05	Fri 1/14/05	[Blue bar]															
7	Site Utilities	70 days	Mon 3/7/05	Fri 6/10/05	[Blue bar]															
8	Site Lighting	20 days	Thu 5/12/05	Wed 6/8/05	[Blue bar]															
9	Parking Lots	50 days	Thu 6/9/05	Wed 8/17/05	[Blue bar]															
10	Excavation / Foundation	65 days	Fri 1/14/05	Thu 4/14/05	[Red bar from Jan to Apr]															
11	Drill & Blast	30 days	Fri 1/14/05	Thu 2/24/05	[Blue bar]															
12	Bulk Excavation	60 days	Fri 1/21/05	Thu 4/14/05	[Blue bar]															
13	Temporary Shoring	5 days	Thu 2/10/05	Wed 2/16/05	[Blue bar]															
14	Temporary Shoring	5 days	Tue 3/1/05	Mon 3/7/05	[Blue bar]															
15	Footings	9 days	Mon 3/7/05	Thu 3/17/05	[Blue bar]															
16	Column Footings	8 days	Tue 11/1/05	Thu 11/10/05	[Blue bar]												[Blue bar]			
17	Wall Footings	8 days	Tue 11/1/05	Thu 11/10/05	[Blue bar]												[Blue bar]			
18	Structural System	47 days	Mon 4/11/05	Tue 6/14/05	[Red bar from Apr to Jun]															
19	Steel Fabrication for Unit 1	10 days	Mon 4/11/05	Fri 4/22/05	[Blue bar]															
20	Steel Fabrication for Unit 2	10 days	Mon 4/25/05	Fri 5/6/05	[Blue bar]															
21	Steel Fabrication for Unit 3	8 days	Mon 5/9/05	Wed 5/18/05	[Blue bar]															
22	Below Grade Rough-Ins for Unit 1	15 days	Wed 5/11/05	Tue 5/31/05	[Blue bar]															
23	Below Grade Rough-Ins for Unit 2	20 days	Mon 5/9/05	Fri 6/3/05	[Blue bar]															
24	Below Grade Rough-Ins for Unit 3	12 days	Mon 5/23/05	Tue 6/7/05	[Blue bar]															
25	Erect Strcutural Steel for Unit 1	3 days	Mon 5/9/05	Wed 5/11/05	[Blue bar]															
26	Erect Structural Steel for Unit 2	3 days	Thu 5/12/05	Mon 5/16/05	[Blue bar]															
27	Erect Structural Steel for Unit 3	3 days	Tue 5/17/05	Thu 5/19/05	[Blue bar]															
28	Connect Steel for Unit 1	2 days	Thu 5/12/05	Fri 5/13/05	[Blue bar]															
29	Connect Steel for Unit 2	2 days	Tue 5/17/05	Wed 5/18/05	[Blue bar]															
30	Connect Steel for Unit 3	2 days	Fri 5/20/05	Mon 5/23/05	[Blue bar]															
31	First Floor	73 days	Wed 5/11/05	Fri 8/19/05	[Red bar from May to Aug]															
32	Masonry for Unit 1	20 days	Wed 5/11/05	Tue 6/7/05	[Blue bar]															
33	Metal Decking for Unit 1	4 days	Thu 5/12/05	Tue 5/17/05	[Blue bar]															
34	Erect Joists for Unit 1	3 days	Wed 5/18/05	Fri 5/20/05	[Blue bar]															
35	Connect Joists to Columns for Unit 1	3 days	Mon 5/23/05	Wed 5/25/05	[Blue bar]															

- Benner Pike Shops
- State College, PA
-
-
-
-
-
-



Site Layout Planning

Site layout plans were divided into major phases of the construction for Better Pike Shops. Excavation phase, superstructure phase, and finish phase were created to give an idea of how each phase was done.

Excavation Phase

- Since there is no previous building standing, no demolition was necessary.
- The site has sloping ground in which the difference in the height between the highest point and the lowest point was 20 feet.
- The excavation was performed in the direction from high portion of the site to low portion.
- Large portion of the soil excavated from the high portion was used in filling the low portion of the site.
- Total of 14 acres were excavated with 80,000 yards being hauled after the fill.

Superstructure











- Steel was erected in the order from East to West.
- Steel was staged in the future parking lots of the mall so the degree turn of the crane boom is minimized.
- One 120 ton mobile crane was used for the whole erection.


Finish

- The construction was performed in the order from East to West.
- Interior finish was performed primarily for Unit 1 (Ross Dress For Less) and Unit 2 (Bed, Bath & Beyond).
- With Unit 1 and 2 possessed by the owner, rest of the building was finished with the fences and temporary office relocated.












LEGEND

-  DOZER
-  TRAFFIC FLOW
-  PEDESTRIAN FLOW
-  EXCAVATION FLOW
-  TEMP. FACILITY
-  EXISTING BLDG
-  FENCE
-  BOUNDARY LINE
-  DUMP TRUCK
-  EXCAVATOR



LEGEND


-  STEEL TRUCK
-  TRAFFIC FLOW
-  PEDESTRIAN FLOW
-  ERECTION FLOW
-  TEMP. FACILITY
-  EXISTING BLDG
-  FENCE
-  BOUNDARY LINE
-  120 TON MOBILE CRANE

BENNER PIKE SHOPS
STATE COLLEGE, PA








INYOUNG HWANG
10/31/05

1/32" = 1'-0"

STEEL ERECTION PLAN



LEGEND

-  TRAFFIC FLOW
-  PEDESTRIAN FLOW
-  INTERIOR FINISH WORK FLOW
-  TEMP. FACILITY
-  EXISTING BLDG
-  FENCE
-  BOUNDARY LINE

BENNER PIKE SHDPS
STATE COLLEGE, PA

INYOUNG HWANG
10/31/05

1/32" = 1'-0"

FINISH PLAN

- Benner Pike Shops
- State College, PA
-
-
-
-
-
-



Assemblies Estimate

Exterior Closure

The Benner Pike Shops are consisted of three major components on its exterior closure. Painted concrete blocks covered most of the side and back portions of the building. EIFS (Exterior Insulation Finish System), also known as synthetic stucco is used for the final finish of the front façade of the structure. Large portion of the front façade is covered by the combination of aluminum framing with glass windows and doors. Split faced concrete blocks are used for small portion of the façade. CMU materials are horizontally reinforced through out the exterior closure. Hollow metal doors are located in the back of the structure for each store. The estimate is based on RS Means Assemblies Estimate Cost Data.

* Exterior closure take off for the assemblies estimate can be found in Appendix A.



Assemblies Estimate (Con'd)

Concrete Block Wall	Quantity	Unit	Cost / S.F.		Total Cost
			Material	Installation	
SYSTEM 4.1-211-1510 Unreinforced Concrete Block Wall, 12" X 8" X 16", Styrofoam Core Fill					
Concrete block wall, 12" thick		S.F.	2.59	5.77	
Styrofoam insulation		S.F.	0.81	0.01	
Horizontal joint reinforcing, alternate courses		S.F.	0.07	0.12	
Control joint		L.F.	0.10	0.05	
Total	23808	S.F.	3.57	5.95	\$226,652.16

Split Face Block Wall	Quantity	Unit	Cost / S.F.		Total Cost
			Material	Installation	
SYSTEM 4.1-213-1710 Unreinforced Split Face Block Wall, 12" X 8" X 16", 0 Scores, Styrofoam Core Fill					
Split face block wall, 12" thick		S.F.	4.05	7.22	
Styrofoam insulation		S.F.	1.03	0.01	
Horizontal joint reinforcing, alternate courses		S.F.	0.07	0.12	
Control joint		L.F.	0.10	0.05	
Total	8208	S.F.	5.25	7.40	\$103,831.20

E.I.F.S.	Quantity	Unit	Cost / S.F.		Total Cost
			Material	Installation	
SYSTEM 4.5-110-5180 E.I.F.S., Cement Board Sheathing, 8" Metal Studs, 2" EPS					
Total	13932	S.F.	4.90	8.90	\$192,261.60

E.I.F.S.	Quantity	Unit	Cost / S.F.		Total Cost
			Material	Installation	
SYSTEM 4.5-110-5310 E.I.F.S., CMU Block, 8" X 10" X 16", 2" EPS					
Total	948	S.F.	4.43	10.30	\$13,964.04

Wood, Steel & Aluminum	Quantity	Unit	Cost / Unit		Total Cost
			Material	Installation	
SYSTEM 4.7-110-7250 Aluminum, Single Hung, Insulating Glass, 3'-4" X 5'					
Total	279.75	S.F.	267.00	106.00	\$104,346.75

- Benner Pike Shops
- State College, PA
-
-
-
-
-



Assemblies Estimate (Con'd)

Wood, Steel & Aluminum	Quantity	Unit	Cost / Opening			Total Cost
			Material	Installation		
SYSTEM 4.6-100-3450						
Steel 18 GA Door, Hollow Metal, 1 Door, 3'-0" X 7'-0"		Each	845.00	206.00		
Total	18	Each	845.00	206.00		\$18,918.00

Wood, Steel & Aluminum	Quantity	Unit	Cost / Opening			Total Cost
			Material	Installation		
SYSTEM 4.6-100-4550						
Steel 24 GA Door, Overhead, Rolling, Electric Oper. 8'-0" X 8'-0"		Each	935.00	545.00		
Total	3	Each	935.00	545.00		\$4,440.00

Grand Total						\$664,413.75
--------------------	--	--	--	--	--	---------------------

- Benner Pike Shops
- State College, PA
-
-
-
-
-



Detailed Structural Systems Estimate

Detailed structural systems of the Benner Pike Shops were estimated using RS Means Construction Cost Data. Estimate is based on different structural systems of the building, which are foundations, slab on grade, steel columns & beams, and metal decking. Concrete waste factor and steel connection factors are encountered as 5% and 10% respectively, of total cost for each. Knee bracing was performed for the connection among web joists, wide flange beams, and hollow steel columns.

* Take off for the detailed structural systems estimate can be found in Appendix B.



Detailed Structural Systems Estimate (Con'd)

Description	Size	Quantity	Unit	Unit Cost			Total Cost
				Material	Labor	Equipment	
Foundations							
Footings	3' x 3' x 1'	22	C.Y.	226.00	45.00	0.29	\$5,878
w/ formwork	5' x 5' x 1'	24	C.Y.	226.00	45.00	0.29	\$6,531
	5'-6" x 5'-6" x 1'-6"	25	C.Y.	226.00	45.00	0.29	\$6,839
	6'-6" x 6'-6" x 1'-10"	78	C.Y.	226.00	45.00	0.29	\$21,226
	7'-6" x 7'-6" x 1'-4"	15	C.Y.	226.00	45.00	0.29	\$3,956
	7'-6" x 7'-6" x 2'	50	C.Y.	226.00	45.00	0.29	\$13,565
Wall Footings	12" x 24" x 1700'	126	C.Y.	226.00	45.00	0.29	\$34,162
w/ formwork							
Reinforcing	#4 bars	0.34	Ton	760.00	580.00		\$454
	#6 bars	1.27	Ton	760.00	580.00		\$1,706
	#7 bars	1.23	Ton	760.00	580.00		\$1,643
	#8 bars	0.90	Ton	720.00	335.00		\$946
Footing Columns	TS 8" x 8" x 5/16"	4	Each	610.00	43.50	29.20	\$2,536
	TS 8" x 8" x 1/4"	2	Each	580.00	42.25	27.50	\$1,609
	TS 8" x 6" x 3/8"	2	Each	320.00	38.50	24.50	\$802
	TS 10" x 8" x 3/8"	2	Each	680.00	45.70	32.30	\$1,805
	TS 10" x 8" x 1/2"	1	Each	710.00	47.16	33.20	\$903
	4" Dia. Standard Pipe	2	Each	200.00	36.25	24.75	\$646
Concrete Waste	5% of concrete cost						\$4,608
Assumption	All footing columns have height of 16 inches All footing columns are estimated with unit costs based on 14 feet long structural tubing Concrete waste factor is assumed to be 5% of total concrete cost						
Slab on Grade							
Slab on Grade	4" thick	109122	S.F.	1.07	0.65	0.01	\$188,781
w/ finish							
Reinforcing	6 x 6 - W2.1 x W2.1	1091	100 S.F.	25.50	19.60		\$49,204
Welded Wire Fabric							
Formwork	6" high with 4 uses	1700	L.F.	0.26	2.96		\$5,474
Bulkhead forms							
Gravel Fill	4" deep	109122	S.F.	0.16	0.13	0.01	\$32,737
Concrete Waste	5% of concrete cost						\$9,439
Assumption	Concrete waste factor is assumed to be 5% of total concrete cost						



Detailed Structural Systems Estimate (Con'd)

Columns & Beams							
Structural Tubing	TS 10" x 8" x 3/8"	21	Each	680.00	45.70	32.30	\$15,918
	TS 8" x 6" x 3/8"	32	Each	320.00	38.50	24.50	\$12,256
Beam	W 24 x 68	552	L.F.	65.50	2.70	1.27	\$38,347
	W 24 x 76	900	L.F.	73.00	2.70	1.27	\$69,273
	W 24 x 55	60	L.F.	53.00	2.70	1.27	\$3,418
	W 24 x 94	90	L.F.	90.50	2.78	1.30	\$8,512
	W 24 x 62	117	L.F.	59.50	2.70	1.27	\$7,426
	W 18 x 35	1161	L.F.	33.50	3.13	1.46	\$44,222
	W 18 x 40	368	L.F.	38.50	3.13	1.46	\$15,857
	W 16 x 26	667	L.F.	25.00	2.07	1.33	\$18,943
	W 16 x 45	29	L.F.	43.00	2.59	1.66	\$1,370
	W 16 x 36	125	L.F.	34.00	2.42	1.55	\$4,746
	W 12 x 26	350	L.F.	25.00	2.35	1.51	\$10,101
	W 21 x 57	175	L.F.	56.00	2.87	1.35	\$10,539
	W 21 x 50	385	L.F.	48.00	2.82	1.32	\$20,074
	W 21 x 44	490	L.F.	42.50	2.82	1.32	\$22,854
	W 30 x 99	122	L.F.	95.50	2.50	1.17	\$12,099
	W 30 x 108	46	L.F.	104.00	2.50	1.17	\$4,953
	W 27 x 84	54	L.F.	81.00	2.52	1.18	\$4,574
	W 10 x 22	567	L.F.	21.00	3.45	2.21	\$15,116
	W 8 x 18	18	L.F.	17.00	3.45	2.21	\$408
	W 8 x 31	54	L.F.	30.00	3.76	2.41	\$1,953
Open Web Joist	26K9	43827	L.F.	8.15	1.36	0.68	\$446,599
	26K12	241	L.F.	8.45	1.36	0.68	\$2,526
	26K10	258	L.F.	8.30	1.36	0.68	\$2,664
	28K10	7702	L.F.	8.80	1.25	0.62	\$82,185
	28K9	1056	L.F.	8.00	1.25	0.62	\$10,423
	28K7	1488	L.F.	7.20	1.25	0.62	\$13,496
	20K4	893	L.F.	4.50	1.50	0.74	\$6,017
	20K5	5894	L.F.	4.92	1.50	0.74	\$42,204
	22K7	8308	L.F.	6.00	1.50	0.74	\$68,458
	22K4	2016	L.F.	5.10	1.50	0.74	\$14,797
	22K6	707	L.F.	5.45	1.50	0.74	\$5,438
	22K9	190	L.F.	6.80	1.50	0.74	\$1,721
	30K9	1008	L.F.	8.10	1.25	0.62	\$10,050
	16K9	576	L.F.	6.00	1.67	1.67	\$5,380
	12K1	72	L.F.	3.25	2.00	0.99	\$449
	10K1	29	L.F.	3.05	2.50	1.24	\$196
Steel Connection	10% of steel cost						\$105,556
Assumption	All footing columns are estimated with unit costs based on 14 feet long structural tubing Steel connections are assumed to be 10% of total steel cost						

- Benner Pike Shops
- State College, PA
-
-
-
-
-



Detailed Structural Systems Estimate (Con'd)

Metal Decking							
Metal Roof Deck	1-1/2" deep 22 GA	109122	S.F.	1.06	0.24	0.02	\$144,041
Steel Connection	10 % of steel cost						\$14,404
Assumption	Steel connections are assumed to be 10% of total steel cost						
Grand Total							\$1,715,014

Description	Size	Quantity	Unit	Unit Cost			Total Cost
				Material	Labor	Equipment	
Square Foot Method (Entire System)		109122	S.F.	11.95	3.44	0.33	\$1,715,014

- Benner Pike Shops
- State College, PA



General Conditions Estimate

Description	Quantity	Unit	Unit Cost	Total Cost	% of Total GC Cost
Project Staff					
Project manager	40	Week	\$1,625	\$65,000	5.74%
Superintendent	40	Week	\$1,500	\$60,000	5.30%
Superintendent	24	Week	\$1,500	\$36,000	3.18%
Field engineer	48	Week	\$995	\$47,760	4.22%
Field engineer	48	Week	\$995	\$47,760	4.22%
Field engineer	48	Week	\$995	\$47,760	4.22%
Administrative Requirements					
Permits	1	L.S.	\$75,000	\$75,000	6.63%
Bonds	1	L.S.	\$90,000	\$90,000	7.95%
Insurances	1	L.S.	\$60,000	\$60,000	5.30%
Field office expense	12	Month	\$140	\$1,680	0.15%
Construction photos	1	L.S.	\$292	\$292	0.03%
Temporary Facilities & Jobs					
Temporary heat	1	L.S.	\$9,863	\$9,863	0.87%
Temporary lighting	1	L.S.	\$13,005	\$13,005	1.15%
Temporary power	1	L.S.	\$13,092	\$13,092	1.16%
Trailer	8	Month	\$150	\$2,400	0.21%
Surveying	1	L.S.	\$1,818	\$1,818	0.16%
Telephone bill	12	Month	\$204	\$2,448	0.22%
Scaffolding	12	Month	\$59	\$708	0.06%
Temporary fencing		L.F.	\$4	\$0	0.00%
Temporary signs	200	S.F.	\$16	\$3,280	0.29%
Daily clean up	190	1000 S.F.	\$23	\$4,378	0.39%
Final clean up	190	1000 S.F.	\$47	\$9,016	0.80%
Equipment Rental					
Concrete cart (1 week rental)	6	Each	\$165	\$990	0.09%
Vibrators (1 week rental)	3	Each	\$32	\$96	0.01%
Concrete mixer (1 week rental)	2	Each	\$2,010	\$4,020	0.36%
Excavator (1 month rental)	2	Each	\$4,175	\$8,350	0.74%
Tractor (2 weeks rental)	4	Each	\$1,770	\$14,160	1.25%
Vibratory compactor (2 weeks rental)	2	Each	\$1,680	\$6,720	0.59%
Dump truck (1 month rental)	4	Each	\$1,175	\$4,700	0.42%
Generator (1 month rental)	2	Each	\$195	\$780	0.07%
Tracktor loader (2 weeks rental)	1	Each	\$835	\$1,670	0.15%
120 ton mobile crane (1 week rental)	1	Each	\$7,550	\$7,550	0.67%
40 C.Y. Dumpster (2 weeks rental)	20	Each	\$805	\$32,200	2.84%
Temporary Toilets (12 months rental)	4	Each	\$195	\$9,360	0.83%
GC Fees				\$450,000	39.76%
Grand Total				\$1,131,854	100.00%

- Benner Pike Shops
- State College, PA
-
-
-
-
-



Appendix A

Concrete Block			
<u>Split faced concrete block</u>		<u>Painted concrete block</u>	
Size	S.F.	Size	S.F.
12" x 8" x 16"	392	12" x 8" x 16"	1600
12" x 8" x 16"	128	12" x 8" x 16"	1260
12" x 8" x 16"	48	12" x 8" x 16"	384
12" x 8" x 16"	224	12" x 8" x 16"	320
12" x 8" x 16"	528	12" x 8" x 16"	400
12" x 8" x 16"	204	12" x 8" x 16"	640
12" x 8" x 16"	384	12" x 8" x 16"	608
12" x 8" x 16"	152	12" x 8" x 16"	352
12" x 8" x 16"	540	12" x 8" x 16"	720
12" x 8" x 16"	1080	12" x 8" x 16"	320
12" x 8" x 16"	100	12" x 8" x 16"	1600
12" x 8" x 16"	48	12" x 8" x 16"	2088
12" x 8" x 16"	280	12" x 8" x 16"	304
12" x 8" x 16"	280	12" x 8" x 16"	640
		12" x 8" x 16"	1008
		12" x 8" x 16"	960
		12" x 8" x 16"	736
		12" x 8" x 16"	5500
		12" x 8" x 16"	1464
		12" x 8" x 16"	1488
		12" x 8" x 16"	1920
Sum	4388		24312
		subtract doors	24(3'x7')
Total	8208		23808
E.I.F.S.			
<u>On 8" Metal Stud</u>		<u>On 10" Conc. Block</u>	
	S.F.		S.F.
	1536		448
	400		500
	1536		
	4480		
	1120		
	916		
	180		
	120		
	940		
	240		
	112		
	1200		
	320		
	832		
Total	13932		948
Window		Door	
<u> Alum. Framing</u>		<u> Insul. flush type</u>	
Size	S.F.	Size	S.F.
64' x 12'	768	(3' x 7')18	378
38' x 18'	684		
(7' x 16')27	3024		
Total	4476		378



Appendix B

Description	Size	# of material	Span	Quantity	Unit
Foundations					
Footings	3' x 3' x 1'			22	C.Y.
w/ formwork	5' x 5' x 1'			24	C.Y.
	5'-6" x 5'-6" x 1'-6"			25	C.Y.
	6'-6" x 6'-6" x 1'-10"			78	C.Y.
	7'-6" x 7'-6" x 1'-4"			15	C.Y.
	7'-6" x 7'-6" x 2'			50	C.Y.
Wall Footings	12" x 24" x 1700'			126	C.Y.
w/ formwork					
Reinforcing	#4 bars			0.34	Ton
	#6 bars			1.27	Ton
	#7 bars			1.23	Ton
	#8 bars			0.90	Ton
Footings Columns	TS 8" x 8" x 5/16"	39	16 in	14	L.F.
	TS 8" x 8" x 1/4"	26	16 in	14	L.F.
	TS 8" x 6" x 3/8"	22	16 in	14	L.F.
	TS 10" x 8" x 3/8"	25	16 in	14	L.F.
	TS 10" x 8" x 1/2"	12	16 in	14	L.F.
	4" Dia. Standard Pipe	26	16 in	14	L.F.
Slab on Grade					
Slab on Grade	4" thick			109122	S.F.
w/ finish					
Reinforcing	6 x 6 - W2.1 x W2.1			1091	100 S.F.
Welded Wire Fabric					
Formwork	6" high with 4 uses			1700	L.F.
Bulkhead forms					
Gravel Fill	4" deep			109122	S.F.



Appendix B (Con'd)

Columns & Beams					
Structural Tubing	TS 10" x 8" x 3/8"	21		14	L.F.
	TS 8" x 6" x 3/8"	32		14	L.F.
Beam	W 24 x 68	12		46	L.F.
	W 24 x 76	10		90	L.F.
	W 24 x 55	2		30	L.F.
	W 24 x 94	2		45	L.F.
	W 24 x 62	3		39	L.F.
	W 18 x 35	23		43	L.F.
	W 18 x 40	8		46	L.F.
	W 18 x 35	4		43	L.F.
	W 16 x 26	29		23	L.F.
	W 16 x 45	1		29	L.F.
	W 16 x 36	5		25	L.F.
	W 12 x 26	25		14	L.F.
	W 21 x 57	5		35	L.F.
	W 21 x 50	11		35	L.F.
	W 21 x 44	14		35	L.F.
	W 30 x 99	2		61	L.F.
	W 30 x 108	1		46	L.F.
	W 27 x 84	1		54	L.F.
	W 10 x 22	27		21	L.F.
W 8 x 18	2		9	L.F.	
W 8 x 31	6		9	L.F.	
Open Web Joist	26K9	8	128	214	L.F.
	26K12	1	43	28	L.F.
	26K10	1	46	28	L.F.
	28K10	8	83	58	L.F.
	28K9	4	44	30	L.F.
	28K7	1	40	186	L.F.
	20K4	1	24	186	L.F.
	20K5	2	48	307	L.F.
	22K7	5	134	62	L.F.
	22K4	12	30	28	L.F.
	22K6	1	34	104	L.F.
	22K9	1	34	28	L.F.
	30K9	4	45	28	L.F.
	16K9	4	24	30	L.F.
	12K1	3	12	10	L.F.
10K1	1	16	9	L.F.	