
Dustin Faust Construction Management 4/12/2007



Senior Thesis – Spring 2007



Dustin Faust

Construction Management Option

http://www.arche.psu.edu/thesis/eportfolio/2007/portfolios/DFF110/

Dustin Faust Construction Management 4/12/2007 THE PENNSYLVANIA STATE UNIVERSITY BORLAND LABORATORY RENOVATION UNIVERSITY PARK, PA

PROJECT TEAM

OWNER: THE PENNSYLVANIA STATE UNIVERSITY CONSTRUCTION TEAM: LEONARD S. FIORE ARCHITECTS: BOWER LEWIS THROWER LEED TEAM: ATELIER TEN STRUCTURAL ENGINEER: GANNETT FLEMMING MECHANICAL ENGINEER: R.G. VANDERWEIL ACOUSTICS, AV/IT: ACENTECH INC.



PROJECT OVERVIEW

LOCATION: CORNER OF CURTAIN RD. AND SHORTLIDGE RD. BUILDING SIZE: 61,415 GROSS SQUARE FEET

ESTIMATED COST: \$15,000,000

BUILDING HEIGHT: 3 STORIES - 56'

BUILDING DATES: DECEMBER 1 ST, 2006 TO APRIL 23, 2008

ARCHITECTURAL FEATURES

RENOVATING THIS 1930S BUILDING INTO CLASSROOMS, OFFICES, AND DIGITAL DESIGN STUDIOS FOR THE COLLEGE OF ARTS AND ARCHITECTURE

WILL BE THE FIRST LEED CERTIFIED PROJ-ECT FOR AN EXISTING BUILDING ON ANY PENN STATE CAMPUS

MEP SYSTEMS

NEW HVAC SYSTEM SUPLIED BY THE UNIVERSITY'S HIGH PRESSURE STEAM AND CHILLED WATER SYSTEMS

PRIMARILY FLUORESCENT LIGHTING WITH OCCUPANCY SENSORS FOR LEEDS THE CERTIFICATION

NEW UNDERGROUND UTILITIES INSTALLED



ARCHITECTURAL ENGINEERING CONSTRUCTION MANAGEMENT CAPSTONE PROJECT

HTTP://WWW.ARCHE.PSU.EDU/THESIS/EPORTFOLIO/2007/PORTFOLIOS/DFF110/

Dustin Faust Construction Management 4/12/2007

Dr. Riley PENNSTATE Borland Laboratory Renovation

Executive Summary

The Pennsylvania State University, Borland Laboratory Renovation has recently begun construction under the General Contractor of Leonard S. Fiore. The notice to proceed was given on December 1st, 2006, and the project has a substantial completion date of April 4th, 2008. Leonard S. Fiore, Inc. has worked on many astounding projects around the State College, Pa area, and has also completed many projects for Penn State. Some of their recent work for Penn State has been, Pattee Library, Community Arts Center, Research Center, and The Bryce Jordan Center Renovations.

During the Fall 2006 and Spring 2007 Semesters, I will be working on this project as an employee of The Pennsylvania State University Office of the Physical Plant (PSU OPP). Due to the tardiness in the completion of The University Creamery, there was a delay in removing production machinery from the Borland Laboratory. This caused the project start time to be pushed back drastically. However it has also allowed ample time for the Architects, Bower Lewis Thrower, to produce a 100% complete bid set. To date there has only been one minor set of revisions issued.

This renovation will be the first LEED rated project for an existing building on any Penn State Campus. Penn State has hired a construction group that specializes in designing LEED buildings. Atelier Ten has formed a list of the different LEED items they believe could be achievable for this project. This list if completed will give The Borland Laboratory Renovation a LEED Certification rating. In this review I will be looking at many different options, including a redesigned domestic water system as well as a redesign of the HCAV system. These items strive to make this renovation more Green to work towards the plans of the AIA 2030 Challenge which I will also be covering.

Dustin Faust Construction Management 4/12/2007




Table of Contents

Cover	1
Thesis	Abstract 2
Execut	ive Summary 3
Table o	of Contents 4-5
Project	t Information and Background
	Project Background
	Project Information
	Client Information
	Staffing Plan and Project Delivery System
	Building Systems Summary
	Project Schedule
	Project Cost Summary
Analys	is #1 – AIA 2030 Challenge18-24
	Executive Summary
	Background
	Proposal
	Conclusions


PENNSTATE Borland Laboratory Renovation

Analysis #2 – Domestic Water System Re-Design (Breadth).....25-33 **Executive Summary** Introduction **Solution** Comparison Conclusions **Executive Summary** Introduction **Solution** Comparison Conclusions **Appendix A – OPP Quality Service Action Plan Appendix B – Detailed Schedule Appendix C – Survey Results** Appendix D – U.S. Conference of Mayors – Resolution #50 **Appendix E – Pipe Space and Riser Detail** Appendix F – Detailed Copper Piping System Estimate **Appendix G – Detailed PEX Piping System Estimate**

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation





PENNSTATE Borland Laboratory Renovation



Project Background

The Penn State Borland Laboratory housed the Penn State Creamery for over 73 years, making it one of the most popular buildings on the University Park Campus. It is due to this fact that newly named Borland Building is being renovated, and not torn down to make room for a new structure. The current state of the Borland Laboratory consists of three different periods of construction. The renovation will take this building back to its original footprint of 1932, when the construction of Borland Laboratory was completed. From 1932 till its current state, the building has gone threw many renovations, and 2 additions. In the years 1960 through 1961, a raw-milk receiving room was added onto the back (North Side) of the building, as well as the sales room that was added to the front (South Side) of the structure.

Project Information

The Borland Laboratory is being totally renovated from its original use as Dairy Science Classrooms, and the production and sales of dairy products. After the renovation is complete, this building will house the College of Arts and Architecture. This College is currently split up between many buildings, and will soon have a building to house everyone in one spot. The layout for this building has been designed with enough offices to hold the staff and faculty for Art History, E-Learning, and Integral Arts, as well as the Deans and Associate Deans for these majors. There is ample room left for a few classrooms on the second floor, as well as four large studios and two large lecture halls designed to hold 150 students each.

Dustin Faust Construction Management 4/12/2007


PENNSTATE Borland Laboratory Renovation

Client Information

The Pennsylvania State University is ranked 40th among the <u>world's top 100 global</u> <u>institutions</u>. Penn State follows a list of very high quality standards that are backed up by the Office of the Physical Plant's <u>Construction Services Unit</u>. The Construction Services team is in charge of making sure that the project is a safe work environment for the workers and everyone on campus. Their job also consists of ensuring the Universities quality standards are met, that the job stays on schedule, and that the project is built to the specifications. The Construction Services Unit is a big part of any project on campus and more about their role in any project can be found in Appendix A on page 43.


Penn State has chosen to renovate this existing building instead of demolishing it and rebuilding. The main factor in this decision was to preserve a historical site. The Borland Laboratory was built in 1932 to enhance the research of dairy products. They also produced and sold ice-cream from this facility that has been known as the "University Creamery" ever since and has become a landmark at Penn State for anyone visiting. The creamery has just been moved one block East on Curtain road to the brand new Food Sciences building and the sales room has been renamed to the Berkey Creamery.

Then Pennsylvania State University has given a construction cost estimate of \$11,800,000 and a total project cost of \$15,000,000. This will include a lot of planning and scheduling on both sides of the project, because the campus is occupied by nearly 40,000 students almost everyday. This makes utility shutdowns and tie-ins very difficult to not disrupt the normal day activities of the students.



Staffing Plan and Project Delivery System

The staffing Plan located bellow shows all of the parties involved on the Borland Laboratory Renovation project. Also shown are the two types of contracts that have been utilized for this project. Penn State holds a cost and fee contract with Bower Lewis Thrower, the architect, who has sub-contracted out for all of the engineers, using a lump sum contract. Penn State also holds a lump sum contract with Leonard S. Fiore, the General Contractor. Fiore also holds a lump sum contract with all of the sub-contractors being utilized on the building.



http://www.arche.psu.edu/thesis/eportfolio/2007/portfolios/DFF110/

Dustin Faust Construction Management 4/12/2007

Dr. Riley PENNSTATE Borland Laboratory Renovation

Building Systems Summary

Demolition

Being a renovation of the existing Borland Laboratory, three months will be spent in the demolition and abatement phases for this project. All together, the interior walls on the ground, first, and second floors will be demolished to make room for a new floor plan. As an effect to this, the HVAC system will be totally removed from the building to make room for a new state of the art system. As for any Plumbing and Electrical fixtures, the supply lines will be cut and terminated at the entry point to the building. During the construction phase, the existing electrical supply to the building will be metered by Penn State University Office of the Physical Plant (OPP) and used for the temporary construction power. This will be used until the new electrical utility lines are installed across Shortlidge Road. The existing water supply will also be metered by OPP and used during the construction phase.

Along with the demolition phase comes a very large portion of this project. That is to remove the dairy products sales room on the South side of the building and also the raw-milk receiving room on the North side of the building. These two portions of the existing building where additions to the original structure. They will be removed and brick will be matched to the original to fill in any spaces needed. Also the beginning of the demolition phase will include asbestos abatement. Like many of the other older buildings on The Pennsylvania State University Campus, the Borland Laboratory contains asbestos fire proofing on the ceilings as well as pipe insulation, and floor tiles that must be abated. Before any other demolition or construction begins, the abatement crew will remove all of the harmful substances, following the Environmental Health and Safety Codes.

Structural Steel Frame

Since this project is a renovation of the Borland Laboratory, and the existing building envelope will be reused. There is a minimal amount of structural steel framing to be done on the first and second floors. Due to the relocation of duct banks, elevator shafts, and stairs, there will be an estimated 27.5 Tons of steel added to support the above floors. On the Second floor, in the existing attic, space will be made to allow for more offices and storage space. A skylight section will be cut into the roof to allow natural light to enter these areas. The majority of steel connections for this area have been designed for a double angle shear connections.

Cast in Place Concrete

The original project scope called for very little cast in place concrete aside from new sidewalks and patios in the landscape. During the demolition phase, a lot of unforeseen conditions were uncovered. During the construction of the original building, a base floor was poured and then the terracotta block walls were placed on top of this. After that was completed, a finish layer of concrete was placed on top partially burying the walls, and causing each room to have a different finished floor height. Due to this problem, a change order has been issued to place a flow able fill of concrete into each section in order to attempt to level out each floor.

Dr. Riley PENNSTATE Borland Laboratory Renovation

Mechanical System

There are two mechanical rooms located in the basement. MB001 contains domestic water pumps, low pressure steam water heaters, and the hot water pumps. Located in MB002 are the chilled water pumps that take the University supplied chilled water and pumps it to the Air Handling Units (AHU) on the above floors.

This project requires 4 Air Handling Units. AHU1 and AHU2 are both located on the Second Floor in room M223. They are designed by <u>Trane</u> to have a maximum of 14,000 Cubic Feet per Minute (CFM) of air flow. The other two units (AHU3 and AHU4) are located on the room in on the Penthouse floor in room M301. These two units have also been designed by Trane and have a maximum CFM of 12,000.

There will be two different types of fire protection utilized on this project. A wet system will be used in all pipe spaces, common areas, offices, and classrooms. Due to some equipment that could be damaged by a water leak, in the mechanical rooms and computer labs, and dry system will be utilized using schedule 40 galvanized piping.

Electrical System

The Borland Laboratory power system is supplied by The Pennsylvania State University's power plant. Before entering the building, the power system will run through a transformer supplied by the University. Upon entering the building, the power supply is fed into a 280/120V, 3 phase, 4 wire, 2000 A switchgear. This switchgear then distributes the power to many different areas. The main switchgear carries a total connected and demanded load of 543.6 KW.

PENNSTATE Borland Laboratory Renovation

The emergency power is also being supplied from The Pennsylvania State University. It will come from the University's campus emergency back-up system. The emergency power for this building is switched at a 240/120V, 2 phase, 3 wire, 150A transfer-switch. This switch will automatically transfer power to the Normal Emergency and Emergency circuits in the case of a power loss.

Masonry

A lot of careful work will be put into the masonry part of this project. Due to the two additions that were added onto the original building, a large amount of brick will need to be replaced to match the original façade. It will be attempted to salvage some of the original brick that is part of a retaining wall that is being removed. A sample of brick has also been picked out with a special colored mortar that has been placed into a mock-up and approved for use as well.

Excavation

There will be the usual excavation done to the exterior of the building for landscaping and other architectural features, as well as for the new utility lines. The only excavation needed for the building is a 8'x8'x10' pit for the elevator shaft, and two sump pump pits 9 feet deep in the basement that will need to be hand dug..

PENNSTATE Borland Laboratory Renovation

Project Schedule

Below is a schedule showing the administrative milestones for the Borland Laboratory Renovation. A detailed schedule has been included in Appendix B on pages 44-60. Some important milestones that I would like to point out are the all of the mockups. For a renovation project, mockups are a very important process. This is to ensure to the owner that the materials being used on the project match the original materials, which have been aged, as close as possible. Extensive research of bricks, stone, and joint sealant has been done to allow a wide variety of choices for the Penn State officials to choose from.


Two other very important mockups are for the masonry restoration, and the masonry cleaning process. There are many spots in the existing façade that contain damaged brick that must be delicately replaced, in order to not disturb the surrounding brick. In conjunction with this, all of the limestone on the building is being cleaned. Many test samples have been done to find a suitable acid wash that will not damage the nostalgic look of the limestone, or hurt the brick that is surrounding it. Penn State is very proud of the historical buildings on all of the campuses, and strive to keep them up to date while preserving their historical

Administrative Milestone Schedule

Activity	Activity Description	Orig Dur		%	Early Start	-inigh	2006 DEC JAN	FEB MAR	APR MAY					NOV	DEC			2008 MAR A		Y JUN I
ADMINISTR 10	Notice to Proceed	0	0	100	01DEC06A		Notice to Proceed	1	1		1	1				1	1		1	
20	Mobilize/Fence	3	3	0	01DEC06	05DEC06	Mobilize/Fence		1		1	i i		1 1	1	i t	1		1	i. L
660	SUBMITTALS/APPROVALS	120	120	0	01DEC06	22MAY07			: Vs	UBMITTALS/AP	PROV	NLS		1 1		1	1		1	1
670	FABRICATION/DELIVERY	160	160	0	15DEC06	02AUG07			:		F	ABRICATIO	WDELIVERY			1	1		1	1
1860	PREFUNCTION TEST AND INSP.	280	280	0	24JAN07	03MAR08						n over starting		×	X	A CONTRACTOR OF STREET	₩	REFUNCT	ION TEST	IND INSP.
2810	MASONRY MOCKUP	0	0	0	05APR07					KUP	1	1		1 1		1	1		l l	1
2820	MASONRY RESTORATION MOCKUP	0	0	0	05APR07		1			TORATION MOO	CKUP	1		I I		1	1		1	1
2830	MASONRY CLEANING MOCKUP	0	0	0	05APR07		1	1	♦MASONRY CLEA	ANING MOCKU	P 	1		1 1 1 1		1 1	1 1		1	1
2840	STONE MOCKUP	0	0	0	05APR07		1				1	1		1 1		1	1		1	1
2870	WINDOW/GLAZING MOCKUP	0	0	0	14MAY07				♦ WIN	DOW/GLAZING	MOCK	UP					1		1	i.
	SUBMIT OEM/ CLOSEOUT DOCS.	60	60	0	23MAY07	16AUG07		1				SUBMIT	OEM/ CLOS	EOUT DOC	S.	t I	I		1	1
2860	JOINT SEALANT MOCKUP	0	0	0	29JUN07			l I	i I		IT SEAL	ANT MOCK	UP	i i 1 i	_	i I	1		i	i
2850	FINISH CARP. MOCKUP	0	0	0	16AUG07		1	l I I	1		1	♦FINISH C	ARP. MOCK	UP I		1	1		1	1
1870	FUNCTIONAL TESTING	130	130	0	14SEP07	20MAR08	1		1 1	2	i I			H.	XX			≡VFUNC" ■□	TIONAL TE	TING
1800	COMMISSIONING/FLUSHOUT	20	20	0	04MAR08	31MAR08	1		1	1	1	1		- ct	MINISSIO	NING/FLUS			I	
1810	SUBSTANTIAL COMPLETION	0	0	0	-	18MAR08		1	1	1	1	1		1 1		I I	1	♦SUBST ♦	TANTIAL CO	MPLETION
1830	COMPLETE PUNCHLIST	15	15	0	19MAR08	08APR08			I		1	i				i	1		COMPLETE	PUNCHLIST
1850	FINAL CLEANING	20	20	0	26MAR08	22APR08	1	1	1	1	î I	l		1 I 1 I		I I	i	6		LEANING
1840	FINAL COMPLETION	0	0	0	23APR08			1	1	1	1	1		1 I 1 I		1	1		♦FINAL	COMPLETION
tart Date inish Date ata Date un Date	01DEC 22APR 01DEC 14FEB07 16:	08				Early Bar Target Bar Progress Bar Critical Activit	BL1D	Borland La	S. Fiore, Inc. b Renovation Schedule	Shoo	at 1 of 17	Date 14FEB07 08JAN07 10DEC06		lude site and lude interior li emo/Abatemer	nishos			Ch	necked	Approved
© I	Primavera Systems, Inc.																		-	

http://www.arche.psu.edu/thesis/eportfolio/2007/portfolios/DFF110/

Dustin Faust Construction Management 4/12/2007



Project Cost Summary

ACTUAL COST ESTIMATE

The total area being renovated on this project is 76,000 sf. Below is a cost

breakdown showing the estimated costs for this building, and unit costs.

• Base Building: **\$10,365,600**

o Unit Cost: \$136.40 /sf

• Site Development: **\$518,400**

o Unit Cost: 5%

- Utilities: **\$360,000**
- Major Maintenance Upgrades: \$381,000
- Telecommunications Networking: **\$175,000**
- Total Estimated Construction Costs: **\$11,800,000**

o Unit Cost: \$155.30 /sf

• Soft Costs: **\$2,000,000**

o Unit Cost: 16.9%

PENNSTATE Borland Laboratory Renovation

- o Total Estimated Project Costs (w/o FF&E): \$13,800,000
 - o Unit Cost: \$181.6 /sf
- FF&E: **\$1,200,000**
 - o Unit Cost: 10.2%
- o Total Estimated Project Costs (w/ FF&E): \$15,000,000

o Unit Cost: \$197.4 /sf


Parametric Estimate using D4 Cost 2002

Using this program I compared the Borland Laboratory Renovation to a College Expansion & Renovation at Brookhaven College located in Dallas, Texas. The estimate given for this college renovation was for a 20,000 square foot project. I adjusted the provided information to fit the Borland Laboratory project, and produced a fairly accurate estimate of \$14,547,725. This estimate came within \$400,000 of the actual predicted cost for this project.

RS Means SF Estimate

The estimate given by RS Means is about half of the actual cost for this building, coming in at \$9,112,150. This is due to the extensive mechanical and AV/IT system that Borland Laboratory will hold.

Dustin Faust Construction Management 4/12/2007





Executive Summary


Dustin Faust

4/12/2007

This proposal is a very critical issue in the construction industry. The following research done covers The American Institute of Architects (AIA) 2030 Challenge. The AIA was formed on February 23rd, 1857 by 13 architects, and has represented all of America's architects since. The AIA acts as the voice of the architectural profession, and provides many services and resources to its members. One goal of this group is to make the construction industry more eco friendly. Their way of doing this was to develop the AIA 2030 Challenge.

The 2030 challenge was founded by Edward Mazria from the AIA. He is an internationally known architect for his 30 years of work designing environmentally friendly structures. The AIA 2030 challenge was designed to be a flexible, non-traditional plan, with protecting Earth's environment being its primary goal.


The following research includes a background of the 2030 challenge, a list of problems that Earth is facing, and the solution to making this plan effective. Also included is a compilation of surveys taken from various architects in the field.



Background


4/12/2007

Everyone has heard about Global Greenhouse Gas Emissions, and the effects it has on our environment. The most commonly known causes to this problem are gas emissions, and power plants. However, Unknown to many people, the construction industry has posed a huge effect on the greenhouse gases that pollute this world. Bellow is a graph comparing the major carbon creating industries showing that the building industry has climbed to be the highest.




Source: U.S. Energy Information Administration statistics


The American Institute of Architects (AIA) has proposed a plan called The 2030 Challenge to fix this problem. An investigation done by the AIA Research Corporation has determined that by the year 2030, 150 billion square feet of building renovations will be completed. Along with another 150 billion square feet of new construction.



Since the Borland Laboratory Renovation is a remodeling project this proposal will look at how the construction industry can become greener with renovation projects. The goal is to reduce the use of fossil fuels to construct and operate all buildings by the year 2030, making them carbon-neutral. This must be completed by designing high-performance, carbon-neutral buildings as well as renovations. As seen bellow in a diagram done by the AIA research Corporation, the remodeling industry is a great part of the total construction done in the country.

4/12/2007





Proposal

The main goal set by the AIA 2030 Challenge is that the fossil fuel reduction for all new and remodeled building increase to:

- o 60% in 2010
- o 70% in 2015
- o 80% in 2020
- o 90% in 2025
- Carbon Neutral by 2030.

There are many solutions possible to push the construction industry towards meeting these goals. The best place to start is at the source of the problem. That is in the design phase of all renovations. Architects and engineers must consider the Earth's environment when designing and building projects. To ensure this, a Green Design course should be administered to all architectural and engineering students.

A survey was conducted through the Architecture Faculty at Penn State. The results can be found in Appendix C on pages 61-63. These results show that none of the people surveyed have heard of the AIA 2030 Challenge. However when informed of the challenge, and its goals, they all feel that it is an excellent idea, and believe that it is achievable.

The survey shows that the AIA 2030 Challenge is an outstanding program, however, it is not widely known. This leads into the second part of the solution, education of the public. The best way to lead the public is by example. That is why I propose that Penn State put into effect a plan to meet the goals set by this challenge.

PENNSTATE Borland Laboratory Renovation

The Pennsylvania State University is a growing college community that is widely known for its State-of-the-Art facilities, and beautiful campuses. If a plan were implemented at this university to develop more green, and carbon neutral buildings, not only would it help the cause, but it would also set an example for other colleges, and builders across the country.

Possibly the biggest challenge for this project will be to convince the owners, and future builders to make their properties more carbon-neutral. In accordance with this, a resolution has been proposed to adopt the 2030 challenge in city buildings. Saying; The U.S. Conference of Mayors will encourage its members to adopt the following "2030 Challenge" for building performance targets. New construction, renovation projects, repairs and replacements of city buildings shall be designed to achieve a minimum delivered fossil-fuel energy consumption performance standard of one half the U.S. average for that building type as defined by the U.S. Department of Energy. Also to follow green building practices to the maximum extent possible. Resolution number 50 is located in Appendix D on page 64-66.

During the 1970's, a energy crisis led to a massive amount of research being developed on the materials used in the building industry. New materials such as high-performance glazing's for glass materials, more efficient and recycled insulating materials, and new geo-thermal mechanical systems were formed. A large part of the carbon being emitted comes from the production of energy which is used to produce green items. To further advance the 2030 challenge, more efficient ways of making energy must be used. Such as, photovoltaics, solar hot water, fuel cells, micro-hydro, wind, geo-exchange, etc.



Conclusions

4/12/2007

In conclusion, the AIA 2030 challenge is well underway, however it is not on pace to achieving its upcoming goal of a 60% reduction by the year 2010. The solutions I proposed will help push this country towards the goals set. To date, the Mayors of Albuquerque, Seattle, Chicago, and Miami have accepted resolution #50 for their respective cities, and show how this can be put into effect world-wide.

The problem does not lie within the technology, we have the technologies to be able to produce carbon neutral buildings and energy. The obstacle is in the education of the public.

Dustin Faust Construction Management 4/12/2007





Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

Executive Summary


The Borland Laboratory Renovation has been designed with a costly copper tubing domestic water system. Not only is this system expensive, but the soldered joints being used are very time intensive. This part of my research explores a cross-linked polyethylene tubing also known as PEX tubing, which is unfamiliar in larger buildings.

Extensive research has been done on PEX tubing including long-term pressure testing in extreme temperature and pressure conditions for more than 30 years. PEX tubing also undergoes extreme testing against the effects of chlorinated water to ensure it can withstand chlorines' effects on natural materials.

In order to ensure an accurate comparison between the design system, and the proposed system, a detailed take-off of each system has been completed. These take-offs were then estimated by Schuylkill Sales Company, a plumbing contractor in the Easter Pennsylvania area. All prices in the comparison are from APR Supply company, and do not include any markups. A labor savings has also been estimated for the comparison to show any schedule savings.

After comparing the two systems, a savings of \$8,668.56 and 96 man hours has been estimated when using the proposed PEX tubing system. Further details will be covered in the following analysis.

Dustin Faust Construction Management 4/12/2007



Introduction

In concurrence with the 2030 challenge, this analysis will discuss redesigning the domestic water piping system to a more green material. The current piping system consists mostly of copper tubing. A new system has been designed using a cross-linked polyethylene tubing. Contrary to popular belief, this product also known as PEX is a green material. It is often confused with a normal polyethylene tubing called PE which causes many toxins when manufactured. Also PE tubing was unable to be ground up and recycled for new tubing. New developments allow the PEX tubing to be recycled and also give it a much longer life span. PEX tubing is manufactured cleanly and consumes far less energy than the manufacturing of metallic piping. Also the price of copper is very, high, and climbing.

Helping the environment isn't the only benefit to using this product. The Borland Laboratory Renovation is a perfect place for PEX tubing to be used. Since this is a plastic like material, it allows the tubing to be bent around corners and odd shapes without the use of extra fittings. This project is an existing building which would make it difficult to run ridged copper tubing around the many obstacles that exist in the floor and ceiling plenums.

The domestic water system that is currently being installed is an all copper system using soldered joints. The new proposed PEX system will look very similar to the designed system. Currently, the supplies for each floor have been designed to come from the basement through a floor penetration in the pipe space between each bathroom. A detail of this can be seen in Appendix E on page 67. From the penetration through the floor, the water is then distributed to of the necessary locations.

PENNSTATE Borland Laboratory Renovation

Solution

The price of copper tubing is at an all time high. My solution for this problem is something that has not been used in an commercial building sense before. PEX tubing is well know for being a cheap and effective way to supply domestic water, and hot water for heating purposes to residential buildings. However metallic piping is still preferred in larger buildings such as the Borland Laboratory Renovation.

There are many perks to using PEX tubing in a building such as this. They are as follows:

- PEX tubing is much cheaper compared to copper tubing.
- Due to flexibility, PEX tubing is easier to handle and install.
- PEX tubing is safe for the environment.
- PEX tubing is the most heavily tested piping material in the world.
- PEX tubing is much lighter than traditional metallic pipe, causing a reduction in the manufacturing and transportation of the material.
- A manifold system typically used with PEX tubing allows for all of the shutoff valves to be located in one spot rather than spread around the building.
- PEX tubing can be recycled into a variety of plastic fillers.



Comparison

4/12/2007

Designed Copper Tubing System

The designed copper tubing system uses a rigid type L copper tubing, ranging in sizes from 3" to $\frac{1}{2}$ ". This tubing uses copper fittings which is joined by using a soldering operation. The soldering operation involves melting a non-lead material into the joints of the pipe making a air and water tight seal. This non-lead solder has a much lower melting temperature than the copper piping allowing it to flow into the very small gap between the tubing and the fitting, with-out damaging the piping.

The cost of this system with out any mark-ups has been compiled. A overview of this estimate is shown bellow. The detailed estimate that was done can be found in Appendix F on pages 68-72.

Copper Piping System	
Copper Pipe Total Cost	\$17,122.70
Copper Fittings Total Cost	\$3,839.57
Total Cost	\$20,962.27

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

Proposed PEX Tubing System

The Proposed PEX tubing system will consist of a combination of PEX tubing and copper tubing. This is because PEX tubing is only practically used in the sizes ranging from $1'' - \frac{1}{2}''$. In the newly designed system, copper piping will be run from the basement to a manifold on each floor that is located in the piping space between the bathrooms. The same area the designed risers are located.


PEX tubing is a flexible material that can be bent around corners with-out the need of a fitting. An example of this is demonstrated in the figure below. When a fitting is necessary, a brass fitting is used that has a set of reversed barbs on it to lock the pipe onto it. A cinch ring is then placed over the joint, and a specialized crimper is used to tighten this ring around the pipe and fitting making a air and water tight seal. This seal is unlike a soldered seal, and can be rotated easily to allow adjustments without compromising the seal of the joint.



Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

One of the biggest differences between the designed copper system, and the proposed PEX system, is the new system uses a home-run manifold. With this system, the water supplies are run from the basement to each floor and then distributed from there. The pipes supplying each facility will go in the same path as the copper has been designed. However with the copper system, each faucet is supplied from the ceiling plenum, where the shut-off valve for it is located. One of the advantages to a manifold system is that all of the shut-off valves are located in a centralized location, at the manifold. This makes it extremely easier to isolate certain parts of a system. Due to the size of the pipe supplying each floor, a prefabricated manifold can not be utilized, and one will need to be made using copper fittings. An example of a prefabricated manifold can be seen below. The manifold made with copper fittings would look similar to this.



31

http://www.arche.psu.edu/thesis/eportfolio/2007/portfolios/DFF110/



A detailed cost estimate of this system has been compiled, and is located in Appendix G on pages 73-77. Located bellow is an overview of this estimate showing just the rates of the materials with out any mark-ups. The same amount of piping is used for each system, however, the PEX system uses a combination of copper and PEX tubing. Due to this, there are some extra fitting that need to be utilized in order to adapt from PEX to copper pipe. However this extra cost is compensated by the elimination of many of the 90 ° elbows that are used in the rigid piping system.

Dustin Faust

4/12/2007

	PEX Piping System	
F	PEX & Copper Pipe Total Cost	\$10,866.84
I	PEX & Copper Fittings Total Cost	\$1,426.84
	Total Cost	\$12,293.71



Conclusions

4/12/2007

PEX vs. Copper Comparison


Aside from the advantages of using a PEX system that were covered above, there are two others that have a great impact on this project. That is the cost and schedule savings. The total cost savings between the two for just materials with no mark up is \$8,668.56. Along with this, there is an estimated time savings of 96 man hours. This will add onto the cost savings, as well as have an effect on the construction schedule.


Recommendations

My recommendations for this project are based off of three different things. The first two are the obvious. That being the cost and schedule savings. They might seem miniscule on such a large project, however in the end, every penny, and hour counts. The third thing is my experience of working with PEX tubing. I worked with Schuylkill Sales Company for many years, and used PEX tubing extensively on many residential buildings. It was used successfully in new construction and renovations. I found this tubing very easy to work with, and in most times creates a better final product.

In conclusion I recommend using the PEX & Copper system for this project for all of the above stated reasons. I feel that in conjunction with the AIA 2030 challenge, and more and more buildings being build using green methods, that PEX tubing will be seen a lot in commercial buildings, and not just in a residential aspect.

Dustin Faust Construction Management 4/12/2007





http://www.arche.psu.edu/thesis/eportfolio/2007/portfolios/DFF110/

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

Executive Summary

Following with the same theme of the research on the Borland Laboratory Renovation, this analysis will cover a green option for the HVAC mechanical system. When designing the mechanical system for a building, there are many options. This analysis will compare two of them. Those two systems are, a geo-thermal system, and the designed system. The designed system uses steam supplied by the university for heat, and chilled water also supplied by the university.

The advances in geo-thermal systems have grown exponentially. This system is another example of the many things that the commercial buildings can learn from residential houses. Just like PEX tubing, geo-thermal HVAC systems were originally developed for and used primarily in residential houses. In the past 15 years, this type of system has grown more popular in federal and commercial sectors.

The standard system that has been designed for this project is very un-efficient. For the cooling, water is received from Penn State's chilled water system, and supplied to the Air Handling Units (AHUs) in the mechanical room. The heating system works the same way. Low Pressure steam is used to supply heat to the AHUs.

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

Introduction

Following with the AIA 2030 Challenge, Penn State is trying to due its part. The Borland Laboratory Renovation will be the first renovated building on a Penn State Campus to be LEED Certified. The amount of points specified for this building is very close to obtaining a Silver LEED Rating. This could easily be accomplished by changing a few small things in the demolition phases of the project. However, a great way to work toward the 2030 challenge is to use a green mechanical system on this project.

The advances in geo-thermal heating and cooling have greatly increased in the past few years. A study has been completed that compares the existing HVAC system, to one that uses geo-thermal technologies. The coal burned in Penn State's power plant creates a great amount of the carbon that the AIA 2030 challenge is trying to eliminate. The use of a geothermal HVAC system on the Borland Laboratory Renovations would only be a start to fixing the carbon problem on the University Park Campus. However it is a step in the right direction.


Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation


Solution

The issue of green house gasses can not be fixed in one day. However, by using the energy that is readably supplied by the Earth, we can reach our goal. A geo-thermal HVAC system uses the natural heat and cooling that is trapped beneath the ground to heat and cool a building.

Unlike the air, water, and soil on the surface, underground, the earth and water stay at a very stable temperature of about 55 ° F at a depth of 10 ft, or more. To capture this stored energy and use it in buildings, many feet of pipe are either vertically submerged in various wells in the ground, or run horizontally 10 or more feet under the ground. During the heating months, a specially formulated liquid is pumped through these pipes, which captures the heat from the soil, and circulated back to the AHUs in the mechanical room. During the cooling months, the same process is repeated, however the soil sucks the heat from the liquid, making it cooler, and sending it back to the AHUs. An example of these loops and how they work can be seen in the figures below.



Dustin Faust Construction Management 4/12/2007



Listed below are a few advantages of using a geo-thermal heat pump system over any standard HVAC system.

- A very durable piping with a life cycle of 30 to 50 years.
- A 25 to 40 percent savings in heating and cooling cost.
- A Earth friendly system.
- Very simple controls.
- No need to use the University's steam or chilled water systems.



Comparison

4/12/2007

University Supplied HVAC System

The Pennsylvania State University, University Park, uses 270,000,000 kWh annually. Along with that outstanding amount of energy, 452,000 Mcf of natural gas, and 72,000 Tons of bituminous coal are used to run this campus. Most of the buildings on campus have systems in place that use the low pressure steam, and chilled water supplied. These systems account for most of this energy being used. With all of that natural gas, and coal being burned, this creates a very large amount of carbon that is being released into the Earth's atmosphere.

The System designed for the Borland Laboratory Renovation consists of 4 Trane AHUs. Two of these units are 35 tons and have a maximum of 14,000 Cubic Feet per Minute (CFM). The other two units are 30 tons and 12,000 CFMs. In most buildings, the HVAC systems are over designed to allow in extreme fluctuations in temperature, causing excessive energy consumption. However after speaking with the manager in charge of all heating and cooling systems on the University Park Campus, it was determined that due to a lack of funds, these 4 units are not over designed.

PENNSTATE Borland Laboratory Renovation

Geo-Thermal Heat Pump System

As explained above, a geo-thermal heat pump system requires a vast amount of tubing immersed in the soil or ground water for this to work efficiently. According to Schuylkill Sales Company, a rule of thumb for estimating the amount of tubing needed for a system is 200-250 ft/Ton. Using this rule, with the 4 units adding up to 130 Tons of heating a cooling, a maximum of 32,500 ft or 6.16 miles of tubing would be required.

At this point in the analysis, it was determined that this type of system would not be feasible for the Borland Laboratory Renovation. The amount of piping needed to allow for this geo-thermal heat pump system to run efficiently would require a large amount of undeveloped land. The area for this underground tubing can not have a parking lot or any other structure on top of it. This would cause all of the heat to be trapped underground for an extended period of time during climate changes. This would cause the system to not work properly. In the area around the Borland Laboratory Renovation, there is not enough green space to allow a system of this type. So the calculations stopped at this point.

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

Conclusions


Due to the lack of green space around the Borland Laboratory Renovation, the use of a geo-thermal heat pump system is not possible. In theory this system is a very good idea, and great for the environment. This type of system can and has worked very well for various buildings with a large amount of green space around.

With some planning from the Pennsylvania State University Office of the Physical Plant, and geo-thermal heat pump system could be utilized in all of the building on the University Park campus. This would eliminate a large amount of carbon that is being produce here, and save a large amount of money in the future. In order to make this work, the University would have to have a large amount of land that is used only for a geo-thermal well bed. I believe that with enough wells in place, the geo-thermally treated liquid could be circulated throughout the campus and to each building just like the existing steam and chilled water lines.

A plan like this is something for Penn State to consider in the future. This would require all of the HVAC systems on campus to be changed in every building. Along with a vast amount of underground piping, this would be a very costly campus wide renovation.

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation



Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation



Appendix A

QUALITY SERVICE ACTION PLAN CONSTRUCTION SERVICES OFFICE OF PHYSICAL PLANT

OUR CUSTOMERS: Facility Coordinators, Project Managers, Project Coordinators, Contractors, Parking Office, faculty, students, university personnel, community, L&I inspectors, local codes/zoning, police services, Accounting, Design Professionals, Design Services, building users, and other OPP departments.

OUR CUSTOMERS' EXPECTATIONS: Facilitation of the timely delivery of quality projects. They also expect us to be courteous and reliable while being committed to maintaining a positive and safe working environment.

OUR QUALITY SERVICE STANDARDS:

SAFE ENVIRONMENT:

- 1. Maintain organized and safe project sites.
- 2. Ensure installation of signage to communicate unsafe areas.
- 3. Ensure proper separation between occupied and non-occupied spaces.
- 4. Assure jobsite safety through inspection and observation.
- 5. Initiate and monitor corrective actions.
- 6. Focus on the environment around jobsite to ensure public safety.

SERVICE ATTITUDE:

- 1. Respond in a courteous, positive, and timely manner.
- 2. Empathetically listen to customers' needs and concerns.
- 3. Effectively communicate project information to all entities involved.

STEWARDSHIP:

- 1. Ensure contractors comply with contract requirements and quality standards.
- 2. Continuously inspect, monitor, and evaluate performance of contractor.
- 3. Coordinate project requirements to help facilitate the timely completion of the project.
- 4. Provide leadership at job conferences to resolve project issues.

EASE OF SERVICE:

- 1. Clearly identify all points of contacts for the work.
- 2. Ensure availability to allow timely resolution of project issues.
- 3. Provide continuous customer assistance throughout project process.
- 4. Pro-actively communicate project status.


EFFICIENCY:

- 1. Take a pro-active team approach maintaining positive relationships.
- 2. Establish a quality control action plan for the project.
- 3. Reduce rework through continuous monitoring of the work.
- 4. Attempt to review assigned projects during the pre-construction stage.
- 5. Periodically review and streamline the flow of communication.
- 6. Monitor project long-lead items to ensure timely delivery.
- 7. Track project schedule providing input throughout the project.
- 8. Commit to an efficient close-out/turnover of the project.

DEAR CUSTOMER,

The Construction Services department within Design and Construction Services is committed to exceeding your expectations by providing a positive and safe working environment through leadership and collaborative efforts. We will continuously strive to ensure all contract requirements are met in a timely manner and at the highest quality.

Dustin Faust Construction Management 4/12/2007



Appendix B

Detailed Schedule

Detailed Schedule

ID Ind Floor W 70	Description	Dur			Elalah	N DEC	JAN	FEB	MAR	APR	MAY	JUN	07 JUL	AUG S	P OCT	NOV	DEC	JAN	FEB	IVIAIS	APR	IVIAT 1	JUN
1000		A THE WEAR	Dui	Start	Finish		1.1.1.1.1	1.1.1.1		1.1.1.1.	1.1.1.1	1-1-1-1-1-1	1.1.1.1.				1.1.1.1	1 1 1 1 1	1 1 1 1		. 1. 1. 1. 1.	0.1.1.1.1	1.1.1.1
	Salvage	3	3	0 15DEC06	19DEC06	∕√ Sah □	vage				1			1		1	1						
80	Misc. Abate	3	3	0 18DEC06	20DEC06	∕ Wis □	sc. Abate	i.		0. L	1		1	1		1	1 1		() ()		1		
90	Demo Walls and Ceilings	15	15	0 20DEC06	11JAN07		Demo V	Walls and	d Ceiling	S	1			1		1	1		1	F.	1		
100	Floor Abate	6	6	0 12JAN07	19JAN07		Floo	or Abate		1	1		1	1		1	1		l I		1	1	
110	Clear and Cleanup	2	2	0 22JAN07	23JAN07		Cle	ear and C	leanup	1	1		1	1		1	1				1	1	
890	CEILING HANGERS	5	5	0 24JAN07	30JAN07			CEILING	HANGER	S i	1		1	1		1	1				1	1	
260	SPRAY INSULATION	15	15	0 26FEB07*	16MAR07		1		SPR.	AY INSUL	ATION		1	1		1	l F		1		1	1	
490	HVAC MAIN DUCTS	25	25	0 19MAR07	23APR07		5	1			AC MAI	NDUCTS	1	1		1	1		 		1	1	
470	SPRINKLER ROUGH-INS	10	10	0 26MAR07	09APR07		1	1			KLER RO	DUGH-INS	1	1		1	1				1	1	
1880	HVAC BRANCH DUCTS	15	15	0 03APR07	23APR07		1	1			AC BRA	NCH DUC	TS	1		1	1		1		1	i	
140	FLOOR OPENING	10	10	0 05APR07	18APR07		1	1			OOR OPE	NING	1	1		1	1	and more the same instances of the second second	 		1	1	
460	METAL STUD FRAMING	15	15	0 10APR07	30APR07		1	1			METAL \$	STUD FRA	MING	1		1	1				i I	1	
500	ELECTRIC/TELE. ROUGH-INS	20	20	0 17APR07	14MAY07		1	I I				CTRIC/TE	LE. ROUG	HHNS		1	1		1 1 1 1		 	1	
230	ELEVATOR STEEL	5	5	0 19APR07	25APR07		. 1	1			LEVATO	R STEEL	1	1			1		 		1	1	
480	PLUMBING ROUGH-INS	10	10	0 01MAY07	14MAY07			1		A	PLU	MBING RO	DUGH-INS						1		1	1	
640	PATCH WALLS/MAS. INFILLS	10	10	0 01MAY07	14MAY07		.1					CH WALL	S/MAS. IN	FILLS		1	1				I	1	
930	TELECOM CLOSET	10	10	0 01MAY07	14MAY07		1	1				ECOM CL	OSET	1		1					1	i	
690	MEP INSPECTIONS	5	5	0 15MAY07	21MAY07		l J	1		1		EP INSPE		1		1	1		1 1		1	1	
870	HVAC INSULATION/ATC	15	15	0 22MAY07	12JUN07		I I	1		1			CINSULAT	non/at¢		1	1		 		1	1	
t Data	04054					BL1D							Sheet 2 of 1	17					_			1.0	
t Date sh Date	01DE0 22API		Contract (1997)	and a state of the	Early Bar	BLID		10	2 breno	Fiore, Inc	c		31001 2 01 1	Date	1		Revisio	m			Checked	An	proved
a Date	01DE0		No. of Concession, Name		Target Bar			Bor	land I ah	Renovati	ion			14FEB07	Revised to inc	lude site and					University	- AP	10000
Dato	14FEB07 16		10 - 10 - 10 - 10 - 10 - 10 - 10 - 10 -	the second second	Progress Bar			BOI	Target S	Schedule				08JAN07	Revised to inc								
					Critical Activi	ty			raiget S	Chedule				10DEC06	Preliminary D	emo/Abatem	ent Plan						
		_																					
C	Primavera Systems, Inc.																					1	

arly 2006 2007 2008 N DEC JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC JAN FEB MAR APR MA hish	
	I I I I
07	
	1
G07	1
G07	
	1
	1
	1
	1
	1
	1
507 Final Paint	1
	1
	1
ndu Baz BL1D Shoot 3 of 17	
ariy Bar Date Date Date Chaster	Approved
arget Bar Berland Lab Renovation 14FEB07 Revised to Include site and shell	
Tarret Schedule U8JAN07 Revised to include interior finishes	
10DEC06 Preliminary Demo/Abatement Plan	
ritical Activity 10DEC06 Preliminary Demo/Abatement Plan	

Start Date	01DEC06	Early Bar	BL1D	Sheet 3 of 17		
Finish Date	22APR08		Leonard S. Fiore, Inc.		Date	Revision
Data Date	01DEC06	Targot Bar	Borland Lab Renovation		14FEB07	Revised to Include site and shell
Run Date	14FEB07 16:14		Target Schedule		08JAN07	Revised to include Interior finishes
		Critical Activity	raiget Schedule		10DEC06	Preliminary Demo/Abatement Plan
		<u> </u>				
© Primavera Sy	ystems, Inc.	-				

Activity ID	Activity						2006						200	1								21	800		
	Description	Dur	Rem Dur	%	Early Start	Early Finish	N DEC	JAN	FEB	MAR		MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN
2nd Floor Ea	CONTRACTOR OF THE OWNER OWNER.	27-0 S					1111111		1 1			1		de la de de de			the hand of the		1	1	1		1.1.1.1	l'ale al de la s	hand as the district
30	Salvage	3	3	0	01DEC06	05DEC06	AV Salvage)				ł		1	ł			i		1	1		4. 1		
40	Attic Demo	7	7	0	06DEC06	14DEC06		Demo				1		1	1		1	l t		1	1		1		1
50	MEP Abate (Lights)	10	10	0	15DEC06	29DEC06		WEP Aba	te (Lights))		1		1	1			1		1	1		1		
60	Clear and Cleanup	5	5	0	02JAN07	08JAN07		Clear	and Clean	nup	1	1		1	1			1		1	1		1		ſ
940	STEEL DWGS	20	20	0	17JAN07*	13FEB07			STE	EL DWGS	1	I		1	1		1	l		1	1		i		1
1060	CEILING HANGERS	5	5	0	31JAN07	06FEB07				IG HANGE	RS	1		1				1 		1	1		a norma norma da la L		
1120	STEEL APPROVALS	15	15	0	14FEB07	06MAR07		1			APPROVA	LS		1	1		1	I I		1	I I		1	1	
950	CLEARSTORY STEEL FAB	20	20	0	07MAR07	04APR07		1	₂		CLEARS	TORY ST	REEL FAB	1	1		1	1		1	1		1	1	
1050	FLOOR INFILL	10	10	0	08MAR07	21MAR07		1			OOR INFIL	L		1	1		1	1		1	1		I	1	l.
1080	SPRAY INSULATION	15	15	0	19MAR07	09APR07		1			SPRAY	INSULA	TION	1	1		1	1		1	1		1	1	
960	DEMO ROOF OPENINGS	15	15	0	05APR07	25APR07				ł	DE DE	EMO RO	OF OPENIN	IGS			Ĩ	1		1	I		1	1	i i
970	CLEARSTORY STEEL FRAMING	15	15	0	09APR07	27APR07		I				LEARST	ORY STEE	L FRAM	NG		1	i I		1	i		i i	1	
1100	HVAC MAIN DUCTS	20	20	0	24APR07	21MAY07						₩ ₩	AC MAIN I	DUCTS	1		1	1		1	l F		1	1	
1000	EXTERIOR FRAMING/SIDING	10	10	0	30APR07	11MAY07		, I				IVEXTĖ □	RIOR FRAM	Ming/sid I	NNG		1	1		1	1 1		1	1	l I j
1040	ROOF DECKING	10	10	0	30APR07	11MAY07		1				ROOF	DECKING		1			1		1	l I		1	1	1
1130	SPRINKLER ROUGH-INS	10	10	0	01MAY07	14MAY07		1					NKLER RO	DUGH-IN	S I			1		1	1		1		1
1890	HVAC BRANCH DUCTS	10	10	0	08MAY07	21MAY07		1	1				AC BRAN	CH DUCT	rs i		1	1		1	1		1	1	
990	CLEAR STORY ROOFING	10	10	0	14MAY07	25MAY07		1	I		1		LEAR STO	RY ROO	FING		I	i I		i	1		1	1	
1030	DEMO ROOF	10	10	0	14MAY07	25MAY07		1	1		1 1		EMO ROO	F /	1		1	1		1	l. I		1	1	
														Sheet 4 of 1	7										
art Date hish Date	01DEC0 22APR0			and the same		Early Bar	BL1D		1.	2 brance	Fiore, Inc			510014 011	Da	to I			Revision				Checked	1 Ar	pproved
nish Date	01DEC		s see the second second	iligen and and		Targot Bar			Bo	rland Lah	Renovatio	on			14FEB07	And in case of the local division of the loc	vised to inclu	de site and s	and the state of the second seco				SHOONING	- 4	- and a state
in Date	14FEB07 16:			in chin		Progress Be			50	Target S	chedule				08JAN07	Ro	vised to inclu	de interior fir	hishos						
				-ballass ap		Critical Activ	vity			, anglet e					10DEC0	6 Pro	liminary Den	o/Abatemen	t Plan						
	Primavera Systems, Inc.																			1					

Activity ID	Activity Description	Orig Dur	Rem Dur	% Early Start	Finish	2006 N DEC		MAR APR		2007 I JUL /						MAR		MAY JUN
1110	METAL STUD FRAMING	15		0 15MAY07	05JUN07	11111				TAL STUD FRAM			I I I I I I I	1 1 1 1	1 1 1 1 1 1	1 1 1 1 1		TITI
1150	ELECTRIC/TELE. ROUGH-INS	20	20	0 22MAY07	19JUN07					ELECTRIC/TEL	LE. ROUGH	-INS						
980	CLEAR STORY WINDOWS	10	10	0 29MAY07	11JUN07					LEAR STORY W	VINDOWS							
1010	PATCH EXT. ROOF	10	10	0 29MAY07	11JUN07					ATCH EXT. ROO	OF					1	1	1
1140	PLUMBING ROUGH-INS	10	10	0 06JUN07	19JUN07				1	PLUMBING RC	DUGH-INS		1 1 1 1		1	1	1	1
1020	PERMANENT DRY	0	0	0	11JUN07				♦ P ♦	ERMANENT DR	RY .				1	1		1
1090	FINAL SPRAY INSUL.	3	3	0 12JUN07	14JUN07		1 1			FINAL SPRAY IN	NSUL				1	1		T
1170	MEP INSPECTIONS	3	3	0 20JUN07	22JUN07						TIONS		1 1		i I	1	1	i I
1160	HVAC INSULATION/ATC	15	15	0 25JUN07	16JUL07				1 1 1 1		INSULATIO	DN/ATC			1	1	1	1
1180	CEILING FRAMING	15	15	0 05JUL07	25JUL07				I I I I		ILING FRAM	<i>I</i> ING			I	1	1	1
1190	DRYWALL/PLASTER	25	25	0 19JUL07	22AUG07							VALL/PLASTI	ĒR			1		1
1200	PRIME PAINTING	10	10	0 16AUG07	29AUG07	annan a' commission (dalamani) a' a			I I I I	1		ME PAINTING	3 ₁ 1		1	1	1	1
1210	ACOUSTICAL CEILING GRID	8	8	0 30AUG07	11SEP07		1 1		1 1	1		ACOUSTICA	L CEILING GR	ID	I	1	1	i.
1230	DOORS & HARDWARE	5	5	0 30AUG07	06SEP07		1 1		1 1 1 1	1		OORS & HA	RDWARE		l T	1	1	L L
1270	FLOORING	10	10	0 12SEP07	25SEP07							FLOORI	NG		I I	1	1	1
1260	HVAC DIFFUSER, GRILLS	10	10	0 12SEP07	25SEP07							HVAC D	IFFUSER, GRI	LLS		I.	1	1
1290	ELECTRIC LIGHTING, DEVICES	10	10	0 12SEP07	25SEP07		1 1			1	Ê		NC LIGHTING,	DEVICES	1	(1
1280	SPRINKLER DEVICES	5	5	0 12SEP07	18SEP07	<u>i</u> re	1 1		1 1 1 1	1		SPRINKLE	RDEVICES		f I	l l	1	1
1300	TELECOM EQUIPMENT	5	5	0 12SEP07	18SEP07				1 1	1		and the second se	EQUIPMENT		ľ	1	1	1
rt Date	01DEC		Reported		Early Bar	BL1D				Sheet 5 of 17					1.6			
sh Dato	22APF	08			Target Bar		Lee	onard S. Fiore,	Inc.		Date	Doulsort to in	the second se	Revision	_		Checked	Approved
a Date Date	01DEC 14FEB07 16		- mone full		Progress Bar		Borl	and Lab Renov Target Schedu	vation		14FEB07 08JAN07	CONTRACTOR OF A DESCRIPTION OF A DESCRIP	clude site and she clude interior finis	the state of the s				
			NAME AND A		Critical Activity	/		raiget Schedu			10DEC06	and the second se	emo/Abatement P	the second s				
0	Primavera Systems, Inc.					1												

Activity ID	Activity Description	Orig Dur	Rem Dur	%	Early Start	Early Finish	2006 N DEC		FEB	MAR	APR	MAY	20 JUN	JUL	AUG					JAN		MAR	08 APR	MAY	JUN
1320	SECURITY EQUIPMENT	5	5	0	19SEP07	25SEP07						 					SECU	RITY EQU	IPMENT						
1770	FINAL PAINT	5	5	0	26SEP07	02OCT07			1									AL PAINT							
1330	ACOUSTICAL CEILING TILE	5	5	0	26SEP07	02OCT07										1		USTICAL	CEILING TIL	E					
1310	CASEWORK	8	8	0	030СТ07	12OCT07									l. C	1		ASEWO	RK						l.
1350	BALANCING	5	5	0	03OCT07	09OCT07									l. L	1	∕™⁄B/	ALANCIN	G		1				6
1340	FIELD PUNCHLIST	10	10	0	15OCT07	26OCT07			1						l. I	1			PUNCHLIST	-			1		E
1st Floor We	st					and share a second second			I			1 1			1	1		1	1		1		1		1
200	Salvage	3	3	0	19JAN07	23JAN07			Salvage			I I			1	1		1			1		1		E E
210	Misc. Abate	3	3	0	19JAN07	23JAN07			Misc. Aba	to		 			1	1		l I			1				li li
270	Floor Abate	6	6	0	24JAN07	31JAN07			Floor A	bate .					l.	1		1			1		1		
240	Clear and Cleanup	2	2	0	01FEB07	02FEB07		í	Clear a	nd Clear	nup				1										
220	Demo Walls and Ceilings	20	20	0	05FEB07	02MAR07					Walls and	Ceilings													
250	Final Cleanup	2	2	0	05MAR07	06MAR07				Final 📙	Cleanup				1	1		1			1				
1351	CEILING HANGERS	5	5	0	07MAR07	13MAR07					LING HAI	IGERS			1	1		l I							1
1360	FLOOR OPENING	10	10	0	05APR07	18APR07			1			LOOR OPE	NING		1	1		1			ļ				1
1370	ELEVATOR STEEL	5	5	0	19APR07	25APR07			1			ELEVATO	R STEEL				12	1							
1400	HVAC MAIN DUCTS	25	25	0	22MAY07	26JUN07			1					HVAC M	AIN DUCT	S		1					1		
1430	SPRINKLER ROUGH-INS	10	10	0	30MAY07	12JUN07			l 		a pendit i birogram		SPR	NKLER	Rough-In	NS		1			1				
1900	HVAC BRANCH DUCTS	15	15	0	06JUN07	26JUN07			1			1 1		HVAC BE	RANCH DU	UCTS		I	i L				1		
1410	METAL STUD FRAMING	15	15	0	13JUN07	03JUL07						 			STUD FF	RAMINO	3	1							
art Date	01DE	0.061			1		BL1D							Sheet 6 c	(17)					1	_				
art Date nish Date	22AP			18 1 19 12 1 1		Early Bar	DEID		1	eonard	S. Fiore,	Inc.		511001 0 0	D	Dato			Revisi	on			Checked		pproved
ata Date	01DE	C06				Target Bar			B	orland La	b Renov	ation			14FEB	07		include site							
un Date	14FEB07 1	6:14	damente di las	Contraction of the		Progress Ba	Sec. 2			Target	Schedul	е			08JAN	the Local Distance of	and include the Number of Street Party of Street	Construction of the local division of the lo	arior finishes tement Plan						
0	Primavera Systems, Inc.																								

Activity ID	Activity Description	Orig Dur	Rem Dur	%	Early Start	Early Finish	2006 N DEC	JAN	FEB	MAR	100 B		2007 JUN JUL						DEC	JAN		MAR	2008 APR	MAY	JUN
1450	ELECTRIC/TELE. ROUGH-INS	20		0	20JUN07	18JUL07						1													
1440	PLUMBING ROUGH-INS	10	10	0	05JUL07	18JUL07					1	I.			ING ROU	GH-INS		1						1	É
1390	PATCH WALLS/MAS. INFILLS	10	10	0	05JUL07	18JUL07				(1	 -			WALLS/N	AAS. INFI	ILLS								1
1420	TELECOM CLOSET	10	10	0	05JUL07	18JUL07					L L	l. E			OM CLOS	ET	1	1				1			E
1460	MEP INSPECTIONS	3	3	0	19JUL07	23JUL07			1		1	E E			NSPECTI	ONS	1	1				1			E E
1470	HVAC INSULATION/ATC	15	15	0	24JUL07	13AUG07						L. L.	í		HVAC IN	SULATIC	ON/ATC	1				1			ľ.
1480	CEILING FRAMING	15	15	0	02AUG07	22AUG07										NG FRAM	MING	1				1		1	E
1490	DRYWALL/PLASTER	25	25	0	16AUG07	20SEP07					ŀ				Part Wilder Hanning		VALL/PL	ASTER			l I	1		1	L. F
1500	PRIME PAINTING	10	10	0	14SEP07	27SEP07			1	l		I.		I.		PRI	IME PAI	NTING			1	1		1	1
1510	ACOUSTICAL CEILING GRID	8	8	0	28SEP07	09OCT07			1						I		ACOUS	TICALC	eiling (GRID	l	l I		1	
1520	CERAMIC TILE	8	8	0	28SEP07	09OCT07								1			CERAM	IC TILE				1		ļ	
1530	DOORS & HARDWARE	5	5	0	28SEP07	04OCT07						1		1			DOORS 8	& HARDV	VARE			I I		1	
1550	FLOORING	10	10	0	10OCT07	23OCT07						I I		i I	Ì			DORING				: 		1	i I
1560	HVAC DIFFUSER, GRILLS	10	10	0	10OCT07	23OCT07			1	1	1	1 1		1	1		₩ Where the second s	AC DIFF	USER, G	RILLS	I I	1		-	
1580	ELECTRIC LIGHTING, DEVICES	10	10	0	10OCT07	23OCT07			1	1	1	1		1	ł			ECTRIC	LIGHTIN	G, DEVIC	ES	1		1	I I
1570	SPRINKLER DEVICES	5	5	0	10OCT07	16OCT07			1	1		1		1			SPRII	NKLER	DEVICES			1			I.
1590	TELECOM EQUIPMENT	5	5	0	10OCT07	16OCT07			1									COMEC	UIPMEN	п		1			
1540	PLUMBING FIXTURES & ACC.	5	5	0	10OCT07	16OCT07		****						1	1			IBING FI	XTURES	8 ACC.	1	1		1	1
1610	SECURITY EQUIPMENT	5	5	0	17OCT07	23OCT07			1		1	l		1	i L		∕ √SE	CURITY	equipm	ENT	1	I I		i I	i I
tart Dato	01DEC	06				Early Bar	BL1D						Sheet	7 of 17							_				
inish Date lata Date tun Date	22APF 01DEC 14FEB07 16	:06				Target Bar	ur -		l Bi	orland La	S. Fiore, Ind ab Renovati Schedule	c. ion			Date 4FEB07 8JAN07	and the second se	the second s	e site and s e interior fir	and the second se	'n			Checke	1	Approved
			0.57.50			Critical Activ	vity			raiget	Schedule			1000	ODEC06	Prolimir	nary Demo	/Abatemen	t Plan						
©	Primavera Systems, Inc.													F		_									

Activity ID	Activity Description	Orig Dur	Rem Dur	%	Early Start	Early Finish	2006 N DEC				- CLO	MAY	JUN			SEP	and the second	NOV		JAN	FEB	MAR	2008 APR		JUN
1600	TOILET PARTITION	3	3	0	17OCT07	19OCT07			1								Сто	DILET PA	RTITION			1			1
1780	FINAL PAINT	5	5	0	24OCT07	30OCT07			E E	i. L					î Î			FINAL F	PAINT					1	i. I
1630	ACOUSTICAL CEILING TILE	5	5	0	24OCT07	30OCT07			E E	E E		1			1	l			TICAL C	EILING TIL	E			1	l. L
1620	CASEWORK	8	8	0	31OCT07	09NOV07			l L	l.		1	1		1				EWORK					1	i i
1650	BALANCING	5	5	0	31OCT07	06NOV07				1		1	I.		1	l.		BALA	NCING			1			l.
1640	FIELD PUNCHLIST	10	10	0	12NOV07	27NOV07			E.			1	1		1	1				PUNCHLIS	т	1		1	i.
st Floor Eas		and the second							1	1		1	1		1	1		1	1		1	1	-	1	1
the same of sold sound and the	Salvage/Selective Demo	5	5	0	12JAN07	18JAN07			Salvage/S	Selective	Demo	1	l. L		1	1		1	Ē.		l I	1		1	É E
130	Misc. Abate	3	3	0	12JAN07	16JAN07		∕∨ M	lisc. Aba	te		1	1			1		l I	1		1	1		1	E E
150	Ceiling Abate	10	10	0	19JAN07	01FEB07			Ceili	ng Abate		1	l. L		1	1		1	E.		1	1		1	L. L
190	Floor Abate	6	6	0	19JAN07	26JAN07			Floor A	Abate		1			1	1		1	L		1			1	l. L
1220	MISC. STEEL DRAWINGS/APRVL	25	25	0	31JAN07*	06MAR07			A		C. STEEL	DRAWING	S/APRVL		1	1		1	E.			1		1	E .
160	Clear and Cleanup	2	2	0	02FEB07	05FEB07		ana 1111 111 111 111 111 111 111		ar and Clo	eanup	1	1			1		1	1	an a mBanna ann ann an t]		1	
170	Finish Wall Demo. and MEP	20	20	0	06FEB07	05MAR07				Finis Finis	sh Wall D	emo. and N	IEP			1		1	E E			1		I I	1
180	Final Cleanup	2	2	0	06MAR07	07MAR07			1	Fina	al Cleanu	p	l I			1		l	E E		1	1		1	1
1990	MISC. STEEL FAB	20	20	0	07MAR07	04APR07			1		∭ Mise ■	C. STEEL F	AB		1	1		1	L.		l.	1		I J	
1980	CEILING HANGERS	5	5	0	14MAR07	20MAR07			1			HANGERS			1		1							1	
1960	FLOOR INFILL	10	10	0	05APR07	18APR07	1		1	1		FLOOR INI	FILL						-k						
2080	STEEL RISER FRAMING	10	10	0	05APR07	18APR07			1	1		STEEL RIS	ER FRA	/IING					1		1			1	
2090	RISER CONCRETE	10	10	0	19APR07	02MAY07			1	1			CONCR	ETE	I I	1			1		1	1		1	I
														1			1						_		
rt Date ish Date	01DE 22AF				Constant State of Land	Early Bar	BL1D			1.00000	d C Eler	Inc		Sheet 8	of 17	Date			Revis	ion		1	Checke	d l	Approved
ish Date ta Date	01DE		12 (20) Mil			Target Bar	- 1 + C ²¹			Borland	d S. Fiore Lab Rend	, Inc.			14F		Revised to incl	ude site an					OTIOCKO		Approved
n Date	14FEB07 1		State Spinster	AT THE WAR		Progress Ba	Concernant and Concernant			Targ	et Sched	ule			08J	N07	Revised to incl	ude interior	finishes						
				last din anderen		Critical Activ	rity								10D	EC06	Preliminary De	mo/Abatem	ent Plan						
C	Primavera Systems, Inc.																								

Activity ID	Activity Description		Rem Dur	%	Early Start	Early Finish	2006 N DEC	JAN	FEB	MA	R AP	R MA	Y JU	2007 IN JUL	AUC	G SEI	oc.		DV DE	C JAN	FEB	MAR	2008 APR	MAY	JUN
2030	HVAC MAIN DUCTS	20		0 27.	JUN07	25JUL07		1111	LLL	1111	1111	1 1 1 1	1111		HVAC	MAIN DU			1 1 1 1 1	1.1.1.1	1111	1 1 1 1		1111	
2040	SPRINKLER ROUGH-INS	10	10	0 05.	JUL07	18JUL07			1				1			ER ROUG	SH-INS								
2060	HVAC BRANCH DUCTS	10	10	0 12.	JUL07	25JUL07				I I		i I	I I			BRANCH	DUCTS				Ì				l I
2070	METAL STUD FRAMING	15	15	0 19.	JUL07	08AUG07			1				1			ETAL STU	D FRAMI	NG			t			l L	1
2110	ELECTRIC/TELE. ROUGH-INS	20	20	0 26.	JUL07	22AUG07			1	1		1	1	É			RIC/TELE	ROUG	I-INS		I.			1	1
2100	PLUMBING ROUGH-INS	10	10	0 09/	AUG07	22AUG07			1	i.			í.			VPLUME	ING ROU	GH-INS			i -			T T	
2050	PATCH WALLS/ MAS. INFILL	10	10	0 09/	AUG07	22AUG07			1	1						PATCH	WALLS/ I	WAS. INI	FILL			1		1	1
2140	MEP INSPECTIONS	3	3	0 23/	AUG07	27AUG07			t. K	1		1	f L		í		NSPECTI	ONS	1		t. K	1		t. L	1
2170	HVAC INSULATION/ATC	15	15	0 28/	AUG07	18SEP07				A.			T.		1		HVAC IN	SULATI	ON/ATC		1	1		E E	1
2180	CEILING FRAMING	15	15	0 075	SEP07	27SEP07			1				1		1			NG FRA	MING		i. T	1			1
2190	DRYWALL/PLASTER	25	25	0 21	SEP07	25OCT07			1	l I		i I	i I		1	ĺ			WALL/PLA	STER	1	1			I.
2200	PRIME PAINTING	10	10	0 120	OCT07	25OCT07			1	1		1	1		1	l I			IE PAINTIN	IG	1				1
2210	ACOUSTICAL CEILING GRID	5	5	0 260	OCT07	01NOV07			1	1		1	1		1	1		Ļ	OUSTICAL		GRID	1); 1. —	1
2220	DOORS & HARDWARE	5	5	0 260	OCT07	01NOV07			1			1	l.		1				ORS & HA		1				1
2230	FLOORING	15	15	0 021	NOV07	26NOV07			1	1		1	1		1							1			
2240	HVAC DIFFUSER, GRILLS	10	10	0 021	NOV07	15NOV07			1	1		i T	Î.		1	i.			- 1			1			1
2260	ELECTRIC LIGHTING, DEVICES	10	10	0 021	NOV07	15NOV07			1	1		1	1		1	1					IG, DEVICI	ES		-	1
2250	SPRINKLER DEVICES	5	5	0 021	NOV07	08NOV07			1	1		1	I I		1	1		μ	SPRINKLE		i.	1		1	1
2270	TELECOM EQUIPMENT	5	5	0 021	NOV07	08NOV07			1	1		1	1		1	1			TELECOM	EQUIPME	NT 	1 T		1	t t
tart Date	01DEC					Early Bar	BL1D							Shoot 9	9 of 17					- date:					
inish Date bata Date tun Date	22APF 01DEC 14FEB07 16	:06				Target Bar Progress Bar Critical Activ				Borland	rd S. Fior Lab Rer get Scher	ovation			08.	Date EB07 JAN07 DEC06	Revised to	include in	Re te and shell terior finishes batement Plan				Checkee		Approved
©	Primavera Systems, Inc.																								

Activity ID	Activity	Orig		%	Early Start	Early Finish	2006 N DEC	JAN FEB M	AR APR	MAY	20(JUN)7 JUL	AUG	SEP	ОСТ	NOV	DEC JAN
2280	Description SECURITY EQUIPMENT	Dur 5	Dur	0	09NOV07	15NOV07	<u> </u>			1111		1 1 1 1	1 1 1 1	1 1 1 1	1111	SECU	RITY EQUIPN
2200	CECCITIFIE CONTINENT	5	J	U	03140707	13140 007		i i									
2300	ACOUSTICAL CEILING TILE	5	5	0	16NOV07	26NOV07		1 1		1 1		1					COUSTICAL C
2340	FINAL PAINT	5	5	0	27NOV07	03DEC07				1 1			1				FINAL PAINT
2320	BALANCING	5	5	0	27NOV07	03DEC07		1		1							BALANCING
2290	CASEWORK	8	8	0	04DEC07	13DEC07											CASEWOR
2310	FIELD PUNCHLIST	10	10	0	14DEC07	31DEC07				1							
Ground Floo	or West			and the				1 1		l. I	0		1			1	
330	Salvage	3	3	0	12MAR07	14MAR07						1	1			1 (1 1	
340	Misc. Abate	3	3	0	12MAR07	14MAR07			Misc. Abate	1 1						1 1 1 1	
360	Floor Abate.	6	6	0	20MAR07	27MAR07			Service Alt	bate.			1			1 1	
370	Clear and Clean	2	2	0	28MAR07	29MAR07		1	Clear a	nd Clean						1 1	
350	Demo Walls and Ceilings	20	20	0	30MAR07	27APR07				✓Demo Wa	alls and Ce	ilings				1 I	
450	Final Cleanup	2	2	0	30APR07	01MAY07		I I I 1	1	∛Final Cl □						1 I 1 I	
1651	CEILING HANGERS	5	5	0	02MAY07	08MAY07					ľ.		1			1 I 1 I	
1661	FLOOR OPENINGS	10	10	0	02MAY07	15MAY07					OR OPEN						
1671	ELEVATOR STEEL	5	5	0	16MAY07	22MAY07				∆ VE	LEVATOR	STEEL					
1701	HVAC MAIN DUCTS	25	25	0	26JUL07	29AUG07				1				HVAC N	IAIN DUC	rs	
1681	INSTALL ELEVATOR	15	15	0	27JUL07	16AUG07								TALL EL	EVATOR		
1731	SPRINKLER ROUGH-INS	10	10	0	02AUG07	15AUG07				1	E .		SPF	RINKLER	ROUGH	NS	
1971	HVAC BRANCH DUCTS	15	15	0	09AUG07	29AUG07				1					RANCH D	UCTS	
Start Date	01DI	EC06				Early Bar	BL1D	1				Sheet 10 of	17				1
Finish Date	22AI	PR08				Target Bar		Leon	ard S. Fiore,	Inc.			Di 14FEB0		oulead to lo	ude site and sh	Revision
Data Date Run Date	01Di 14FEB07 1	EC06				Progress Ba	214	Borlan	d Lab Renov rget Schedul	vation le			08JAN0	7 R	COLUMN 2 IN COLUMN 2 IN COLUMN 2 IN COLUMN 2	ude site and sh ude interior fini	and the second se
			1090-00-000	ang kanang di man	na na sta sanayan)	Critical Activ	vity	Ta	iger concau				10DEC0	6 Pr	oliminary Do	mo/Abatement	Plan
©	Primavera Systems, Inc.																

		2008		المربوب والمح
JAN	FEB MAR	APR	MAY	JUN J
IPMEN		1.1.1.1.1	1111	1111
PMEN	1			
1	1			
L CEILI	NG TILE			
1				
NT				
}				
IG				
			1	
			1	
ORK)	1	
1				
IELD PL	JNCHLIST	1		
1				
I	1			
1				
1	1			
	i i			
18				
1				
	-			
4				
1	· · · · · · · · · · · · · · · · · · ·			
J.				
1				
1	1			
1	1	1		
1	1			
1	1		0 1	
1	1	1		
1	1		(I	
1	1	1	()	
1	1		(I	
	1			
1	1			
-1	i		6	
1	1			
1	1			
1	1			
1			-	
		Checked	A	pproved
			_	


Activity ID 1711	Activity Description	Orig		% Early	Early	DEO	LANI FED AS		AV UIN	2007		OCT NOV DEC	JAN FEB	2008	MAN	UIN
1711		Dur	Dur	Start	Finish	DEC					AUG SEP					
	METAL STUD FRAMING	15	15	0 16AUG07	06SEP07							AL STUD FRAMING				
1751	ELECTRIC/TELE. ROUGH-INS	20	20	0 23AUG07	20SEP07				l.			ELECTRIC/TELE. ROUGH-IN	S I I			
1741	PLUMBING ROUGH-INS	10	10	0 07SEP07	20SEP07			1111-11-11-11-11-11-11-11-11-11-11-11-1	I	1		PLUMBING ROUGH-INS	1 1			1.
1691	PATCH WALLS/MAS. INFILLS	10	10	0 07SEP07	20SEP07			I.	l.	I i		PATCH WALLS/MAS. INFILLS	6 1 1			
1721	TELECOM ROOM	10	10	0 07SEP07	20SEP07			1	ł	1		TELECOM ROOM	1 1			E E
1761	MEP INSPECTIONS	3	3	0 21SEP07	25SEP07			li li	-							
1771	HVAC INSULATION/ATC	15	15	0 26SEP07	16OCT07				I.		í		атс			
1781	CEILING FRAMING	15	15	0 050CT07	25OCT07			k l	1				3			i.
1791	DRYWALL/PLASTER	25	25	0 19OCT07	26NOV07			ł	1	I			LL/PLASTER			
1801	PRIME PAINTING	10	10	0 16NOV07	03DEC07		1 1	l, l,	t t	1			PAINTING			
1811	ACOUSTICAL CEILING GRID	6	6	0 04DEC07	11DEC07		1 1	l E	1	1	l		OUSTICAL CEILING	GRID		1
1821	CERAMIC TILE	3	3	0 04DEC07	06DEC07								AMIC TILE			
1831	DOORS & HARDWARE	5	5	0 04DEC07	10DEC07		1 1		I.	1	1		ORS & HARDWARE			1
1841	PLUMBING FIXTURES & ACC.	5	5	0 07DEC07	13DEC07			1	Î 1				UMBING FIXTURES	& ACC.		I. F
1851	FLOORING	10	10	0 12DEC07	27DEC07		. I I I I	1	1	1	l I		FLOORING			l L
1861	HVAC DIFFUSER, GRILLS	10	10	0 12DEC07	27DEC07		1 1		L I	1	l I		HVAC DIFFUSER, C	GRILLS		
1881	ELECTRIC LIGHTING, DEVICES	10	10	0 12DEC07	27DEC07				1	1				IG, DEVICES		
1871	SPRINKLER DEVICES	5	5	0 12DEC07	18DEC07					1	1 1	S ANS	PRINKLER DEVICES	an dama da ang da da ang da		1
1891	TELECOM EQUIPMENT	5	5	0 12DEC07	18DEC07			1		1			ELECOM EQUIPMEN	IT	1	
		200				BL1D				Sheet 11 of 17	7					
art Date aish Date	01DEC 22APF	808			Early Bar	BLID	Leor	ard S. Fiore, Inc.		3100011011/	Date	Revis	lon	Checke	d j	Approved
ta Date	01DE0		d. Store an		Target Bar		Borlar	nd Lab Renovation			14FEB07 08JAN07	Revised to include site and shell Revised to include interior finishes				
n Date	14FEB07 16		Siles of Station		Critical Activity		Та	arget Schedule			Calculation of the address of the second sec	Preliminary Demo/Abatement Plan				
0	Primavera Systems, Inc.															

Activity ID	Activity Description	Orig	Rem	%	Early Start	Early Finish	2006 N DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JA
1901	TOILET PARTITION	Dur 3	Dur 3	0	14DEC07	18DEC07		1111		1111	1111	1111	1 1 1 1	1111	1111	1 1 1 1	1111	1 1 1 1		TOILET
1501		3	3	U	HULOU/	TODEOU/				Ĵ.				i		1				
1911	SECURITY EQUIPMENT	5	5	0	19DEC07	27DEC07			1					1		1				SECI
1961	FINAL PAINT	5	5	0	28DEC07	04JAN08			1			t i		1		1				
1931	ACOUSTICAL CEILING TILE	5	5	0	28DEC07	04JAN08			1	1		1	t 1 1	1		1		1	Í	
1921	CASEWORK	8	8	0	07JAN08	16JAN08			1	1		1 1		1		1		1	1	
1951	BALANCING	5	5	0	07JAN08	11JAN08			1	1		1		1		1		1		
1941	FIELD PUNCHLIST	10	10	0	17JAN08	30JAN08			1	1		r r	1	1		1		L.		
Found Floo	or East and the second second	Con lo 1	15 CON						Ì	Ť		1	1	1		1		I.	1	
280	Salvage/ Selective Wall Demo	5	5	0	05MAR07	09MAR07			1	∕∕√Salv	age/ Sele	ctive Wall I	Demo	1		1		1	1 1	
400	Misc. Abate	3	3	0	05MAR07	07MAR07			1	Misc	. Abato	1		1		1		1		
290	Ceiling Abate	15	15	0	12MAR07	30MAR07			1		Ceiling	Abate				1		I.	I. I	
300	Floor Abate	6	6	0	12MAR07	19MAR07			1	∕ ™F	loor Abat	0	l.			1		l l	1	
320	Clear and Cleanup	2	2	0	03APR07	04APR07			1	1	Clear	and Clean	up	i		1				
310	Finish Demo Walls and MEP	20	20	0	05APR07	02MAY07			1	1			Demo Wa	Is and ME	P	 		1	1	
410	Final Cleanup	2	2	0	03MAY07	04MAY07			1	1		Final C	leanup	1		1		1	1	
2370	M015 FLOOR FRAMING	10	10	0	07MAY07	18MAY07			1	1			15 FLOO	R FRAMIN	G	1		l.	t. L	
2350	CEILING HANGERS	5	5	0	09MAY07	15MAY07			1	1			LING HAI	IGERS		1			I I	
2330	FLOOR INFILL	15	15	0	21MAY07	11JUN07 .			I	i i			FLO	OR INFILL		1				
2380	M015 FLOOR SLAB	5	5	0	21MAY07	25MAY07			4	1			M015 FLC	OR SLAB		1			1	1
2390	T015/M015 ROOMS	15	15	0	29MAY07	18JUN07			1	1			Т	15/M015 R	OOMS	1		1		
art Date	01DE	C06					BL1D							Sheet 12 of	17					
ish Date	22AF	ROB				Early Bar				Leonard	S. Fiore,	Inc.			D	ato			Rovis	sion
ta Date	01DE		Contractor In	N. 10. 10.		Progress Ba				Borland L	ab Renov	ation			14FEB		evised to inc	And and a second second second second	and the second se	
n Date	14FEB07 1	6:14		The lot of the	CALIFIC AND INCOME.	Critical Activ				Targe	t Schedu	le			10DEC	and the second s	evised to inc reliminary De	the design of the second strength of the	Contraction of the Association o	
						V Offical Activ														
6	Primavera Systems, Inc.																			

	. 2	008		
JAN FEB	MAR	APR	MAY	JUN J
ET PARTITION	1 1 1 1 1	1 1 1 1	1111	1 1 1 1 1
ETTAKINON				
CURITY EQUIP	MENT			
CORTTEQUE				
	1			
FINAL PAINT	8) 1			
ACOUSTICAL C	EILING TI	LE		
	1			
CASEWOR	< Contract of the second s			
201				6
BALANCING	1			i.
	ř.			6
	UNCHLIS	т		
	1			1
I	1			I
1	(I			1
1				t
1				ř. – I
1		1		1
1		1		Ē.
1				l,
1				E
1.				l l
1				1
1				C
				I
1	1			
	1. 17			
	4			
	1			
1	r T			
1	1			
1	1			
1	1			
1	í.			i l
				·
		Checked	^	pproved

Activity	Activity			% Early	Early	2006 N DEC	JAN FEB M	AR APR MAY	2007 JUN JUL	AUG SE	P OCT NOV DEC	JAN FEB	2008 MAR APR	MAY JUN
ID	Description	Dur	Dur	Start	Finish						VHVAC MAIN DUCTS			
2400	HVAC MAIN DUCTS	20	20	0 30AUG07	27SEP07				1					
2410	SPRINKLER ROUGH-INS	10	10	0 07SEP07	20SEP07						SPRINKLER ROUGH-INS			
2430	HVAC BRANCH DUCTS	10	10	0 14SEP07	27SEP07						VHVAC BRANCH DUCTS	4	() ()	
2440	METAL STUD FRAMING	15	15	0 21SEP07	11OCT07				1	í	METAL STUD FRAMING			i.
2480	ELECTRIC/TELE. ROUGH-INS	20	20	0 28SEP07	25OCT07					1		OUGH-INS		
2470	PLUMBING ROUGH-INS	10	10	0 120CT07	25OCT07		1 1			1		H-INS		
2420	PATCH WALLS/MAS. INFILLS	10	10	0 120CT07	25OCT07				1 1	i t		S. INFILLS		
2510	MEP INSPECTIONS	3	3	0 260CT07	30OCT07			1.		1		IS		
2540	HVAC INSULATION/ATC	15	15	0 310CT07	20NOV07				1	I		JLATION/ATC	I	
2550	CEILING FRAMING	15	15	0 09NOV07	03DEC07					1		G FRAMING		
2560	DRYWALL/PLASTER	25	25	0 27NOV07	03JAN08					1		VDRYWALL/PLAS	TER	
2570	PRIME PAINTING	10	10	0 18DEC07	03JAN08					I		VPRIME PAINTIN	G	l
2580	ACOUSTICAL CEILING GRID	15	15	0 04JAN08	24JAN08		1 1	1	1 1	i	1 1		CAL CEILING GRID	
2590	DOORS & HARDWARE	5	5	0 04JAN08	10JAN08			l	1 1 1	1	I L I L	DOORS & HAI	RDWARE	
2600	FLOORING	15	15	0 25JAN08	14FEB08			1	1 1	- 1	I I I I		ORING	1
2610	HVAC DIFFUSER, GRILLS	10	10	0 25JAN08	07FEB08					1	1 1		DIFFUSER, GRILLS	
2630	ELECTRIC LIGHTING, DEVICES	10	10	0 25JAN08	07FEB08					i.			TRIC LIGHTING, DEV	/ICES
2620	SPRINKLER DEVICES	5	5	0 25JAN08	31JAN08			l.		i T	i i		LER DEVICES	i
2640	TELECOM EQUIPMENT	5	5	0 25JAN08	31JAN08		I I I I	l		1			OM EQUIPMENT	l
irt Date	01DE0				Early Bar	BL1D			Sheet 13 o' 17	1				
ish Date	22APF		and the second se		Target Bar			ard S. Fiore, Inc.		Date 14EEB07	Revisio	m	Checked	Approved
ta Date n Date	01DEC 14FEB07 16				Progress B	ar -	Borlar	nd Lab Renovation arget Schedule		14FEB07 08JAN07	Revised to include site and shell Revised to include interior finishes			
			No. 1 State		Critical Acti	vity	Ta	iger Schedule		10DEC06	Preliminary Demo/Abatement Plan			_
C	Primavera Systems, Inc.													

Activity ID	Activity Description	Orig Dur	Rem Dur	%	Early Start	Early Finish	2006 N DEC	JAN FEB	MAR	APR MAY JUN	2007 JUL	AUG SEF	ост	NOV	DEC	JAN
2650	SECURITY EQUIPMENT	5		0	01FEB08	07FEB08								1		
2670	ACOUSTICAL CEILING TILE	12	12	0	08FEB08	25FEB08			1		1					
2700	FINAL PAINT	5	5	0	15FEB08	21FEB08					i i	1				
2660	CASEWORK	8	8	0	22FEB08	04MAR08				1 1	1	1		1 1		
2690	BALANCING	5	5	0	26FEB08	03MAR08		1	1	1 I	1	1		 		
2680	FIELD PUNCHLIST	10	10	0	05MAR08	18MAR08			j k t		1	1		1		
Basement								1	1	1 1	1	1		1		
380	Misc. Abate	8	8	0	28MAR07	09APR07		1		Misc. Abate	. 1			1 1		
440	Clear and Cleanup	2	2	0	10APR07	11APR07	×.	1	1	Clear and Cleanup	ł	1		l l		
390	MEP Demo	6	6	0	12APR07	19APR07		1	1	MEP Demo	1	1		I		
420	Final Cleanup	2	2	0	07MAY07	08MAY07		1		🏹 Final Cleanu	p			1		
430	Demo/Abatement Complete	0	0	0		08MAY07		I.		♦Demo/Abate	ment Complete	0		1		
1700	MB002 ELECT. ROOM	20	20	0	09MAY07	06JUN07		1	l I		002 ELECT. RO	MOC		1		
1380	MB001 MECH ROOM	20	20	0	09MAY07	06JUN07		1	1		001 MECH RO	OM		1		
1240	ELEVATOR PIT	20	20	0	16MAY07	13JUN07		. 1	1		LEVATOR PIT			1		
1820	UNDERGOUND UITLITIES	20	20	0	21MAY07*	18JUN07		1	1		UNDERGOUN	D UITLITIES		1		
1910	PSU PULL CABLES	15	15	0	05JUN07	25JUN07			1		PSU PULL (CABLES		1		
1710	PANELS AND GEAR	15	15	0	07JUN07	27JUN07		l I			PANELS A	ND GEAR		1		
1660	H W-C W PUMPS	15	15	0	07JUN07	27JUN07		1	1		₩HW-CWP	UMPS		1		
1730	TRANSFORMERS	10	10	0	07JUN07	20JUN07		1 T	1		TRANSFORM	IERS		1		
Start Date	01DE	C06					BL1D				Sheet 14 of 13	7				
Finish Date	22AF	PR08				Early Bar			Leonard S	. Fiore, Inc.		Date			Revisia	n
Data Date	01DE			Contraction of the		Target Bar		B	orland Lal	b Renovation		14FEB07	Revised to inc	the local phone in a contract of the she had been	the desire is since the second second	
Run Date	14FEB07 1	6:14	10-10-10-10-10-10-10-10-10-10-10-10-10-1	tunte et all		Critical Act	(ACAS)		Target	Schedule		08JAN07 10DEC06	Revised to inc Preliminary De	the strength of the state of the strength os strength of the strength os s	the second se	
						<u>.</u>										_
C	Primavera Systems, Inc.															
										57						



Activity ID	Activity Description	Orig Dur	Rem Dur	%	Early Start		2006 N DEC	JAN	FEB	MAR	APR		JUN	2007 JUL			EP	ост	NOV	DEC		FEB	MAR	008 APR		JUN
1250	ELEVATOR STEEL	10	Contraction of the second	0	14JUN07	27JUN07				1.1.1.1				VELEV4	ATOR ST	'EEL				1		1				
1720	WIRING AND DEVICES	15	15	0	28JUN07	19JUL07						1	i		WIRING	AND DE	VICES	5	1			1				1
1670	H W PIPING	20	20	0	28JUN07	26JUL07						1 1	i	<u>\:</u>	⊠HWI □	PIPING			1			1				h.
1790	C W PIPING	10	10	0	28JUN07	12JUL07						I I I I	i		WPIPI	IG			1			l t			1	t. t
1680	CONTROL WIRING	5	5	0	28JUN07	05JUL07						1 1	i		NTROL N	WRING			1			1			1	1
1740	PERMANENT POWER	5	5	0	20JUL07	26JUL07										ANENT	POWE	ĒR	1			1			1	
1690	SYSTEM START UP/ADJUST	10	10	0	27JUL07	09AUG07						, , , ,				YSTEM	STAR	t up/ad	JUST			1	1		i i	E E
MECHANIC	AL PENTHOUSE	- Milalian					_					1 1			1	I			1	4	_	1	1		1	1
860	STEEL DWGS/APPROVALS	25	25	0	10JAN07*	13FEB07			STE	EL DWG	S/APPRC	VALS			I I	1			1	1			1		1	E L
910	ATC DWGS/APPROVALS	20	20	0	05FEB07*	02MAR07				ATC DV	NGS/APP	ROVALS			1	1			1						1	1
1930	ACF DRAWING APPROVAL	20	20	0	12FEB07*	09MAR07	s			ACF	DRAWING	APPROV	AL		1	È.			t L	1					1	
850	STEEL FAB	20	20	0	14FEB07	13MAR07				≡Vste	EL FAB				i t	1			1	i T		1			1	
920	ATC FAB AND DELIVERY	80	80	0	05MAR07	26JUN07						,		ATC F	AB AND	DELIVE	RY		1	T T		1	l		1	l. I
1940	ACF FAB AND DELIVERY	60	60	0	12MAR07	05JUN07							ISVACF □	FAB ANI	DELIV	ERY			l t	l	(((())))))	1			1	
700	DEMO ROOF AND PARAPET	10	10	0	14MAR07	27MAR07						OOF AND	PARAP	ET	l l	1			1	L L		1				
720	PENTHOUSE STEEL FRAMING	10	10	0	28MAR07	11APR07						ITHOUSE S	STEEL	FRAMING	G	Ţ			1			1				l.
760	SLAB ON DECK	5	5	0	12APR07	18APR07						AB ON DE	1		1	1			i. L			1			Y.	
1070	METAL DECK	5	5	0	12APR07	18APR07					∆⊽m □□	ETAL DEC	ĸ		1	1			1	i.		1	1			l.
740	MASONRY WALLS	15	15	0	19APR07	09MAY07						MASC	DNRY W	ALLS	i L	1			l I	l I		1				I. E
730	PENTHOUSE ROOF	5	5	0	10MAY07	16MAY07							NTHOU	SE ROOI	Fl	1			l F	1		1	1		1	l.
tart Dato	01DE	C06					BL1D							Sheet 1	5 of 17											_
inish Date	22AP	R08 🕂				Early Bar			L	eonard s	S. Fiore,	Inc.		0.1001 1		Date				Revi	sion		1	Checked		Approved
ata Dato	01DE	C06				Target Bar			B	orland La	b Renov	ation				FEB07		Number of Contract of Contractory of Contractory	lude site a	Contract of the design of the design of the local data and the local d						
un Date	14FEB07 10	5:14		12.0	a constant and	Critical Activ				Target	Schedul	B				DEC06			lude interio emo/Abater							
©	Primavera Systems, Inc.														_											

Activity ID	Activity Description	Orig Dur			arly Early start Finish		UL AUG SEP OCT NOV DEC JAN FEB MAR APR MAY JUN
750	PENTHOUSE LOUVERS	5	5	0 10MA	Y07 16MAY07		
780	ACF 1AND 2	20	20	0 06JU	N07 03JUL07		CF 1AND 2
1920	ATC INSTALL AND ADJUST	20	20	0 27JU	N07 25JUL07		TC INSTALL AND ADJUST
770	MEZZANINE FRAMING/GRID	5	5	0 05JUI	_07 11JUL07		MEZZANINE FRAMING/GRID
790	ACF 3 AND 4	20	20	0 12JUI	_07 08AUG07		
800	PLENUMS/DUCTWORK	15	15	0 09AU	G07 29AUG07		
810	CONTROLLERS/WIRING	10	10	0 09AU	G07 22AUG07		
820	ACF 1 AND 2 STARTUP	5	5	0 30AU	G07 06SEP07		ACF 1 AND 2 STARTUP
830	ACF3 AND 4 STARTUP	5	5	0 30AU	G07 06SEP07		ACF3 AND 4 STARTUP
840	CONDITIONED AIR	5	5	0 07SE	P07 13SEP07		
ITEWORK							
2010	E&S CONTROLS	5	5	0 12FE	307* 16FEB07	E&S CONTROLS	
1950	SITE DEMO	90	90	0 19FE	307 26JUN07		EDEMO
2000	GARAGE DEMO	5	5	0 26FE	307* 02MAR07	GARAGE DEMO	
2020	GRADING	90	90	0 05MA	R07 11JUL07		GRADING
1970	CREAMERY DEMO	5	5	0 05MA	R07 09MAR07		
2460	SITE STORM	20	20	0 19MA	R07 16APR07		
2500	SITE LIGHTING	20	20	0 17AP	R07 14MAY07		
2880	UNDERGROUND UTILITIES	20	20	0 21MA	Y07* 18JUN07		RGROUND UTILITIES
2130	CONCRETE PAVING	40	40	0 05JU	N07 31JUL07		
			l				
art Dato hish Dato	01DE 22AF				Early Bar	Sho Leonard S. Fiore, Inc.	et 16 of 17 Date Revision Checked Approved
ish Date	01DE				Target Bar	Borland Lab Renovation	14FEB07 Revised to include site and shell
n Date	14FEB07 1		5 x 4 *		Progress Ba	Target Schedule	08JAN07 Revised to include interior finishes
					Critical Activ		10DEC06 Preliminary Demo/Abatement Plan
	Primavera Systems, Inc.						

Description AIRS	Dur	Rem Dur	%	Early Start	Early Finish	2006 N DEC	JAN	FEB MA		MAY	JUN	JUL	AUG		ост	NOV	DEC	JAN		MAR	APR		JUN
	15	15	0 26	6JUN07	17JUL07						\triangle		STAIRS			1	1						
SLAB	5	5	0 27	7JUN07	03JUL07		1					PAVER	LAB				1		1				
VERS	5	5	0 05	5JUL07	11JUL07		1						AVERS				1						k L
L	20	20	0 18	BJUL07	14AUG07		1						TOPS	OIL			1						E.
	5	5	0 01	1AUG07	07AUG07		1	1		l.	1			6			1		1				l F
CAPING	20	20	0 08	BAUG07	05SEP07		1	1				1			CAPING	1	1						
RNISHINGS	5	5	0 06	6SEP07	12SEP07		1	1		l. F		1			FURNIS	HINGS	1						1
		Section 1					1	i i		1	1	1	1			1	1		1 1				1
RY CLEANING	20	20	0 03	3APR07*	30APR07		1	1		MASON	RY CLEAN	ING	1			t. L	1		1				1
RY REPOINTING	20	20	0 10	DAPR07	07MAY07		1	1			NRY REP	OINTING	t t			1 1	l I						1
E AB CAULKING	20	20	0 12	2APR07	09MAY07		1	1			OVE AB C	AULKING	1			1	1		1				
RY WALL INFILLS	25	25	0 24	4APR07	29MAY07		1	1	Ĺ		MASONR	Y WALL I	IFILLS			1	1		1				l.
OR PAINTING	40	40	0 30	DMAY07	25JUL07		- 1	ļ					XTERIOR	PAINTIN	IG	1	1						1
W FAB AND DELIVERY	0	0	0 01	1AUG07*			1	l l		1			WINDOW	FAB AN	D DELIV	ERY	1		1				1
VINDOWS	20	20	0 01	1AUG07	28AUG07		I	Ì		1	I I			DEMO W	INDOWS	i –	1						1
. WINDOWS	25	25	0 01	1AUG07	05SEP07		1			1	1				LL WIND	ows			[
DOORS	10	10	0 06	6SEP07	19SEP07		1	L.		t T	l I	1			STALL D	OORS	1		1				t I
	L CAPING RNISHINGS RY CLEANING RY REPOINTING E AB CAULKING RY WALL INFILLS OR PAINTING V FAB AND DELIVERY VINDOWS . WINDOWS	L 20 SAPING 20 RNISHINGS 20 RNISHINGS 5 RY CLEANING 20 RY REPOINTING 20 E AB CAULKING 20 RY WALL INFILLS 25 OR PAINTING 40 V FAB AND DELIVERY 0 VINDOWS 20 . WINDOWS 25	L 20 20 SAPING 20 20 RNISHINGS 20 20 RNISHINGS 5 5 RY CLEANING 20 20 RY REPOINTING 20 20 RY WALL INFILLS 25 25 OR PAINTING 40 40 V FAB AND DELIVERY 0 0 VINDOWS 20 20	L 20 20 20 14 5 5 0 0 CAPING 20 20 0 0 RNISHINGS 5 5 0 0 RY CLEANING 20 20 0 0 RY REPOINTING 20 20 0 14 E AB CAULKING 20 20 0 14 RY WALL INFILLS 25 25 0 24 OR PAINTING 40 40 0 34 V FAB AND DELIVERY 0 0 0 0 WINDOWS 25 25 0 0	L2020018JUL07SAPING55001AUG07CAPING2020008AUG07RNISHINGS55006SEP07RY CLEANING2020003APR07*RY REPOINTING2020010APR07E AB CAULKING2020012APR07RY WALL INFILLS2525024APR07OR PAINTING4040030MAY07V FAB AND DELIVERY00001AUG07*WINDOWS2225001AUG07	L 20 20 0 18JUL07 14AUG07 SAPING 5 5 0 01AUG07 07AUG07 SAPING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY REPOINTING 20 20 0 10APR07 07MAY07 E AB CAULKING 20 20 0 12APR07 09MAY07 RY WALL INFILLS 25 25 0 24APR07 29MAY07 OR PAINTING 40 40 0 30MAY07 25JUL07 V FAB AND DELIVERY 0 0 01AUG07* 28AUG07 WINDOWS 25 25 0 01AUG07 05SEP07	L202020018JUL0714AUG07APING55001AUG0707AUG07APING2020008AUG0705SEP07RNISHINGS55006SEP0712SEP07RY CLEANING2020003APR07*30APR07RY REPOINTING2020010APR0707MAY07E AB CAULKING2020012APR0709MAY07RY WALL INFILLS2525024APR0729MAY07DR PAINTING4040030MAY0725JUL07V FAB AND DELIVERY00001AUG07*28AUG07WINDOWS2525001AUG0705SEP07	L202020018JUL0714AUG0755001AUG0707AUG0755008AUG0705SEP07RNISHINGS55006SEP0712SEP07RY CLEANING2020003APR07*30APR07RY REPOINTING2020010APR0707MAY07E AB CAULKING2020012APR0709MAY07RY WALL INFILLS2525024APR0729MAY07OR PAINTING4040030MAY0725JUL07V FAB AND DELIVERY00001AUG07*28AUG07WINDOWS2525001AUG0705SEP07	L2020018JUL0714AUG07APING55001AUG0707AUG07APING2020008AUG0705SEP07RNISHINGS55006SEP0712SEP07RY CLEANING2020003APR07*30APR07RY REPOINTING2020010APR0707MAY07E AB CAULKING2020012APR0709MAY07RY WALL INFILLS2525024APR0729MAY07DR PAINTING4040030MAY0725JUL07V FAB AND DELIVERY00001AUG07*28AUG07WINDOWS2525001AUG0705SEP07	L 20 20 0 18JUL07 14AUG07 5 5 0 01AUG07 07AUG07 SAPING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY REPOINTING 20 20 0 12APR07 07MAY07 E AB CAULKING 20 20 0 12APR07 09MAY07 RY WALL INFILLS 25 25 0 24APR07 29MAY07 OR PAINTING 40 40 0 30MAY07 25JUL07 V FAB AND DELIVERY 0 0 01AUG07* 28AUG07 JINDOWS 25 25 0 01AUG07 05SEP07	L 20 20 0 18JUL07 14AUG07 14 15 5 0 01AUG07 07AUG07 14 15 5 0 01AUG07 07AUG07 14 15 5 0 08AUG07 05SEP07 12 12 12 0 08AUG07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY CLEANING 20 20 0 03APR07 30APR07 RY CLEANING 20 20 0 12SEP07 RY REPOINTING 20 20 0 12APR07 09MAY07 RY WALL INFILLS 25 25 0 24APR07 29MAY07 RY WALL INFILLS 25 25 0 01AUG07* 25JUL07 V FAB AND DELIVERY 0 0 0 01AUG07 28AUG07 VINDOWS 25 25 0 01AUG07 05SEP07	L 20 20 0 18JUL07 14AUG07 APING 5 5 0 01AUG07 07AUG07 APING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY REPOINTING 20 20 0 10APR07 07MAY07 E AB CAULKING 20 20 0 12APR07 09MAY07 SY WALL INFILLS 25 25 0 24APR07 29MAY07 OR PAINTING 40 0 30MAY07 25JUL07 VINDOWS 20 20 0 1AUG07 28AUG07 WINDOWS 25 25 0 24AUG07 28AUG07	L 20 20 0 18JUL07 14AUG07 APING 5 5 0 01AUG07 07AUG07 APING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY REPOINTING 20 20 0 12APR07 07MAY07 EAB CAULKING 20 20 0 12APR07 09MAY07 CR PAINTING 40 0 30APR07* 25JUL07 VALL INFILLS 25 25 0 24APR07 25JUL07 VAL INFILLS 20 20 0 01AUG07* 25JUL07 VINDOWS 20 20 0 01AUG07 28AUG07 VINDOWS 25 25 0 01AUG07 05SEP07	L 20 20 0 18JUL07 14AUG07 APING 5 5 0 01AUG07 07AUG07 APING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY CLEANING 20 20 0 10APR07 07MAY07 RY REPOINTING 20 20 0 10APR07 07MAY07 RY REPOINTING 20 20 0 12APR07 09MAY07 RY WALL INFILLS 25 25 0 24APR07 29MAY07 YFAB AND DELIVERY 0 0 0 01AUG07* 25JUL07 VINDOWS 25 25 0 01AUG07 28AUG07 VVINDOWS 25 25 0 01AUG07 05SEP07	L 20 20 0 18.JUL07 14AUG07 AL 5 5 0 01AUG07 07AUG07 APING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY CLEANING 20 20 0 12APR07 07MAY07 EAB CAULKING 20 20 0 12APR07 09MAY07 EAB CAULKING 20 20 0 12APR07 29MAY07 SR PAINTING 40 40 30MAY07 25JUL07 VFAB AND DELIVERY 0 0 01AUG07* 25JUL07 VINDOWS 25 25 0 01AUG07 28AUG07 VINDOWS 25 25 0 01AUG07 05SEP07 DOORS 10 0 06SEP07 19SEP07 19SEP07	L 20 20 0 18JU07 14AUG07 APING 20 20 0 18JU07 14AUG07 APING 20 20 0 08AUG07 07SEP07 APING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 06SEP07 12SEP07 RY CLEANING 20 20 0 10APR07 07MAY07 RY REPOINTING 20 20 0 10APR07 07MAY07 RY REPOINTING 20 20 0 12APR07 09MAY07 RY WALL INFILLS 25 25 0 24APR07 29MAY07 RY WALL INFILLS 25 2 0 01AUG07* 25JU07 V FAB AND DELIVERY 0 0 0 01AUG07* 28AUG07 05SEP07 MINDOWS 25 25 0 01AUG07* 28AUG07 05SEP07 DOORS 10 0 0.05SEP07 15SEP07	L 20 20 0 18JUL07 14AUG07 APING 5 5 0 01AUG07 07AUG07 APING 20 20 0 08AUG07 05SEP07 RNISHINGS 5 5 0 068UG07 05SEP07 RY CLEANING 20 20 0 03APR07* 30APR07 RY REPOINTING 20 20 0 12APR07 07MAY07 EAB CAULKING 20 20 0 12APR07 09MAY07 RY WALL INFILLS 25 25 0 25JUL07 29MAY07 YEAB AND DELIVERY 0 0.0 01AUG07 25JUL07 VINDOWS 25 25 0 01AUG07 28AUG07 WINDOWS 25 25 0 01AUG07 28AUG07 DOORS 10 0 06SEP07 19SEP07	L Z	L 20 20 0 14AUG07 L 20 20 0 14AUG07 14AUG07 APING 20 20 0 0BAUG07 05SEP07 RNISHINGS 5 5 0 0BAUG07 05SEP07 RY CLEANING 20 20 20 08 0BAPR07 30APR07 RY CLEANING 20 20 0 10APR07 30APR07 30APR07 RY REPOINTING 20 20 20 10 10APR07 07MAY07 EAB CAULKING 20 20 20 10 10APR07 29MAY07 SR PAINTING 40 40 20 20 0 14AUG07* 29MAY07 Y FAB AND DELIVERY 0 0 01AUG07* 29MAY07 29MAY07 29MAY07 Y FAB AND DELIVERY 0 0 0 14AUG07* 29MAY07 29MAY07 Y FAB AND DELIVERY 0 0 0 01AUG07* 28AUG07* 29MAY07 Y FAB AND DELIVERY 0 0 0 01AUG07* 28AUG	L 20 0 18.007 14.0067 L 5 5 0 0.1007 07.0067 APING 20 20 0 08.007 05SEP07 RNISHINGS 5 0 0.6007 05SEP07 12SEP07 RV CLEANING 20 20 0 0.040707 12SEP07 RY REPOINTING 20 20 0 0.040707 07MaY07 EAB CAULKING 20 20 0 12APR07 07MaY07 YVALLINFILLS 25 25 0 12APR07 29MaY07 YFAB AND DELIVERY 0 0.4007* 25UL07 WINDOWS 25 25 0 0.4007* 25H07* LOORS 10 0 05SEP07 19SEP07	L 20 20 0 18JUL07 14AUG07 L 20 20 0 18JUL07 14AUG07 L 20 20 0 01AUG07 07AUG07 APING 20 20 0 0AUG07 05SEP07 12SEP07 RNISHINGS 20 20 20 0 0AUG07 07MAY07 RY REPOINTING 20 20 20 10 0AAPR07* 30APR07* 30APR07* RY REPOINTING 20 20 20 10 0AAPR07 07MAY07 RY REPOINTING 20 20 20 24APR07 03MAY07 RY ALLINFILLS 25 25 20 24APR07 25JUL07 Feature RP AINTING 40 40 20 01AUG07* 25JUL07 Feature Feature Feature Feature MINDOWS 20 21AUG07* 25JUL07 25JUL07* Feature Feature Feature Feature Feature	L 20 20 0 18UUG77 18UUG77 07AUG77 APING 20 20 0 0 605EP07 07AUG77 07AUG77 APING 20 20 0 0 605EP07 125EP07 125EP07 RNISHINGS 20 20 0 0 605EP07 125EP07 125EP07 RY CLEANING 20 20 0 0 30APR07* 00APR07 07MAY07 RY REPOINTING 20 20 0 0 30APR07* 00APR07 07MAY07 RY REPOINTING 20 20 0 0 30APR07* 03APR07 07MAY07 RY REPOINTING 20 20 20 20 20 20APR07* 03APR07* RY MALLINFILLS 25 25 0 0 40APR07* 03MAY07 25JUL07 RY PAINTING 40 40 0 0 404G07* 25JUL07 25JUL07 RY PAINTING 20 20 20 20 20 20APR07* 25JUL07	L 20 20 0 13UUG77 14AUG07 APING 5 5 0 01AUG07 07AUG07 07AUG07 APING 20 20 0 08AUG07 05SEP07 12SEP07 YCLEANING 20 20 0 03APR07 30APR07 30APR07 YCLEANING 20 20 0 10APR07 07MY07 07MY07 YCLEANING 20 20 20 10 0APR07 30APR07 YCLEANING 20 20 20 10 10APR07 07MY07 YCLEANING 20 20 20 20 20 04 10APR07 07MY07 YCLEANING 20 20 20 20 20APR07 29MAY07 YCHAB AND DEL/YERY 20

Start Date	01DEC06	Early Bar BL1D		Sheet 17 of 17		
Finish Date	22APR08		Leonard S. Fiore, Inc.	and all the second second second	Date	Revision
Data Date	01DEC06	Target Bar	Borland Lab Renovation	14F	EB07	Revised to include site and shell
Run Date	14FEB07 16:14	Progress Bar	Target Schedule	08.J	AN07	Revised to include interior finishes
		Critical Activity	Target Schedule	10D	DEC06	Preliminary Demo/Abatement Plan
© Primavera	a Systems, Inc.					-

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation

Appendix C

Survey Results

1) Before Today, have you heard of the AIA 2030 Challenge?

- No

- No

- No

- No

- No

- No

2) What do you think of the challenge, is a good idea, and why?

- good idea, but poor execution...the less than rigorous coordination between hosts and presenters left me scrambling, and the Q&A at the end was painfully ephemeral

- good idea - it makes sense, is good for the environment, and engages externalities as an important issue for designers

- Something larger, more international is required, but that doesn't mean that this is a bad idea, just too small-scaled. What are the penalties for not doing it?

- Absolutely. We must act to deal with climate change.

- I think that it is an excellent idea since energy consumption from buildings are a major contributor to the problem.

- An excellent idea! While a lot of lip service goes into energy conservation in this country, we do very little to put existing means into practice.



3) Do you feel that Penn State should implement a program to work toward this challenge, and why?

- at least it should become a pet project for someone on the faculty in order to keep the torch burning and have someone to pass off to

- yes, as an institution in the public eye, leadership in this field is not only responsible, but arguably part of its mission

- Should be some further study, with positive interest developed in the broadest possible terms. It's not JUST a building problem.

- Yes. AE and Arch students need to be part of the solutions.

- Yes, Penn State as an educational and research institution should be spearheading such a challenge.

- I believe PSU should have such a program. We educate the policy makers of tomorrow and as a major university have the means to reach a large number of people.



4) Do you feel that the goals set by this challenge can be completed by the year 2030? and why.

- y'know other than for the sequestering carbon dioxide I can't even remember the damn goals

- About the challenge per the website:
- 1. Not enough info on what the goals are.
- 2. Unclear as to the means to achieve it.

Bigger problems: why should anyone adopt the standards voluntarily? The direct costs are higher, with no mechanism for internalizing the current externalities (such as the market-based solution seen in carbon trading). You can change behavior in three ways: legislate it (use of force), encourage it (the moral argument), or incentivize it (prod individuals to act in their self interest). The first is typical for planning efforts, the second is usually ineffective when the rubber hits the road (example: people bought SUVs knowing they were not 'green', they slowed down when gas prices rose); the third typically happens when the negative impact is directly impacting them (i.e. the ocean laps on the city limits of Santa Fe). This scheme needs to rely on the first, not the second or the third.


- Can't be done without broad popular and governmental support, also institutional involvements and, of course, cooperation by multi-national corporations, who are largely responsible for carbon emissions.

- Yes. They are pretty modest.

- Yes, they are reasonable and within reach.

- I think a lot of this depends on political will and economics. If there is a financial incentive to do something, people will do it. Politics must make this a number one priority.

Dustin Faust Construction Management 4/12/2007



Appendix D

U.S. Conference of Mayors – Resolution #50

Resolution No.50 Submitted By: The Honorable Martin Chavez Mayor of Albuquerque The Honorable Greg Nickels Mayor of Seattle The Honorable Richard M. Daley Mayor of Chicago The Honorable Manuel A. Diaz Mayor of Miami

ADOPTING THE "2030 CHALLENGE" FOR ALL BUILDINGS

WHEREAS, the U.S. Conference of Mayors has previously adopted strong policy resolutions for cities, communities, and the federal government to take actions to reduce fossil fuel consumption and global warming pollution; and

WHEREAS, the Inter-Governmental Panel on Climate Change (IPCC), the international community's most respected assemblage of scientists, has found that climate disruption is a reality and that human activities are largely responsible for increasing concentrations of global warming pollution; and

WHEREAS, the U.S. Building Sector has been shown to be the major consumer of fossil fuel and producer of global warming causing greenhouse gases; and

WHEREAS, the federal government through programs fostered within many of its key agencies and numerous state governments as well as municipalities across the U.S. have adopted high performance green building principles; and




Borland Laboratory Renovation



WHEREAS, a recent study completed by Lawrence Berkeley National Laboratory, the most definitive cost-benefit analysis of green buildings ever conducted, concluded that the financial benefits of green design are between \$50 and \$70 per square foot, more than 10 times the additional cost associated with building green; and

- WHEREAS, the large positive impact on employee productivity and health gains suggests that green building has a cost-effective impact beyond just the utility bill savings; and
- WHEREAS, studies have indicated that student attendance and performance is higher in high performance school buildings; and
- **WHEREAS.** recognizing that a building's initial construction costs represent only 20-30 percent of the building's entire costs over its 30 to 40 year life, emphasis should be placed on the "life cycle costs" of a public building rather than on solely its initial capital costs; and
- WHEREAS, the construction industry in the U.S. represents a significant portion of our economy and a significant portion of the building industry is represented by small business and an increase in sustainable building practices will encourage and promote new and innovative small business development throughout the nation; and
- WHEREAS, the American Institute of Architects (AIA), the national professional organization representing architects has adopted a position statement calling for the immediate energy reduction of all new and renovated buildings to one-half the national average for that building type, with increased reductions of 10% every five years so that by the year 2030 all buildings designed will be carbon neutral, meaning they will use no fossil fuel energy.

NOW, THEREFORE, BE IT RESOLVED that the U.S. Conference of Mayors will encourage its members to adopt the following "2030 Challenge" for building performance targets: New construction of City buildings shall be designed to and achieve a minimum delivered fossil-fuel energy consumption performance standard of one half the U.S. average for that building type as defined by the U.S. Department of Energy. Renovation projects of City buildings shall be designed to and achieve a minimum delivered fossil-fuel energy consumption performance standard of one half the U.S. average for that building type as defined by the U.S. Department of Energy. All other new construction, renovations, repairs, and replacements of City buildings shall employ cost-effective, energy-efficient, green building practices to the maximum extent possible; and




NOW, THEREFORE, BE IT FURTHER RESOLVED that the U.S. Conference of Mayors will work to increase the fossil-fuel reduction standard for all new buildings to carbon neutral by 2030, in the following increments:

> 60% in 2010 70% in 2015 80% in 2020 90% in 2025


Carbon-neutral by 2030 (meaning new buildings will use no fossil fuel GHG emitting energy to operate); and


- **BE IT FURTHER RESOLVED** that the U.S. Conference of Mayors will urge mayors from around the nation to join this effort by developing plans to fully implement the above mentioned targets as part of their procurement process and by establishing policies to insure compliance and measure results; and
- **BE IT FURTHER RESOLVED** that the U.S. Conference of Mayors will urge mayors from around the nation to develop plans to fully implement the above mentioned targets for *all* new and renovated buildings within the City; and
- **BE IT FINALLY RESOLVED** that the U.S. Conference of Mayors will work in conjunction with ICLEI Local Governments for Sustainability and other appropriate organizations to join this effort to develop plans to fully implement similar targets as mentioned above. Project cost: Unknown



<u>Appendix E</u>

Pipe-Space and Riser Detail






Appendix F


Detailed Copper Piping System Estimate

		Size of Pipe	Linear Ft.	Price per Foot	Total Cost
Basement					
	Cold Water				
		3"	129' 5"	\$23.30	\$3,029.00
		1 1/2"	5' 1"	\$7.51	\$37.55
	Hot Water				
	HOL WALER	1 1/2"	53' 3"	\$7.51	\$398.03
	Hot Water Return				
		1"	53' 3"	\$4.23	\$224.19
Ground Floor					
	Cold Water				
	Cold Water	3"	123' 5"	\$23.30	\$2,865.90
		1"	201' 8"	\$4.23	\$854.46
		3/4"	438' 6"	\$2.94	\$1,290.66
	Hot Water				
		1 1/2"	122' 6"	\$7.51	\$923.73
		1"	3' 7"	\$4.23	\$16.92
		3/4"	114' 10"	\$2.94	\$338.10
	Hot Water Return				
		1"	121' 6"	\$4.23	\$516.06
		3/4"	73'	\$2.94	\$214.62

Dustin Faust Construction Management 4/12/2007



		Size of Pipe	Linear Ft.	Price per Foot	Total Cost
	oor Bathroom Area				
	Cold Water				
		2"	41' 3"	\$11.69	\$479.29
		1"	40' 10"	\$4.23	\$173.43
		3/4"	65' 4"	\$2.94	\$191.10
		1/2"	108' 0"	\$1.85	\$199.80
	Hot Water				
		1"	29' 5"	\$4.23	\$126.90
		3/4"	68' 1"	\$2.94	\$199.92
		1/2"	91' 8"	\$1.85	\$170.20
	Hot Water Return				
		3/4"	27' 2"	\$2.94	\$79.38
1st Floor					
13111001					
	Cold Water				
		3/4"	96' 5"	\$2.94	\$285.18
		1/2"	12'	\$1.85	\$22.20
	Hot Water				
		3/4"	98' 2"	\$2.94	\$288.12
		1/2"	12'	\$1.85	\$22.20
	Hot Water Return				
		1/2"	90' 4"	\$1.85	\$166.50




		Size of Pipe	Linear Ft.	Price per Foot	Total Cost
	or Bathroom Area				
	Cold Water				
		2"	25' 3"	\$11.69	\$292.25
		1"	15' 8"	\$4.23	\$67.68
		3/4"	34' 7"	\$2.94	\$102.90
		1/2"	140' 7"	\$1.85	\$260.85
	Hot Water				
		3/4"	31' 10"	\$2.94	\$94.08
		1/2"	130' 5"	\$1.85	\$242.35
	Hot Water Return				
		1'2"	14' 3"	\$1.85	\$25.90
2nd Floor					
	Cold Water				
		3/4"	244' 10"	\$2.94	\$720.30
		1/2"	36'	\$1.85	\$66.60
	Hot Water				
		3/4"	241' 7"	\$2.94	\$711.48
		1/2"	36'	\$1.85	\$66.60
	Hot Water Return				
		1/2"	222' 3"	\$1.85	\$410.70



	Size of Pipe	Linear Ft.	Price per Foot	Total Cost
Second Floor Bathroom				
Area				
Cold Water				
	2"	25' 4"	\$11.69	\$292.25
	1"	24'	\$4.23	\$101.52
	3/4"	46' 1"	\$2.94	\$135.24
	1/2"	106' 6"	\$1.85	\$197.95
Hot Water				
	3/4"	14' 4	\$2.94	\$41.16
	1/2"	82' 10"	\$1.85	\$153.55
Hot Water Return				
	1/2"	14' 4"	\$1.85	\$25.90
			Copper Piping Total	\$17,122.70

Dustin Faust Construction Management 4/12/2007



Copper Fittings			
Description	Quantity	Price	Total Cost
3" x 2" x 3" Cp. T	1	\$72.30	\$72.30
3" x 3" x 2" Cp. T	2	\$71.25	\$142.50
3" x 2" x 1" Cp. T	1	\$81.93	\$81.93
3" Cp. 90 °	9	\$47.84	\$430.56
2" x 2" x 1" Cp. T	12	\$23.57	\$282.84
2" x 2" x 3/4" Cp. T	7	\$22.85	\$159.95
2" Cp. 90 °	2	\$16.26	\$32.52
2" Male IP x Cp. Adpt.	2	\$18.89	\$37.78
1 1/2" Cp. T	2	\$19.41	\$38.82
1 1/2" x 1 1/2" x 3/4" Cp. T	4	\$14.44	\$57.76
1 1/2" Cp. 90 °	17	\$8.10	\$137.70
1 1/2" Male IP x Cp. Adpt.	2	\$9.22	\$18.44
1" FM IP x Cp. Adpt.	15	\$6.29	\$94.35
3'4" FM IP x Cp. Adpt.	9	\$2.58	\$23.22
3/8" FM IP x 1/2" Cp. Eared Els	52	\$7.79	\$405.08
1/2" FM IP x Cp. Eared Els	6	\$3.97	\$23.82
Misc. Cp. Fittings (1" - 3/4" - 1/2")			\$1,800.00
		Copper Fittings Total	\$3,839.57
		Copper Piping Total	\$17,122.70
		Copper System Total	\$20,962.27


PENNSTATE Borland Laboratory Renovation

Appendix G

Detailed PEX Piping System Estimate


	Size of Pipe	Linear Ft.	Price per Foot	Total Cost
Basement				
Cold Water				
	3"	129' 5"	\$23.30	\$3,029.00
	1 1/2"	5' 1"	\$7.51	\$37.55
Hot Water				
	1 1/2"	53' 3"	\$7.51	\$398.03
Hot Water Return				
	1"	53' 3"	\$1.35	\$71.55
Ground Floor				
Cold Water				
	3"	123' 5"	\$23.30	\$2,865.90
	1"	201' 8"	\$1.35	\$272.70
	3/4"	438' 6"	\$0.86	\$377.11
Hot Water				
	1 1/2"	122' 6"	\$7.51	\$923.73
	1"	3' 7"	\$1.35	\$4.73
	3/4"	114' 10"	\$0.86	\$98.90
Hot Water Return				
	1"	121' 6"	\$1.35	\$164.03
	3/4"	73'	\$0.86	\$62.78

Dustin Faust Construction Management 4/12/2007



	Size of Pipe	Linear Ft.	Price per Foot	Total Cost
Ground Floor Bathroom Area				
Cold Water				
	2"	41' 3"	\$11.69	\$479.29
	1"	40' 10"	\$1.35	\$55.35
	3/4"	65' 4"	\$0.86	\$55.90
	1/2"	108' 0"	\$0.47	\$50.76
Hot Water				
	1"	29' 5"	\$1.35	\$39.83
	3/4"	68' 1"	\$0.86	\$58.48
	1/2"	91' 8"	\$0.47	\$43.24
Hot Water Return				
	3/4"	27' 2"	\$0.86	\$23.22
1st Floor				
Cold Water				
	3/4"	96' 5"	\$0.86	\$82.56
	1/2"	12'	\$0.47	\$5.64
Hot Water				
	3/4"	98' 2"	\$0.86	\$84.28
	1/2"	12'	\$0.47	\$5.64
Hot Water Return				
	1/2"	90' 4"	\$0.47	\$42.30


Dustin Faust Construction Management 4/12/2007



	Size of Pipe	Linear Ft.	Price per Foot	Total Cost
First Floor Bathroom				
Area Cold Water				
Cold Water	2"	25' 3"	\$11.69	\$292.25
	2 1"	25 3 15' 8"	\$1.35	\$292.25
	3/4"	13 8 34' 7"	\$0.86	\$29.67
	1/2"	140' 7"	\$0.47	\$66.27
Hot Water				
	3/4"	31' 10"	\$0.86	\$27.52
	1/2"	130' 5"	\$0.47	\$61.34
Hot Water Return				
	1'2"	14' 3"	\$0.47	\$6.58
2nd Floor				
Cold Water				
	3/4"	244' 10"	\$0.86	\$210.70
	1/2"	36'	\$0.47	\$16.92
Hot Water				
	3/4"	241' 7"	\$0.86	\$208.12
	1/2"	36'	\$0.47	\$16.92
Hot Water Return				
	1/2"	222' 3"	\$0.47	\$104.34

75


Dustin Faust Construction Management 4/12/2007



	Size of Pipe	Linear Ft.	Price per Foot	Total Cost
Second Floor Bathroom				
Cold Water				
	2"	25' 4"	\$11.69	\$292.25
	1"	24'	\$1.35	\$32.40
	3/4"	46' 1"	\$0.86	\$39.56
	1/2"	106' 6"	\$0.47	\$50.06
Hot Water				
	3/4"	14' 4	\$0.86	\$12.04
	1/2"	82' 10"	\$0.47	\$39.01
Hot Water Return				
	1/2"	14' 4"	\$0.47	\$6.82

PEX & Copper Piping Total \$10,866.87

Dustin Faust Construction Management 4/12/2007



PEX & Copper Fittings


Description	Quantity	Price	Total Cost
3" x 2" x 3" Cp. T	1	\$72.30	\$72.30
3" x 3" x 2" Cp. T	2	\$71.25	\$142.50
3" x 2" x 1" Cp. T	1	\$81.93	\$81.93
2" x 2" x 1" Cp. T	12	\$23.57	\$282.84
2" x 2" x 3/4" Cp. T	7	\$22.85	\$159.95
2" Male IP x Cp. Adpt.	2	\$18.89	\$37.78
1 1/2" Cp. T	2	\$19.41	\$38.82
1 1/2" x 1 1/2" x 3/4" Cp. T	4	\$14.44	\$57.76
1 1/2" Male IP x Cp. Adpt.	2	\$9.22	\$18.44
1" PEX x 1" FM IP	15	\$5.89	\$88.35
3/4" PEX x 3/4" FM IP	9	\$2.82	\$25.38
1/2" PEX x 1/2" FM IP Eared Els	58	\$4.06	\$235.48
1" PEX x 1" CP sweat	15	\$2.43	\$36.45
3/4" PEX x 3/4" CP sweat	9	\$1.50	\$13.50
1/2" PEX x 1/2" CP sweat	58	\$0.83	\$48.14
1" Cinch Rings	30	\$0.70	\$21.00
3/4" Cinch Rings	18	\$0.65	\$11.70
1/2" Cinch Rings	116	\$0.47	\$54.52


PEX & Copper Fittings	
Total	\$1,426.84
PEX & Copper Piping Total	\$10,866.87

PEX System Total \$12,293.71

Dustin Faust Construction Management 4/12/2007

PENNSTATE Borland Laboratory Renovation





Works Cited

Alliant Energy, <u>Alliant Energy Geothermal – Home Page</u>. April 11, 2007 <u>http://www.alliantenergygeothermal.com/stellent2/groups/public/documents/pub</u> /geo_001407.hcsp

Architecture 2030, Edward Mazria, <u>2030 Challenge, Carbon Neutral Buildings</u>. Feb. 20, 2007

http://www.architecture2030.org/open_letter/index.html

Plastic Pipe and Fittings Association, <u>PPFA Home Page</u>. February 1, 2007 <u>http://www.ppfahome.org/</u>

U.S. Department of Energy, <u>Department of Energy - Buildings</u>. March 15, 2007 http://www.energy.gov/energyefficiency/buildings.htm


Breon, Dan. Personal Interview. February 16, 2007

Brubaker, Lew. Personal Interview. February 15, 2007

Elder, John. Personal Interview. February 15, 2007

Heltman, Tim. Personal Interview. February 12, 2007

Dustin Faust Construction Management 4/12/2007





Dustin Faust Construction Management 4/12/2007


PENNSTATE Borland Laboratory Renovation

Acknowledgements

I would like to personally thank for all of their help and support on this Architectural Engineering Capstone Project. Without their help, this research would not have been possible.

- John Bechtel The Pennsylvania State University, Assistant Vice President of Operations
- Tim Heltman The Pennsylvania State University, Project Manager, The Borland Laboratory Renovation
- John Elder Aramark
- Lew Brubaker Leonard S. Fiore, Construction Manager, The Borland Laboratory Renovation
- Dan Breon The Pennsylvania State University, Construction Services, The Borland Laboratory Renovation
- Mark Bodenshatz The Pennsylvania State University, Vice President of Operations
- Ronald Faust Schuylkill Sales Co.
- Dr. Riley The Pennsylvania State University, Construction Management Faculty
- Steve Howel APR Supply Company

Dustin Faust Construction Management 4/12/2007



Borland Laboratory Renovation

Weight Matrix

Description	Research	Value	Constructabilit	Schedule	Total
		Engineering	y Review	Reduction	
AIA 2030 Challenge	30%	0%	10%	0%	40%
Domestic Water Re-	5%	20%	10%	5%	40%
Design					
HVAC Re-Design	5%	10%	5%	0%	20%
Total	40%	30%	25%	5%	100%